

FIELD GEOLOGY

BY

B. N. MUKHERJEE, M.A.

Premchand Roychand Scholar

PROFESSOR OF MATHEMATICS,

SCOTTISH CHURCH COLLEGE, CALCUTTA (BENTD.)

FOURTH EDITION

PUBLISHED BY

THE INDIAN PRESS, LTD.

ALLAHABAD (INDIA)

1941

[AUTHORISED HINDI VERSION IN THE PRESS]

**PRINTED AND PUBLISHED BY THE INDIAN PRESS, LTD.,
ALLAHABAD, CALCUTTA, BANARAS.**

To
The Memory of
MY MOTHER

PREFACE TO THE FOURTH EDITION

During the last ten years, since the third edition of this book was prepared, the science of geology has continued its rapid progress. Through intensive research, many advances have been made in the understanding of physiographic processes and forms, in the classification of metamorphic rocks, in the field interpretation of igneous bodies, and in the subsurface correlation of strata. Especially notable has been the increased use of various geophysical methods for geologic exploration.

In revising "Field Geology" for this fourth edition, we have aimed to include among new topics only those which can be said definitely to be applicable in the study of pure geology in its numerous branches—especially stratigraphy, structural geology, and geologic history—and we have refrained from including discussion of methods that are of very limited application in pure geology. New material will be found on mass movements, varvs, lensing strata, permeability of sedimentary rocks, flow structure and fracture structure in igneous rocks, field study of igneous bodies, preferred orientation of mineral constituents of rocks, analysis and classification of folds and faults, electrical logging, subsurface correlation by radioactivity, and so on. The chapters on airplane mapping and geophysics have been rewritten and enlarged. An abbreviated table for the identification of common rock minerals has been included as Appendix II, and the table for classification of igneous rocks has been revised as Appendix III.

A few words of explanation are in order in partial reply to questions from interested users of the book. We have not seen fit to expand Chapter X on Mineral Deposits because adequate treatment of geology applied to mines and mining would necessitate a great increase in the size of the book, and, furthermore, we

believe that this is a subject which can be more satisfactorily handled in a separate volume. With regard to Chapter XXIII on Geophysical Methods, the object of our treatment is not to teach the student to become a geophysicist, but rather to explain to the geologist how the geophysical methods may be of service for elucidation of geologic problems. After due consideration, the Bibliography has been retained at the end of the book rather than dividing it into separate groups of references appended to the end of each chapter.

Space will not permit naming all those who helped the author by various suggestions for this revision. Many teachers and many students were interrogated for their opinions, and as far as practical their ideas have been followed. In particular, we wish to express our gratitude to Professors J. D. Barksdale, R. L. Belknap, M. P. Billings, Eliot Blackwelder, A. F. Buddington, H. E. Culver, R. F. Flint, R. H. Hopper, R. E. Marsell, V. E. Monnett, L. R. Page, H. E. Quinn, V. E. Scheid, G. M. Schwartz, Gayle Scott, R. E. Sherrill, H. T. U. Smith, P. B. Stockdale, W. T. Thom, Jr., F. M. Van Tuyl, and W. A. Ver Wiebe, for their constructive criticisms; and to Messrs, J. F. Anderson, Wm. M. Barret, Paul Browning, C. B. Claypool, L. G. Ellis, W. E. Hollingsworth, J. D. Marr, C. R. Nichols, John M. Pearson, R. E. Rettger, B. E. Richert, H. W. Rose, L. C. Smith, and L. W. Storm, for assistance in preparing new material for the fourth edition. To the late Dr. Donald C. Barton, also, we owe a debt of gratitude for several valuable suggestions. Among the 61 new illustrations, several were drawn from outside sources, with the kind permission of authors and publishers. Acknowledgment for these has been given individually under the respective figures.

F. H. LAHEE.

PREFACE TO THE FIRST EDITION

This book treats the subject of geology from the field standpoint. It is intended both for a textbook and for a pocket manual. As a manual the author hopes that it will be of service not only to students of geology, but also to mining engineers, civil engineers, and others whose interests bring them in touch with geologic problems. The book has been written on the assumption that the reader has an elementary knowledge of general geology and also an acquaintance with a few common minerals and rocks.

The first twelve chapters are concerned with the recognition and interpretation of geologic structures and topographic forms as they are observed. Here the aim has been to describe together phenomena which in certain respects resemble one another, but which may be of diverse origins. Where possible the treatment has been empirical rather than genetic. In order to assist the reader in identifying various forms and structures, a number of tables or keys have been prepared. From the very nature of geology they cannot be final or complete. They are presented with the hope that they may be of some value at least in showing what features to observe in the field.

In the last six chapters are described methods of geologic surveying, the nature and construction of maps, sections, and block diagrams, the interpretation of topographic and geologic maps, the solution of certain geologic computations, and the preparation of geologic reports.

An appendix containing several tables of practical value, a bibliography to which there are many footnote references throughout the text, and an index which has been made as comprehensive as possible, will be found at the end of the book.

The author wishes to express his sincere gratitude to his wife, to Professors W. M. Davis, W. Lindgren, R. A. Daly, and H. W. Shimer, and to Dr. J. D. Mackenzie, for valuable advice and criticism.

For illustrations the writer is indebted as follows, the specific sources being noted in certain cases in parentheses:¹ to Professor W. Lindgren for Figs. 159 and 246 ("Mineral Deposits"); to Professor R. A. Daly for Figs. 84, 96, and 109 ("Igneous Rocks and Their Origin"); to the *Geographical Journal* (London) for Fig. 295 (replaced in 4th ed.); to the Harvard Geological Museum for permission to photograph specimens for Figs. 13-17, 71, 229, 233, and 234; to the University of Chicago Press and the *Journal of Geology* for Figs. 49 and 456; to the Carnegie Institute of Washington for Figs. 277, 291, and 292; to the Geological Society of America for Figs. 4A and B (modified), 157, 158 (modified), 254, and 287; to Dr. W. F. King, Chief Astronomer, Department of the Interior, Ottawa, for Fig. 68 (from R. A. Daly's "Geology of the North American Cordillera at the 49th Parallel"); to Mr. R. W. Sayles for Fig. 32; to the Geological Survey of New Jersey and the U. S. Geological Survey for Fig. 296; to the U. S. Geological Survey for Figs. 5 (*An. Rept.* 7), 41, 77, 96, 97 (*Bull.* 404), 166-168 (*An. Rept.* 13), 227 (*Bull.* 275), 232 (*Bull.* 239), 248 (*An. Rept.* 4), 250 (*Folio* 15), 268 (*Bull.* 576), 269, 271-275, 279 (*Prof. Paper* 82), 288 (*An. Rept.* 17), 294, 297, 298, and 299 (*Prof. Paper* 82), 301, 302, 304, 305, 310, 313 (*Prof. Paper* 64), 315, 318 (*Bull.* 273), 319, 320, 323, 324 (*Prof. Paper* 61), 325 (*Prof. Paper* 67), 335, 339 (*Prof. Paper* 61), 340 (*Monog.* 1), 341-343, 344 (*An. Rept.* 21), 345, 480 (*Bull.* 300), 514, and 545; to the Coast and Geodetic Survey for Plate I; to Professor C. K. Leith for Fig. 130; to Professors E. Blackwelder and H. H. Barrows for Fig. 231B; and to Professor W. M. Davis for Figs. 265-267, 308, 336, and 337. Figures 265 (redrawn by F. H. L.), 266, 267, 308, and 336 were taken from Professor Davis' "Geographical Essays," and Fig. 337 from "Physical Geography"

¹ In this paragraph the original figure numbers have been changed to agree with their present numbers in the fourth edition.

by W. M. Davis and W. H. Snyder, by permission of Ginn and Company, Publishers.

To Professor H. F. Reid the author is grateful for permission to draw from his articles published in Bulletins 20 and 24 of the Geological Society of America.

The late Dr. C. W. Hayes very generously gave the writer entire freedom to borrow from his "Handbook for Field Geologists." Several mathematical tables were copied from this source.

F. H. L.

CONTENTS

	PAGE
PREFACE TO THE FOURTH EDITION.	vii
PREFACE TO THE FIRST EDITION.	ix
CHAPTER I. INTRODUCTION.	1
GENERAL DEFINITIONS	1
1. Processes of Erosion.	1
2. Products of Erosion.	1
3. Mass Movements.	2
4. Bedrock, Outcrop, and Exposure Defined	2
5. Lithosphere Defined	2
6. Field Geology Defined.	3
7. Observation and Inference	3
8. Correlation.	4
9. Multiple Working Hypotheses	4
10. The Study of Exposures	5
11. Primary and Secondary Features Defined	6
12. Dip, Strike, and Attitude Defined.	6
13. Discrimination between Transported and Residual Deposits	6
TABLES FOR THE IDENTIFICATION OF ROCK FEATURES	7
14. Use of the Tables.	7
15. Parallel Banded or Streaked Character.	8
16. Single Strips or Bands.	10
17. Intersecting Banded Pattern	11
18. Massive Character	11
19. Inclosed Areas or Bodies.	12
20. Contact Lines; Mutual Relations of Contiguous Rock Masses	14
21. Gradational Changes in Rocks	15
22. Cracks or Fractures.	15
23. Curvature of Bands or Streaks	16
24. Inclination of Banded Structure.	17
25. Sequence of Steps in Field Work	17
CHAPTER II. FEATURES SEEN ON THE SURFACES OF ROCKS.	18
COLORS OF ROCKS	18
26. Black, Gray, and Dark Brown	18
27. Yellow and Brown.	18

	PAGE
28. Red and Pink	18
29. Lighter Shades and White	19
30. Green and Gray Spots.	20
31. Relations of Colors to Surfaces of Weakness	20
SURFACE FEATURES OTHER THAN COLOR	20
32. Smoothness and Polish.	20
33. Granularity.	21
34. Great Irregularity.	22
35. Scratches, Grooves, and Ribs.	23
36. Pits and Hollows	29
CHAPTER III. ROCK PARTICLES AND FRAGMENTS.	34
GENERAL NATURE	34
37. Shape and Surface Markings.	34
38. Dimensions of Particles and Fragments	34
CHARACTERS OF ROCK PARTICLES	35
39. Composition	35
40. Shape	36
41. Angular Particles	37
42. Subangular Particles.	38
43. Rounded Particles.	38
CHARACTERS OF LARGER ROCK FRAGMENTS, PEBBLES, ETC.	39
44. Identification.	39
45. Angular Fragments	40
46. Scratched, Faceted Pebbles.	41
47. Pebbles with Scars or Indentations	43
48. Polished, Faceted Pebbles	44
49. Subangular Pebbles	45
50. Rounded Pebbles and Boulders.	45
51. Elongated and Flattened Pebbles	47
52. Pebble-like Bodies.	47
CHAPTER IV. ORIGINAL SURFACE FEATURES OF SEDIMENTS	48
CLASSIFICATION.	48
53. Identification of Minor Irregularities of Surface.	48
DESCRIPTION AND EXPLANATION	49
54. Beach Cusps	49
55. Ripple Marks.	49
56. Wave Marks	51
57. Rill Marks.	51

CONTENTS

XV

	PAGE
58. Sun Cracks	52
59. Rain Prints	53
60. Bubble Impressions	54
61. Frost Marks	54
62. Animal Tracks	54
CHAPTER V. ORIGINAL STRUCTURES AND STRUCTURAL RELATIONS OF SEDIMENTARY ROCKS	
STRATIFICATION	55
63. Bedding in Mechanical Deposits	55
64. Bedding in Chemical and Organic Deposits	56
65. Absence of Bedding in Sedimentary Deposits	56
66. Interstratification of Materials of Diverse Origin	58
67. Pseudostratification	59
CONSOLIDATION	59
68. Consolidation of Mechanical Sediments	59
69. Consolidation of Chemical Sediments	61
70. Consolidation of Organic Sediments	61
71. Porosity and Permeability of Sediments	61
72. Compression of Sediments	63
MODES OF OCCURRENCE	65
73. Primary Dip	65
74. Conformity and Its Significance	66
75. Relations between Unconsolidated Transported Deposits and Bedrock; Regional Unconformity	67
76. Relations between Unconsolidated Residual Deposits and Bedrock; Regional Unconformity	69
77. Regional Unconformity in Bedrock	69
78. Overlap; Transgression and Regression of Sediments	70
79. Clastic Dikes	74
80. Clastic Pipes	76
STRUCTURES DEPENDING ON THE MUTUAL RELATIONS OF BEDS OR LAMINÆ	
81. Local Unconformity; Contemporaneous Erosion	76
82. Sun Cracks	79
83. Contemporaneous Deformation	80
84. Cross-bedding	80
A. Cross-bedding Defined	80
B. Delta Structure	80
C. Compound Foreset Bedding in Deltas	82
D. Torrential Cross-bedding	83

	PAGE
E. Other Types of Foreset Bedding in Water-laid Deposits	83
F. Wave-built Cross-bedding.	84
G. Eolian Cross-bedding.	85
H. Ripple-mark,	86
I. Comparison of Types of Cross-bedding	87
85. Lenses.	87
86. Uniform Lamination.	89
87. Transverse Textural Variation within Single Beds and Laminæ	89
88. Stratigraphic Interval Defined	90
89. Variations in Stratigraphic Interval	90
90. Pinching or Lensing of Strata.	90
91. Lateral Variations in Texture, Porosity, and Permeability	91
92. Rhythms or Cycles in Stratification	91
PARTICLES AND FRAGMENTS IN CLASTIC DEPOSITS.	92
93. Isolated Pebbles and Boulders	92
94. Intraformational Fragments	92
95. Isolated Masses of Unconsolidated Material in Surface Deposits.	94
96. Arrangement of Pebbles	94
97. Arrangement of Sand Grains	95
98. Position of Fossils.	96
FIELD INTERPRETATION OF SEDIMENTARY MATERIALS	97
99. Nature of the Parent Rock.	97
100. Quiet Deposition or Current.	98
101. Depth of Water for Lake and Marine Sediments.	98
102. Direction of Current	98
103. Strength of Current	99
104. Climate.	99
105. Physiographic Conditions at Time of Deposition.	101
106. Characters of Marine, Littoral, and Continental Deposits	101
107. Conditions of Unconformity.	104
108. Stratigraphic Sequence	110
109. Age Relations of Sedimentary Materials	110
110. Relative Age of Clastic Dikes and Pipes.	111
111. Discrimination between Separate Glacial Epochs.	111
CHAPTER VI. FIELD RELATIONS OF IGNEOUS ROCKS	114
TERMINOLOGY AND CLASSIFICATION.	114
112. General Definitions.	114
113. Flow Structure.	118
114. Pyroclastic Rocks	121

CONTENTS

xvii

	PAGE
115. Contact Zones.	121
116. Classification of Eruptive Bodies.	121
117. Size of Eruptive Bodies	127
NATURE AND CONSOLIDATION OF MOLTEN ROCK.	127
118. Nature of Molten Rock.	127
119. Consolidation of Molten Rock.	128
CONTACTS	130
120. Shape of Contacts	130
121. Sharpness of Contacts	131
CONTACT ZONE IN THE ERUPTIVE ROCK	133
122. Principal Phenomena of the Contact Zone	133
123. Marginal Texture	133
124. Vesicular and Amygdaloidal Structures	134
125. Discrimination between Vesicular Structure and Weather Pits	134
126. Discrimination between Amygdaloidal and Porphyritic Structures.	134
127. Flow Structure.	135
128. Fracture Systems.	135
129. Marginal Variations in Composition	135
130. Schliers and Segregations	138
CONTACT ZONE IN THE COUNTRY ROCK	138
131. Contact Metamorphism.	138
132. Baking	139
133. Discoloration	140
134. Mineralogical and Chemical Alterations	140
135. Cleavage	142
INCLUSIONS	143
136. Cognate and Foreign Inclusions	143
137. Overhead Stopping and Intrusive Breccias	143
138. Characters of Inclusions.	144
139. Source of Inclusions	146
140. Discrimination between Inclusions and Segregations	147
141. Discrimination between Large Inclusions and Roof Pend- ants	147
142. Discrimination between Inclusions and Erosion Patches	148
FIELD INTERPRETATION AND CLASSIFICATION OF ERUPTIVE BODIES	149
143. Shape of Eruptive Bodies.	149
144. General Summary with Reference to the Interpretation of Contact Phenomena	151

	PAGE
145. Field Recognition of Eruptive Bodies.	152
146. Field Study of Structures of Igneous Rocks	153
ERUPTIVE BODIES IN RELATION TO THEIR TIME OF ORIGIN . . .	154
147. Relative Age.	154
148. Geologic Age	156
ERUPTIVE BODIES IN RELATION TO THE LAND SURFACE . . .	156
149. Significance of the Exposure of Intrusive Rocks	156
150. Topographic Expression of Igneous Bodies.	157
151. Relations of Contacts to Erosion.	157
152. Relations of Contact Zones to Topography	162
153. Effects of Topography on the Shapes of Outcropping Dikes, Sills, and Contacts.	162
CHAPTER VII. TILTED AND FOLDED STRATA.	163
DEFORMATION OF ROCKS	163
154. Fracture and Flowage.	163
TERMINOLOGY AND CLASSIFICATION.	164
155. Principal Kinds of Folds or Flexures	164
156. Terms of General Application	165
157. Varieties of Folds	167
158. Size of Folds.	172
159. Competent or Controlling Beds	172
160. Strike, Dip, and Pitch	174
CAUSES AND CONDITIONS OF FOLDING	175
161. Causes of Tilting and Folding	175
INTERPRETATION OF TILTED AND FOLDED STRATA	183
162. Discrimination between Primary and Secondary Dip . . .	183
163. Amount of Tilting	185
164. Direction of Forces.	185
165. Significance of Minor Folds in Relation to Major Folds. .	186
166. Top and Bottom of Steeply Inclined, Vertical, and Over- turned Beds.	187
FOLDS IN RELATION TO THEIR TIME OF ORIGIN.	188
167. Age of Folds.	188
168. Two or More Periods of Folding.	188
169. Folds That Originate in Unconsolidated Sediments. . . .	189
170. Discrimination between Folds Originating before and after Consolidation	193

CONTENTS

xix

	PAGE
FOLDS IN RELATION TO THE LAND SURFACE.	194
171. Topographic Expression of Folds.	194
172. Breadth of Outcrop Defined	195
173. Effects of Topography on Breadth of Outcrop	195
174. Effects of Topography on the Distribution of Outcrops	196
175. Traverses across and along the Strike	197
176. Sequence of Strata in a Cross-strike Traverse	198
177. Correlation of Outcrops.	199
CHAPTER VIII. FRACTURES AND FRACTURE STRUCTURES.	200
FRACTURES IN ROCKS.	200
178. Relations of Fractures to Zones of the Lithosphere.	200
FAULTS	200
TERMINOLOGY AND CLASSIFICATION.	200
179. General Nature of Faults.	200
180. Terms of General Application	203
181. Kinds of Displacement.	206
182. Classification of Faults	210
183. Terms for Fault Blocks.	216
184. Omission and Repetition of Beds Defined.	219
185. Variations in Dip and Displacement of Faults.	219
186. Relations of Faults to Folds	220
GEOLOGIC EVIDENCES FOR FAULTING	221
187. Principal Evidences of Faulting	221
188. Slickensides and Other Features on Fault Surfaces.	222
189. Visible Displacement of Veins, Dikes, Strata, Etc.	223
190. Fault Breccia Zones	223
191. Drag.	223
192. Discontinuity of Linear Structures along Their General Trend; Offset	224
193. Abrupt Termination of Structures along Their Trend.	227
194. Repetition of Beds.	230
195. Omission of Beds	233
196. Omission and Repetition of Beds Observed in Drill Holes	233
FAULTS IN RELATION TO THEIR TIME OF ORIGIN	234
197. Relative Age of Faults	234
198. Warped and Folded Faults	234
199. Geologic Age of Faults	236
200. Post-Pleistocene Faults in Bedrock.	236
201. Faults That Originate in Unconsolidated Sediments	236

	PAGE
202. Discrimination between Faults Originating in Sediments before and after Consolidation.	237
FAULTS IN RELATION TO THE LAND SURFACE.	238
203. Classification of Topographic Forms Related to Faulting	238
204. Topographic Expression of Horsts, Grabens, and Basins	239
205. Effects of Topography on the Trend of Fault Lines.	240
206. Inliers and Outliers Produced by Erosion of Faults.	241
207. Effects of Faulting on Streams.	241
208. Displacement Relative to Sea Level	241
209. Original Inclination of a Fault Scarp.	242
210. Topographic Forms as Evidences of Faulting	243
JOINTS	244
TERMINOLOGY AND CLASSIFICATION.	244
211. Definitions	244
212. Classification	244
DESCRIPTION OF JOINTS.	245
213. Primary Fracture Systems in Igneous Rocks.	245
214. Columnar and Transverse Jointing Related to Igneous Eruption	246
215. Primary Fracture Systems Related to Flow Structure in Igneous Rocks.	247
216. Sheet Jointing in Massive Rocks.	250
217. Columnar and Transverse Jointing Not Related to Igneous Eruption	251
218. Intersecting Joint Systems in Stratified Rocks.	251
INTERPRETATION OF JOINTS	255
219. Interpretation of Joints.	255
JOINTS IN RELATION TO THEIR TIME OF ORIGIN	256
220. Age of Joints	256
JOINTS IN RELATION TO THE LAND SURFACE	258
221. Relations of Joints to Erosion and Topography	258
FRACTURE CLEAVAGE	258
222. Definition and Origin.	258
BRECCIAS AND AUTOCLASTIC STRUCTURES	259
223. Definition and Classification.	259
CHAPTER IX. METAMORPHIC ROCKS.	263
METAMORPHISM IN GENERAL.	263
224. General Conditions and Effects of Metamorphism	263

CONTENTS

xxi

	PAGE
STUDY OF ROCK CLEAVAGE.	271
225. Relations of Flow Cleavage and Fracture Cleavage.	271
226. Discrimination between Flow Cleavage and Fracture Cleavage	272
227. Discrimination between Bedding and Cleavage.	272
228. Relations of Cleavage and Bedding in Folds.	273
229. Uses of Cleavage in Geologic Interpretation.	274
230. Distortion of Original Structures, Fossils, Pebbles, Etc.	275
DEGREES OF METAMORPHISM AND ORIGIN OF METAMORPHIC ROCKS	278
231. Degrees of Dynamic Metamorphism in Clastic Sedimentary Rocks	278
232. Discrimination between Metamorphosed Sedimentary Rocks and Metamorphosed Igneous Rocks	280
233. Discrimination between Primary and Secondary Gneisses.	281
234. Relative and Geologic Age	282
235. Original Depth of Metamorphic Rocks	282
CHAPTER X. MINERAL DEPOSITS	283
MINERAL DEPOSITS IN GENERAL.	283
236. Terminology and Classification	283
STUDY OF SUBSEQUENT MINERAL DEPOSITS	284
237. Origin of Subsequent Deposits.	284
238. Forms of Subsequent Mineral Deposits.	285
239. Distribution of Subsequent Deposits	286
240. Composition of Subsequent Deposits.	286
241. Size of Vein Deposits.	287
242. General Field Relations of Veins.	287
243. Discrimination between Open Space Deposits and Replacement Deposits.	287
244. Discrimination between Veins and Dikes	288
CHAPTER XI. TOPOGRAPHIC FORMS	290
LAND FORMS IN GENERAL	290
245. Land Forms and Their Recognition.	290
SLOPES	291
246. Significance of the Inclination of Land Surfaces	291
CLIFFS	293
247. Cliffs in General.	293
248. Fault Cliffs	294
* 249. Volcanic Cliffs.	295

	PAGE
250. Destructional Cliffs.	297
251. Faceted Spurs.	302
BEACHES	305
252. Classification and General Characters.	305
BENCHES AND TERRACES.	309
253. Definitions and Identification	309
254. Fault Benches.	310
255. Constructional Terraces.	311
256. Destructional Benches and Terraces	312
257. Degradation and Aggradation of Rivers.	314
PLAINS	315
258. Terminology and Identification	315
259. Volcanic Plains	317
260. Constructional Plains.	317
261. Destructional Plains	322
SWAMPS.	326
262. Definition and Classification.	326
VALLEYS AND BASINS	327
263. Terminology and Identification	327
264. Fault Valleys and Basins	330
265. Basins Caused by Tilting and Warping.	334
266. Volcanic Basins	334
267. Constructional Valleys and Basins	334
268. Destructional Basins.	337
269. Destructional Sinks	337
270. Destructional Valleys.	339
A. In General.	339
B. Valleys of Differential Erosion; Contact Valleys	339
C. V-shaped Valleys.	340
D. Solution Valleys	341
E. Destructional Gaps.	341
F. Valleys and Channels without Streams	342
G. Glaciated Valleys.	343
H. Cirques and Drift Hollows.	345
HANGING VALLEYS	346
271. Definition and Classification	346
CAVES AND NATURAL BRIDGES	347
272. Caves	347
273. Natural Bridges	348

CONTENTS

xxiii

	PAGE
HILLS, RIDGES, AND OTHER POSITIVE LAND FORMS	348
274. Terminology and Identification	348
275. Fault Mountains.	350
276. Volcanic Cones	350
277. Constructional Hills and Ridges	350
278. Destructional Hills and Ridges.	359
CHAPTER XII. TOPOGRAPHIC EXPRESSION	364
TOPOGRAPHIC EXPRESSION IN GENERAL	364
279. Mutual Relationship of Topographic Forms	364
CYCLES OF TOPOGRAPHIC DEVELOPMENT.	365
280. Definition.	365
281. Cycle of River Erosion	365
282. Cycle of Mountain Glacier Erosion	368
283. Cycle of Marine Erosion	368
284. Cycle of Arid Erosion	373
TOPOGRAPHIC EXPRESSION DEVELOPED IN TWO SUCCESSIVE CYCLES	375
285. Topographic Unconformity Defined	375
286. Abandoned Shore Lines	376
TOPOGRAPHIC EXPRESSION IN ITS RELATION TO GEOLOGIC STRUC- TURE	380
287. Valley Pattern.	380
CHAPTER XIII. TOPOGRAPHIC MAPS AND PROFILE SECTIONS	383
FEATURES SHOWN ON TOPOGRAPHIC MAPS.	383
288. Classification of Features	383
289. Contours	383
290. Scale.	385
291. Direction.	386
292. Requisite Data on a Completed Contour Map.	386
293. Aerial Photographic Maps.	386
PROFILE SECTIONS	386
294. Nature of Profile Sections.	386
295. Construction of a Profile Section.	388
296. Enlargement of Profile Sections	389
INTERPRETATION OF CONTOUR MAPS	390
297. Direction of Ascent and Descent.	390
298. Elevation of a Given Point	391

	PAGE
299. Spacing of Contours	391
300. Distance between Two Points.	382
301. Visibility	392
302. Inclination of a Slope.	394
CHAPTER XIV. GEOLOGIC SURVEYING	395
PART I. GENERAL OBSERVATIONS	395
NATURE OF GEOLOGIC SURVEYING.	395
303. Definition and Aim.	395
304. Uses of Geologic Surveying	395
305. Diversity of Surveys	396
306. Scope of Geologic Field Work	396
STUDY OF OUTCROPS	396
307. Most Likely Places for Exposures	396
308. Examination of Outcrops	397
309. Discrimination between Boulders and Outcrops	397
310. Tracing Outcrops	397
311. Importance of Contacts.	398
312. Discrimination between Igneous Contacts, Unconformities, and Faults	398
313. Location of Contacts Buried under a Soil Mantle	400
314. Sinuous Contacts in Low-dipping Beds	401
315. Location of Eruptive Contacts.	401
316. Obscure Bedding.	403
317. Determination of Strike and Dip of Strata	403
318. Degree of Accuracy in Taking Strike and Dip of Strata	406
319. Cross-bedding.	406
320. Bevelling of Outcrops	407
321. Settling of Beds	408
322. Field Correlation.	408
323. Attitude of Contorted Strata	411
324. Attitude of Eruptive Contacts.	411
SCHEDULE FOR FIELD OBSERVATIONS	413
325. General Data to Be Observed and Recorded.	413
GENERAL SUGGESTIONS	
326. Beginning a Field Problem	414
327. Collecting and Trimming Specimens	416
328. Taking Photographs	417
329. How Much Shall Be Undertaken in the Field?	418
330. Degree of Accuracy in Field Work.	419

	PAGE
CHAPTER XV. GEOLOGIC SURVEYING.	420
PART II. INSTRUMENTS AND OTHER EQUIPMENT USED IN GEOLOGIC	
FIELD MAPPING	420
331. The Compass and Clinometer	420
332. Use of the Compass	420
333. Setting the Compass	423
334. Use of the Clinometer	424
335. The Locke Level.	426
336. The Abney Level.	427
337. The Telescopic Hand Level	428
338. Adjustment of Hand Levels.	428
339. Comparison of Hand Levels.	429
340. The Aneroid Barometer.	429
341. The Paulin Altimeter.	431
342. The Barograph	431
343. The Watch	432
344. The Plane Table.	432
345. Paper for the Plane Table.	433
346. Stadia and Leveling Rods.	433
347. The Open Sight Alidade	434
348. The Telescopic Alidade.	434
349. Care of the Alidade.	436
350. Adjustment of the Alidade	437
351. Stadia Reduction Tables	439
352. Stadia Slide Rule	439
353. Scale for Plotting	440
354. The Protractor	440
355. The Steel Tape	440
356. The Odometer.	440
357. The Tally Register or Pace Counter	440
358. The Camera.	441
359. Base Maps	441
360. Additional Equipment	441
CHAPTER XVI. GEOLOGIC SURVEYING	443
PART III. INSTRUMENTAL METHODS IN FIELD MAPPING	443
GENERAL CONSIDERATIONS.	443
361. Procedures in Geologic Mapping.	443
362. Traverse Defined.	443
363. Quantities Measured.	444
364. Correction of Pace Lengths	445
365. Controls for Mapping.	446
*366. Detail and Reconnaissance Mapping	447

	PAGE
367. Note-taking in General.	448
368. Four Principal Methods of Field Mapping	449
THE COMPASS AND CLINOMETER METHOD	449
369. Definition.	449
370. Equipment	449
371. Preparation of the Notebook	450
372. Compass Traverses.	451
373. Notes for a Compass Traverse.	453
374. Plotting Compass Traverses.	457
375. Correction of Plotted Compass Traverses.	458
THE HAND LEVEL METHOD	459
376. Definition.	459
377. Equipment	460
378. Determination of Strike.	460
379. Determination of Dip.	460
380. Hand Level Traverses	461
381. Note-taking.	461
THE BAROMETER METHOD.	461
382. Definition.	461
383. Equipment	462
384. Horizontal Control for Mapping by Barometer	462
385. System of Recording Stations	464
386. Graphic Method of Note-taking	464
387. Tabulation Method of Note-taking.	466
388. Necessity for the Correction of Barometric Readings.	467
389. Correction for Atmospheric Pressure Variations	469
390. Methods of Checking Barometric Readings	470
391. Plotting the Correction Curve.	474
392. Application of the Correction Curve	478
393. Comparison of Different Correction Curves for the Same Route on Different Days	478
394. Correction for Atmospheric Temperature	480
395. Source of Temperature Data.	484
396. Method of Correcting for Both Temperature and Pressure Variations.	485
397. To What Extent Is Correction of Barometric Readings for Temperature Fluctuations Desirable?	488
398. Degree of Precision of the Barometer Method.	489
399. Rate of Mapping.	489
THE PLANE TABLE METHOD.	490
400. Definition.	490
401. Equipment	490

CONTENTS

xxvii

	PAGE
402. Preparation of the Map Paper.	492
403. Centering and Levelling the Plane Table	492
404. Determination of Declination	493
405. Orienting the Plane Table.	495
406. Lining in a Station.	496
407. Determination of Horizontal Distances.	497
408. Long Sights.	498
409. Inclined Sights.	501
410. Correction for Curvature and Refraction	504
411. Methods of Determining Location	506
412. Determination of Elevations	514
413. Application of the Methods of Location.	524
414. Variations in Plane Table Parties	526
CONCLUSION.	526
415. Comparison of the Methods of Field Mapping.	526
416. Sources of Error.	527
417. Limits of Error	528
418. Factors Affecting Choice of Method	530
419. Topographic Contour Sketching	530
420. Schedules for Mapping	531
CHAPTER XVII. GEOLOGIC SURVEYING.	536
PART IV. AIRPLANE MAPPING.	536
421. Methods	536
422. Errors and Distortion in Aerial Photographs.	540
423. Application to Geology.	542
424. The Stereoscope in Geologic Mapping	550
CHAPTER XVIII. SUBSURFACE GEOLOGIC SURVEYING	559
425. Scope.	559
426. Methods of Drilling	559
427. Reliability of Samples	563
428. Oriented Cores.	565
429. Correlation of Samples from Bore-holes.	568
430. Electrical Surveying of Bore-holes	573
431. Drilling-rate Charts	581
432. Geothermal Data in Relation to Geology	582
433. Use of Radioactivity in Logging Bore-holes	587
434. The Problem of Crooked Holes	588
435. Directional Drilling	593

	PAGE
CHAPTER XIX. MODES OF GEOLOGIC ILLUSTRATION.	594
GEOLOGIC MAPS	594
436. Definitions	594
437. Conventional Patterns, Lines, and Symbols	594
438. Position of Boundaries between Rock Bodies	598
439. Relations of Topography to Geologic Mapping.	599
440. Filling in an Outcrop Map of Stratified Rocks.	603
441. Use of Profile Sections in Geologic Map Construction.	604
442. Nature of the Legend.	606
443. Requisite Data for a Completed Geologic Map	606
JOINT DIAGRAMS AND MAPS	608
444. Methods of Representing the Attitude of Joints	608
GEOLOGIC SECTIONS.	609
445. Definitions and General Nature	609
446. Methods of Indicating Geologic Structure.	611
447. Position of Sections across Folded Strata	611
448. Operations Necessary in the Construction of Geologic Sections.	613
449. Construction of a Rectangular Geologic Section across Folded Strata.	613
A. Transfer of Data Recorded on a Map.	613
B. Correlation of Rocks	615
C. Location of Boundaries	615
D. Filling in the Section	616
450. Construction of a Profile Geologic Section across Folded Strata	616
451. Comparison of Rectangular and Profile Sections.	618
452. Interpretation of Dips in the Construction of Geologic Sections	618
A. Observations on Homoclinal Dips	619
B. Observations on Dips of Varying Amount and Direction	620
C. Studies across Axial Regions	623
453. Sections across Igneous Bodies.	624
454. Vertical Sections of Faults	625
455. Requisite Data for a Completed Geologic Section	626
STRUCTURE CONTOUR MAPS	626
456. Nature of Structure Contour Maps.	626
WELL LOGS	631
457. Definition.	631
458. Correlation of Logs.	634

CONTENTS

xxix

	PAGE
459. Electrical Logs for Correlation	641
460. Radioactivity in Correlation	645
SUBSURFACE MAPS	645
461. Definition	645
462. Construction	645
463. Comparison of Surface and Subsurface Maps; Convergence Maps	649
464. Effects of Crookedness of Bore-holes on Subsurface Mapping	654
CONTOUR MAPS OTHER THAN STRUCTURE CONTOUR MAPS. . . .	659
465. Examples Mentioned	659
BLOCK DIAGRAMS	659
466. Definitions	659
467. Construction of Block Diagrams	660
468. Requisite Data for a Completed Block Diagram	665
SKELETON DIAGRAMS	666
469. Definition and Description	666
SERIAL DIAGRAMS	668
470. Use and Character	668
COLUMNAR SECTIONS	668
471. Definition	668
PLANS, SKETCHES, AND PHOTOGRAPHS	670
472. Requisite Data for Plans, Sketches, and Photographs . .	670
CHAPTER XX. INTERPRETATION OF GEOLOGIC MAPS.	671
473. Significant Features on Geologic Maps	671
474. Outcrop Areas	671
475. Boundaries of Outcrop Areas	671
476. Strike Symbols	673
477. Conformable Strata	673
478. Igneous Rocks	678
479. Unconformities	679
480. Faults	679
481. Geologic History	680
CHAPTER XXI. GEOLOGIC COMPUTATIONS	683
COMPUTATIONS IN GENERAL	683
482. Measurements and Computations Previously Discussed . .	683
483. Application of Computations Explained in the Present • Chapter	683

	PAGE
SOLUTION OF PARTICULAR PROBLEMS	684
484. Line of Intersection of Two Planes, Not Parallel.	684
485. Point of Intersection between a Line and a Plane	687
486. Thickness of a Layer.	689
487. Depth of a Point in an Inclined Surface.	690
488. Determination of Strike and Dip When the Elevations of Three Points in an Inclined Surface Are Given.	691
489. Determination of Strike and Dip from Two Components.	694
490. Slip and Shift of Faults.	696
CHAPTER XXII. PREPARATION OF GEOLOGIC REPORTS.	702
THE REPORT AS A WHOLE.	702
491. General Instructions.	702
492. Parts of a Manuscript Report.	703
THE TEXT OF A GEOLOGIC REPORT	703
493. Order of Topics	703
494. Abstract	704
495. Introduction.	705
496. Summary and Conclusions	705
497. Geography	705
498. Stratigraphy and Petrography.	706
499. Geologic Structure.	707
500. Geologic History.	707
501. Economic Considerations	708
PARTS OTHER THAN THE TEXT	708
502. Quotations and Footnotes.	708
503. Illustrations.	709
504. Table of Contents, Index, Etc..	712
CHAPTER XXIII. GEOPHYSICAL SURVEYING	713
505. Definition and Classification.	713
GRAVIMETRIC METHODS.	716
506. Gravity and Its Expression	716
507. Variations in Gravity.	716
508. Quantities Measured by the Torsion Balance and Gra- vimeter	719
509. Effects of Topography on Gravity Observations	721
510. Units of Gravity Measurement	723
511. Graphic Representation of Gravity Data	726
512. Gravity Surveying for Geologic Structure.	727

CONTENTS

xxx1

	PAGE
513. Comparison of Torsion Balance and Gravimeter.	734
MAGNETOMETRIC METHOD.	736
514. The Earth's Magnetic Field.	736
515. Measurement of Magnetic Anomalies.	737
516. Correction of Magnetic Readings	738
517. Compilation of Field Data	739
518. Application to Geology.	741
SEISMIC METHODS	742
519. Elastic Earth Waves.	742
520. Instruments Used in Seismographic Work.	746
521. The Refraction Method.	747
522. Applications of Refraction Seismic Work to Geology.	748
523. The Reflection Method.	755
524. Applications of the Reflection Method to Geology	763
ELECTRIC METHODS.	766
525. Electrical Conditions within the Lithosphere.	766
526. Classification of Methods of Electrical Surveying.	768
527. Methods Which Utilize Electrical Fields of Force Artificially Produced	770
SUMMARY ON THE GEOPHYSICAL METHODS.	778
528. Limitations of Methods.	778
APPENDIX.	781
APPENDIX I. Geologic Time Scale	782
APPENDIX II. Identification Table of Common Rock Minerals.	783
APPENDIX III. Classification of Igneous Rocks	784
APPENDIX IV. Classification of Sedimentary Rocks	785
APPENDIX V. Classification of Metamorphic Rocks	786
APPENDIX VI. Table for the Identification of Clastic Sedimentary Rocks	787
APPENDIX VII. Land Survey Divisions, United States	796
APPENDIX VIII. Measurement and Weight.	798
APPENDIX IX. Solution of Triangles.	800
APPENDIX X. Natural Circular Functions.	801
APPENDIX XI. Equivalent Angles of Slope and Per Cent Grades	802
APPENDIX XII. Equivalent Dips Expressed in Angles and in Feet Per Mile	803
APPENDIX XIII. Correction for Dip in Directions not Perpendicular to Strike.	804
APPENDIX XIV. Protractor for Correction of Dip	805

	PAGE
APPENDIX XV. Graphic Determination of Dip Components When Dips Are Measured in Feet per Mile.	807
APPENDIX XVI. Dip, Depth, and Thickness of Inclined Strata.	809
APPENDIX XVII. W. S. Tangier Smith's Chart	810
APPENDIX XVIII. Stadia Tables	813
BIBLIOGRAPHY	817
INDEX.	829

FIELD GEOLOGY

CHAPTER I

INTRODUCTION

GENERAL DEFINITIONS

1. Processes of Erosion.—On the earth's surface various agents are engaged in the work of rock destruction. Rivers wear their channels; waves undermine the cliffs along shores; wind, when it has free play, scours the rocks over which it blows; and glaciers abrade their beds. These are all processes in which the agent is moving while in operation. There are other kinds of work in which the agents are essentially motionless. For instance, alternate heating and cooling in regions of wide temperature range may cause the separation of grains and chips from the surface of a rock; moisture in the cracks of a rock expands in freezing and may wedge off block after block; certain minerals may be decomposed and carried away in solution; and so on. Whether accomplished by moving or motionless agents, the various processes of rock destruction come under the head of *erosion* (*e*, off, + *rodo*, gnaw). Mechanical wear by rivers, wind, etc., is *corrasion*; chemical wear is *corrosion*. Many of the processes effected by agents which are essentially motionless are included in the term, *weathering*. Weathering accomplished in a chemical way is *decomposition* and that accomplished in a mechanical way is *disintegration*.

2. Products of Erosion.—Through erosion a quantity of *débris* is formed equivalent to the amount by which the rocks are worn down. Ordinarily it is borne away from its source, part being in solution and part being handled mechanically, and is eventually

accumulated as sedimentary materials.¹ Deposits of this sort are called *transported*. If products of erosion remain *in situ* they are known as *residual deposits*. Transported deposits are *chemical* if they were precipitated from solution, and they are *mechanical*, *fragmental*, or *clastic*, if they consist of detached particles and fragments of the parent rock and if their accumulation was brought about by mechanical means. Chemical and mechanical sediments may be *organic* or *inorganic*, depending either upon the nature of the materials or upon the agent of their deposition: All these deposits, including clay, mud, sand, gravel, soil, and the like, are known collectively as *mantle rock*.

3. Mass Movements.—Processes of erosion involve not only the transportation of individual particles and fragments of rock by such agents as wind, water, and ice but also the moving of masses of rock débris. These processes are classified as *mass movements*. They include slow flowage (rock creep, soil creep, solifluction); rapid flowage (sheetflood, mudflow, débris avalanche); landslide (slump, débris slides, rock slides); and subsidence (over mines, caverns, etc.). As suggested by these names, all these movements are due to insufficient support to prevent the settling or collapse of masses of rock material under the pull of gravity. In the different classes of mass movement, interstitial water (or ice) may be effective in lubricating or otherwise facilitating the movement.²

4. Bedrock, Outcrop, and Exposure Defined.—Everywhere below the mantle rock, solid rock, or *bedrock*, is known to exist. When the bedrock projects through the overlying mantle of detritus, the protruding portions are called *outcrops*. Outcrops and also sections in the unconsolidated superficial mantle rock may be referred to as *exposures*.

5. Lithosphere Defined.—If erosion should continue long enough in any region and if the products of this erosion should

¹ *Sediment* and *sedimentary* are used in this book in their widest sense with reference to all rocks which originate upon the earth's surface and which are derived through the destruction of preëxisting rock.

² For a full discussion of this subject, see Bibliog., SHARPE, C. F. STEWART, 1938.

be removed; at last rocks might be exposed which were once at great depth. This is just what has happened over broad areas on the continents and consequently we are able today to see and study rocks some of which have been several miles below the earth's surface. We may say, then, that we are in some degree familiar with the solid part of the earth down to a depth of several—probably well within 25—miles, at least as far as the continents are concerned. Of the ocean basins we know much less; but of this fact we can feel certain, that for some distance beneath the ocean floor, as likewise for some distance beneath the land surface, the earth consists of *rocks* of one kind or another. This outer rocky shell of the earth, of which the continental portions have been to a certain extent brought within our observation, is the *lithosphere*.

6. Field Geology Defined.—When rocks and rock materials are investigated in their natural environment and in their natural relations to one another, the study is called field geology. Field geology seeks to describe and explain the surface features and underground structure of the lithosphere. Physiography and structural geology are equally important in the science of field geology. Subsurface geology, likewise very important, pertains to the study of rock relationships by the use of data obtained underground, as in mines or from drilled wells. It is in contrast to surface geology, which is the collection and study of superficial evidences.

7. Observation and Inference.—Field geology is necessarily founded upon observation and inference. Only features that are superficial can be observed; all else must be inferred. We may study the surface of an outcrop, of a valley, or of a sand grain, but in attempting to explain the internal structure of the outcrop, or what underlies the valley, or how the sand grain was fashioned, we are forming inferences by interpreting certain visible facts. The ability to infer and to infer correctly is the goal of training in field geology, for one's proficiency as a geologist is measured by one's skill in drawing safe and reasonable conclusions from observed phenomena.

8. Correlation.—No geologic structures and no land forms, such as hills, valleys, and the like (245),¹ exist as isolated phenomena. Every geologic feature is in some way dependent upon, or associated with, other geologic features, and this dependency or association the field geologist must discover. This is what is meant by *correlation*. The word signifies the description or explanation of one geologic phenomenon in relation to others. Here is an example to illustrate the case: By definition all outcrops are exposed portions of the bedrock underlying the superficial unconsolidated mantle rock. Accordingly, when the geologist examines a series of outcrops he should bear in mind that they are not single, detached forms, but that they are visible parts of a rock body which is continuous beneath the soil and that the rocks or structures which they exhibit are in some way mutually related. He will be *correlating* these outcrops when he studies them from this broad point of view and endeavors to explain these mutual relations.

9. Multiple Working Hypotheses.—Geologic interpretation is facilitated by what is termed the method of multiple working hypotheses. Suppose, for instance, that the surface of a rock is marked by parallel grooves. In order to explain the origin of this feature, the geologist should call to mind all possible ways in which such parallel grooves might be produced. These are his working hypotheses. To determine which is the right one, he must examine the rock surface for other phenomena which are associated with the grooves, for each hypothesis postulates a certain group of geologic features which are mutually related.

The same principle may be applied where extensive correlation is necessary. The distribution of outcrops in a small area may be such as to suggest that a certain igneous rock comes into contact with a certain sedimentary rock, but the actual junction line may be concealed beneath the mantle rock. The relation may be explained on the assumption that the two rock bodies meet in an intrusive contact, in a fault, or in a surface of

¹ Numbers in parentheses refer to the articles in the text, denominated by the side headings.

unconformity. These three working hypotheses the geologist would have to keep in mind while looking for further evidence to ascertain which is the true interpretation.

10. The Study of Exposures.—Every geologic surface has features which deserve an explanation. They may be purely superficial or they may be cross sections of structures or forms that extend below the surface. In the latter event they probably belong to the structure of the rock. To discriminate between such superficial and structural characters, break off a fragment of the bedrock, or, in the case of an unconsolidated deposit, scrape off some of the surface material. The freshly exposed surface will settle the question.

If the observed features are superficial, in respect to their origin they may be related to the surface on which they are found in one or another of these four ways: (1) They may still be in process of formation, although perhaps the agent that made them is not acting continuously. (2) They may have been made by some agent no longer working and may not yet have suffered alteration under the new conditions. This often holds for Pleistocene glacial scorings on hard, fine-grained rocks; but smoothed, striated surfaces are soon destroyed on exposed coarse granular rocks, which are much more susceptible to disintegration. (3) The surface features, if on bedrock, may have been preserved for a time under unconsolidated deposits which have recently been removed (75, 76). Disintegration in coarse rocks may be prevented by such a cover. On the other hand, a soil mantle may sometimes promote decomposition of the buried rock. (4) A buried surface like that just mentioned may be preserved for a much longer time by a thick cover of consolidated strata (77). Erosion of the overlying formation may reëxpose the old surface provided the latter happens to coincide with the new erosion surface; but such instances are very rare and the exposure of the old surface cannot be complete.

If the observed features are structural, extending into the bedrock or the mantle rock, as the case may be, they should be examined with this fact constantly in mind. A line is then the cross section of a surface and an area (band or patch) is the cross

section of a body that has three dimensions. The trend of the line is often indicative of the form of the surface which it represents, and the shape of the area is suggestive of the form of the body, but there are many exceptions. The geologist should always look over the outcrop or the deposit to see if he can find the structural surface or body exposed on two faces of this outcrop as nearly as possible at right angles to one another.

11. Primary and Secondary Features Defined.---It is sometimes convenient to refer to the features on exposures as *primary*




FIG. 1.—Dip and strike. *bac* is a horizontal plane.

or *secondary* according as their origin was contemporaneous with, or subsequent to, the origin of the material in which they are seen. Examples of primary structures are bedding in sedimentary rocks, ripple marks, flow structure in lava, and the like. Among secondary features may be

mentioned surface stains on outcrops, glacial scratches, and fractures in rocks.

12. Dip, Strike, and Attitude Defined.—When one wishes to state the position of an inclined flat surface, two definite quantities are necessary. One must know the *dip*, that is, the maximum angle of slope of the surface, and one must know the *strike*, which is the direction of the intersection of the surface with any horizontal plane (Fig. 1). The dip is an angle in a vertical plane and must always be measured *downward* from the horizontal plane. The direction of dip is perpendicular to the strike. Dip and strike together determine the position or *attitude* of a surface with respect to horizontality and to compass directions.

the attitude of a relatively thin layer of uniformness will be that of the layer's upper or lower surface.

Discrimination between Transported and Residual Deposits.—Transported and residual deposits have been defined

in Art. 1. They can usually be distinguished in the field by their relations to the underlying bedrock. As a rule, transported materials are quite unlike the rock beneath them, whereas residual deposits commonly grade down into the subjacent rock or at least show some chemical resemblance to the latter (refer to Chapter III and to Arts. 75, 76).

TABLES FOR THE IDENTIFICATION OF ROCK FEATURES

14. Use of the Tables.—The succeeding tables are intended for use by beginners in field geology. They require very little acquaintance with geologic structures, but they do call for an elementary knowledge of the more common mineral and rock species. They are not to be regarded as absolutely complete. They are suggestive rather than final, indicating by references the places in the text where further information may be found. These references are to the numbered articles. Chapter and page citations are designated as such.

Among the general terms employed, the following may need definition. *Parallel banded or streaked character* refers to any structure or surface marking which may catch the eye on account of its linear appearance. *Massive character* may be regarded as the opposite of banded or streaked character. There is no linear appearance. *Inclosed areas* are superficial patches or spots scattered here and there on the surface of the exposure. *Inclosed bodies* are crystals, pebbles, rock fragments, or any other individual forms, entirely surrounded by a matrix of some kind of material. A *contact*, in general, is a surface between two contiguous rock masses. In this book the word is used to include igneous contacts (115), surfaces of conformity (74) and of unconformity (75), faults (179), and vein contacts (238). A *contact line* is the line of intersection of a contact surface with the surface of an exposure or with the surface of bedrock covered by mantle rock; *i.e.*, a contact line may be exposed or concealed. Other terms are either self-explanatory or are defined in the citations.

15. Parallel Banded or Streaked Character.—The exposure has a parallel banded or streaked appearance

A. Due merely to a system of parallel fractures (see Art. 22)

B. Not due to parallel fractures. The banded or streaked appearance is

1. Purely superficial (10), being due to

a. Parallel stains which trend down a sloping surface or follow parallel grooves. Such stains may consist of iron rust (yellow, buff, brown), fine soil (brown, gray, black, etc.), moisture, or organic growths (green, yellow, pink, etc.) (refer to Chapter II).

b. Parallel scratches or grooves (35).

2. Due to a structure which extends into the rock, but is viewed only in cross section, this structure being

a. A parallel arrangement of constituents which are longer than they are wide. If the rock is composed of constituents of different kinds and

(1) All, or most of, the constituents have parallel orientation, the rock is probably a schist; less likely, a gneiss. Mica or hornblende is usually abundant (Chapter IX).

(2) Only one or two kinds of constituents are distinctly orientated,

(a) The constituents with parallel arrangement being larger and more conspicuous than those not so arranged, the parallel constituents may be

(a₁) Flat concretions, with their flatness in the planes of the bedding of clay or mudstone, sand or sandstone.

(b₁) Flattish pebbles in an unmetamorphosed gravel or conglomerate (96).

(c₁) Flattened or somewhat spindle-shaped pebbles in a moderately sheared conglomerate. Such pebbles are generally more or less coated with mica.

(d₁) Broken strips (inclusions) of country rock inclosed in an igneous matrix, probably arranged in the direction in which the matrix flowed when it was molten (138).

(e₁) Phenocrysts in an igneous rock, probably arranged in the direction in which the matrix flowed when it was molten (112).

(f₁) Flakes of clastic mica, usually muscovite in this case, in muds, sands, mudstones, or sandstones (97).

(b) The constituents with parallel arrangement being smaller than those not so arranged, the parallel constituents probably belong to the matrix or groundmass of a schist containing metacrysts (224).

- b. A single layer which may intersect other structures in the adjacent rock (wall rock) and may, or may not, trend parallel to some fracture system in the wall rock (refer to Art. 16).
- c. A layered structure in which the several layers differ in respect to the composition, or size, or some other character, of their constituents. If
 - (1) The banding is limited to a particular belt or strip of rock and
 - (a) The banding is parallel to the edges of the strip, this banding may be due to
 - (a₁) Successive injections of igneous material along the same course. This feature, when seen, is most common in dikes and sills.
 - (b₁) Flow structure in a dike or a sill along the trend of its contact (127).
 - (c₁) Vein structure. For the distinction between veins and dikes refer to Art. 244.
 - (b) The banding forms an acute angle with the edges of the belt or strip, the structure is probably cross-bedding (84).
 - (2) The banding is not limited to a particular belt or strip of rock. If
 - (a) The banding is simple, in one set only, and
 - (a₁) The rock is fine-grained or has no grain, and
 - (a₂) Any visible constituents are not conspicuously oriented in parallel position, the banding may be
 - (a₃) Flow structure in lava (rhyolite, etc.) (112), especially if amygdales or phenocrysts are scattered through the rock. However, some fine-grained lavas look exceedingly like rocks of (b₁).
 - (b₂) Lamination, or bedding, in mud, clay, fine sand, etc., and in rocks derived therefrom, provided large grains, if anywhere present, are grouped in layers parallel to the banding. Exceptionally, sand grains or pebbles may be seen scattered indiscriminately in laminated muds and shales (93).
 - (c₂) Lamination or coarser bedding in limestone and chemical precipitates for the recognition of which chemical tests are often necessary.
 - (b₂) Visible constituents, principally mica, have parallel orientation, the banding is probably schistosity (224).

- (b₁) The rock is as coarse as a medium-grained sandstone, or coarser, so that the grains can be recognized, and
 - (a₁) The banding, as a whole, is of fairly regular and continuous character along its trend, although some layers may be lenticular, this banding may be due to
 - (a₂) Flow structure in an igneous rock along the trend of its contact with its country rock (Cf. c, (1), (a), above).
 - (b₂) Stratification in transported sedimentary materials (63).
 - (c₂) Any parallel structure, answering to the description, in residual materials, such structure having been originally present in the rock from which these materials were derived. Look for the parent rock (13, 76).
 - (d₂) Gneissic structure (224), seen in both primary and secondary gneisses. Secondary gneisses are generally associated with mica schists and often have schistose layers and other evidences of metamorphism. For the discrimination between primary and secondary gneisses (see Art. 233). In gneissic structure there is always a certain degree of mineral parallelism.
 - (e₂) Schistosity, this term always likewise implying parallel mineral arrangement (224).
 - (b₂) The bands (sometimes mere streaks) are present in igneous, usually granite-like, rock. They are generally short, and grade, especially at their ends, into the surrounding rock. They are often darker than the surrounding rock. Such bands or streaks are probably schliers (112).
- (b) The banding is complex and is
 - (a₁) Due to differences of color or intensity of color, and is often definitely related to two or more intersecting sets of fractures (refer to Art. 17).
 - (b₁) Due to differences of texture in adjacent layers, and has no necessary relation to fractures, it is probably a variety of cross-bedding (84).

16. Single Strips or Bands.—The exposure exhibits a strip or band which distinctly differs in character from the rock on each side. The band may be associated with others of the

same kind, but it is not one of a series of more or less similar parallel bands which together form the entire surface of the exposure. If

- A. The band is purely superficial, it is probably a local stain (10).
- B. The band is the cross section of a structure which extends into the rock, and
 - 1. Consists of angular fragments of the rocks on both sides of it, it may be a fault breccia or a vein breccia (223).
 - 2. Consists of silicate minerals such as are common in igneous rocks, or consists of rock glass, or of very dense, compact material showing no grain (felsite), it is probably
 - a. A sill or a flow if it is essentially parallel to associated strata (116, 145).
 - b. A dike if it crosses an igneous rock or the stratification of a sedimentary rock (116, 226).
 - 3. Consists of vein minerals, it is probably a vein (238, 244).

17. Intersecting Banded Pattern.—The exposure is marked by intersecting bands which trend in various directions. If

- A. The bands are merely the result of a color variation in the rock and are always definitely associated with fractures in intersecting sets, they are probably an effect of weathering, the agents having worked inward from the fractures (31).
- B. The bands differ in texture or composition from the adjacent rock, and
 - 1. Consist of silicate minerals common in the igneous rocks, they are probably intersecting dikes.
 - 2. Consist of vein minerals (240), they are probably veins which were deposited in intersecting fractures.
 - 3. Consist of sandstone in shale, or of mudstone or calcareous mudstone in limestone, they may be the lithified fillings of old sun cracks viewed in plan (58).

18. Massive Character.—The exposure has a massive appearance, its constituents being neither grouped in layers nor oriented in parallel position. If

- A. The rock is of very fine and uniform grain,¹ and is
 - 1. White, gray, or light-colored, rather soft or medium hard, and reacts for carbonates, it is probably a fine, massive limestone, marble, or dolomite.
 - 2. White or light-colored, highly siliceous, and very hard, it may be a fine quartzite or a siliceous replacement of massive limestone.

¹ In all cases under "A" further search may prove that the rock is a thick bed interstratified with other sedimentary rocks.

3. Gray or dark gray, brownish, buff, etc., generally has a clayey odor, and may be soft or hard, it may be a dust deposit (loess), a deposit of unlaminated clay, or the consolidated rocks derived from these materials (65).
- B. The rock is as coarse as a medium sandstone or coarser, being of relatively uniform grain, and consisting very largely of
 1. Grains of calcite or of dolomite, it is marble (224).
 2. Grains of quartz, it is quartzite (224).
 3. Grains of the silicate minerals which ordinarily constitute igneous rocks (Appendix III), it is an igneous rock or is the residual disintegration product (often arkose) of an igneous rock (76).
- C. The rock as a whole is relatively coarse, consisting of large grains or fragments in a finer matrix, reference should be made to the key in Art. 44.

19. Inclosed Areas or Bodies.—The surface of the exposure exhibits conspicuous bodies or areas (generally cross sections of bodies) surrounded by a relatively fine matrix. If

- A. The areas are purely superficial (10), they may be color stains (26-31), or exfoliation scars (33, 142), or erosion remnants such as are described in Art. 151.
- B. The areas are cross sections or faces of inclosed bodies which are
 1. Single crystals, in part or entire, they may be
 - a. Phenocrysts in igneous rocks, especially if the matrix is massive and is composed of silicate minerals (112). If the matrix is banded, the phenocrysts are apt to have parallel orientation.
 - b. Metacrysts in a metamorphic rock, especially if the matrix is marble (test for carbonates) or is schistose (224). If the matrix is banded or streaked and its constituents have parallel orientation, the metacrysts are apt to have diverse orientation.
 2. Mineral aggregates, or are bodies clearly not single crystals, and if these bodies
 - a. Have well-marked outlines and
 - (1) An angular form with sharp corners as if due to breaking, they are probably fragments in some kind of breccia (refer to 43, 223).
 - (2) A more or less well rounded form, without sharp corners and without projecting knobs, and have
 - (a) A radial or concentric arrangement of some or all of their constituents, as seen in cross section, and
 - (a₁) Form the bulk of the rock, adjacent individuals being in contact, having a flattened oval shape, and usually measuring 1 to 2 or 3 ft. in length, the bodies may be "pillows" in "pillow lava" (112).

- (b₁) Do not form the bulk of the rock, adjacent individuals, seldom in contact with one another, being
 - (a₂) Inclosed within a very fine dense or glassy matrix, the bodies may be spherulites or lithophysae in lava (refer to a good textbook of petrology).
 - (b₂) Inclosed within a fine-grained matrix which may have flow structure, the bodies may be amygdaloids, especially if they are oval in cross section, are arranged with their lengths parallel (112), and consist of vein minerals (240).
 - (c₂) Inclosed within a fragmental matrix usually consisting of angular pieces of lava and volcanic dust, as in volcanic agglomerate (223), are probably volcanic bombs (112).
 - (d₂) Inclosed within a massive matrix consisting of silicate minerals characteristic of igneous rocks, are probably segregations or rounded inclusions (140).
- (b) A concentric fracture structure, most pronounced toward the periphery, but no concentric or radial arrangement of constituents, and are contained in a matrix of the same constituents, in an unconsolidated or consolidated state, the bodies are probably boulders of disintegration still *in situ* (50).
- (c) No radial or concentric structure, and are
 - (a₁) Inclosed within a fine-grained matrix which may have flow structure, etc. (continue as in (a) (b₂) above).
 - (b₁) Inclosed within a fragmental matrix, etc. (continue as in (a) (c₂) above).
 - (c₁) Inclosed within a massive matrix, etc. (continue as in (a) (d₂) above).
 - (d₁) Inclosed within a matrix of sand or sandstone of uniform texture, the bodies may be
 - (a₂) Concretions if they are formed of similar sand or sandstone, more compactly cemented (68), or
 - (b₂) Clay galls if they consist of clay (if in sand), or shale (if in sandstone) (94).
 - (e₁) Inclosed within a matrix of clay or argillite, the bodies may be clay concretions if they consist of similar clay or argillite, more compactly cemented (68).
 - (f₁) Inclosed within a matrix of sand grains and smaller pebbles, as in an ordinary gravel, the bodies are pebbles (50).

- (3) A more or less well rounded form, often with projecting knobs or excrescences, they may be
 - (a) Concretions (of clay, marcasite, flint, etc.) if they are in a sedimentary matrix (68).
 - (b) Corroded inclusions if they are in an igneous matrix (138).
- (4) An elongate oval, spindle-shaped, rodlike, or lenticular form, the bodies may be
 - (a) Sheared pebbles in a schistose matrix, especially if they are clearly individual bodies (51).
 - (b) Lenses in a schistose or gneissic matrix, if they are merely lenticular areas (aggregates) which are relatively poor in mica, between wavy or winding layers relatively rich in mica (224).
- b. Have indistinct or blended outlines, gradational into the surrounding matrix, and are
 - (1) Irregular, often wavy streaks or patches in a distinctly igneous rock refer to Art. 15.
 - (2) Irregular, often bent and twisted, sand or gravel layers in gravel or till, they may be "necks" (95).
 - (3) Roughly lenticular bands of sand or gravel (sandstone or conglomerate) in distinctly sedimentary banded materials, the body is a lens (85).
 - (4) Lenticular areas in schists, refer to (4) above.

20. Contact Lines; Mutual Relations of Contiguous Rock Masses.—An exposure has two (or more) parts which meet in a fairly well defined line (contact line) and differ from one another in color, texture, composition, structure, or surface marking. Neither occurs included or surrounded by the other. If

- A. The difference in character is superficial (10), and
 - 1. Is not related to any underlying difference within the rock, it may be due to the fact that
 - a. The rock is stained in one place and is not stained, or is stained in a different way, in another place.
 - b. The rock is wet in one place and dry in another.
 - c. The rock has been affected in a different manner in two places, possibly because it was partly protected from erosion for a time (10).
 - 2. Is related to an underlying difference in the rock, it is probably due to the fact that the two kinds of rock are affected in different ways by the same erosive agents (see B, below).
- B. The difference in character is due to a difference in the underlying rock, and

1. The contact line lies between two bands, both of which are parallel to the line, and
 - a. The bands are sections of adjacent laminae or beds in unmetamorphosed, or metamorphosed sediments (232) (refer to Art. 15), the line may be called a line of conformity (74).
 - b. The bands consist of igneous or of metamorphic rock, refer to Art. 15 for the banding.
2. The contact line lies between two bands, or two banded series, which are not parallel both to one another and to the line,¹ and
 - a. Both bands or banded series are sections of adjacent laminae or beds in sedimentary rocks, or in metamorphosed sediments, the line may be a line of local unconformity (81), or one of regional unconformity (75), or a fault line (179, 312).
 - b. Both bands or banded series are not sedimentary, the line may be one of unconformity, or igneous contact, or a fault (312).
3. The contact line has any other relations, not mentioned above, to banded or massive rocks, determine the nature and classification of the rocks and then refer to Art. 312.

21. Gradational Changes in Rocks.—A rock exposure displays a gradational change in the texture, composition, or structure, of the materials of which it consists. If

- A. The change appears to be directly related to a contact line, and
 1. Is present in a sedimentary rock or in a metamorphosed sediment (232), and if
 - a. The contact line is a line of conformity or of unconformity (Art. 20), the variation is probably an effect of slow and uniform change of conditions during sedimentation when the rock was formed (81, 87).
 - b. The contact line is an igneous contact (Art. 20), the variation is probably attributable to contact metamorphism which was induced as a result of the eruption (115, 131-134).
 - c. The contact line is a fault, the variation is a result either of heat or pressure involved in the faulting, or of metamorphism accomplished by solutions or gases which travelled along the fault (134, 237).
- B. The change does not appear to be directly related to a contact line, it may be an effect of blended unconformity (76) or of blended igneous contact (115).

22. Cracks or Fractures.—The rock exposure is traversed by one or more cracks. Examination of such a crack shows that

¹ Both banded series may be parallel to one another and not to the line, or one series may be parallel to the line and not the other, or the series may be parallel neither to one another nor to the line.

- A. The broken ends of structures which trend across the crack have not been separated, or have been only very slightly separated, along the crack. If
 - 1. The crack is one of a set of closely and rather regularly spaced, parallel fractures, the crack is a cleavage crack and the set is called a cleavage (222, 224).
 - 2. The crack is single, or is one of a set of fractures not very closely spaced, the crack is a joint and the set is a joint set or joint system (211).
- B. The broken ends of structures which trend across the crack have been separated by displacement along the crack. Such a crack is a fault (179, 189).

23. Curvature of Bands or Streaks.—The rock exposure has a banded appearance and the bands are curving. First determine the probable nature of the rock and the banded structure by reference to Art. 15. If

- A. The rock is igneous, the curved form is probably a result of flow when this rock was molten (112, 127).
- B. The rock is sedimentary, and
 - 1. Has a finely banded (laminated) character, and the laminæ are in sets which
 - a. Are not parallel to the main bedding, and if the laminæ in all sets are curved, those in each set having simple and nearly parallel curvature and being truncated by the adjacent sets, the phenomenon is probably a variety of cross-bedding (84).
 - b. Are parallel to the main bedding, and if
 - (1) The laminæ in some or all sets are curved, those in each set having a wavy curvature in which the arches and troughs are of approximately equal size and shape, and the arches are never bent over the troughs, the phenomenon is probably ripple-mark (84, H). The span of the arches and troughs may be different in different sets, and any set may have its arches truncated by the overlying laminæ, whether these be straight or curving.
 - (2) The laminæ in some sets are curved and in other sets are straight or are much less curved, those in the curved sets often being of more or less irregular form or of unequal size, with associated breaks in their continuity and with the arches often bent well over the troughs, the phenomenon is probably a variety of folding such as is described in Art. 169.
 - 2. Is finely or coarsely bedded, and all the beds or laminæ are more or less similarly curving, sometimes in a very complicated manner, the curves consisting of archlike and troughlike bends, the phenomenon

is probably a result of similar folding such as is described in Arts. 157, 165.

- C. The rock is metamorphic, the curvature of the bands may be
 1. An original feature (A and B, 1, above) not yet destroyed because the rock has not suffered much deformation.
 2. Folding such as that described in B, 2, above, but generally of a more complex nature. This is to be expected in the mica schists.

24. Inclination of Banded Structure.—The exposure has a banded appearance and the bands are inclined. First determine the probable nature of the rock and the banded structure by reference to Art. 15. If

- A. The rock is igneous, the inclined attitude (12) may have significance, as mentioned in Art. 146.
- B. The rock is sedimentary, being
 1. Mud, clay, argillite, shale, or slate, and has its bedding inclined more steeply than 3° or 4° to the horizontal, this rock has probably been tilted from its original position (Art. 73). If its bedding is inclined not over 3° or 4° , it may or may not have been tilted since its deposition.
 2. Sand, sandstone, gravel, conglomerate, volcanic ash, or any other relatively coarse fragmental material, and has its bedding inclined more steeply than 35° to the horizontal, it has probably been tilted from its original position (73, 246). If it dips 35° or less, it may or may not have been tilted from its original position.
- C. The rock is metamorphic, the attitude of its banding is significant according as it was derived from an igneous rock or from a sedimentary rock (refer to A and B, above).

25. Sequence of Steps in Field Work.—In all field work, the outcrop to be examined, or the area to be examined, should first be rapidly looked over to form a rough, general idea of the nature of the problem and of the best mode of procedure. In regions where sedimentary rocks predominate, this preliminary reconnaissance should include an effort to outline the stratigraphic sequence (108). Then should follow a more careful, detailed examination of all evidence available for the solution of the problem. It is well to work from known to unknown, or from simple to complex, areas and to cross-check evidence whenever possible. For further discussion of this subject, see Arts. 325 and 326.

CHAPTER II

FEATURES SEEN ON THE SURFACES OF ROCKS

COLORS OF ROCKS

26. Black, Gray, and Dark Brown.—In igneous rocks primary gray shades are generally due to an intermixture of light and dark minerals. The more black grains (biotite, hornblende, augite, magnetite, etc.) there are, the darker gray is the rock. Gray sandstones also may owe variations in tone to variations in the content of black mineral particles, especially of magnetite. In shales, slates, and limestones, and some sandstones, grays are often caused by carbonaceous matter in the rock.

Dark brown and black incrustations of secondary origin are seen on some outcrops in arid regions. They are called *desert varnish*. These coatings consist of iron and manganese oxides believed to have been deposited from evaporating moisture which has risen to the surface by capillary action.

27. Yellow and Brown.—Yellow and brown are nearly always secondary colors. They are caused by the rusting (oxidation and hydration) of such iron-containing minerals as biotite, hornblende, augite, garnet, pyrite, etc. Because iron-bearing minerals break down very readily, this sort of yellow staining may be found even in dry climates. Some bright yellows are due to the growth of minute organisms.

28. Red and Pink.—Conglomerates, sandstones, and mudstones are sometimes red because the pebbles or grains which compose them were derived from an older red rock. The color is primary with the sedimentary rock, although it may have been either primary or secondary in the original parent rock. In this way red feldspar may color a sedimentary rock. Some pinkish and purplish sands are tinted by garnet grains.

The red color peculiar to some extensive sedimentary formations—notably parts of the Permian and Triassic—is due to the presence of finely disseminated hematite (Fe_2O_3). The origin

of this substance here is still imperfectly understood. It seems to have been pretty definitely associated with conditions favoring oxidation and impeding or preventing reduction. It has been ascribed to oxidation caused by a low groundwater level in accumulating sediments and their consequent exposure to interstitial air. Others have suggested that the red color may have originated while the sediments were deeply buried. In any case an essential condition seems to have been the absence of decaying organic matter which, if contained in sediments, acts as a reducing agent.

After rocks have been broken up by weathering in warm, humid climates, derived residual soils and clays may become red by superficial dehydration of ferric hydrates. Below the surface they remain yellowish or brown. In some places bright pinks and reds, like certain yellow tints, are produced by organisms.

29. Lighter Shades and White.—Through weathering original colors may be changed to lighter secondary shades of the same hue, or to white. This may be caused in at least five ways: (1) Feldspar grains in a rock may decompose to dull white powdery kaolin. (2) By the formation of minute solution cavities in more or less transparent soluble minerals, such as calcite, transparency is lost and the grains appear to be white. These two processes are characteristic of moist climates. (3) Organic coloring matter is sometimes "bleached" out of sedimentary rocks. (4) In dry climates, where the rainfall is slight, thin white incrustations of certain carbonates may be formed on the rock surfaces in the same way as the desert varnish, above described.¹ (What effect would a heavy shower have upon these soluble incrustations?) (5) Another phenomenon to be seen in climates where disintegration prevails is the production of minute fractures within the mineral grains, due to the action of frost or of temperature changes. Whitening of this origin, like

¹ Caliche, a whitish limey deposit found in semiarid regions, may be exposed in local areas, but its formation probably takes place near the base of the upper soil layer. It consists of soluble constituents leached from this upper soil and deposited below. See Bibliog., PRICE, W. ARMSTRONG, 1933.

that mentioned in (2) above, is due to the reflection of light from innumerable minute surfaces.

30. Green and Gray Spots.—Greenish or grayish spots or bands on red rocks may owe their presence to organic matter. Either the green has been produced by a reduction of the red iron oxide in proximity to the organic remains, or the rock has been reddened by oxidation except surrounding this organic matter. The action may have been caused by hydrogen sulphide gases associated with such organic matter (see 31).

31. Relations of Colors to Surfaces of Weakness.¹—A change of hue is sometimes associated with joints, faults, or even with igneous contacts, which are intersected by the outcrop surface. This is because such surfaces of weakness may afford access to decomposing solutions that bring about discoloration. The rock may appear to be striped or perhaps marked with a pattern of irregularly crossing bands. Since agents of discoloration always work inward, the maximum change is found at the surface of attack.

In a small joint block, a uniform inward gradation of color is not always seen. The water may enter from all sides, dissolve or decompose a little of the rock substance, carry it in, and then deposit it more or less concentric with the surface of the block. Such a joint fragment, if several times subjected to the same process, may display a number of concentric bands when it is split open.

Red sedimentary materials, colored by ferric oxide, may be bleached adjacent to faults or fissures up which hydrogen sulphide gas has ascended.²

SURFACE FEATURES OTHER THAN COLOR

32. Smoothness and Polish.—Smooth rock surfaces, and particularly those which are distinctly polished, have probably been rubbed by some abrasive agent which was furnished with

¹ Any fractures or contacts, and even the mutual contact surfaces of the grains, in rocks may be called *surfaces of weakness*.

² Bibliog., MOULTON, GAIL F., 1926.

finely divided scouring material, such as dust, rock flour, etc. Coarser particles scratch (35). Polish is generally limited to hard rocks, for it is not taken so well by softer varieties. Outcrops may be polished by wind carrying dust or ice crystals, by glacial ice, and by water currents or waves which are transporting sand or silt.

Polish made by wind, waves, and streams, is rather dull, whereas glacier-made polish may be of such perfection that objects are clearly reflected in it. Eolian dust polish is to be expected in desert regions and in other places where the prevailing winds are dry. Ice-crystal polish is seen only at high altitudes and latitudes where projecting rocks, unprotected by a snow cover, are frequently subjected to snow storms accompanied by winds of high velocity. Glacial polish is found in districts formerly overridden by ice. Another method by which rocks may be polished is by faulting, but here the smoothed surface cannot be seen unless the rocks on one side of the fault are gone. Fault-made polish is associated with slickensides (35, H). Polished surfaces are not necessarily flat or broadly rounded. They may be hummocky, grooved, scratched, or pitted.

33. Granularity.—Frost action, repeated temperature changes, and certain other processes of disintegration, cause the dislodgment of the grains of such coarse rocks as granite, diorite, gneiss, coarse marble, etc. The grains separate either in fragments along their mineral cleavages, or individually or in aggregates along their contacts with adjacent grains. Sometimes thin sheets or great slabs of rock may spall off by exfoliation (45). The effect of this loosening of mineral grains, singly or in groups, is to roughen the surface of the rock. So rough may the outcrops become in arid climates and at high altitudes that the sharp edges of the grains cut one's fingers. Such surfaces, if exposed to wind erosion, become more or less smoothed and polished.

Granularity of surface may be produced under water when one of the rock constituents is peculiarly susceptible to hydration. Accompanying this chemical change there is usually an increase in volume which, when affecting hundreds of grains over a rock

surface, brings about strains and stresses that finally cause the dislodgment of particles. This is an example of disintegration performed by decomposition.

34. Great Irregularity—The original surfaces of some kinds of lava are exceedingly irregular (120). This character may be observed on recent flows and also on lava sheets which have been buried and subsequently reëxposed.

If a rock suffers disintegration, not by the removal of small grains or spalls, but by the detachment of joint blocks, the outcrop acquires a secondary surface which is of great irregularity. Sometimes faults, cleavage planes, or other surfaces of weakness,



FIG. 2.—Profile section of an outcrop which is undergoing erosion through the removal of joint blocks. There are two prominent joint sets inclined in opposite directions.

function instead of joints. The process by which the blocks are detached is called *natural quarrying*. It includes the bergschrund action of glaciers, the plucking of moving ice, the ordinary frost action of northern climates, and the maintenance of cliffs undermined by rivers and waves (250). In the last case the blocks fall because their support has been eroded away by the undermining, but their loosening is often assisted by frost action or by root growth.

On some irregular secondary rock surfaces corners and edges are sharp (Fig. 2) whereas on others they are more or less rounded. Rounding may be the result of concentric weathering (50) or of some sort of abrasion. Evidently, if in a given region rock exposures continue highly irregular with all edges and corners sharp, the dislodgment of blocks must be more rapid than any rounding process. On ordinary surfaces of low inclination concentric weathering or scouring, as the case may be, can generally keep pace with natural quarrying. It follows that sharp edges and corners are found typically on vertical or steeply inclined surfaces. They are present on the roofs of erosion caves (272) and overhanging cliffs. They are more common in fine-grained

and homogeneous rocks, for disintegration is often too rapid in the coarser varieties.

Rock exposures of the kind just described may subsequently undergo abrasion. If ice is the abrading agent, it is apt to destroy all traces of the original surface; but wind and water merely round off the corners and scour out the hollows. They smooth over the ruggedness of the old exposure and produce a hummocky surface. The lee sides of roches moutonnées may show this kind of rounding performed by the later current action of glacial waters. Rocky coasts which are not very steep display hummocky, wave-worn erosion surfaces (Fig. 3), for, since the




FIG. 3.—Profile section of a rock surface worn by wave erosion. Note the definite relation between the joints, inclined in the general direction *ab*, and the outline of the rock surface

joint blocks are wedged out one at a time at long intervals, the waves are able to keep pace with the quarrying.

It is easy to distinguish between those hummocky surfaces which originate by abrasion and those that originate by disintegration. The former are more or less smooth, while the latter are granular and rough.

35. Scratches, Grooves, and Ribs.—Under the head of primary grooves and ribs may be mentioned the ropy structure of pahoehoe lava, and, in sedimentary rocks, ripple marks and rill marks (55, 57).

Scratches are always made by abrasion. Some secondary grooves are the product of scouring and others are made by weathering. Scratches on the floor and side of a groove, about parallel to its trend, may be accepted as proof of its origin by

scour. Scratches and abrasion grooves may be produced by ice, wind, landslides, mud flows and rock glaciers, by faulting, and by human means. Other secondary grooves may be made by solution and by differential weathering. All abrasion furrows indicate by their trend the general direction in which the agent moved, but whether the motion was in one way, along the line, or in the other, must be demonstrated by other criteria.

Below is a table to assist in the identification of scratches and grooves. The letters in parentheses refer to paragraphs in the succeeding context.

KEY FOR THE IDENTIFICATION OF SCRATCHES AND GROOVES

A. Scratches (always implying abrasion),

1. If notably parallel,

a. May be slickensides (H) if they are on a rock surface that can be traced into the bedrock and if displacement is visible where this surface passes into the bedrock.

b. May be landslide scratches (D) if they are on a bare rock surface which is on a steep hill slope and is just above a mass of landslide débris, or if they are on a rock surface which is locally covered by landslide débris.

2. If showing some deviation in trend and if

a. Present on a rock surface which is locally covered by till or other unsorted rock débris, may be glacial striæ (A), or scratches made by mud flow or rock glaciers (E).

b. Present on a rock surface which is locally covered by wind-blown sand, may be furrows made by wind scour (C).

B. Grooves with smoothed or polished surfaces and with evidences of abrasion,

1. The marks of abrasion being in the form of definite scratches which

a. Have the characters of glacial striæ, are probably grooves made by true glacier, rock glacier, or mud flow (B, E; see also J).

b. Have the character of slickensides, are probably grooves made by faulting (I).

2. The marks of abrasion being short furrows and subordinate grooves, may be wind-made grooves (C).

C. Grooves, usually with rough granular surfaces, and

1. Not intimately related to the rock structure, may be solution grooves, especially if they are found on such soluble rocks as limestone (F).

2. Parallel to the rock structure, the grooves being on the weaker layers and the ridges on the stronger layers, may be grooves of differential weathering (G).

—A. *Glacial scratches or striae* (sing., stria) are found on rock surfaces that have been smoothed by ice scour in regions




FIG. 4.—Features produced on rock surfaces by glacial abrasion. The arrow points in the direction of ice motion. A, plan of a crescentic gouge. B, section of crescentic gouge, taken through *a* and *b* in Fig. A. *cabd* is the glaciated rock surface. A crack was formed along *bc*, and then a chip broke off along *ac*. C, chatter marks associated with glacial striae. D, section of a pebble which has protected the rock matrix in its lee, *a*, and has caused the ice to gouge out this matrix on the thrust side, *b*. The depression at *b* may occur as a groove on three sides of the pebble, trailing out in the direction of ice motion. E, crescentic fractures in plan. F, microscopic section of quartzite showing six crescentic features extending downward from the glaciated surface, *ab*, of the rock (enlarged 14 diameters). G, glacial striae. Such striae sometimes begin abruptly and taper out in the direction of ice motion.

of past or present local or continental glaciation (Fig. 4, G). They may be present on horizontal, inclined, or vertical surfaces. On valley walls the striae are commonly inclined about parallel to the grade of the valley floor. Scratches with the same trend are said to belong to one set. When more than one distinct

set marks an outcrop, the different sets are generally the effects of the symmetrical retreat of a single ice lobe (Fig. 5). They are not likely to belong to different ice advances, because the earlier marks would almost surely have been destroyed.




FIG. 5.—Changes in the direction of striae due to change of glacial motion in the retreat of an ice lobe from *AA* to *BB*. (After T. C. Chamberlin.)

—**B.** *Glacial grooves* are in many respects similar to striae with which they are associated. They range in size from deep scratches to glacial valleys (270, G). They may be straight or sinuous, and they may be continuous for many feet. In cross section their profiles not infrequently show an angle or shoulder on each side, which divides the concavity of the groove from the convexity or broader concavity of the adjoining rock surface (Fig. 6).

—**C.** *Wind-made furrows* are not common because their origin necessarily depends upon a very constant direction of wind motion. They have been described as occurring on the crater of Mt. Pelée, where heavy dust-laden steam clouds rolled



FIG. 6.—Profile section of a grooved glacial rock surface, drawn transverse to the direction of ice motion.

over the ground down the slopes of the crater and scoured out furrows on the old lava.¹ Grooves of wind origin are short, and they soon narrow and die out to give place to others beside them. Unlike most glacial grooves they round off into the adjacent ridges.

¹ Bibliog., Hovey, E. O.

—D. The slide of a mass of rock *débris*, or of snow laden with soil and rocks, may scratch and scour a rock surface to some extent, but abrasion cannot be very deep on account of the suddenness and shortness of the action. Landslides are confined to relatively steep slopes and the scars produced are purely local. Landslide scratches trend down the slope. In the same position, high on a valley side, glacial striae would be likely to trend nearly at right angles to the slope. If scratches are still preserved on a landslide scar, the fallen *débris* below is probably still recognizable by its hummocky topography (277).

—E. Mud flows and rock glaciers resemble landslides in that they consist of rock detritus, but their motion is slower and may be continuous for many years. By the constant rubbing of the moving mass, bedrock may be scored in great U-shaped grooves sometimes many feet in depth and width. These grooves are broadly sinuous and are marked by smaller parallel furrows and scratches. They are exceedingly like glacial grooves and their discrimination may be difficult. Careful search should be made for the materials—mud flow, rock glacier *débris*, or true moraine—which did the work.

—F. *Solution grooves* are more or less parallel furrows that sometimes develop on inclined and vertical surfaces of soluble and fairly homogeneous rocks like limestone and marble. They always trend down the slope, for they are made through slow corrosion by water as it trickles down over the surface. These furrows can be distinguished from abrasion grooves because they are often very uneven along their course, they are not scratched or striated, and the confluences between them are generally narrow and sharp.

—G. In rocks having a parallel structure, for instance, strata and schists, adjacent layers may differ in their susceptibility to decomposition or to disintegration. The layers which are easily affected will be eroded away more rapidly than the others, so that the rock will become ribbed and furrowed (Fig. 7). Since layers which are highly liable to decomposition may

be very resistant to disintegration, it follows that the rib-makers in a given rock in a dry, cool climate may be the furrow-makers




FIG. 7.—Section of a ribbed rock surface. The ribs (horizontally ruled) are of calcareous shale which is here more resistant to erosion than the intervening layers of limestone.

in a climate that is moist and warm. Grooves of this class coincide with the outcropping edges of the layers. Like the solution grooves in homogeneous rocks, they are uneven along their length and they lack scratches. Their width is dependent upon the thickness of the layers.

—**H. Slickensides**, the scratches and grooves produced by faulting (188), are sometimes exposed on the earth's surface when one of the fault blocks has been removed by erosion. The fault surface on which they occur may have any position and on this surface the slickensides may lie in any direction. No rule can be laid down for their attitude. Slickensides on a given surface may be straight or they may curve, but they are always notably parallel. They may be interrupted at irregular intervals by steplike breaks (Fig. 8), with the drop always on the same side when well preserved. Fault surfaces are often polished.

In regions of glaciation slickensides may be confused with striæ. If followed along their course they will usually be found to pass into the rock where the eroded fault block has not yet been entirely removed. Striæ, if of Pleistocene or later age, are purely superficial on the bedrock. A possibility which must not




FIG. 8.—Part of a fault surface, showing vertical slickensides. The steplike breaks across the slickensided surface here indicate that the block in the figure moved up *ab* with reference to the block which has been removed *cd*. If the relative motion had been in the opposite direction, these steplike breaks would have been rubbed off.

be overlooked is that of an ancient glaciated surface which has been long concealed under solid rock and has been recently uncovered in part (10).

—**I.** By the powerful grinding action of faulting parallel grooves and ribs of considerable size may be chiselled out on the opposing rock faces of the fault.¹ When exposed by erosion these grooves must be distinguished from those of superficial origin. They are more regular than any other type of furrow. They are themselves lined with scratches, all parallel. In cross section their profiles usually display no shoulders. They trend nearly straight or in broad curves, and are not markedly serpentine. They are not limited to valley floors nor to any other topographic form. Along their length they may rise and sink, but this they do *as a group*. Individual variations are slight. Exposed fault grooves of large size are seldom seen, and where they do occur they are restricted to outcrops whose surfaces happen to coincide with the fault surface.

—**J.** Along cart paths and highways, scratches and ruts worn in low protruding rocks by the wheels of passing vehicles are sometimes mistaken for marks of glaciation. If there is doubt, comparison should be made with ledges beyond the reach of wagons, where the real striæ will be discovered if they are present.

36. Pits and Hollows.—Pits and hollows of primary origin include large and small depressions on the surfaces of lava flows, and certain fossil impressions, such as footprints, made on muds and sands while these materials were still unconsolidated. Care should be taken not to confuse with fossil impressions any of the indentations described below.

Secondary pits and hollows in rocks may be the result of abrasion or of weathering. The more common varieties are classified below.

KEY FOR THE IDENTIFICATION OF PITS AND HOLLOWES ON ROCK SURFACES

- A. Depressions definitely related to grains, pebbles, fossils, inclusions, or other bodies contained in the rock, are probably due to differential erosion. If these depressions

¹ *Bibliog.*, GREGORY, H. E.

1. Have rounded edges and smooth surfaces, and are present on smooth rock surfaces, they may be abrasion pits produced, for the most part, by wind or water (A).
2. Have sharp edges and usually rough surfaces, and are present on rocks with rough surfaces, they may be weather pits due to the solution and removal of grains, pebbles, etc. (F, I).
- B. Depressions not definitely related to grains, pebbles, etc.,
 1. If present on abraded rock surfaces, may be chatter marks, crescentic gouges (B, C), pits associated with hard obstructions (Fig. 4, D), potholes (D), or cupholes (E).
 2. If present on corroded rock surfaces, of limestone, gypsum, rock salt, etc., may be solution pits (G).
 3. When present on weathered or abraded rock surfaces, may be pits due to honeycomb weathering (H) or pits formed by organisms (I, J).

—A. Finely pitted surfaces are characteristic of wind erosion on granular rocks that are composed of minerals of different hardness. When dust or sand is blown against such a rock, the soft grains are worn away faster than the hard ones. At the same time all the edges and corners of the projecting hard grains are rounded. Thus, the surface of the rock becomes smooth to the touch, although closely indented with small rounded pits the dimensions of which depend upon the size of the eroded grains.

—B. Chatter marks and crescentic gouges¹ are indentations produced by glacial abrasion. *Chatter marks* are small dents that are found in rows of two or more, sometimes accompanying and running parallel to glacial scratches and grooves. They are produced by a rhythmic vibratory motion due to friction between the bedrock and rock fragments held in the overriding ice. In their origin they resemble the rows of dots made by drawing on a blackboard with a piece of chalk held nearly perpendicular to the board. Chatter marks are often distinctly convex on one side, and the convexity is turned in the direction from which the ice moved (Fig. 4, C).

—C. *Crescentic gouges* (Fig. 4, A, B), occasionally met with on the "upstream" or stoss slope of glaciated rocky knobs, measure from a few inches to 5 or 6 ft. from horn to horn and lie

¹ Bibliog., CHAMBERLIN, T. C., 1888, and GILBERT, G. K., 1906.²

with their length perpendicular to the adjacent striae. Like chatter marks they are found in sets of two to half a dozen or more. Their convex edges usually point in the direction in which the ice moved.

—D. Of much larger size than the depressions already noted are *potholes*. A pothole is formed by the constant swirl of an eddy which carries pebbles or sand round and round in one spot. Gradually a hole is bored downward into the rock. The sand and pebbles that served as the tools may often be found at the bottom of the depression. Whether the vortex be one in a current of wind or water or ice, the action is the same, although the rate of abrasion may vary. Potholes are most commonly of fluvial origin. Occasionally they may be observed along rocky coasts and in glaciated valleys where the topographic configuration localized eddies; but many of the depressions of this nature in glacial valleys are made by water plunging through holes in the ice. These are called "*moulins*" or "*mills*." Here the concentration of action is due, not necessarily to a constant vortex, but to the maintenance of an opening in stationary ice for a time sufficiently long. Since true potholes open upward, the analogous excavations cut by wind rarely come under the definition, for wind eddies may work in any direction. Yet the process by which the holes are carved is identical.

—E. On a small scale abrasion, combined with solution, may wear cup-shaped hollows, called *cupholes*, on the surfaces of rocks like limestone (Fig. 9, A). In a certain sense they are miniature potholes.

—F. Decomposition and solution play an important rôle in modifying rock surfaces. Their action is generally differential. Soluble substances may be leached out from rocks which as a whole do not readily decompose and cavities may then remain, which indicate by their shape the nature of the material removed. Thus, from rocks that contain cubical holes, pyrite may have been carried away. Sometimes fossils are dissolved out and their impressions are left as small cavities on the surface of the rock. Similarly, limestone pebbles in conglomerate may be dissolved

out from a shaly or sandy matrix. In moist climates basic segregations (112) are apt to decompose more rapidly than the granitic rocks in which they are contained. The hollows formed by their weathering have granular surfaces. In cases of this kind there are usually some depressions which still have a little of the original substance left in them. These should be sought in order to explain their formation.

—G. A very characteristic feature of corrosion surfaces on soluble rocks is the presence of abundant saucer-shaped pits,




FIG. 9.—Profile section through the surface of a limestone exposure, showing two varieties of solution pit (about $\frac{2}{3}$ natural size).

and this does not of necessity indicate any differential tendency in the chemical wear. Limestones and marbles may be very uniform and yet display this effect, generally on surfaces of low inclination. Where the slope is greater the pits may coalesce and become grooves (35, F). Between the hollows are sharp-edged divides (Fig. 9, B). If the divides are rounded, the corroding water probably carried some silt which did a little abrasion.

—H. On fine granular rocks such as sandy shale and sandstone, decomposition sometimes produces what is known as *fret-work* or *honeycomb weathering* (Fig. 10). At different spots on the exposure small pits arise through the decomposition of mineral grains. As these cavities grow deeper and larger and as they

become more numerous, they unite at the surface while they are still separate below. In the less resistant laminae enlargement takes place more quickly than in those more resistant.

Fretwork weathering is characteristic of the surfaces of granular rocks, such as tuffs, granitoid rocks, sandstones, and conglomerates, where these are exposed in arid climates. Under these conditions, occasional action of hydration and solution, probably occurring for the most part immediately following infrequent showers, is concentrated more and more in the pits or "niches"




FIG. 10:—Section of a specimen of sandstone exhibiting fretwork weathering. *a*, divide between two depressions; *b*, a similar divide, nearly worn away; *c*, opening into a depression behind the plane of the sketch. The bedding is horizontal. Why is there a projecting rim bordering each cavity?

as these develop. The resulting debris may be removed by wind, rain, wet-weather rills, organisms, etc. Such pits may grow to the size of caverns several yards in all three dimensions.¹

—**I.** Corrosion of rock surfaces is not restricted to sub-aerial outcrops. It has been recorded as occurring below water level in lakes. Or, again, it may go on beneath the soil where moisture rich in products derived from vegetable decay may etch a pitted or corrugated surface. Subsequently the soil may be removed by natural or artificial means and so expose the rock.

Corrosion pits are generally a fraction of an inch to a few inches across. Their interiors are often roughened by projecting insoluble grains.

—**J.** Certain molluscs dissolve out cavities in which they dwell. The holes grow larger with the growth of the animal. Their organic origin may be indicated by the presence of the animals themselves, or of the shells, in some of the chambers.

¹ *Bibliog.*, BLACKWELDER, E., 1929.

CHAPTER III

ROCK PARTICLES AND FRAGMENTS

GENERAL NATURE

37. Shape and Surface Markings.—Rocks may be broken into fragments either by forces acting within the lithosphere or by processes at the earth's surface. Sometimes the fragments, as mere products of shattering, suffer no wear, and sometimes they are rubbed or ground or pounded until their original shape is modified. According to their mode of origin, they have distinctive characters of form, surface, or composition. For example, many glaciated pebbles are striated, just as is the glaciated bedrock. They served as the tools by which the ice scratched the rock, and the tools themselves suffered abrasion in the process. It follows that if we examine the constituents of a fragmental deposit or of a consolidated fragmental rock, we may be able to discover how that material was made, for very often the deposit or rock originated under the control of the same agents which were concerned in fashioning the individual constituents. In studying solid rocks there is need to discriminate between destructional fragments of the kind just mentioned and certain other bodies which are of quite a different nature (43, C; 52).

38. Dimensions of Particles and Fragments.¹—The distinction between sand and gravel has arbitrary limits. In this book the term "sand" will be used for deposits in which the individual grains are not greater than 2.5 mm. nor less than 0.05 mm. in diameter.² When the particles are between 2.5 and 0.75 mm. the sand is coarse; when between 0.10 and 0.05 mm., it is fine

¹ Refer to Appendix IV.

² Bibliog., HATCH, F. H., and RASTALL, R. H., p. 39.

Grains smaller than 0.05 mm. belong to such materials as mud, silt, clay, and loess. Their characters will not be described here since they cannot be seen with a hand lens. Particles larger than 2.5 mm. in diameter are of gravel texture and will be discussed below under the term of *rock fragments*. *Pebbles* are rock fragments of small or moderate size which have been more or less rounded and which acquired this form by erosional processes. *Boulders* are masses larger than pebbles, but of similar shape and origin.

CHARACTERS OF ROCK PARTICLES

39. Composition.—Residual sands formed by disintegration are composed, for the most part, of the minerals present in the parent rock, for they have been subjected neither to attrition nor to decomposition on a large scale. On the other hand, sands that have been transported for a long time consist of minerals that are relatively resistant either chemically or physically or both. (Why?) Quartz is the most common ingredient of such sands, and in regions where micaceous rocks abound, muscovite and bleached biotite may be in considerable quantity. Garnet, magnetite, zircon, and rutile are also counted among the more indestructible minerals, but the last two are seldom abundant. If transportation has been comparatively short and rapid, the sand may contain mineral particles which would have been quite broken up under longer handling.

The composition of sand suggests not only the amount of transportation, but also the climate in the region where the erosion was in progress. A deposit which is rich in decomposable mineral grains is indicative of a very dry climate, and one that is strikingly lacking in such minerals points to decomposition as having been a very efficient erosional process. A high percentage of quartz indicates that the sand is a product of slow erosion in a warm, moist climate, where the more decomposable minerals had ample time to decay and pass away in solution. Feldspar is a decomposable mineral, yet it is not at all uncommon in sands of continental origin, even in moist climates. It is

fairly resistant to chemical destruction, although less so than quartz. Consequently, its presence is not to be accepted as unquestionable proof of an arid climate. On the contrary, hornblende, augite, and particularly biotite, all iron-bearing silicates which are extremely liable to decay, are good evidence for aridity, or of erosion by ice.

The nature of the parent rock is likewise indicated by the composition of the derived sand. In this respect sands that have been subjected to little transportation are most valuable. Garnet and magnetite often come from gneisses and schists; quartz and feldspar from gneisses, granites, etc.; and micas from schists and certain igneous rocks.

The significance of clastic mica in muds and mudstones may well be mentioned here. Such mica is typical of continental sediments (106). When found in pelites that seem to be of marine origin, it usually means that they were accumulated near the shore.

40. Shape.¹—Most mineral particles owe their form partly to their manner of breaking and partly to the kind of erosion which has affected them. The grains may be angular, faceted, subangular, or pitted. Their shape is seldom, in itself, a decisive criterion for the origin of the deposit in which they are found, but it is of considerable assistance. One must be careful not to draw conclusions from too brief an examination. Few fragmental deposits consist of grains derived in only one way. Wind-worn particles may be intermingled with those handled by water; and so on. It is the prevailing character of the majority of the particles that must be ascertained.

The key which is given below includes the more common varieties of broken or worn rock particles.

KEY FOR THE IDENTIFICATION OF ROCK PARTICLES

A. Grains sharply angular,

1. Consisting of volcanic glass or other volcanic material are probably volcanic sands (41, B).

¹ Bibliog., SHERZER, W. H.

2. Consisting of the mineral constituents of rocks especially susceptible to disintegration (usually rocks of relative coarse texture) are probably disintegration sands (**41, A**).
3. Present in a layer of limited thickness and consisting of fragments of the rocks on both sides of the layer, may be breccia particles (**41, D**).
- B. Grains with one or more worn or broken facets which are marked off from the surrounding surface by sharp edges,
 1. Generally associated with glaciated pebbles, in till, etc., are probably glacial faceted sand grains (**41, C**).
 2. Associated with rounded eolian sands, are probably broken or chipped wind-blown grains.
- C. Subangular grains, with edges and corners somewhat rounded may be aqueoglacial sands (**42**) or sands of the next class (D), not fully rounded.
- D. Rounded grains which, if broken, show
 1. Concentric structure on the fracture surface are probably constructional sands (**43, C**).
 2. No concentric structures on the fracture surface, and are
 - a. Above 0.75 mm. in diameter, may be eolian, marine, and fluvialile sands (**43, A**).
 - b. Below 0.75 mm. in diameter, are probably eolian sands (**43, A**).

41. Angular Particles.—**A.** Residual disintegration sands have sharp edges and corners (Fig. 11, A) because they have been detached from the bedrock along their contact surfaces with other grains and have suffered no corrosion and no rolling by wind or water. If they break up still further, minerals without cleavage, like quartz, crumble into highly irregular fragments, the micas separate into thin flakes, and most other minerals with cleavages fall into small irregular blocks faced by the cleavage planes.

—**B.** Volcanic sands (Fig. 11, B) are angular because they are largely the product of explosive shattering. They consist of chips and slivers of rock glass with here and there phenocrysts, broken or entire, and occasional pellets of glass rounded in the air by mutual attrition or by twirling, if thrown up as liquid drops.

—**C.** Ice-worn sand grains (Fig. 11, C) have faces which have been ground by glacial abrasion.

—**D.** Solid rocks are sometimes found to have been crushed by movements within the earth (**223**). The finer particles, so made, are angular or subangular.

—E. On the whole, angularity of grain signifies disruption in place or disruption followed by brief and rapid transportation. The glaciated particles noted in C, above, are an exception.

42. Subangular Particles.—If subjected to corrosion or to attrition for a sufficiently long time, angular grains may become subangular. Their edges become blunted. Aqueoglacial sands (Fig. 11, D), are commonly of this nature, for whatever angularity they may have acquired through fracture or through glacial abrasion has been modified by subsequent wear in running water. The larger grains may still show traces of the facets planed off by glacial scour.




FIG. 11.—Characteristic grains from disintegration sand (A), volcanic sand (B), glacial sand (C), aqueoglacial sand (D), eolian sand (E), river sand (F), and sand oolitic (G).

43. Rounded Particles.—A. Long handling by wind or running water produces rounded grains. This shape is typical of eolian sands (Fig. 11, E). In river and beach sands, too, the grains are usually pretty well rounded (Fig. 11, F). Particles having a diameter less than a certain quantity are apt to escape rounding because they are held in suspension as long as they are swept by a current. The size below which the grains remain angular is about 0.75 mm.

in running water and about one-fifth this amount in wind. The difference is due to the greater buoyancy of water.¹ Under special conditions marine sands may continue angular or subangular for a long while, even though they are larger than the size just noted. After the fall of the tide, they may be kept moist by capillary action between the grains. The moisture serves not only as a cushion to prevent the rubbing of the particles on one another, but also as a check to their

¹ Bibliog., GRABAU, A., pp. 61, 226; and ZIEGLER, V., p. 654.

transport and handling by wind. However, wind along low open shores soon rounds the dry grains in the upper layer of the beach, and consequently wind-worn grains are often scattered through beach deposits. Typical eolian sands occur only in desert regions. They may contain some particles which were broken or chipped by impact. As a general rule, sands that are well rounded and average considerably less than 0.75 mm. in diameter are probably of eolian origin.

—B. The student will probably have very little occasion to distinguish corroded sand grains from those mechanically rounded, since most sands are of mechanical origin. A difference may be mentioned here. Chemical agents tend to excavate small pits on the surface of a grain and the luster of the pits is like that of the whole grain. If there are indentations on abraded particles, these are the remains of the original uneven fracture, or of subsequent hard blows, and they are present merely because the particle has not been worn down enough to erase them. Rolling and repeated slight impact cooperate to fashion an evenly rounded surface, convex on all circumferences. The multitude of minute scars resulting from this sort of abrasion somewhat dull the luster of the particle, so that, in this case, the luster of remaining indentations is different from that of the grain as a whole. These features need a hand lens for their examination.

—C. Rounded sands of constructional origin (Fig. 11, G) compose oölites, pisolites, and some greensands. Cross sections of these grains show them to have a concentric structure. Further description of their characters may be found in textbooks on petrology.

CHARACTERS OF LARGER ROCK FRAGMENTS, PEBBLES, ETC.

44. Identification.—In Art. 19, pebbles and other detached rock bodies are listed principally according to their characters when seen in cross section. The following key is based almost wholly upon such features as roughness, smoothness, scratches, dents, etc., which may be observed on the surfaces of the pebbles or bodies. Reference is also made to form.

KEY FOR THE IDENTIFICATION OF ROCK FRAGMENTS¹

- A. Angular fragments, bounded by fracture surfaces, may result from various processes of weathering or of brecciation. References are given in the context (45).
- B. Faceted pebbles which have
 - 1. The facets smoothed or polished, and sometimes pitted, may be wind-worn (48).
 - 2. The facets scratched or grooved, may belong to classes noted under C below.
- C. Scratched and grooved pebbles, if
 - 1. Of various shapes (round, faceted, blunted, etc.), and with the scratches running in various directions, may be glacial pebbles (46).
 - 2. Of various shapes, and with one or more facets, each facet being local, usually separated from the adjacent surface by sharp edges, and marked by parallel scratches (running in but one direction), are probably slickensided fragments or pebbles (46).
 - 3. Elongate (sometimes spindle-shaped) or flat and sometimes bent, with the scratches or grooves running parallel to the length of the pebble, may be compressed (sheared) pebbles (51), especially if they are more or less coated with mica.
- D. Pitted or dented pebbles or fragments, if they have
 - 1. The indentations definitely related to mineral grains, may be wind-worn pebbles (48).
 - 2. The indentations not related to the mineral constituents,
 - a. These indentations usually being isolated and saucer-shaped, and generally
 - (1) Unaccompanied by fractures, may be pebbles of a soluble rock, like limestone, the indentations having been formed by solution (47).
 - (2) Accompanied by radiating fractures, may be pebbles of any sort of rock with compression dents (47).
 - b. These indentations usually being in groups converging at the blunted end of the pebble, are probably glaciated pebbles (46).
- E. Subangular pebbles are usually fragments which have not yet been fully rounded (see also B) (49).
- F. Rounded pebbles and boulders, if with
 - 1. Smooth surfaces, may be river or beach pebbles (50).
 - 2. Rough surfaces, may be pebbles or boulders of disintegration (50).

45. Angular Fragments.---At the earth's surface angular rock fragments may result from exfoliation, plucking, sapping, frost

¹ The reader's attention is called to Art. 52.

action, disruption by landslide and lightning, and by volcanic explosion. When massive rocks weather by exfoliation, relatively thin, curved, edged pieces split off. These are called *spalls* (Fig. 12). Fragments separated from the bedrock by plucking, sapping, or any of the other processes of disintegration, are bounded by surfaces of weakness (31). They are the negatives, as it were, of the outcrop surfaces produced in the same manner (34). Such fragments are generally found at the bases of cliffs where they have accumulated as slide rock in a heap or sheet called *talus*.

Landslide detritus is angular if the materials were solid bedrock before the slip. Both landslide *débris* and *talus* consist of fragments of all sizes and in both some of the fragments may have bruises or random scratches made in the downfall. The difference between the two kinds of deposit is mainly topographic (279).



FIG. 12.—Formation of a boulder of exfoliation. Part of the original surface of the rock may be seen at the extreme left. The rough edge are the scars of flakes or spalls which have split off. Two such spalls (near the upper part of the figure) are nearly detached.

Shattering of rocks by lightning has been recorded, but is very rarely seen or recognized. In mountainous districts where the work of lightning would be most effective, frost and temperature changes are by far the most active forces of rock destruction.

Other kinds of angular fragments are described elsewhere, as follows: blocks made by volcanic outburst (112, 223); intraformational fragments (94); various kinds of breccia (223).

46. Scratched, Faceted Pebbles.—Scratched, faceted pebbles are nearly always the result of glacial abrasion. They have been planed off by rubbing against bedrock while held in moving ice. Such pebbles may shift their position in the ice from time to time and thus receive several facets or "soles." Each facet is marked by striæ which run in various directions (Figs. 13, 14). In this respect they differ from detached pieces of the striated

bedrock, which are more apt to have a large majority of the scratches on only one face and, on this face, trending in one



FIG. 13.—A glacially striated pebble found by J. B. Woodworth in Pleistocene till in Gaspé, Quebec. Note the diversity in direction of the scratches.



FIG. 14.—Striated pebble with splintered or snubbed end. (Coll., J. B. Woodworth.)



FIG. 15.—Detached fragment of the striated rock floor over which glacial ice moved. Note the parallel arrangement of the striæ. The figure shows chatter marks in the deepest scratch. (Coll., J. B. Woodworth.)

direction (Fig. 15). Sometimes a pebble which was held in one position for too short a time to become faceted may be round and yet bear striæ.

Occasionally care may be necessary to discriminate between slickensided fragments and glaciated pebbles, especially in deformed rocks having relatively few pebbles in an abundant fine-grained matrix. Where surfaces of internal rock slipping have grazed a pebble, the slickensides probably continue across the pebble into the matrix. Such slickensides, like the striae on detached fragments of a glaciated rock pavement, lie parallel to one another.¹ In fault breccias the fragments may be slickensided (188).

47. Pebbles with Scars or Indentations.—A. Pebbles with concave fracture scars are as typical of ice abrasion as are striated



FIG. 16.—Limestone pebbles indented by solution while they were under compression in a conglomerate. The pits mark the spots where adjacent pebbles were in contact

pebbles. They are angular or subangular and may or may not have glacial scratches. The scars are thought to have been made by splintering or wedging of small chips from the pebble while it was pressed with great force by the ice against bedrock, or was jammed between two blocks of rock (Fig. 14). These scars should not be mistaken for the concave indentations next described.

—B. Circular or oval concave hollows may be produced, both by solution and by simple pressure unassisted by chemical processes, on the surfaces of the pebbles in a conglomerate. A solution hollow is formed where, in the compression of the rock, a small pebble is squeezed against a larger pebble. At their mutual contact the larger one is dissolved away and the smaller one is pressed into the hollow. Solution indentations

¹ For further criteria see Bibliog., WOODWORTH, J. B., 1912 (a), p. 457; and WENTWORTH, CHESTER K., 1928.

are confined for the most part to pebbles of soluble rocks like limestone (Fig. 16).

—C. Concave hollows made by compression without solution are rare. They need special conditions for their origin. The paste of the conglomerate must be relatively weak and compressible, yet it must be strong enough to prevent complete fracturing of the pebbles when the rock is subjected to stress. As in the previous case, the small pebbles indent the larger ones. If the



FIG. 17.—Wind-worn pebbles. That on the right is an einkanter; that on the left is a dreikanter.

pressure exceeds a certain quantity, variable under different conditions, the impressed pebbles crack.

Both types of indentation (B and C) interrupt the continuity of the original surface of the pebble, and in both the depth of the hollow is not more than a fraction of the diameter of the smaller pebble.

48. Polished, Faceted Pebbles.—Polished, faceted pebbles are made by wind action. They are called *glyptoliths* (γλυπτὸς, carved; λίθος, stone) or *ventifacts* (*ventus*, wind; *facere*, make). A pebble too large to be transported is worn by the impact of blown sand and dust. The side toward the prevailing wind direction is planed off and more or less polished, and if the pebble is granular, its surface is pitted. (Why?) Often there are two of three

directions from which the wind blows most of the time, so that the exposed surface of the pebble acquires two or three facets which meet in rather sharp, smoothed edges; or, several faces may be worn because the pebble falls into a new position whenever the sand has been blown out from beneath it. If there is one such edge between two distinct faces, the pebble is called an *einkanter* (one-edge); if there are three edges and three faces, it is called a *dreikanter* (three-edge); and so on (Fig. 17).

49. Subangular Pebbles.—Subangular pebbles and boulders are those which have had their edges and corners somewhat



FIG. 18.—Three building bricks in successive stages of rounding by wave erosion

rounded, but which have not yet lost all traces of their original angular character. Glacial faceted pebbles, modified by running water, are typical of eskers and kames (277) and of other aqueo-glacial deposits. Talus blocks may lose their angularity through the influence of weathering. Landslide fragments and the fragments in fault breccias sometimes have their edges blunted by rubbing during the movement.

50. Rounded Pebbles and Boulders.—Rounded pebbles and boulders are shaped by rolling or by concentric weathering. River pebbles, rolled downstream, and beach pebbles, rolled up and down the beach, are indistinguishable. Both types pass through subangular stages and finally become well rounded with

smooth surfaces, free from scratches. Soft and hard grains are planed off alike, although here and there some brittle grains may have been chipped out by hard knocks. The ultimate form depends upon the original nature of the rock fragments. Cubical blocks become spherical, while flat slabs are worn to thin, oval pebbles (Fig. 18).

Concentric, or spheroidal, weathering is a passive process by which rounded boulders of disintegration are formed. The agents



FIG. 19.—Development of boulders of disintegration. The boulder in the center of the figure is still in place. It has been formed from a joint block by the gradual removal of the surrounding rock. Other joint blocks appear in less advanced stages of disintegration (Owens Valley, Cal.). (Drawn from a photograph by J. H. Blake.)

include repeated freezing and thawing of water in the cracks and interstices of the rock and such chemical agents as carbonation, oxidation, and hydration of certain of the mineral constituents, resulting in localized expansion because the new minerals occupy more volume than the old. These agents work inward from the corners, edges, and surfaces of joint blocks. The corners wear away faster than the edges, and the edges faster than the surfaces, so that a rounded internal core at length remains (Figs. 12, 19). From this the grains come off singly or in shells or spalls. Boulders of disintegration differ from boulders of

attrition in being much weathered on the outside, and in having rough, granular surfaces (Cf. 33).

51. Elongated and Flattened Pebbles.—In metamorphic rocks pebbles and other rock fragments may have their original shapes entirely altered. Even equidimensional pebbles may be compressed in such a way that they become long, spindle-shaped rods, or they may be flattened into thin sheets. By rubbing



FIG. 20.—A pebble of quartzite elongated by compression in dynamic metamorphism. Length about 6 in.



FIG. 21.—A pebble of quartzite elongated, edged, and fluted by severe compression in dynamic metamorphism. Length about 9 in.

against adjacent pebbles, during the shearing of the rock (230), they may be slickensided, fluted, and ribbed (Figs. 20, 21).

52. Pebble-like Bodies.—Sometimes rocks contain pebble-like bodies which are really not pebbles at all. In plutonic rocks rounded or oval masses may be segregations or inclusions (112, 140). They differ in composition from the matrix which surrounds them. Other pebble-like or boulder-like forms include concretions (68), some kinds of fossils, volcanic bombs (112), and lava "pillows" (112).

CHAPTER IV

ORIGINAL SURFACE FEATURES OF SEDIMENTS

CLASSIFICATION

53. Identification of Minor Irregularities of Surface.—

During the process of construction of sedimentary deposits, there are sometimes produced certain minor irregularities of surface. These may be of considerable value in determining the origin of consolidated strata in which they may be reëxposed either in cross section or, if the rock surface happens to coincide with the original bedding surface, in their old superficial aspect. These features may be grouped according to their general appearance, as follows:

KEY FOR THE IDENTIFICATION OF MINOR SURFACE FEATURES OF UNCONSOLIDATED SEDIMENTS

- A. Ridges, or ridge-like forms, associated or not associated with depressions, if
 - 1. V-shaped in plan, measuring several feet from one to another, and if found near the upper borders of beaches, may be beach cusps (54).
 - 2. Parallel or subparallel ridges, generally between 2 and 6 or 8 in. apart, may be ripple marks (55).
 - 3. Very low ridges, somewhat irregular in form, generally less than $\frac{1}{8}$ in. high, trending along beaches, may be wave marks (56).
- B. Channel-like or groove-like forms, if
 - 1. Small channels, branching or not, trending down the slope of the beach or other deposit, may be rill marks (57).
 - 2. Cracks in mud or clay, occurring in a ramifying system, are probably sun cracks (58).
 - 3. Short, shallow, gashlike openings in clay or mud, may be frost marks (61).
 - 4. Resembling footprints, may be fossil trails (62).
- C. Shallow depressions, if present
 - 1. As scattered circular or nearly circular, saucer-shaped hollows, may be rain prints (59), spray imprints (59), or bubble impressions (60).
 - 2. In series, may be fossil footprints (62).

DESCRIPTION AND EXPLANATION

54. Beach Cusps.—Along lake and sea beaches, particularly the latter, triangular ridges or cusps are sometimes found at regular intervals of 10 to 40 ft. or more (Fig. 22). “When most typically developed the beach cusp has the form of an isosceles triangle with its base parallel to the beach, but at its upper edge, and its apex near the water.”¹ According to Johnson, beach cusps are formed through “selective erosion by the swash” which constructs “shallow troughs of approximately uniform breadth,” beginning with “initial, irregular




FIG. 22.—Plan of beach cusps. The cusps point down the beach

depressions in the beach.”² Their ultimate size and spacing are proportional to the size of the waves.

55. Ripple Marks.—Ripple marks,³ confined for the most part to coarse and fine sands, may be formed by water waves or by currents of wind or water. Current-built ripple marks are sometimes called *current marks*.

Wave-made ripple marks are common on beaches. They are symmetrical in cross section, having equal slopes on each side of the crest line. While in process of formation they are practically stationary, and, if they are the product of a uniform swell in relatively quiet water, their crests are apt to be sharp and the intervening troughs are rounded (Fig. 23, A). However, by slight changes in the strength of the waves or by a decrease in the resulting agitation of the water, the crests are soon rounded off (Fig. 23, B). Indeed, the rounding may proceed to such an extent, and the sand which has been removed

¹ Bibliog., GRABAU, A., p. 706.

² Bibliog., JOHNSON, D. W., p. 620.

³ Bibliog., BUCHER, W. H., 1919; and TWENHOFEL, W. H., 1926, pp. 451, *et seq.*

from the crests may so far fill the troughs, that the system of ripples becomes a series of alternating flattened ridges and V-shaped depressions (Fig. 23, C). Rounded crests and troughs are most often found. The larger grains lodge in the troughs and the small ones form the crests. Mica flakes settle in the troughs, or on the front slopes (Cf. 97).




FIG. 23.—Transverse profile sections of wave-made ripple marks.

Current ripple marks, whether made by wind or water, are unsymmetrical in cross section (Fig. 24). One slope is steeper and shorter than the other, and the short slope is always inclined in the direction in which the current is moving. Troughs and crests are both rounded. The sand particles are swept




FIG. 24.—Transverse profile section of current-made ripple marks. The current flowed in the direction of the arrow.

up the long slope and are dumped over the crest down the steep slope. On account of this migration of particles, the whole system of ripples advances slowly in the same direction as the current. Ripple marks may be made by wind on slopes inclined as steeply as sand will stand (246), and their trend may be in any direction on such a slope; but ripples formed by

water are seldom observed on surfaces that slope more than 5° or 6° . In eolian ripple marks the coarse grains are on the crests and the finer ones are in the troughs. In water current-made ripples the fine grains are on the crests and the coarse ones are in the troughs and on the short, steep slopes of the ridges (Cf. 97). The span between adjacent crests of a ripple system is rarely more than a few inches.

56. Wave Marks.—Wave marks (also called *swash marks*) are very low, narrow, wavy ridges to be seen on sand beaches.




FIG. 25.—Plan of wave marks on a sea beach. The land is above, and the sea below, the figure, as drawn.

They are seldom over $\frac{1}{16}$ in. high and $\frac{1}{8}$ in. wide. Each is made by the swash of water that runs up the beach after the breaking of a wave. As the tide goes down, every swash more or less destroys the earlier wave marks, and builds one of its own, so that it is common to find wave marks cutting into those next higher on the beach (Fig. 25). This relation may possibly be of some use in showing in which direction the sea lay when sediments, now consolidated, were deposited.

57. Rill Marks.—The word “rill mark” has been applied to three kinds of structure. (1) After the swash of a wave up the beach, the returning water may scour little channels in the sand, which unite in trunk channels, and these again join with others, like a miniature river system. In this case each set of rill channels branches up the beach (Fig. 26, A, B). (2)

Small streams that debouch on sandy or clayey flats sometimes divide and may branch many times before the water finally runs off or passes into the ground. The channels or rill marks of



FIG. 26.—Types of rill marks. In each case the water flowed in a direction from top to bottom of the diagram.

this type branch *down* the slope (Fig. 26, C). They resemble the much larger channels made by the distributaries on deltas.

(3) Water flowing down a sandy beach scours a small channel on each side of such an obstruction as a half-buried pebble or shell (Fig. 26, D-F) and the two channels generally unite in a short gully just below the obstruction. On the upstream side a low ridge may be built. This third kind of rill mark is evidently an index to the direction in which the current flowed. Of the three varieties the second is most apt to be preserved.




FIG. 27.—Sun-cracked clay as seen in plan. The shrinkage of the clay has exposed an underlying bed of sand (stippled) in the cracks. (Cf Fig. 28.)

53. Sun Cracks.—When dried under the sun's rays for a sufficiently long time, mud and clay shrink and crack in a network of fissures which inclose polygonal areas (Fig. 27). These fissures are called *sun cracks*, *mud cracks*, or *desiccation fissures*. In cross section they may be wedge shaped, thinning out downward, or they may have parallel walls (Fig. 28). They may be as

much as several inches wide at the top and 10 ft. deep,¹ but they are generally smaller. Their best development is found in

¹ Bibliog., GRABAU, A., p. 709.

localities where long exposure and a dry, warm climate are possible conditions. Sun cracks are therefore most characteristic of playas and the flood plains of large rivers in semiarid and arid regions. They may also be found on exposed, low, shelving




FIG. 28.—Sun cracks in section. A, sun-cracked clay layer above a bed of sand. The sand is exposed in the cracks. (Cf. Fig. 27.) The clay chips have curled a little at their edges. B, sun-cracked clay, the cracks tapering out downward.

shores of lakes in seasons of low water, and, more rarely, on tidal mud flats. Locally they may be seen in the bed of any drying mud puddle. They are essentially continental in origin




FIG. 29.—Rain prints in clay. (About $\frac{3}{8}$ natural size.)

and always indicate that the water in which the mud or clay accumulated was relatively shallow¹ (88).

59. Rain Prints.—Clays, muds, and fine sands may preserve the impressions of rain drops. Each imprint is a shallow circular hollow with a very slight encircling ridge which was raised by the

¹ Bibliog., BARRELL, J., 1903, p. 524.

impact of the drop (Fig. 29). If there was no wind during the shower, the rim is of approximately equal height all round each impression; but if the rain fell obliquely, the part of the rim on the lee side of the hollow is higher (Fig. 30). Rain prints are especially characteristic of continental mud deposits. Spray imprints, from the splash of breakers, may be formed on beaches.




FIG 30.—Profile sections across rain prints formed during a shower (A) when there was no wind, and (B) when the wind was blowing from left to right.

60. Bubble Impressions.—Impressions made by bubbles of gas or air rising* to the surface of mud flats, marsh deposits, beaches following the retreat of waves, and the muddy or fine sandy bottoms of water bodies, may very closely resemble rain imprints. Bubble impressions are circular depressions of small size, which, unlike rain imprints, are more likely to be without marginal rims than with

such rims.

61. Frost Marks.—Frost as well as rain may leave its vestiges. When moisture in mud or clay freezes, it forms bladed and branching crystals of ice, casts of which remain after the crystals have melted and the water has passed away. Under the conditions for the perservation of mud cracks, rain prints, etc., frost marks may become lithified.

62. Animal Tracks.—Sometimes terrestrial animals leave records of their existence in footprints and trails in fine-grained sediments, particularly in clays of playas and river flood plains. If these impressions are left on marine sand or mud at low tide, they are generally, though not always, washed away by the next incoming tide. Most tracks and burrows preserved on the borders of lakes and seas are those of aquatic organisms. Depressions of various kinds, particularly those due to differential weathering of inclusions, segregations, pebbles, or other such bodies, are not infrequently mistaken for footprints (see Art. 10 for the discrimination between superficial and structural features).

CHAPTER V

ORIGINAL STRUCTURES AND STRUCTURAL RELATIONS OF SEDIMENTARY ROCKS

STRATIFICATION

63. Bedding in Mechanical Deposits.—Mechanical deposits consist of the fragments of preëxisting rocks. If such fragments are transported prior to their accumulation, the agent that carries them may have the power of separating the lighter ones




FIG. 31.—Bedding consisting of layers of sand and gravel. The thick sand bed in the lower half of the figure was somewhat eroded by the stream that deposited the overlying layer of gravel. (Length about 20 ft.)

from those which are heavier. This process is called *sorting*. It is characteristic of handling by wind and by running water. As long as the transporting current is weak, it moves only light particles and these are somewhere spread out as a fine-grained layer. If the current becomes stronger, it may bear heavier

fragments and may distribute them as a coarser layer above the earlier, finer materials. Thus, by variations in the efficiency of the transporting agent, a deposit may come to have a layered structure, known as *bedding* or *stratification* (Fig. 31). The *beds* or *strata* (sing., *stratum*), as the layers are called,¹ may differ from one another either: (1) in texture, that is, in the size of their constituent particles or fragments; or (2) in composition, since variation in weight may be due to differences in specific gravity, a property closely related to chemical composition; or (3) in both texture and composition. Evidently, then, bedding in a deposit is a proof of changing conditions during accumulation.

64. Bedding in Chemical and Organic Deposits.—In chemical and organic deposits, likewise, bedding indicates that the conditions of accumulation were not uniform. In superficial chemical deposits (salt, gypsum, sodium carbonate, bog iron ore, etc.), bedding may be produced, during sedimentation, by changes in the chemical substance precipitated or by variations in the quantity of contained chemical or mechanical impurities. These changes may owe their origin to oscillations in weather or climate.

65. Absence of Bedding in Sedimentary Deposits.—Provided we accept the statement that bedding is a result of changing conditions, then absence of bedding, or perfectly uniform character, is what might be expected in deposits accumulated under very uniform conditions. However, there are other explanations for this feature. The several important causes for such absence of bedding in a sedimentary deposit may be summarized as follows: (1) the rate of accumulation may have been too rapid for sorting; (2) the transporting agent, by its nature, may have lacked the power of sorting; (3) the method of accumulation may have been unadapted to sorting; (4) the materials supplied may have been too uniform in character; (5) slumping of the materials after their deposition may have destroyed an original bedded structure.

In the sudden fall and quick heaping up of landslide debris there is no chance for sorting. Talus is practically free from

¹ Very thin beds are usually termed *laminæ* (sing., *lamina*).

bedding, although there may be a tendency for the larger blocks to roll to the base of the slope. The slow accumulation of materials by overriding ice (drumlins, etc.), the gradual lowering of englacial and supraglacial débris in the melting of a stagnant glacier, and the falling of rock particles and fragments of all sizes from ice walls or from the ice front—these are all processes which are not accompanied by sorting, provided water has no share in the deposition. Such deposits, of glacial origin, are



FIG. 32.—Section in till. Note entire absence of bedding. The hammer handle is about 15 in. long. (Photo by R. W. Sayles.)

called *till* (Fig. 32). Till may be defined as glacial material which shows no bedding, or, at best, bedding of very obscure and irregular character. Even in water-laid materials sedimentation may be too rapid for sorting. Thus, alluvial cone gravels at the base of a steep mountain range may have very rude bedding and they may even closely resemble till, so poorly defined are the strata. Likewise, the gravels of eskers and kames are rarely well stratified, because their formation is rapid, débris of all sizes falls out from the supporting ice walls, and the beds, such as they are, are obscured or destroyed by slumping after the supporting ice

is removed by melting. Absence of bedding in coarse deposits of water-worn materials is sometimes called *pell-mell structure*.

In fine sediments absence of stratification indicates very uniform conditions of deposition, that is to say, there was probably very little action of waves or of currents to modify the process. This massive structure may be found sometimes in dust deposits (loess), in quiet water deposits, and in chemical and organic deposits.



FIG. 33.—Section of a basalt flow resting on alluvial cone gravels, as seen on the wall of a small canyon. The contact runs from left to right near the middle of the figure. The lava is vesicular near its upper surface and less so near its lower surface, and is compact in its middle portion. It is partly covered by later river-laid gravels, not shown. Note the rude hexagonal columnar jointing. (Owens Valley, Cal.)

66. Interstratification of Materials of Diverse Origin.—If one carries to an extreme the idea of changing conditions as related to stratification, one can easily understand how mechanical and chemical deposits, chemical and organic deposits, and other rock materials which are formed at the earth's surface, may be interstratified. Good examples of this phenomenon are: (1) the interstratification of salt and gypsum with layers of mud and sand in the basins of salt lakes which have suffered considerable variations in depth and salinity; (2) the interstratification of peat with clay or sand; (3) the interstratification of bedded with unbedded

deposits, such as aqueoglacial sands and gravels with till (76); and (4) the interstratification of lava flows or pyroclastic debris with materials derived by ordinary processes of erosion (Fig. 33).

67. Pseudostratification.—Occasionally till deposits which have been overridden by ice (drumlins, etc.) exhibit a structure concentric with their surfaces and somewhat resembling stratification. This is not true bedding for it is not due to sorting. It is caused in part by the plastering of layer on layer by the ice and in part by shearing of the till by the great pressure of the ice.

The student should guard against confusing foliation in metamorphosed rocks (227) and sheet jointing in some eruptive rocks (216) with stratification. Both of these structures are of secondary origin (see also Art. 97).

CONSOLIDATION

68. Consolidation of Mechanical Sediments.—Mud, sand, and gravel are unconsolidated mechanical sediments. Under certain conditions these may become mudstone, sandstone, and conglomerate, respectively. In like manner all fragmentals have their consolidated equivalents. Peat may become coal; till may become tillite. There are several ways in which consolidation may be brought about, and, while it is generally effected at considerable depths within the lithosphere, it may occur at the earth's surface. For instance, the baking of clay under the sun's hot rays is a surface phenomenon, but this kind of consolidation is only partial and the dried clay would hardly be called a rock in the popular sense of the word. Another example is that of the coquina, or shell rock, of Florida. This is a sandstone composed of shell and coral fragments which have been heaped together by wind and water. The process of solidification is thought to be going on at present. Rain water, descending through the deposit, dissolves lime carbonate from the particles and redeposits it a little lower down as a binder between the grains. Occasionally the same kind of thing may be seen in the case of ordinary sands or gravels where the fragments contain abundant iron-bearing minerals. The descending waters

decompose these minerals and redeposit the iron, in the form of limonite (iron rust), as a cement. Superficial consolidation is generally accomplished by one of these two methods, namely, by drying or by the introduction of a cement.

At greater depths consolidation by cementation is a very common process, for the chemical activity of interstitial water increases with increment of temperature, and temperature increases with depth.¹ The weight of the overlying burden assists, too, for pressure is an aid to consolidation. In the formation of coal, compression may predominate as the cause of consolidation. In clay rocks the crystallization of original colloidal matter may cause cementation. Without going further into details, we may conclude that the most important difference between consolidated and unconsolidated mechanical sediments lies in the presence of a cement in the former and its absence in the latter. Like all rules, however, this one has its exceptions.

The cement may have been brought in from without or, more often, it has been derived within the deposit. The four most common binding substances are hematite (Fe_2O_3), limonite ($2\text{Fe}_2\text{O}_3 \cdot 3\text{H}_2\text{O}$), calcite (CaCO_3) and silica (SiO_2). Hematite is red. It is the chief binder in many red sandstones. Limonite is yellow, buff, or brown, and is the cement in brown sandstones. Calcite, colorless or white, may be detected by testing with dilute HCl. Silica, best recognized by means of a polarizing microscope, is very hard and is often the cement in extremely hard sedimentary rocks, such as quartzite.

Occasionally evidences are found of cementation which has been concentrated about such objects as fossil shells, leaves, etc., in a sedimentary accumulation. Each fossil thus becomes surrounded by a jacket of cemented sediments, a jacket which thickens as long as cementation continues. If the unconsolidated sedimentary matrix be removed, these coated bodies, or *concretions*, are found to be of various shapes. Some are spherical, some ovoid, some disc-shaped, and some are very irregular if two or more have become attached in their growth.

¹ See footnote, p. 65.

Fossils are not always found in the hearts of concretions. If chemical deposition once begins at any point, the minute portion already crystallized may stimulate further deposition about itself. The matrix is not always unconsolidated; it is merely less firmly consolidated than the concretions. Concretions may originate, also, by the localized deposition of substances which make room for themselves by actually forcing aside the surrounding rock.

By differential weathering concretions may be loosened from their matrix and accumulated as a residual gravel. They should not be mistaken for true pebbles.

69. Consolidation of Chemical Sediments.—Chemical sediments do not undergo the same type of lithification as do fragmental sediments. Many chemical deposits are precipitated in the crystalline condition, and the resulting crystalline aggregate, if pure, is nearly as hard as the mineral composing it. Abundant impurities may weaken the adhesive properties of such a rock. In other cases the chemical sediment accumulates in a colloidal state and subsequently hardens by a gradual loss of moisture, or, sometimes, by ultimate crystallization. Bog iron ore is a rock probably consolidated from a colloidal condition by loss of water.

70. Consolidation of Organic Sediments.—With respect to their consolidation deposits resulting directly or indirectly from organic processes may be regarded as chemical or mechanical. Some of these sediments, like the unbroken central portions of coral reefs, are precipitated in solid form by processes which are as truly chemical as they are organic. Others, such as certain kinds of coal and the coral sand rock above described, are accumulations of plant debris or of the fragments of animal skeletons, and these, therefore, are mechanical. Their consolidation is accomplished by one or more of the methods described in Art. 68.

71. Porosity and Permeability of Sediments.—All sedimentary materials contain small open spaces which are referred to as *pores* or *voids*. These pores are particularly conspicuous in

coarse fragmental deposits and in some dolomitic limestones.¹ The *porosity* of a rock is the percentage volume of the total pore space in a given volume of the rock. This is usually determined by measuring the quantity of water that a sample of the rock will contain. Thus, if 1 cu. ft. of sandstone, when saturated, holds $\frac{1}{4}$ cu. ft. of water, its porosity is $\frac{1}{4}$, or 25 per cent.

Theoretically, on the assumption that all the grains of a mass of sand are spherical, are of uniform size, and are touching one another, the maximum porosity possible is 47.64 per cent and




FIG. 34.—A. Open arrangement of spherical grains. The centres of the grains in each overlying layer would be directly over the centres of the grains below. The porosity is 47.64 per cent.

B. Close arrangement of spherical grains. In each layer the centres of the grains are above the centres of the open spaces in the next underlying layer, as indicated by the dashed circles. The porosity is 25.95 per cent.

the minimum is 25.95 per cent (Fig. 34). Under these conditions, the size of the grains has no effect on the total pore space, provided the grains are arranged in the same way. In other words, the porosity of a gravel composed of essentially spherical pebbles 2 in. in diameter is practically the same as the porosity of a very fine silt composed of minute spherical particles, although the *size* of the pores, of course, is very different in the two cases.

Variations in the shape of the grains cause only slight differences in the porosity of the rock.

On the other hand, great variation in porosity results from an intermixture of particles of different sizes, for the smaller

¹ Alteration of calcite to dolomite involves a contraction of 12.3 per cent.

grains partly fill the pores between the larger grains. For this reason, since sands and gravels are nearly always composed of large and small particles intermingled, the porosity of these materials is ordinarily less than that of very fine muds and silts in which there is not the same opportunity for great range of size in the constituents.

In loose mechanical sediments, such as sands and gravels, pores are freely communicating, but, in consolidated rocks, they are partly closed, and the minute passages between the grains may be very tortuous, usually on account of the compression and partial cementation of the rock. The relative ease with which such fluids as water, oil, and gas can move through these passages is an index of the *permeability* of the rock.¹ Permeability is high where the pore spaces are large and numerous and where they are freely intercommunicating. Also, a rock with pore spaces of given size, abundance, and continuity is more permeable by fluids of low than of high viscosity. Permeability is sometimes called *tightness*. An oil-bearing rock is *tight* if it yields its oil with difficulty, and it is *open* if it yields its oil freely.

The finer the rock and, therefore, the smaller the pores, the more do friction and other forces serve to retard the movement of fluids through rock materials and to reduce or check the yield of fluids from rock materials. Thus, although a clay may perhaps contain more water than a gravel, both being saturated, the gravel will yield its water very much more readily and more abundantly than the clay, other conditions being equal. The gravel is the more permeable.

72. Compression of Sediments.—During long-continued sedimentation in a region, the strata already laid down are covered by an increasingly thick and heavy overburden which tends to compress them by its weight. The compression, although produced by a force acting downward, is undoubtedly transmitted in all directions, so that the sedimentary material becomes more compact not only across, but also along, the bedding.

¹ Permeability is expressed in units called millidarcies (sing., millidarcy).

As proof of this compression in sediments, we may mention the bending of laminae about inclosed pebbles or other resistant bodies (Fig. 35), the flattening of fossils, and, possibly, the presence of cleavage in some shale formations which have not been folded or otherwise deformed.

The reduction in volume, consequent upon the compression, may be accomplished by: (1) partial squeezing out of inter-




FIG. 35.—Section of laminated slate, showing how the laminae have been bent against the pebble in the compression of the rock. The presence of an isolated pebble in deep-water sediments like this suggests that it was rafted out and dropped.

stitial water or other fluids; (2) closer crowding of the constituent particles; (3) bending and granulation of particles; (4) rearrangement of grains by crystal gliding; and, (5) chemical readjustment, as seen in the recrystallization of schists and gneisses (224). The first two methods, just listed, are especially effective in unconsolidated deposits and are more or less associated

with the lithification of many rocks. The last three methods are more characteristic of changes within rocks already solid, such changes as occur in the metamorphism of rocks (Chapter IX).

Sedimentary materials may vary greatly in their compressibility. Sandstones, limestones, metamorphic and igneous rocks, are practically incompressible. Most of the compaction occurring in sandstones and limestones takes place before cementation has progressed far. Mud, clay, shale, and similar materials undergo considerable reduction in volume, which may be over 40 per cent of the original volume. Athy states that there is, in pure shales, definite relation between density (degree of compaction) and depth (pressure) of burial. His studies reveal in such rocks a compaction of roughly 25 per cent at 1,000 ft., 35 per cent at 2,000 ft., 40 per cent at 3,000 ft., and 45 per cent at 5,000 ft.¹ (161, ¶2). We may add here that the fluids that are present underground in the pores of rocks, such as gas, oil, and even water,

¹ Bibliog., TEAS, L. P., 1923; HEDBERG, HOLLIS D., 1926; ATHY, L. F., 1929 (a); and NEVIN, C. M., and SHERRILL, R. E., 1929. •

are compressed to a degree dependent on depth and several other factors.¹

MODES OF OCCURRENCE

73. Primary Dip.—During accumulation the attitude assumed by strata depends upon the attitude of the constructional surface upon which they are being deposited. Alluvial cone gravels are laid down in rude beds approximately parallel to the surface of the cone (260). Sand blown over the crest of a dune falls on the steep lee slope where it is built up layer on layer. If a hole be dug in a beach, the strata will often be seen to dip seaward parallel to the surface of the beach. Scores of other examples might be cited. The vertical angle between such an inclined layer and the horizontal may be called the *primary dip* or *original*

¹ Experimental data indicate that pure water, if subjected to increasing pressures up to 500 atm. (7,350 lb. per square inch) at temperatures from 32° up to at least as high as 176°F., is compressible by roughly 2.1 per cent of its volume at atmospheric pressure and at the designated temperature. At atmospheric pressure, pure water expands about 2.87 per cent of its volume at 32°F. in being heated from 32° to 176°F.; and, at 500 atm., it expands 3.11 per cent of its volume at 32° in being heated from 32° to 176°F. Water containing salt (NaCl) or other impurities in solution is less compressible than pure water, and the degree of its compressibility decreases with increase in its content of solute. Similarly, saline waters, when heated, are subject to less expansion than pure water under like conditions.

These are statements of interest to geologists in view of the facts (1) that there is a general increase of temperature with depth (Art. 432), which, though extremely variable, averages roughly 1°F. for every 50 to 60 ft. of depth in regions of thick sedimentary prisms; (2) that underground waters reveal an increase in content of NaCl and, to a less extent, of other solutes, with depth, the rate being variable but amounting to an average of at least 16,000 to 18,000 parts of solute per million parts of water (by weight) for each 1,000 ft. of depth in regions underlain by thick sedimentary prisms, like the Gulf Coastal Plain; and (3) that hydrostatic pressure in the lithosphere increases downward at a rate varying from 0.46 lb. per square inch for pure water to 0.502 lb. per square inch for water containing 250,000 parts per million of solids in solution.

References to statistical data may be found in the *Jour. Am. Chem. Soc.*, vol. LIII, p. 3783, 1931, and in *International Critical Tables*, vol. III, p. 40, McGraw-Hill Book Company, Inc., 1928.

dip of the layer. It is also referred to as a *constructional* or *depositional gradient*,¹ particularly as applied to the larger formations such as alluvial plain deposits, deltas, coastal plain formations, etc.

Primary dip, being immediately dependent upon constructional slopes, can never have angles greater than the maximum angle of repose for unconsolidated materials (246). Its values will range for the most part between 30° or 35° and 0°.

Probably a majority of strata of one kind or another are built with a primary dip; but the deeper offshore water deposits of oceans and lakes, the slowly settling dust accumulations of eolian origin, interbedded chemical and mechanical deposits of saline lakes, and a few other types of sediment, are spread out with nearly or quite horizontal attitude.

74. Conformity and Its Significance.—When sediments are being laid down, deposition may be continuous for long periods of time, and yet, because of variations in the strength of the transporting agent or in the nature of the depositing agent, the strata may differ, as we have seen, in texture and composition (63). Such beds, formed one above another, in uninterrupted sequence, are usually parallel to one another. Any stratum in the series is *conformable* with the beds above and below it. This relation between the beds is called *conformity*.

While conformity is often the result of uninterrupted deposition, it is not always so. Sedimentation may entirely cease for a few hours or days or even for several months or years, and, provided the part of the deposit already laid down suffers no kind of erosion or deformation, renewed sedimentation will be in conformity with the older beds. Within the formation evidence of a lapse of time of this sort would rarely be discernible. The essential fact to remember is, that *in a conformable series, there has been no interval of erosion to interrupt the accumulation of the strata.*

¹ "Initial dip," a term which properly should be synonymous with "original dip," was unfortunately applied by Bailey Willis to "original dip plus a certain secondary angle added by settling or tilting of the strata" (161). •

75. Relations between Unconsolidated Transported Deposits and Bedrock; Regional Unconformity.—The upper surface of the bedrock beneath any transported deposit is a sharply defined boundary between the rock and the deposit. It is usually an old destructional surface which is now protected to a large extent from further erosion by its cover of sediments. Such a buried surface of erosion is called a *surface of unconformity*. Furthermore, it is termed *regional unconformity* because the surface is of wide extent.




FIG. 36.—Types of unconformity. A, unconformity between granite (below) and sediments (above); B, disconformity; C, D, nonconformity or angular unconformity; in D the underlying rocks are schists; E, unconformity between limestone and the residual product of its decomposition; F, blended unconformity between granite and the residual product of its disintegration.

Four types of regional unconformity are possible. In each the rock upon which the surface was worn was consolidated at the time of its erosion.¹ This rock, in any given locality, may be: (1) a plutonic rock, such as granite or diorite (Fig. 36, A); (2) a sedimentary formation that has undergone consolidation but no folding (Fig. 36, B); (3) a folded series of consolidated sediments (Fig. 36, C); or (4) a body of regionally metamorphosed rocks (Fig. 36, D). Granite and other plutonic rocks are usually injected into some older *country rock* at considerable depth, and at the time of intrusion the country rock forms a thick roof over

¹ Regional unconformity between two unconsolidated sedimentary formations is possible, although uncommon. The best example is that of the superposition of the deposits laid down by continental ice sheets in two distinct glacial epochs (111).

the magma (112). Extensive consolidation of sediments rarely occurs except after deep burial. Finally, folding on a large scale and regional metamorphism are processes which are limited to depths of several hundreds or thousands of feet below the earth's surface. As each of these four types of rock requires a thick cover for the origin of its existing characters, this cover in each case must have been removed down to the level of the present surface of unconformity. Erosion of so much material, most of which was probably hard rock, takes a long time. *Regional unconformity, therefore, represents a long period of erosion.*

Two special cases of regional unconformity are mentioned above as existing between stratified formations. (1) Stratified rock which is essentially horizontal, never having suffered deformation, may be eroded and overlain by sediments with their bedding parallel to the strata beneath them. This relation is called *parallel unconformity* or *disconformity* (Fig. 36, B). (2) On the other hand, if the older formation was tilted or folded before its erosion, there will be an angle between the strata of the two series. This relation is *angular unconformity* or *non-conformity* (Fig. 36, C). The angle may vary from place to place. The younger series will truncate the edges of the older series.

In the deposit above a regional unconformity are often found pebbles, fragments, or grains of the underlying bedrock. These have usually been transported some distance and they must not be regarded as having been derived necessarily from that part of the bedrock which is just below them. By the nature of the particles and fragments much can be learned of the depositing agent (Chapter III). If the unconsolidated sediments can be removed, the exposed surface of the bedrock may exhibit features which will indicate the agent of erosion (see Chapter II). Very often by such means deposition of the younger formation and erosion of the older rock will be found to have been performed by the same agent, the erosion antedating the sedimentation.

As examples of partially developed regional unconformity between unconsolidated deposits and bedrock the following may

be cited: (1) river gravels on a rock floor formerly channelled out by the river; (2) eolian sands resting on wind-carved rock surfaces of desert regions; (3) glacial wash and till on glaciated bedrock; (4) beach gravels and sands upon a wave-cut bench (256).

76. Relations between Unconsolidated Residual Deposits and Bedrock; Regional Unconformity.—In regions where decomposition prevails the residual deposits sometimes consist of substances which were contained in the bedrock and which cannot be removed in solution. Terra rossa, a red clay derived from limestone, is an example. An accumulation of this sort gradually thickens as a layer that covers and conceals the remaining bedrock (Fig. 36, E). The contact surface, or surface of unconformity, between the two is generally pretty sharp and, if artificially exposed, may exhibit superficial features of corrosive origin, for it is chiefly on this buried surface that the rock has been and still is undergoing chemical erosion.

Residual gravels and sands originating through disintegration grade downward into the rock from which they were derived (Fig. 36, F). If they are later overlain by other sediments and so become the basal portion of a deposit of some thickness, the relations between this sedimentary formation and the underlying bedrock are certainly those of regional unconformity; yet, in this case, there is no distinct *surface* of separation; there is no surface of unconformity. This might be called *blended unconformity*.

77. Regional Unconformity in Bedrock.—When sediments become consolidated, all the relations of unconformity are preserved. There are then two rock formations separated by the surface of unconformity. At least four distinct events are represented: (1) the origin of the older, subjacent formation; (2) the erosion of this body of rock down to the level of the surface of unconformity; (3) the origin of the younger, overlying formation; (4) sufficient erosion of this later series to bring evidence for the unconformity within the zone of observation. The old formation, as stated in the preceding articles, may consist of igneous or sedimentary rocks, metamorphosed or not, but the

new formation can consist only of rocks which originate on the earth's surface (sedimentary or effusive). If the lower part of this younger formation consists of conglomerate or sandstone made of fragments of the older formation, it is called a *basal conglomerate* or *basal sandstone*. With a large percentage of feldspar it is a *basal arkose*.

For the methods of studying regional unconformity, see Art. 107.

78. Overlap; Transgression and Regression of Sediments.—The relations of regional unconformity show that a sedimentary formation is generally initiated by the accumulation of materials on an old erosion surface. It is hardly conceivable that the basal sediments of such a formation could have been laid down simultaneously throughout their extent. We must believe that deposition commenced in one or more restricted, but favorable spots and that the sediments, as they grew thicker and thicker, spread laterally and encroached upon the domain of erosion. In so doing, they *overlapped* the edges of the strata already formed.

Two kinds of overlap are recognized: the transgressive and the regressive. Each may be marine or nonmarine. *Transgressive overlap* may best be illustrated by the case in which the sea is advancing, or *transgressing*, upon a low shelving land mass (Fig. 37, A). At the shore line sand and pebbles accumulate. Their composition and texture depend upon the nature of the rocks of the invaded land area and upon the kind and degree of weathering to which these rocks may have been exposed. Away from the land, beyond the beach sands, are muds, and again beyond these muds there may be organic oozes on the sea floor. These three phases, the sandy, the muddy, and the limy, extend along the coast in roughly parallel belts. This mode of distribution has many exceptions and irregularities, but in a broad way it generally holds true.

As the sea encroaches on the land, the relative positions of these three types of deposit remain more or less constant and the beach sands and pebbles are laid down upon the old erosion




FIG. 37.—A, marine transgressive overlap; lines parallel to the sea floor are called *time lines* (*ab*), for they run through materials deposited contemporaneously; lines essentially parallel to the gravel, sand, and mud deposits are called *formation lines* (*cd*). B, transgressive overlap resulting from the upbuilding of an alluvial cone. C, marine regressive overlap; *ab*, formation line; *cb*, time line. D, lake regressive overlap; the lake floor muds (black) are gradually covered by coarser sediments. (Cf. Fig. 47.)

surface; but the mud comes to overlie the sand deposited at an earlier date, and the ooze overlies an older portion of the mud body. The mud has lapped over the sand, and the ooze, similarly, has lapped over the mud. This is *marine transgressive overlap*. A vertical columnar section through the formation displays *finer clastics over coarser clastics*, or *deep-water sediments over shallow-water sediments* (Fig. 38, A).

Another type of transgressive overlap is that resulting from piedmont deposition by rivers. In the growth of an alluvial cone, the sediments are carried farther and farther out on to the plain, so that they overlap the lower edges of the older strata. Here the overlap is away from the source of supply, whereas in the marine type it is toward the source. To a less extent there is also a headward overlap at the upper margin of the cone where the materials are heaped up against the flank of the range (Fig. 37, B).

Marine regressive overlap (Fig. 37, C) is produced where the sea recedes (regresses) from the land, *i.e.*, when sea level falls. By this process the beach zone migrates out over earlier offshore muds, and at their seaward ends these mud beds overlap the older oozes. In a vertical columnar section, *coarser clastics overlie finer clastics*, or *shallow-water sediments overlie deep-water sediments* (Fig. 38, B). Actual lowering of sea level is not necessary for the origin of marine regressive overlap, for a similar regressive section may be produced if the sea level is stationary and there is a sufficient supply of sediments, or even if sea level is rising, provided the rate of supply exceeds the rate of subsidence of the land.

Lake regressive overlap is very much like marine regressive overlap. Feeding streams constantly tend to fill a lake, so that the shore sands and pebbles are forced to encroach upon the lake-floor muds. A vertical section through a choked lake




FIG. 38.—Ideal sections to illustrate the sequence of deposits laid down (A) in a transgressing sea, and (B) in a regressing sea.

exhibits *coarser sediments over finer sediments*. This is often called the *normal lake succession* (Fig. 37, D).

Different types of overlap may be combined in the same stratigraphic section. Thus, the sea may have advanced on the land and then receded, so that regressive overlap relations are found above those of transgression, and this alternation may be repeated several times (Fig. 39). Again, marine overlap may be replaced by nonmarine overlap, or *vice versa*. The complications are too numerous for consideration in this volume.¹




FIG. 39.—A. Diagrammatic cross section of deposits laid down during successive transgressions and regressions of the sea. Land to the left; sea to the right; sand, stippled; shale, ruled; limestone, brick pattern. At *wz* shallow-water sediments (shale and sandstone predominate; at *yz* deep-water sediments predominate.

B. Columnar section taken at *wz* in Fig. 39, A. Note that the changes in the character of the sediments in a columnar section like this are indicative of alternate transgressive (T), and regressive (R), conditions.

In Fig. 37, A and C, lines parallel to lithologic types (sands, mud, etc.) are *formation lines*, and lines parallel to contemporaneous parts of the deposit are *time lines*. It is obvious that formation lines, *i.e.*, lithologic types, may cross or transgress time lines. Stated more simply, a deposit of given lithologic character may not be of the same age throughout. Fossils—*i.e.*, the remains of animals and plants that lived at the time when the sediments were deposited—are used to determine the geologic age of a sedimentary formation, and those which are particularly characteristic of any formation are *index fossils*. At the time

¹ For further information, see Bibliog., GRABAU, A., Chapter XVIII.

when they lived, these animals and plants flourished under special conditions of environment (temperature, clearness of water, salinity of water), conditions that, in considerable measure, were related to the kind of sediments in which the remains were finally entombed. Therefore, it is important to remember that fossil species, like lithologic types, may and often do transgress time lines in the greater sedimentary formations. Care has to be taken not to rely too implicitly on an index fossil, or even a group of index fossils, as proof that the containing strata in two localities are exactly of the same age.




FIG. 40.—Clastic dike formed by the filling of a fissure from above.

79. Clastic Dikes.—The normal method of sedimentary accumulation is such that, in the terms of stratigraphy, any portion of a deposit must be younger than the materials which underlie it and older than the materials which overlie it (108). The age of a stratum is gradational from oldest at the bottom to youngest at the top. However, there are instances known of *clastic dikes*, that is, of layers of clastic material which intersect other rocks and which, unlike true beds, are of approximately the same age at opposite points in their sides. It is easy to imagine how sand, perhaps, might drift into and finally fill a fissure in bedrock at the surface of the ground or under water (Fig. 40). This mode of origin has been proposed for these dikes in some cases. Another suggestion offered is that detritus has

slowly been let down *pari passu* with the opening of spaces by gradual leaching and removal of the original materials in solution (Cf. Fig. 36, E). Generally the dike material seems to have come up from below in an unconsolidated condition (as loose sand, mud, etc.), probably mixed with water or other fluids. Uprturned strata in the wall rock, upward thinning and termination of the dikes, evidence of flow structure parallel to the walls, inclusions of the wall rock in the dikes, the great size and continuity of some of the dikes,¹ and the similarity of the dike materials with under-




FIG. 41.—Dikes of bituminous sandstone (stippled) in Miocene shale (lined). Section about 50 ft. high. (Taken from folio 163, U. S. G. S.)

lying sediments—all these facts point to fairly rapid injection from a source below (Fig. 41). There are good reasons for believing that the injection was performed under considerable pressure (hydrostatic pressure, or pressure from gas, from the weight of the superjacent rocks, or from combinations of these forces).

Clastic dikes have been recorded as consisting of asphalt, clay, shale, gravel, conglomerate, bituminized and unbituminized sand, hard sandstones, and limestone, and as intersecting granite, sandstone, sand, shale, clay, limestone, and especially coal. The best condition for the origin of these dikes is the presence of

¹ Clastic dikes have been found ranging in thickness from mere films up to several hundred yards and in length from a few inches to over 9 miles. See Bibliog., NEWSOM, J. F.

unconsolidated sedimentary material overlain by a hardened, cracked stratum. They may have been caused by earthquake shocks and earth stresses which tend to fracture rocks and redistribute mobile substances.

80. Clastic Pipes.—Clastic "intrusions," instead of being sheetlike, may have one long and two short dimensions, like a rod. When they have this shape they are termed *pipes*. They are the fillings of irregular tubes and usually have approximately a vertical position. From the fact that the surrounding rock is nearly always limestone and from the structural relations of these pipes, they are believed to have originated either: (1) by the filling of sinks (269); or (2) by the slow settling of debris into a depression which, contemporaneously, was being made in the bedrock by solution. According to both explanations the materials enter from above.

STRUCTURES DEPENDING ON THE MUTUAL RELATIONS OF BEDS OR LAMINÆ

81. Local Unconformity; Contemporaneous Erosion.—Sometimes deposition is interrupted by a period of erosion. The beds already laid down may be somewhat dissected. After a relatively short time the accumulation of sediments may begin again and the eroded surface will be covered up by the later beds. In a deposit built in this manner the upper younger strata are *unconformable* with the lower older strata, and the buried surface of erosion is a *surface of unconformity*; but this structure differs in several respects from regional unconformity (75, 76). In the first place the area of erosion is often of small dimensions compared with the whole formation so that this may be called *local unconformity*. Second, the erosion is accomplished during a short cessation in the upbuilding of the deposits, and is therefore spoken of as *contemporaneous* erosion. And third, the sediments below the surface of unconformity were not lithified at the time of this erosion (see footnote, page 67).

The most common type of local unconformity is the result of stream action. At time of flood a river may cut into and sweep away part of the mud and sand deposited while its current was

less impetuous. By its increase in velocity this stream is enabled to carry coarser sand and gravel. As soon as the speed begins to slacken again, deposition commences. The heavier fragments are dropped first and, while the flood subsides, finer and finer particles are deposited until normal conditions prevail.

A vertical cross section through beds separated by a local unconformity usually shows a finer stratum overlain by a coarser stratum and the two divided by an irregular line (of unconformity) which cuts across the bedding of the lower stratum (Fig. 42). The major stratification above the line of uncon-




FIG. 42.—Section of a surface of local unconformity *ab*, between an older clay and a younger, overlying sandy gravel. The fragments of clay in the gravel are intraformational pebbles. They would still be so classified after lithification of the clay to shale and of the gravel to conglomerate, provided they resulted from contemporaneous erosion.

formity is parallel to that below. (How does local unconformity differ from disconformity?)

Contemporaneous erosion may be caused also by the shifting of aggrading streams on flood plains, deltas, and alluvial cones; in marine deposits by changes in the strength or direction of marine currents; in lake deposits by similar changes in currents; and in eolian deposits by variations in the wind. In all these cases the unconformity is local.

There is a somewhat similar relation between older and younger sediments which may be associated with glaciation. In front of an ice sheet or a mountain glacier aqueoglacial deposits accumulate. Beneath the ice till may be deposited. While the ice front is advancing the water-laid sands and gravels may be overridden, more or less eroded, and subsequently overlain by

till (Fig. 43). The pebbles in such till are many of them water-worn, having been dislodged from the underlying wash, and those which are striated are characterized by very numerous and very fine scratches produced by rubbing against sand rather




FIG. 43.—Section of a surface of unconformity, *ab*, between older cross-bedded sand and younger till.

than bedrock. On the other hand, in the retreat of the ice front, water derived from melting may flow over and erode somewhat earlier till and lay down aqueoglacial muds, sands, and gravels upon this till (Fig. 44). The latter relation is more common than the former because in most cases advancing ice






FIG. 44.—Section of a surface of unconformity, *ab*, between older till and younger gravel.

completely destroys the wash over which it passes. The chief differences between local unconformity and the unconformity produced in each of these cases is that these are surfaces of such broad extent that they can hardly be termed *local*, and they are the result of a change in the agent itself. Nevertheless, they are examples of contemporaneous erosion, as the term has been defined (Cf. 75, 111).

82. Sun Cracks.—Sun-cracked loam and silty clay disintegrate so quickly when moistened that there is little or no opportunity for the preservation of the cracks. Purer clays, if exposed long enough to dry thoroughly, may hold together until the cracks are filled with sand by an invading sheet of water. Sun cracks may be filled also with wind-blown dust or sand. In any case a cross section would show a fine mud or clay deposit overlain (usually) by a somewhat coarser stratum from which small projections, wedge-shaped or rectangular (58), would extend downward a few inches (Fig. 45). The contact between the two deposits would be sharp and would represent a time interval during which sedimentation ceased. In this interval erosion might or might not occur. It would not be unnatural to find contemporaneous erosion exhib-



A



B

FIG. 45.—Sections of sun-cracked clay which has been buried by sand. In B a thin clay layer rested on sand. (Cf. Fig. 28.)




FIG. 46.—Conglomerate produced by interbedding of sand laminae and sun-cracked clay laminae.

ited somewhere along the line of contact (94). Alternating sun-cracked clay laminae and laminae of sand give the rock the appearance of a conglomerate (or breccia) (Fig. 46).

83. Contemporaneous Deformation.—Sometimes an agent of contemporaneous erosion not only scours away strata which have been laid down recently, but also buckles them up or breaks and faults them. Undisturbed beds are then deposited upon the truncated edges of the dislocated layers. This structure, which may be called *contemporaneous deformation*, is mentioned here merely to call attention to it as being a feature which may be developed in strata prior to their lithification, but its description is reserved for Art. 169.

84. Cross-bedding. A. Cross-bedding Defined.—In some deposits, especially in sands, certain beds may exhibit an original lamination oblique to the main stratification. This structure is called *false bedding* or *cross-bedding*. It is generally caused by current action, either of wind or of water, and in some instances



FIG. 47.—Delta structure. *ab*, topsets, *bc*, foresets; *de*, bottomsets or prodelta clays. Note relation of water level to the angle between the foresets and the topsets.

is produced by wave action. It is found in deltas, torrential deposits, sand bars in rivers, marine current deposits, sand reefs, and eolian deposits. Ripple-mark, of both wave and current origin, is a special case of cross-bedding. The principal kinds of cross-bedding are described in the succeeding paragraphs.

—**B. Delta Structure.**—In a delta that has been built under ideal conditions in a standing body of water there are three series of beds, namely, topset, foreset, and bottomset beds (Fig. 47). The *topsets* have a primary dip equal to the angle of slope of the subaerial surface of the delta upon which they were laid down by an aggrading stream. The *foresets* consist of materials dumped over the front of the delta into the lake and hence their primary dip is the angle of repose of the materials under water (20° to 35°). The younger foresets of large deltas have lower primary dips than the older ones.¹ The *bottomsets* are nearly

¹ Bibliog., GRABAU, A., p. 702.

horizontal for they are formed of fine muds or silts that float out and gradually come to rest on the floor of the lake. They are often termed *prodelta clays*.

The foreset group meets the topsets in an angle or in an abrupt curve and it merges with the bottomsets in a broader curve (Fig. 48). Variations in load, course, or velocity may cause the aggrading stream temporarily to degrade its channel and so produce local unconformity between the topsets and the foresets; but erosion of this kind can never occur between the foresets and bottomsets. (How might contemporaneous erosion occur between the foresets and bottomsets?)

The upper ends of the foresets of deltas formed in large bodies of water are often broadly eroded if the action of tides or waves is strong. Whether or not a subaqueous plain of denudation can be maintained on the growing delta depends upon the comparative efficiency of river and waves. If the river is the stronger, the delta will encroach upon the water; but if the waves are stronger, they may carry away and spread the delta deposits below water level.




FIG. 48.—Detailed vertical section through the deposits of a delta. *a*, topsets; *b*, foresets; *c*, bottomsets or prodelta clays.

Provided there has been no erosion of the foresets, the junction between any foreset and the immediately overlying topset bed is a little below the water level at the time that foreset bed was deposited (Fig. 47). This is because the stream can maintain its current for a short distance out from shore. (Explain.)

Uplift and depression of the sea floor may have significant effects upon marine deltas. Slow subsidence (normal condition) results in great depth and volume of topsets (Fig. 49), while small uplifts favor great volumes of foresets and tend to shift seaward the zone of terrestrial sedimentation.¹

¹ *Bibliog.*, BARRELL, J., 1912, pp. 400, 401.

—**C. Compound Foreset Bedding in Deltas.**—The so-called normal delta structure is represented in radial vertical sections as in Fig. 47. If a vertical section were cut concentric with the




FIG. 49.—Ideal section of a delta built out into quiet water while subsidence just balanced deposition. The shore line remained stationary. (After J. Barrell.)

front edge of a delta, *i.e.*, parallel to the strike of the foresets, no cross-bedding would be seen. All other vertical sections would expose foresets with an inclination less than their true dip. In the construction of a lobate delta (260), adjacent lobes inter-




FIG. 50.—Compound foreset bedding. Note that each set of laminae is truncated by the next overlying set. The section is about 4 ft. long.

fere in such a way as to cause the building of foresets dipping now in one direction and now in another.¹ By changes in the stream, such as decrease in load, increase in volume of water, or

¹ Bibliog., SMITH, A. L., p. 437.

shift in course, or by fluctuation of the lake or marine water level, foresets recently deposited may have their upper ends truncated and may then be overlain by new beds of similar nature dipping in the same or in a different direction. *Compound foreset bedding* produced in one or another of these ways is abundantly exemplified in glacial sand plains (Fig. 50). A special variety, called *backset bedding*, has been described by W. M. Davis.¹

—**D. Torrential Cross-bedding.**—In torrential deposits fine, horizontally laminated strata alternate with uniformly cross-bedded strata composed of coarser materials. The cross-laminæ meet the horizontal beds at an acute angle both above




FIG. 51.—Torrential cross-bedding.

and below (Fig. 51). This type of bedding is believed to originate under desert conditions of concentrated rainfall, abundant wind action, and playa lake deposition. The cross-bedded layers are built forward by temporary streams where they debouch upon the playa lake, and the horizontal layers are materials which settle from suspension from the playa lake waters after the feeding stream has withered away.

—**E. Other Types of Foreset Bedding in Water-laid Deposits.**—Sand lenses, such as those to be described in Art. 85, frequently exhibit a uniform cross-bedding of the foreset variety. In the building of a river sand bar, the materials are carried over the bar and are dumped on its front or downstream slope. Filling of hollows and deserted channels may proceed as in the construction of a normal delta, the sand being laid down in

¹ Bibliog., DAVIS, W. M., 1890.

successive foreset beds. These may be seen in sections of the deposit.

Spits are built by the action of longshore currents. Sand is dumped over the growing end of the spit and there it slides down and assumes the angle of repose. The resulting bedding is therefore of the foreset type.

Under certain circumstances minor foreset bedding is produced by currents on the floors of lakes and seas, but it is not characteristic of deposits there accumulated. Yet it has been found even in marine limestones. Cross-bedding of this origin is rarely seen in unconsolidated sediments.

—**F. Wave-built Cross-bedding.**—Lake beaches and marine beaches are built largely by the work of waves. Sand or gravel is thrown up layer upon layer and the beach thus grows toward the water. Since the slope and profile of a beach depend chiefly upon the strength of the waves, and since the stratification and surface of a growing beach are parallel, it follows that variations in wave efficiency may produce slight variations in the structure of the deposit . . . “The beach strata are considerably inclined” and “each layer or group of layers is apt to be intersected by other layers lying at different angles.”¹

This beach structure is not of the same origin as foreset bedding. The angles of inclination of the laminae are less than the ordinary angles of repose. Also, the angles between adjacent groups of laminae are usually only a very few degrees. Wave-built cross-bedding is not often visible in unconsolidated materials. It occurs chiefly on the outer parts of sand reefs. In gravel it is obscure and the arrangement of pebbles may suggest pell-mell structure. In sections of lake beaches it is to be distinguished from the steeper, less regular structure produced by the shove of ice.² The portions of sand reefs above the reach of the waves are of eolian origin and the inner margins are built by the dropping of wind-blown sand into the neighboring lagoon (283).

¹ Bibliog., SHALER, N. S., 1895, p. 165.

² See Bibliog., FENNEMAN, N. M., p. 31.

—**G. Eolian Cross-bedding.**—Cross-bedding of wind construction is marked by its extreme irregularity (Fig. 52). This is due to the variability of direction of winds and the frequent alternation of scouring and deposition. The cross-laminæ of a growing sand dune are of two sets: (1) the foresets which are




FIG. 52.—Eolian cross-bedding.

built on the lee slope and dip at the angle of repose of dry sand (about 30°); and (2) the topsets (or backsets) which are formed on the windward surface of the dune and have an average dip of 5° or 10° against the wind. (How does this differ from the topsets of deltas? What happens to the wind-blown materials




FIG. 53.—Section of a dune, showing topset or backset bedding, *ab*, and foreset bedding, *bc*. The crest, *b*, has advanced a little in the direction of the wind (see arrow), but the dune as a whole has not migrated.

corresponding to the bottomsets of deltas?) The topsets are rarely permanent and may be very thin or absent if the dune is migrating rapidly (Figs. 53, 54). The dip of the foresets decreases down the slope so that these layers curve with their concave sides uppermost. As the dune moves forward, a part of the lower portion of the foresets may be left behind and upon these truncated foresets a new dune may advance from the same

or a new direction. By a repetition of this process the sand deposit comes to have a highly complex structure. Care should be taken to discriminate eolian cross-bedding from compound delta structure and from wave-built cross-bedding.



FIG. 54.—Cross section of a dune, showing foreset bedding. The dune has migrated from *a* to *b* by the blowing of sand from the windward side (see arrow) to the lee side. Contrast this figure and Fig. 53 with reference to the quantity of sand supplied.

—**H. Ripple-mark.**¹—The ripple marks seen in sections of deposits are more commonly of the current-formed species. Since each one of these ripple marks is a miniature dune, we may speak of the laminae which dip against the current as topsets (Fig. 24, *bc*) and those that dip with the current as foresets (Fig. 24, *ab*). Topsets are laid down provided deposition is




FIG. 55.—Ripple-mark in section. Below *ab* and above *ef* the migration of the ripple systems was not so rapid as to prevent the deposition of topsets. Between *ab* and *cd* the ripple marks moved forward just fast enough to prevent topset deposition, but not fast enough for erosion of the foresets. Between *cd* and *ef* migration of the ripple marks was so rapid that the foresets suffered some erosion of their upper ends.

sufficiently rapid during the process of ripple-making (Fig. 55); but if the strength of the current increases beyond a certain limit, which is variable according to several factors, migration of the ripple system is too rapid, and erosion instead of deposition will

¹ "Ripple mark," in this book, is written unhyphenated to signify a single ridge of that name. The plural is "ripple marks." The hyphenated term, "ripple-mark," is used here for the structure which is seen in a cross section of a group of ripple marks.

occur on the back slope of each ripple (Fig. 55). Change in direction of current may cause the superposition of rippled laminae in which the foresets are inclined in different directions. Variations in the speed of the current may bring about superposition of sets of ripples with different spacings between the crests.

—**I. Comparison of Types of Cross-bedding.**—From what has been said, clearly it is not always possible to tell at a glance whether a cross-bedded deposit is of wind or water origin. In most cases its accumulation must have been associated with current action, but sometimes the structure is the work of waves. The foreset type of cross-bedding is the commonest. In deltas it is usually of relatively large dimensions and is associated with topset and bottomset bedding. Torrential stratification is very regular and consists of alternate horizontal and cross-laminated beds. Compound delta structure (foreset and backset) much resembles eolian cross-bedding, but it is more regular, the sand is not wind-worn, and there are often gravel layers interbedded. The form of the unconsolidated deposit as a whole is that of a delta or a sand plain and not of a dune. In beach structure the laminae are inclined to one another at very low angles and there is not so much irregularity as in dunes and in compound foreset bedding. Ripple-mark is on a smaller scale. Sand reefs are not very permanent. They are ultimately thrown on shore and then become eolian deposits. Beach structure is really true bedding with a rather steep primary dip. Bars may be more or less preserved. If they shift they may show some local unconformity. They are truly cross-bedded. Wind cross-beds are usually on a larger scale than water-made ones. The bedding of sand bars may perhaps resemble that of sand dunes. For the discrimination of eolian and aqueous deposits, it is worth while remembering the characteristic distribution of the coarser and finer sand grains on ripple marks (55).

85. Lenses.—Gravel deposits sometimes contain isolated, roughly lenticular beds of sand, which thin out and terminate laterally (Fig. 56). These *lenses* may be the fillings of original

hollows or channels in the gravels or they may be buried sand bars. They may exhibit a uniform cross-bedding of the foreset variety. There is often local unconformity between the lens and the overlying gravel. (Why?)




FIG. 56.—Section of a lens of cross-bedded sand in gravel. The sand was deposited by a current flowing from left to right. The upper surface of the sand is a surface of local unconformity.

The opposite relation may be seen, in which sand contains gravel lenses, but in this case the local unconformity, if present, is between the lens and the underlying sand (Fig. 57). The gravel occupies a channel scoured out and then filled by a current




FIG. 57.—Section of a lens of gravel in sand. The lower surface of the gravel is a surface of local unconformity.

of water. Other like associations may be found, *e.g.*, sand lenses in clay. It should be understood that in order that a channel filling may be of lenticular shape in cross section, the section must be more or less across the trend of the channel.

Very long sand lenses (*e.g.*, a few hundred feet wide, a few score of feet thick, and several thousand feet to several miles long) are

called *shoestring sands*, when they are found buried in mud deposits or in shale formations. They may be the fillings of old stream channels, or they may be old buried offshore bars (283). In the former case, the cross section of the sand deposit will have its greatest width at the top and will have a base convex downward; in the latter case, the cross section will be widest at the base and will have a relatively flat base and a top convex upward.¹

86. Uniform Lamination.—Very fine and even lamination, free from cross-bedding and ripple-mark is often a sign of deposition under quiet conditions, yet under conditions which permitted sorting. This kind of bedding is especially characteristic of some muds and clays which settle gradually to the bottom of quiet water bodies after having been carried thither by surface currents or by wind.

87. Transverse Textural Variation within Single Beds and Laminæ.—It is not uncommon to find that individual beds, which have been transported by wind or by water currents, grade from coarser below to finer above, and that there is a rather sharp transition between the fine part of any bed to the coarse lower portion of the next overlying bed. This is because the velocity (or volume) and therefore the carrying strength of a current generally increase much more rapidly than they decrease. The increase may be so sudden as to cause some local erosion (81).

The same kinds of variation, from coarse below to fine above, may be seen in thin uniform laminæ of quiet water deposition and likewise in volcanic ash and tuff formations. With reference to laminæ deposited in water, whether wind or water current was the transporting agent, after each accession of dust, mud, or silt, the larger grains dropped down before the smaller ones. The next time the water became turbid, large grains settled upon the finest particles of the layer last deposited (Fig. 58). This is characteristic of fine sediments (silts and clays) transported from melting snow and ice deposited in quiet water. The laminæ are then called *varvs* (see Art. 104).

¹ See Bibliog., BASS, N. W., 1934.

88. Stratigraphic Interval Defined.—The distance, measured perpendicular to the bedding, between the corresponding parts of any two strata in a sedimentary formation is called the *stratigraphic interval*, or simply the *interval*, between these two beds. In Fig. 59, *ab* and *cd* are the stratigraphic interval between the




FIG. 58.—Section of fine laminated sandstone, illustrating the gradation in texture in individual laminae.

top surfaces of the limestone beds at two localities, *K* and *M*, where the strata are horizontal and inclined, respectively.

89. Variations in Stratigraphic Interval.—

The interval between any two beds in a sedimentary formation is seldom constant for any great distance. In other words, the strata thicken or thin in various directions. Ordinarily, on a large scale, shallow-water beds (sandstones) are likely to thin, and deep-water beds are likely to thicken, away from the shore line. Furthermore, an extensive formation, such as may have accumulated in a large lake or sea, is likely to become thinner as a whole toward the region of deep water.

90. Pinching or Lensing of Strata.—We have already described, in Art. 85, a minor variety of lens. A somewhat




FIG. 59.—Cross section to illustrate stratigraphic interval.

similar condition may occur on a larger scale. If a stratum continues to thin out in a certain direction, as suggested in Art. 89, it may finally “pinch out” or “lens out” altogether. The beds above and below it will then become contiguous (Fig. 60). This condition is not uncommon, especially in the individual sandstone beds of formations consisting chiefly of shale and sandstone strata. It is sometimes the explanation of the absence, in one locality, of a stratum which is present in another locality in the same region. It may be very important in its effect upon the

movements and distribution of water, oil, or gas, within the beds. Thus, the up-dip pinching of an oil-bearing sandstone may cause the accumulation of the oil near the termination of the bed, on homoclinal dip (155) or on the flank of a fold (Fig. 61). This kind of lensing should not be confused with up-dip termination of strata, due either to overlap (78) or to truncation by unconformity (page 68).




FIG. 60.—Cross section illustrating the lensing or pinching of beds.

91. Lateral Variations in Texture, Porosity, and Permeability.

Not only do strata commonly vary in thickness from place to place, but also they are apt to vary in texture, porosity, and permeability, *laterally, along the bedding*. A sandstone layer, for instance, may gradually grow more and more fine-grained until, perhaps, it may blend into shale; or the interstices between its grains may be filled by more and more original fine clayey mate-




FIG. 61.—Cross section of an anticline showing an example of the accumulation of oil and gas (black, *ab*) where a sandstone bed, *abc*, pinches out up the dip (at *a*). The lower portion, *bc*, contains water.

rial; or its pore space may contain an increasing amount of cement. Limestones, also, may vary considerably in porosity (68-71). These variations in texture, porosity, and permeability, together with the pinching or lensing of beds (90), are frequently called *sand conditions*.

92. Rhythms or Cycles in Stratification.—In many sedimentary formations a more or less orderly repetition of a sequence of

beds or laminae occurs, suggesting a cycle or repeated recurrence of certain conditions during deposition, such as might be caused by weather, season, climate, sea level, etc. For example there may be an alternation between shales and limestones, or between coarser and finer elastics (Figs. 39, 58). The varvs in clay and silt deposits derived from the melting glaciers are an example of small-scale rhythm in stratification (87, 102).

PARTICLES AND FRAGMENTS IN CLASTIC DEPOSITS

93. Isolated Pebbles and Boulders.—The presence of large isolated boulders in relatively fine gravels or sands of shallow water deposition is not very difficult to explain. Such boulders are characteristic of some alluvial cone deposits, and they may be found in beach accumulations. They are common in eskers and kames where they have fallen from the adjacent ice walls, now long ago vanished.

In fine-grained sediments deposited in quiet water, the occurrence of isolated pebbles may be explained by flotation (Fig. 35). Pebbles floated out by drifting roots of trees or by ice may drop here and there into the fine bottom sediments. By their weight these pebbles may bend and somewhat compress the soft layers below them where they fall. Subsequently, if they are buried by continued normal deposition, the overlying laminae will show no bending. After consolidation of the material, the layers above these pebbles may be a little bent, but not so much as those below (72).

94. Intraformational Fragments.—Under certain circumstances, when an unlithified surface deposit is exposed to erosion, it is sufficiently hard and compact to break into slivers or blocks instead of disintegrating into the grains of which it is composed. There are two main causes for such superficial hardening—sun-baking and freezing of interstitial water.

1. When muds, clays, or limy materials are dried by exposure to the atmosphere, sun cracks develop (58, 82). Under these circumstances polygonal fragments between the fissures may peel and become loosened from the underlying beds; and if

deposition begins again they may be incorporated in the sediments immediately above the original sun-cracked surface. These fragments are said to be *intraformational*, and the strata containing them are *intraformational breccias* or *conglomerates*.¹ Usually they are angular and they may look as if they had been torn, but they are sometimes rounded by rolling. They are commonly seen in association with contemporaneous erosion (Fig. 42).

Sometimes in semiarid regions the dry, curled "clay-shavings" are blown away and buried in sand. Then, in the following wet season, moisture, percolating through the sand, may soften the buried shavings and cause them to flatten out parallel to




FIG. 62.—Section of till containing angular masses of unconsolidated sand and clay.

the bedding. In this form they are called *clay galls*. They are regarded as proof of the subaerial origin of the sand or sandstone in which they are found.

2. In cool climates water-soaked muds, sands, and gravels may become cemented by the freezing of their interstitial moisture and may then be disrupted by glacial erosion. If the broken blocks are deposited in till, they are preserved; but if they are handled by water they quickly fall to pieces. These blocks, also, are *intraformational* provided their erosion was of such a nature that it may properly be designated contemporaneous (81). They are angular, with shapes indicative of fracture (Fig. 62). In till deposits and occasionally in aqueoglacial wash, they are striking features, for when seen they are unconsolidated like the matrix that surrounds them. Similar ice-formed blocks have

¹ Bibliog., WALCOTT, C. D.; HYDE, J. E.

been observed in the lithified state (shale, slate, sandstone, etc.) in tillite (Appendix IV).

Any intraformational fragments may be warped or bent either by the weight of the superincumbent beds or, as in the second example, by the force of the eroding ice.

95. Isolated Masses of Unconsolidated Material in Surface Deposits.—The ice-made intraformational blocks just described




Fig. 63.—Section of till containing a deformed lens of gravel.

(94) are isolated masses of unconsolidated material as long as the matrix in which they lie remains unconsolidated. Short lenses of sand or gravel in till, contorted or not, are referred to as "nests" (Fig. 63). They are really *in situ*, having been deposited by water in association with the ice that formed the

till. While they may closely resemble the intraformational blocks, they seldom have outlines which are suggestive of disruption.

Till and wash deposits, and indeed any surface deposits of sufficient age, may contain entirely disintegrated pebbles and boulders of such rocks as granite, schist, and gneiss. Their sharp outline, their rounded or subangular form, and sometimes the indications of surface markings of erosive origin, prove that these boulders were fresh and hard when deposited and that they have disintegrated since they were buried. Their composition and usually their shape are sufficient to distinguish them from the incorporated blocks of sand, clay, or gravel.

96. Arrangement of Pebbles.—In bedded deposits pebbles which are not essentially spherical assume a definite position which varies according to several factors. On beaches composed of a great quantity of thin platy pebbles and beaten by a heavy surf, the pebbles often stand nearly vertically, wedged closely together, thus presenting the least resistance possible to the force of the waves (Fig. 64, A). When such pebbles are relatively few, they lie flat on the beach. Pebbles of greater thickness, but still thinner than wide or long, usually lie more or less flat on the

beach (Fig. 64, B). In river beds where the pebbles lie closely packed, and are comparatively flat, they imbricate or overlap downstream, dipping upstream at a moderate angle, and thus offering the least resistance to the current (Fig. 64, C). If the pebbles are few they lie flat on the bed of the stream. In alluvial cones, aqueoglacial deposits, and wind deposits, the pebbles and boulders are ordinarily so few that they lie flat on the surface. Summarizing, in gravel accumulations where the pebbles are comparatively thin and are abundant they lie so as to present the least resistance to the force of waves or current; where they are associated with a large amount of sand or other fine débris they lie flat. A conglomerate having its pebbles arranged transverse to the main bedding (as A and C in Fig. 64) is called an "edgewise conglomerate." In unstratified deposits, the fragments are irregularly disposed. We may speak of a definite tendency toward parallel arrangement of pebbles or sand grains (97) or fossils (98) in a sedimentary rock as *preferred orientation* (see also Art. 113).¹

97. Arrangement of Sand Grains.—The position of sand grains which are not equidimensional is of some geologic importance. Most of the common minerals occurring in sand, namely, quartz, garnet, magnetite, etc., are such as wear with nearly equal dimensions; but mica (muscovite and, less commonly, biotite) splits along its perfect cleavage into very thin flakes. In sediments which accumulate in very quiet water, mica plates settle flat with the bedding. They are relatively light and may therefore be separated by sorting so that some laminæ may have more mica and some less. J. B. Woodworth² has called attention to the fact that the flakes may settle on the front (or lee) slopes of ripple marks, and that, as a sand deposit is built up, the position




FIG. 64.—Diagram to illustrate the arrangement of pebbles. The arrow in C points with the current.

¹ See Bibliog., KNOPF, ELEANORA B., and INGERSON, EARL, 1938, p. 202.

² Bibliog., WOODWORTH, J. B., 1901.

of the mica in the laminae may give rise to a structure resembling true bedding (Fig. 65). In the same manner mica, if present in wind-blown sand, accumulates on the front slopes of dunes, so that the foreset beds contain a much larger proportion of this mineral than do the topset beds.




FIG. 65.—Apparent bedding, *ab*, caused by the abundance of mica flakes in the foreset laminae of the ripple marks. *cd* is the true bedding.

98. Position of Fossils.—The position of a fossil in a stratum depends upon the original mode of existence of the organism and on the method by which it was interred. Plant remains are sometimes exhumed in the attitude in which the plants




FIG. 66.—Section through strata containing the trunks of ancient trees. The roots are embedded in the original soils. This fact and the position of the trunks in the bedding show that they were still standing when buried.

lived. Ancient trees of the coal period have been found, their roots still buried in the lithified soil and their trunks projecting up through successive layers of the sediments which buried them (Fig. 66). Coal beds sometimes consist of vegetable remains *in situ*. Certain kinds of animal fossils (corals, etc.), also, may occur attached to their ancient rock supports. In such cases it is easy to see that the stratum containing the fossil must be younger than the stratum which served

as the foothold for the organism while it lived.

Free-living, unattached organisms fall flat, and their remains are therefore found spread out parallel with the bedding. With possible exceptions, this is true for broad leaves, for thin, flat shells and tests, for skeletons of fishes, etc.

The valves of clam shells and other similar concavo-convex shells, while sinking through water, settle with the concave side up and the convex side down (Fig. 67, *a*). If there is any motion

in the water, they are soon overturned so that their convex surfaces are now uppermost (Fig. 67, *b*). In this attitude they offer least resistance to currents, and in this attitude they are apt to be buried (Fig. 67, *c*). It is quite common to find shell beds, or elastics containing such shells, with a majority of the valves lying convex side uppermost.




FIG. 67.—Section showing position of concavo-convex shells in accumulating sand.

FIELD INTERPRETATION OF SEDIMENTARY MATERIALS

99. Nature of the Parent Rock.—To determine the original character of the rock from which a sedimentary deposit was derived is a task which varies widely in its possibilities. If the sediment is easily recognized as residual and rests upon its parent rock, there is no difficulty. Even if there are no outcrops of the earlier formation, perhaps because it is quite buried or because it has been entirely eroded away, the problem is still easy provided the sediment is a product of disintegration which suffered little transportation, for its constituent particles are then merely the disarranged grains of the older rock. And in the case of a conglomerate or other psephite, the pebbles tell the story.

From sedimentary materials which were laid down after they underwent long transportation and sorting, or considerable decomposition, the facts are harder to ascertain. There is more chance for mistake. For instance, a highly micaceous sandstone may have been formed from a micaceous igneous rock or from a schist or a gneiss. A sandstone containing a large proportion of

garnet may have come from a garnetiferous schist or gneiss. Sometimes the geologist is helped by noting the character of associated strata. Thus, mudstones with a high kaolin content interbedded with quartz sands suggest that the parent rock was granite or quartz diorite. (Why?) Further details must be left for the student to work out for himself.

100. Quiet Deposition or Current.—Quiet deposition is indicated by very uniform lamination or by entire absence of bedding in fine rocks of uniform texture (86, 87). In both cases the rock is usually a mudstone or a fine-grained sandstone. Deposition under the influence of a current is shown by cross-bedding, local unconformity, current ripple marks, wave marks, rill marks, lenses, etc. Wind-laid sandstones and river-laid clastics nearly always bear evidence of current action. Lake and marine deposits may belong to either class.

101. Depth of Water for Lake and Marine Sediments.—Since current action in lakes and seas grows less efficient away from shore, the coarser materials accumulate for the most part in shallow water. In a way, then, texture is indicative of depth of water. Likewise, the evidences for current action, just cited, appertain principally to shallow water deposits. It should be remembered, however, that these structures are sometimes made far from land by deep water currents.

Marine limestone has been said to form only in deep water, but we know now that the most important essentials for its origin are not depth so much as freedom from turbidity. While probably many limestones have been built up at depths greater than the average depth for the deposition of muds, still, some limestones may perfectly well have accumulated in relatively shallow water, provided the land waste was removed by longshore currents.

102. Direction of Current.—Supposing that a rock does contain current-formed structures, we may desire to know in which direction the wind or water was moving, as the case may be. This is shown by cross-bedding, current ripple-mark, wave marks, rill marks, and to some extent by the attitude of included fossils.

Seaweeds and other aquatic plants, which are attached at the base, may be trailed out with the current. If they are buried and fossilized in this position, they indicate the direction in which the water flowed. Direction of current may be shown by position of the valves of fossil shells where a majority settled on the bottom and were buried with the beak, or hinge, side of the shell pointing against the current.

103. Strength of Current.—Strong currents can handle heavier materials than weak currents. Provided a rock shows evidence of current deposition, its texture is roughly a measure of the efficiency of the agent. In this connection, one should not compare eolian and aqueous elastics. It is unsafe to deduce too definite rules referring to relations between size of grain and strength of current.

104. Climate.—One of the most interesting kinds of information that the geologist is obliged to seek is the nature of the climate at the time of deposition of a given rock formation. Sometimes it is the climate in the area of deposition and sometimes it is the climate in the region where the sediments originated, but whence they were transported before their accumulation. Absence of fossils in marine or lake mudstones may mean that the water was unfavorable to life because of an excessive turbidity, or because of salinity, or because of too low a temperature. Coal is of two kinds, one being formed *in situ*, the fossil roots still passing down into the old soil from which the vegetation absorbed part of its nourishment (98), and the other formed from vegetable débris which was washed together and buried. Coal of the first type accumulated in marshes. It indicates, therefore, a climate which was moist and either warm or cool.

Muds containing a large percentage of kaolin show that the land area whence they came was undergoing decomposition in a relatively warm, humid climate. Quartz sands and quartz-pebble conglomerates may be looked for as the coarser elastics associated with such mudstones. On the other hand, mudstones which have a high percentage of soluble mineral components, are evidence against thorough decomposition and therefore against a

warm, moist climate. They are generally derived by severe glacial abrasion or by wind scour, so that in the former case they indicate a cool climate and in the latter case an arid or semiarid climate.

The varvs in clays and silts of aqueoglacial origin (87) vary in thickness according as the summer (period of melting) was relatively long or short. A succession of thin varvs would thus point to a succession of cool years, and a succession of thick varvs would indicate a succession of warmer years, with short, milder winters and long summers.




FIG. 68.—Casts of salt crystals in argillite. About $\frac{1}{3}$ natural size. (After R. A. Daly.)

A semiarid climate is also suggested in many cases by mud cracks, footprints, clay galls, etc., features which are best preserved where there are long spells of drought interrupted occasionally by showers, or once a year by a rainy season. Desert conditions are indicated by thick eolian sandstones together with playa lake and sheetflood deposits and intercalated beds of salt, gypsum, nitrates, etc. Crystals of salt or their casts (Fig. 68) are considered evidence for aridity during sedimentation. Red color used to be regarded as proof of a desert climate, but it is now known to be characteristic of some widespread decomposition products in warm and temperate humid climates (28). Rounded

quartz sands of which the grains are coated with red iron oxide may be regarded as of desert origin. Arkose and highly feldspathic sandstone may signify a relatively dry climate, either warm or cold. Glacial deposits betoken a cool or cold climate with an excess of precipitation in the form of snow.

105. Physiographic Conditions at Time of Deposition.—Sedimentary rocks may give us information on the physiography of the ancient regions where they originated. It has been pointed out in the preceding article how they indicate desert conditions. One may even go so far as to suggest that the arid region may have been flanked by a mountain range on the side from which the prevailing winds blew, and that this range caught the bulk of the rainfall on its windward slope.

Peat and coal, when *in situ*, mean that the area of deposition was flat and poorly drained. It was generally near sea level and was subject to occasional marine inundation. Hence the not uncommon interbedding of coal and marine clastics.

Products of long and thorough decomposition, such as decomposition clays, not only point to a moist, temperate or warm climate, but also to the fact that the lands where they originated were probably of low relief. They are suggestive of peneplanation. Thick fluviatile gravels and sands generally belong to piedmont alluvial cone deposits and, therefore, indicate the proximity of mountainous country.

106. Characters of Marine, Littoral, and Continental Deposits. Sediments, consolidated or unconsolidated, are divided into three great classes, known as marine, littoral, and continental deposits. The littoral (*littus*, the seashore) zone lies between the average of the monthly highest flood tides and lowest ebb tides. All deposits within this zone are *littoral*. Deposits beyond the seaward margin of the littoral belt are *marine*, and those beyond its landward margin are *continental*, no matter whether the land mass is a true continent or only an island. The student may find it of advantage to have summarized the chief characters of these deposits, in order that their recognition may be facilitated. For the most part the discriminative features must be sought, not

in small individual outcrops, but in large structural sections obtained through the correlation of many outcrops (see Appendix VI).

Marine deposits lack such structures as mud cracks, rain prints, etc., because they are never exposed to the atmosphere, but they may have ripple marks, and, occasionally, local unconformity. Wave-made ripple marks originate usually at depths of less than 100 fathoms. Marine deposits may attain enormous thickness, but their lithologic variation is less than in continental formations. Their bedding is comparatively uniform. Sand, silt, mud, and ooze, and their consolidated derivatives are the common members of the class. Clastic mica is a rare constituent. Exceptionally, pebbles and boulders may be floated by ice and dropped into the finer sediments. Associated conglomerates are probably littoral.

Littoral deposits are not abundant because, being accumulated in a narrow belt, they are never very thick, and because they are especially liable to destruction. They have little variation. They consist chiefly of sand or sandstone with some conglomerate or mudstone associated. Conglomerate beds are seldom more than 100 ft. thick and are generally much less. Being situated between the marine and continental areas, littoral sediments share some of the characters of each of the other two classes. In common with continental deposits, they may contain rill marks, ripple marks, sun cracks, rain prints, imprints and fossils of land organisms, and clastic mica; and, in common with marine deposits, they may have brackish and salt water fossils. Sun cracks, rain prints, footprints, and other phenomena, preserved in mud by virtue of its property of hardening when sun-dried, are less apt to be found in littoral than in continental sediments, because they are destroyed by the advancing tide before they are hard enough for preservation. Wave marks, perhaps, are more characteristic of littoral sands than any other feature, yet even these are sometimes made on lake shores.

Continental deposits constitute the most varied group on account of the many diverse methods in which accumulation may

be brought about. Changes from beds laid by one agent to beds laid by another agent are not uncommon. Eolian and glacial sediments are particularly characteristic, although they are not entirely limited to the continental class. The presence of numerous land or fresh-water fossils is a valuable criterion, but their absence is of negative value. Clastic mica in a fragmental rock is usually indicative of continental sedimentation. As regards the different rock types, conglomerates may attain great thickness, sometimes many hundred feet. Finer clastics may bear evidence of ripple-mark, cross-bedding, and local unconformity. Pelites may be variegated in color. They may contain sun cracks, rain prints, footprints of land animals, etc. Indeed sun cracks, formed as they are chiefly on the flats of river flood plains, low lake shores, and playas, are among the most reliable criteria for continental deposition. Coal beds *in situ* are of even greater significance. Limestones are apt to be continental if, like muds, they have been sun-cracked. Such limestones are rare and of restricted distribution. They may contain brackish-water fossils, but not marine ones.

Marine and lake sediments are typically well stratified, the beds being of pretty uniform texture and thickness. Fluvial and glaciofluvial deposits are stratified, but poorly so; their strata vary greatly in thickness; there is much textural variation; and such features as cross-bedding and local unconformity are characteristic. Eolian dust shows little or no bedding, whereas wind-blown sand is remarkable for its varied cross-lamination and excellent sorting. Deposits laid by ice, or resulting from volcanic outbursts, creepage, landslide, or weathering *in situ*, are generally heterogeneous and unstratified.

The principal and most permanent types of continental deposition are the accumulations of large deltas, piedmont slopes, interior basins in pluvial climates, and deserts. The significant characters of these classes of deposit are as follows:

1. *Large Deltas*.—Fluvial muds or pelites, with mud cracks, etc. (see Appendix VI); associated soil beds and swamp deposits; seaward gradation of the continental sediments into littoral

and marine materials; intercalated wedges of marine strata, laid when the sea flooded the low delta flats, sometimes penetrating considerable distances landward between the continental beds.

2. *Piedmont Slope Deposits*.—Fluviatile sands and gravels with characters such as are listed in Appendix VI.

3. *Interior Basins in Pluvial Climates*.—The deposits may be largely continental or marine according to (a) the depth of the basin, (b) the vigor of peripheral stream erosion, (c) the breadth and height of surrounding lands, (d) the proximity of the sea, and (e) the rate of subsidence of the basin floor, assuming subsidence to be in progress; if continental, the sediments may be fluviatile or lacustrine.

4. *Deserts*.—Lag gravels, colian sands, disintegration sands and gravels, and interbedded playa muds with associated saline precipitates are the common deposits; the sediments are partly colian, partly fluviatile, and partly lacustrine; fossils are rare.¹

107. Conditions of Unconformity.—The field geologist must first of all be able to recognize a regional unconformity and then he must be able to interpret its meaning. The criteria most useful in determining a regional unconformity are: (1) Discordances of bedding at a line of contact; (2) evidence of a former weathered or eroded condition of one formation at its contact with another; (3) presence of a basal conglomerate or of a basal arkose at the line of contact; (4) faults in one body of rocks truncated by the beds of another formation (Fig. 69, A); (5) dikes or other igneous intrusive bodies in one rock formation truncated by the other (Fig. 69, A); (6) abundance of intrusive bodies (dikes, sills, etc.) of a particular kind in one group of rocks and an entire absence of the same in an adjacent formation; (7) a distinctly greater amount of folding or of metamorphism in one formation than in an adjacent formation; (8) discordances of areal distribution of rocks or of structures as seen after plotting a geologic map of the region.²

¹ For further information on this subject refer to Bibliog., BARRELL, J., 1906; and *Ibid.*, 1925.

² See Bibliog., VAN HISE, C. R., 1896, pp. 724-734, for a discussion of these criteria.




FIG. 69.—Relations of unconformity. In A, the straightness of the line of unconformity (*ab*), together with the fact that this line bevels across various kinds of rocks and structures, suggests that it is the section of a buried peneplain. Clearly the dike and the fault are older than the beds above *ab*. In B, *ab* is a line of disconformity. It is the section of a buried land surface that was characterized by mesas and canyons. A basal sandstone is the lower bed in the younger formation. In C, two lines of unconformity are shown, *ab*, and *cd*. How do we know that *ab* is older than *cd*? What two geologic events occurred in the interval between the deposition of the two sets of strata? In D, *ab* and *cd* are lines of unconformity. *ab* is older than *cd*. *ab* is sinuous because it has been folded together with the beds immediately overlying it. *cd* is sinuous because the land surface of which it is a section was a valley-and-hill topography. What features in the diagram prove the two foregoing statements? A basal conglomerate lies in the valleys above *cd*.

Unfortunately there are many chances for error in the recognition of these criteria. (1) Discordances of bedding may be due to contemporaneous erosion, to cross-bedding on a large scale, or to faulting (312). Contemporaneous erosion might be confused with disconformity, and cross-bedding with angular unconformity. Nevertheless, both of these structures are usually local and they are not accompanied by the other criteria for regional unconformity. (2) The second criterion mentioned above is difficult to observe. (3) Autoclastic rocks (*e.g.*, fault breccias, crush conglomerates, etc.) may be mistaken for basal conglomerates. Van Hise has pointed out the following differences:¹ (a) Autoclastic rocks have derived all their material from the adjacent rocks, often both above and below, whereas in basal conglomerates there are apt to be at least a few fragments from foreign sources and all the materials are derived from the lower formation only. (b) In autoclastic rocks the fragments are usually less rounded than in basal conglomerates, but this statement is not intended to imply that the breccia fragments may not be somewhat worn—indeed, sometimes notably rounded—by rock movements, nor that the conglomerate pebbles are always well rounded. (c) The interstices of the autoclastic are often filled with vein material, while in the basal conglomerates the filling is finer detritus. Finally, (d) autoclastic zones may be seen to pass here and there into the unshattered rock, whereas basal conglomerates grade into other finer sediments. Criteria listed under (4) to (8) above should be clear and unmistakable before they are accepted as satisfactory. (6), (7), and (8) might result from extensive faulting instead of unconformity (312). In dealing with this problem, do not be contented to base conclusions on one fact. Search for many lines of evidence and, if all point the same way, then the inference is likely to be correct.

As for the interpretation of regional unconformities, the geologist should seek answers to the following questions: (1) What was the agent of the first erosion and what was the nature

¹See Bibliog., VAN HISE, C. R., 1896, pp. 680, 681, for a discussion of these criteria.

of this erosion? (2) What was the rate of the first erosion? (3) What was the nature of the old erosion surface? (4) What was the rate of deposition of the basal beds of the younger formation? (5) What was the source of these basal beds? (6) How long a period of time elapsed between the two periods of rock formation? (See "time value," defined on page 109.) (7) What is the range of lost strata (see "hiatus," defined on page 109) as stated in the terminology of the geologic time scale? (Appendix I.) (8) What thickness of rocks was removed in the first erosion? (9) What events are represented in the section? These questions can be answered only by studying the nature of the surface of unconformity and the characters and mutual relations of the two formations.

Since surfaces of unconformity are surfaces of past erosion, they should bear just such traces of erosion as would be sought on bedrock outcrops of the present day (see Chapter II). The trouble is that the evidences are usually concealed beneath the overlying formation, although sometimes, it is true, recent erosion has exposed portions of the old surface. Ordinarily the surface must be studied in cross section, merely as a line. The greater the length of the exposed part of this line, the safer will be inferences based upon its examination; but even if it is not continuously exposed, the separate scattered outcrops may be levelled up and correlated so that a fair idea of its character may be obtained.

As explained in Art. 76, a surface (or line) of unconformity does not necessarily accompany unconformable relations. A sharp dividing line between two formations which are unconformable with one another may be due: (1) to strong abrasion in the first period of erosion; or (2) to regional decomposition. A blended transition from the older formation to the younger one, with no sharp line of demarcation, points to deep disintegration in the first period of erosion. Here the basal sediments are disintegration products of the underlying rock. Thus, the distinctness of the line of unconformity helps somewhat toward an understanding of the kind and rate of erosion.

Provided the line of unconformity is distinct, its form may indicate the nature of the old erosion surface. If the line is straight or gently undulating for a long distance, the surface was probably a destructional plain, or, less likely, a bench (256, 261). Greater irregularity of the line points to a more uneven topography. Several possibilities are depicted in Fig. 69.

For interpreting the past, the basal portion of the upper series is of more value to the geologist than the actual line of unconformity. It should be studied with reference to its composition, texture, and structure, and as regards the shapes and surface features of its constituent fragments, if it is of mechanical origin. Information as to the climate at the time of deposition and as to the agent and rate of this deposition may be obtained in the manner described in Art. 104. Conglomerate and arkose frequently appear as the lowermost stratum of the upper series. Arkose generally means short and rapid transportation and deposition which have been quickly inaugurated after a period of slow, long-enduring disintegration. A basal conglomerate, always containing abundant pebbles of rocks in the upper part of the lower formation, is significant of encroaching deposition and of effective abrasion during transportation from the source of supply. Sometimes rocks other than conglomerate and arkose are basal. Above an ice-scoured surface, tillite is to be expected; but if a glacial rock basin (268) were occupied for a time by a lake, finely stratified shale, originally lake clay, might rest on the grooved and striated surface. Limestone on an old erosion surface means: (1) that the initiation of the limestone-forming conditions was so quiet that no mechanical sediments were made; or (2) that such sediments were carried away to be laid down elsewhere as fast as they were formed. Basal sediments, then, need not be deposited by the same agents that eroded the subjacent surface of unconformity. There is no better aid to the interpretation of former conditions than a broad knowledge of present conditions.

Wrong impressions are sometimes formed regarding the source of the basal materials and the direction of their transport.

For instance, if a basal conglomerate composed of granite pebbles were observed overlying, let us say, a quartzite, and half a mile away the granite of the pebbles were found as bedrock below the surface of unconformity, one might assume that the pebbles were derived and carried from the locality of the granite to the site of the conglomerate. It is to be remembered, however, that these features are seen only in a single plane, intersecting the unconformity in a line. The pebbles may have been shaped from this granite, but the granite mass may be of very great extent and the pebbles may have been borne, perhaps many miles, from another part of the same plutonic body, not necessarily exposed in the geologic section. Provided the rock was a transported deposit, there is no necessary relation between the trend of the section and the direction in which the materials were carried. Their true source can only be approximated, and even then only after extensive investigation.

From the standpoint of stratigraphy it is desirable to know what interval of geologic time is represented by the unconformity and how many geologic formations are missing at the unconformity. The former is called the *time value* of the unconformity and the latter is the *hiatus*. Hiatus can easily be determined if it is possible to ascertain the geologic age of the old and the young formations at the surface of unconformity (109). Time value need not be equivalent to hiatus, for there is no reason for assuming that erosion was continuous throughout the period of time represented by the unconformity. Thus, if the two formations are Upper Cambrian and Triassic, the Ordovician, Silurian, Devonian, Mississippian, and Pennsylvanian, but not the Permian, may have been deposited and then eroded before Triassic deposition commenced, or perhaps only the Ordovician was laid down and was worn away during the remaining time from Silurian to Triassic. In the first case the time value is represented by erosion during the interval from the end of the Pennsylvanian to the initiation of the Triassic; whereas, in the second case, the time value is represented by the interval between the end of the Ordovician and the beginning of the Triassic; yet, in both

instances, the hiatus is the same. Time value is a difficult factor to determine.¹

108. Stratigraphic Sequence.—Since strata are accumulated by a process of upbuilding of layer on layer, any bed in unconsolidated sediments is younger than those below it and older than those above it. This original succession from older below to younger above is referred to as *stratigraphic sequence*. Although in most cases it remains *normal* after the consolidation of sediments, it may be *reversed* by overturning of the beds in severe crustal deformation (166).

109. Age Relations of Sedimentary Materials.—The age of a sedimentary deposit or rock, as indeed of any other geologic form or structure, may be regarded from three points of view: (1) If the deposit (or rock) is correlated with its immediate surroundings, it will be found to be younger than some geologic features and older than others. Stated in these terms of comparison, its age is called *relative*. The relative age of any bed within a given formation is obtained by determining the stratigraphic sequence. (2) Geologists have agreed upon a *time scale*, that is, a definite succession of formations for the whole world, and the divisions in this scale have received names (Appendix I). Each division is characterized by a certain suite of fossils, which, though showing a good deal of variation in its species and even in its genera, is still sufficiently distinctive to be of use in settling the place of a fossiliferous deposit in the succession. The age of a body of sediments when referred to this time scale is its *geologic age*. (See last paragraph in Art. 78.) If fossils are absent or scarce in the deposit, its geologic age can be obtained only by correlating it with other bodies of which the geologic age is already known. The geologic ages of all structures and of all rocks other than sediments must be found in this indirect way. (3) The *actual age* of a deposit, expressed in years or centuries, can seldom be ascertained. Even attempts to compute approximate values are likely to be far off.

¹ For further information on this subject, see Bibliog., BLACKWELDER, E., 1909.

Of these three methods of stating the age of sediments, the first and second are commonly followed. The second is the more definite of the two and is the more difficult to establish because fossil species must be identified. The third method, being rarely essayed, will receive no further comment in this book, except to state here that considerable study has been devoted to varvs (104) as an index of the duration of interglacial and postglacial ages; and of other intervals of geologic time during which varved clays are deposited. Also extensive investigations of radioactive substances have been in progress with the purpose of measuring the length of geologic time.

Within a given sedimentary series, we may often say that beds of essentially the same age are at the same *horizon*. "Horizon" is defined as "any given definite position or interval in the stratigraphic column or the scheme of stratigraphic classification."¹

110. Relative Age of Clastic Dikes and Pipes.—Clastic dikes and pipes are clearly younger than their inclosing rock (country rock). If they have originated by filling from above, they are probably associated with some overlying stratum which bears unconformable relations with the country rock, wherefore they may be very much younger than this country rock; but if they were injected from below, the difference between their age and the age of the country rock may be relatively slight.

111. Discrimination between Separate Glacial Epochs.²—In regions of Pleistocene and later glaciation evidences have been found which prove that the ice advanced more than once, that the periods between successive advances were often of considerable length, and that during these interglacial epochs the ice front retreated long distances. Some of the more important criteria for discriminating between the deposits of successive ice advances are briefly outlined below.

1. If beds of terrestrial origin, containing either plant or animal remains, are found between deposits of glacial drift, and if the

¹ Bibliog., A. H. FAY.

² For a more detailed discussion of this subject see Bibliog., SALISBURY, R. D., 1893. The writer has drawn freely from this source.

organic remains are of species known to have existed in a temperate or warm climate, the evidence is strongly in favor of a long period between the laying down of the lower drift sheet and that of the upper. The mere presence of fossils is not always sufficient evidence, because sometimes life, especially plant life, flourishes near or even upon the ice. But this is more particularly true of local mountain glaciers and piedmont glaciers than of the larger ice sheets.

2. If between two sheets of drift there are found local beds of bog iron ore, or marine or lacustrine strata containing the remains of plants or animals that lived in temperate or warm water, a long interglacial period is indicated.

3. A weathered glacial deposit overlain by fresh drift with a sharp boundary between the two is another criterion for two separate glacial epochs. A red or reddish color in the weathered drift points to a warm, moist climate (28). The thickness of the zone of this decay roughly indicates the length of time of exposure to atmospheric influence.

4. When boulders of certain varieties of rock exhibit a distinctly greater degree of weathering in a given moraine or sheet of drift as compared with the degree of weathering in boulders of the same rocks in an adjacent moraine or in an overlying drift sheet, respectively, the presumption is that the deposits were separated by an interglacial epoch of some duration. In both (3) and (4) care must be taken not to confuse superglacial materials of the older glaciation, which decayed while on the surface of the ice, with that part of the drift which may have weathered after its deposition.

5. During the retreat of a glacier, streams from the ice are usually aggrading (why?); but after the ice front has retreated many miles, aggradation may cease and both aqueoglacial and till deposits may suffer erosion. Upon a readvance of the ice, channels cut into the older drift and even into bedrock beneath this drift may be filled up with a new glacial accumulation. Buried valleys of this origin are much larger than the gullies cut by contemporaneous erosion.

6. If, after the disappearance of the ice, a later drift sheet does not entirely cover an earlier one, the topography of the exposed part of the older deposit will show a more advanced stage of dissection than that of the younger. This is as true of the moraines of valley glaciers as it is of the deposits laid by continental ice sheets.

Other criteria, either of less value or more difficult of interpretation, are discussed by Salisbury in the article cited.

With reference to all the criteria mentioned above, the farther north the evidence is found in the case of continental glaciation (in the northern hemisphere), or the higher the altitude at which it is found in the case of mountain glaciation, the more reliable will be the deduction for two distinct glacial epochs. To base judgment on any one of these criteria alone is unsafe. Two or more should be sought in the field before drawing final conclusions. On the other hand, if these lines of evidence are wanting, their absence must not be regarded as absolute proof against two glacial epochs.

CHAPTER VI

FIELD RELATIONS OF IGNEOUS ROCKS

TERMINOLOGY AND CLASSIFICATION

112. General Definitions.—While comparatively few people have actually witnessed a volcano in action, yet most of us know that a common phenomenon of volcanic eruption is the outpouring of lava; and we know further that this lava eventually cools and hardens into solid rock. Such lava, in all cases, has come up from within the lithosphere, and there are reasons for thinking that it may have come up a long way, perhaps many miles. Geology teaches us that molten rock does not always rise far enough to reach the earth's surface. Checked in its ascent, it may consolidate between walls of older, cooler rocks. Any rock which thus forms by consolidation from a molten condition is called an *igneous* rock (*ignis*, fire). Those rocks which become solid after ejection upon the earth's surface, either on land or below water, are *extrusive*, and those which harden from molten material injected below the earth's surface are *intrusive*. Molten rock is usually called *magma* when it is well below the earth's surface, and *lava* when it is just below or upon the earth's surface; but "lava" may also be applied to the *consolidated* extrusive rock. "Lava" is not correctly used except with reference to volcanic extrusion.

All igneous rocks, or certainly a large majority of them, are *eruptive* in the sense that each has probably been derived from a magma that had moved or "broken out" from the place where it originated as *magma*, but the word does not necessarily imply "breaking out" at the earth's surface, *i.e.*, it is not synonymous with "extrusive."

Country rock is a purely relative term used for the older rock into which magma has been intruded. It has no significance as to the composition or structure of this older rock. Blocks of country rock entirely surrounded by igneous material in such a way as to indicate that they were immersed in the magma and were then frozen into it, are *inclusions* or *xenoliths*. "Inclu-




FIG. 70.—Textures of igneous rocks. A, even-granular texture; B, C, D, porphyritic texture. In B the phenocrysts are sharply angular with definite crystal boundaries. In C the phenocrysts have rounded corners and embayments of the groundmass, both features being due to resorption. The parallel arrangement of the phenocrysts in D indicates the direction of flow of the original magma.

sion" must not be confused with "intrusion." The original bounding surfaces of an igneous body, both before and after consolidation, are its *contacts*. Although this term is also applied to unconformities, faults, etc. (14), in the present chapter it will be strictly limited to the walls of igneous bodies. A lava flow has a lower contact that separates it from the bedrock and mantle rock of the old land surface over which it spread,

and an upper contact which may subsequently become the basal surface of younger sediments or of flows superposed upon it without intervening denudation. The contacts of an intrusive rock are the surfaces at which it touches its country rock.

Terms which refer to the grain of igneous rocks, *i.e.*, to its size or to its presence or absence, come under the head of *texture*.



FIG. 71.—Basic segregations in a granitic rock.

Some igneous rocks are distinctly *granular*; others, so fine that no individual grains are visible, are said to be *dense*; and some are *glassy* or *amorphous*. The granular varieties are *even-granular* (Fig. 70, A) if the grains are of approximately uniform size, and *porphyritic* (Fig. 70, B and D) if one (or possibly two) of the minerals is conspicuously larger than the others so that the rock looks spotted. Such a rock is a *porphyry*.¹ The conspicuous grains in it are *phenocrysts* and the finer matrix in which they are scattered is the *groundmass*. The groundmass may be granular, dense, or glassy. If the variation in size of the grains of an igneous rock is so irregular that no distinction can be drawn

between phenocrysts and a groundmass, and many of the grains are exceptionally large, or if all the grains are very large, the texture is *pegmatitic* and the rock is *pegmatite*. In some pegmatites crystals have been found measuring several feet in length.

Features depending upon the arrangement of the constituents within a rock are *lithologic structures*. In the crystallization of

¹ A spotted appearance due merely to differences of color is not porphyritic texture.

molten rock certain minerals sometimes grow in groups, or *segregations*, or *clots* in the magma (Fig. 71). When these segregations are exposed they may appear as roundish spots and patches, commonly darker than the enclosing rock, and often




FIG. 72.—Amygdaloidal structure in lava. Quartz (white) was deposited on the walls of the original vesicles, and subsequently epidote (lined) filled the remaining open spaces. The vesicles in which the amygdales of B were deposited were flattened and drawn out by the flowing of the lava. (Natural size.)

with concentric structure; or they may appear as elongate streaks without any concentric structure. Layers and elongate “bundles” of the minerals composing the body of the rock, but in different proportions, and arranged so as to give it a streaky or



FIG. 73.—Pillow structure in lava ($\frac{1}{2}$ natural size). The concentric rows of dots represent layers of vesicles. Observe that the lower sides of the “pillows” are shaped against the upper surfaces of the underlying “pillows.”

platy appearance, are called *schliers* (*schlieren*). Lavas, when fresh, may be full of small pores or *vesicles*. They are then said to be *vesicular*. While the lava was still liquid, these pores were bubbles that contained gas or water vapor. If the vesicles are

subsequently filled with minerals that are deposited from solution in water or gas, the fillings are called *amygdales* and the structure is called *amygdaloidal* (Fig. 72). *Pillow structure* is formed in mobile lavas under special conditions of viscosity, temperature, and pressure. It makes the surface of a lava flow hummocky. In cross section it is seen to consist of roundish bunches or "pillows" of the lava, piled irregularly upon one another (Fig. 73), with the spaces between the pillows filled with volcanic ash, clastic sediments, limestone, vein deposits, or other minerals.¹



FIG. 74.—Flow structure in lava ($\frac{1}{2}$ natural size).

113. Flow Structure.—All igneous rocks must be regarded as having flowed into place. Those parts of the magma (or lava) that were adjacent to the original contacts cooled sooner and therefore reached stages of relatively high viscosity and, finally, of consolidation, before parts farther inside the igneous body. Where crystallization occurred, some minerals crystallized out of the molten mass before others. These crystals, if elongate or platy in form, had a tendency to turn into parallel position as they were carried along, their long axes being brought into alignment with the direction of flow. Similarly, groups of crystals (schliers, segregations), elongate or platy foreign inclusions (xenoliths), and layers differing somewhat in composition or

¹ For an excellent paper on this subject, see Bibliog., LEWIS, J. V.

texture (Fig. 74), may have become orientated parallel to the direction of maximum flow. In lavas, gas bubbles may be pulled out or flattened (Fig. 72, B). All these parallel features in igneous rocks, due to the effects of flow, are called *primary flow structures*. They are *primary* because they developed during the time of origin of the enclosing rock.

Two definite kinds of flow structure are recognized. One is *linear*, and the other is *platy*. In the former we speak of *flow*




FIG. 75.—Linear parallelism. Phenocrysts, mineral streaks, and xenoliths, arranged along roughly parallel lines, here vertical. In horizontal, and nearly horizontal, sections (top of block), the rock appears to be structureless. Figures 75 and 76 have been reproduced from Robert Balk's "Structural Behavior of Igneous Rocks," with kind permission of the author and the Geological Society of America.

lines; in the latter, of *flow layers*. Figures 75 and 76 illustrate these features. An igneous rock may possess either one or the other of these lithologic structures, or both combined. They may be very distinct, particularly near contacts, or they may be very obscure; but even in the massive granitic rocks, as has been pointed out by Balk,¹ careful search may reveal a faint tendency toward flow structure.

Where, during the origin of a rock, there have been forces that induced the constituent grains or crystals to assume a more or less

¹ Bibliog., BALK, ROBERT, 1937. This is a full presentation of the subject of flow structures and fracture structures in igneous rocks.

parallel position, we say that these grains or crystals have *preferred orientation*. In the case of an igneous rock, the forces causing preferred orientation were related to flowage, and resistance to flowage, of the magma (or lava). It is important to




FIG. 76.—Platy parallelism. Here, in contrast to Fig. 75, the phenocrysts, mineral streaks, and xenoliths are arranged in parallel layers, but parallel flow lines are also present in the layers. In A, the flow layers are horizontal, and the flow lines trend NE-SW. In B, both the flow layers and the flow lines are vertical. In C, the flow lines are horizontal, and the flow layers are vertical. In D, the flow layers are vertical, but the flow lines are inclined at an angle of 45°. (See caption for Fig. 75 for source.)

note that preferred orientation may be exhibited not only by the shape of elongate or flattish grains (dimensional orientation) but also by the arrangement of crystal axes (crystallographic orientation), as observed under the petrographic microscope.¹

¹ See Bibliog., KNOFF, E. B., and INGERSON, E., 1938.

114. Pyroclastic Rocks.—Another group of rocks should be mentioned here, because, although they are like normal clastic rocks in their manner of consolidation (by pressure, cementation, etc.), they are igneous in their ultimate origin. These are the so-called *pyroclastics* ("fire-broken"). When unconsolidated, they consist of volcanic dust, volcanic ash, lapilli, bombs, and broken pieces, large and small, of older rocks that were shattered by the force of eruption. These materials are also called *ejectamenta*. Dust, ash, lapilli, and bombs are generally particles or lumps of lava which were thrown up into the air in a molten condition, but which partly or completely hardened before they fell. Consolidated masses of dust, ash, and lapilli are known as *tuff*, and coarser pyroclastic debris, if consolidated, is *agglomerate* (223). Agglomerate has a tufaceous matrix just as conglomerate has a sandy matrix.

115. Contact Zones.—By virtue of their great heat and other properties, magma and lava may induce changes in the characters of the older rocks in contact with them, and conversely, these older rocks may directly influence the molten material while it cools. Effects of the first kind come under the head of *exomorphism* (ἐξω, outside, + μορφή, form), and those of the second kind come under the head of *endomorphism* (ἐνδον, within, + μορφή, form). Exomorphism and endomorphism are embraced in the term, *contact metamorphism* (μετά, beyond, over, + μορφή, form). These changes are usually most marked at the contact and die out away from it. The zone in which they are conspicuous may be termed the *contact metamorphic zone*, or briefly the *contact zone*, for each rock. If, as sometimes happens, the igneous rock blends into the country rock by a gradual change in character (121), there is no true surface of contact; there is, rather, a *mutual contact zone*. Except for purposes of discrimination, this may still be called a contact (122 to 135).

116. Classification of Eruptive Bodies.—Geologists speak of the *mode of occurrence* of an igneous rock, meaning by that the general form and size of the eruptive body and its relations to adjacent rocks. Extensive investigations the world over have

shown that intrusive masses are of two main varieties. Many were erupted *between* rock walls so that, at the time of their emplacement, they had older rock above and below them, and those which were vertical had side walls that corresponded to such upper and lower contacts; that is, the chambers occupied by these bodies seem to have had relatively small openings by




FIG. 77.—Sills of porphyry (black) in the Carboniferous formation of the Tenmile District, Colorado. (Tenmile District Special Folio, No. 48, U. S. G. S., 1898.)

which the magma gained admission. On the other hand, there are certain intrusive forms (batholiths, stocks, bosses) which, as far as observations demonstrate, enlarge downward and have no bottom contacts. No one has ever discovered a base for such bodies; only their upper or roof contacts and their side walls have been found. Accordingly, Daly¹ has proposed a division of intrusive forms into *injected*, those of the first type, and




FIG. 78.—Section showing three laccoliths. The feeder of *a* is not in the section. The magma followed a fault in rising to *b*. *c* is an interformational laccolith. Note that the strata are arched upward above each of the laccoliths.

subjacent, those which enlarge downward and have no demonstrable basal contact. Igneous bodies which were intruded into sedimentary country rocks are *concordant* if the magma was injected along the bedding planes, and *discordant* (or *transgressive*) if the magma was intruded across the bedding planes.

A *sill* is a layer of igneous material which has been injected between and along the beds of a sedimentary series (Figs. 77.

¹ Bibliog., DALY, R. A., Chapter V.

79, 80). It is relatively thin as compared with its lateral extent. Theoretically it tapers out at the edges, but this feature is seldom visible in a given sill. An *interformational sheet* is identical with a sill except that it has been intruded along a




FIG. 79.—Section of a sill from which short apophyses extend into the country rock both above and below.

surface of unconformity. It is always essentially parallel to the younger, overlying formation. A *laccolith* is like a sill except that the ratio between its thickness and its width is much greater than in the sill. Its roof is distinctly arched (Fig. 78). When a laccolith has been intruded along an unconformity it is said




FIG. 80.—Intrusive bodies in stratified rocks. *a* is a neck in both A and B. *b* is a dike in A and a sill in B. *c* is a sill in A and a dike in B.

to be *interformational* (Fig. 78). Sills, sheets, and laccoliths, although they are always concordant in their major relations, may break across the bedding locally (Fig. 79).

The term *dike* is used in this book for any sheet of igneous material not concordant with bedding (Fig. 80). Its contacts

need not be exactly parallel, *i.e.*, a dike may thin out or it may alternately pinch and swell along its length (143). An *apophysis*




FIG. 81.—Section of a chonolith which was injected *pari passu* with faulting of the country rock. Intrusion was essentially passive.

is a dike which extends out from a larger magmatic body and obviously tapers to a point (as seen in section) (Figs. 79, 83). A *neck* is a roughly cylindrical intrusive mass with one long and




FIG. 82.—Section of a chonolith which was intruded along a fault and which, in its injection, squeezed and contorted the country rock by the hydrostatic pressure of the magma.

two short dimensions. Its axis is usually vertical or steeply inclined (Fig. 80). A *chonolith* is an injection irregular in that its characters are not those of a true dike, sill, sheet, laccolith,

or neck, but, unlike the subjacent bodies, it has a floor (Figs. 81, 82).

A *batholith* is a large, irregular intrusive mass of igneous material which shows no evidence of having a base (Fig. 83). It is discordant in its relations to invaded strata. While its roof is roughly dome-shaped, there are often downward projections of the superjacent country rock which are called *roof pendants* (Fig. 83, *p*). Upward projections of the batholith are known as *cupolas* (Fig. 83, *c*). The side walls of batholiths




FIG. 83.—Block diagram of part of a batholith (white) and its schistose country rock. *c*, cupolas; *p*, roof pendants. Several inclusions of the country rock have been frozen in near the contact.

appear to be steeply and outwardly inclined. A *stock* is a small batholith. A *boss* is a stock with a nearly circular ground plan. Stocks and bosses are sometimes cupolas of concealed batholiths.

As regards extrusion, it has been suggested that, perhaps sometimes in the past, magma may have reached the earth's surface by the foundering of part of the roof of a batholith (Fig. 84). This Daly calls *extrusion by de-roofing*.¹ The two commonest methods, however, are by outflow from fissures and from tubular openings or pipes. These are known as *fissure eruptions* and *central eruptions*, respectively. When extrusion has ceased and the lava has become clogged in the conduit, the fissure type of

¹ Bibliog., DALY, R. A., p. 121.

filling is a dike or a sill, according to its relations, and the pipe filling is a *volcanic neck*. A *flow* is a sheet of lava. A *volcanic*




FIG. 84.—Ideal section illustrating the hypothesis that the rhyolite and the thermal phenomena of the Yellowstone Park are directly related to the foundering of part of the roof of a late-Tertiary batholith. (After R. A. Daly.)

cone is a conical, often symmetrical hill of volcanic material, either entirely ash or cinders, entirely lava, or partly lava and




FIG. 85.—Ideal section of a volcanic cone that has been built up on older rock (vertical ruling). The cone consists of pyroclastic material intersected by dikes of lava (black) which branch from the central neck. Along the course of each dike the lava rose until it broke out on the side of the cone, down which it flowed. The dike on the left is older than that on the right. (Why?) Bedding in the fragmental material has the characteristic angle of repose.

partly pyroclastic débris (Fig. 85). In any case it is apt to be intersected by dikes of lava.

The several modes of occurrence above defined may be classified as follows:¹

¹ After DALY, with some omissions and modifications. Other less common types are described by DALY; A. W. GRABAU, "A Comprehensive Geology"; and other authors of geological treatises.

A. Intrusive modes.**1. Injected masses.**

- a.* Concordant injections (intruded along bedding planes; occur only in stratified rocks). Sills, interformational sheets, laccoliths.
- b.* Discordant injections (intruded across the bedding planes if in stratified rocks). Dikes, apophyses, necks, chonoliths.

2. Subjacent masses.

- a.* Batholiths, stocks, bosses.

B. Extrusive modes.**1. Fissure eruptions.****2. Extrusion by de-roofing.****3. Central eruptions.**

Attendant phenomena: necks, flows, cones, etc.

117. Size of Eruptive Bodies.—Sills and interformational sheets may range in thickness from a fraction of a millimeter to over 1,000 ft., and in lateral extent from a few millimeters to many miles. Laccoliths vary in thickness from a fraction of an inch to several miles; they are commonly thicker than sills. They may be over 100 miles in length and nearly as wide, although they are usually smaller. Dikes may be from less than 1 mm. to over a mile in thickness, and they may be traced a few millimeters or as much as 25, 50, or even 100 miles. Chonoliths have dimensions similar to those of laccoliths. With regard to area of outcrop, stocks and bosses are arbitrarily taken as less, and batholiths as more, than 40 square miles. A batholith may be exposed over thousands of square miles. Individual flows are generally several feet thick and they may be over 100 ft. thick. If successive flows have been poured out one upon another, the total thickness may amount to many hundreds of feet. Volcanic necks may be from 10 ft. to a mile in diameter, but are seldom as much as 1,000 ft.

NATURE AND CONSOLIDATION OF MOLTEN ROCK

118. Nature of Molten Rock.—Magma may be regarded as a hot solution of certain volatile and nonvolatile substances. The nonvolatile ones include silica (SiO_2) and the oxides of Al, Fe, Mg, Ca, Na, and K, which, separate or in combination, com-

pose the principal constituents of igneous rocks. There is a wide variation in the proportions of these ingredients in different magmas, and correspondingly igneous rocks vary much in chemical composition (Appendix III). The volatile substances ("mineralizers"), such as water vapor, CO_2 , HCl , etc., probably enter only in small part into the composition of the minerals. Most of them escape either into the wall rocks (134), or, in the case of lava, into the atmosphere. The explosiveness of some kinds of volcanic eruption is occasioned chiefly by the escape of gases and vapors under diminished pressure.

119. Consolidation of Molten Rock.—By the process of eruption magma is brought up into regions of lower pressure and lower temperature. For subjacent eruption the change in both conditions is probably not large, but for injected and extruded bodies it may be very great. Reduction of pressure may have a number of effects of which, perhaps, the more important are the expansion of the magma itself, the expansion of its gases, and the increased chemical activity of these gases, which is an important cause of the high temperatures of lavas and probably magmas also.¹

Reduction in temperature induces cooling which may be very gradual or rapid. When magma is cooling a temperature will at length be reached at which some of the nonvolatile constituents will begin to separate from the hot solution as crystals. Now, crystallization always implies that the molecules of which the crystals are being formed must have enough freedom in the liquid to move and orient themselves, and this freedom depends upon the fluidity or mobility of the magma. If the cooling is very slow, so that the magma does not soon become viscous, relatively few crystals will originate and these will grow by the addition of molecules until the mass has become a coarse crystalline rock. But if cooling is very rapid the magma may become so sticky that the molecules are unable to move about and combine. The liquid becomes stiffer and harder, without crystallization, until it is a glass. If cooling is a little less sudden, yet not

¹See writings of THOS. A. JAGGAR, ARTHUR L. DAY, *et al.*

so slow as in the first example, there may be some opportunity for the molecules to move before the liquid becomes too viscous. Crystals may then originate at a great many points so near together that they will soon interfere and the resulting rock will be fine-grained. Evidently, then, *rate of cooling* is an important factor influencing the texture of an igneous rock.

The volatile constituents, or mineralizers, may be conceived of as lubricating the magma, as making it less viscous. By virtue of this property, not only do they increase the mobility of the molten material as a whole, but also they facilitate molecular movements within it, *i.e.*, they assist crystallization. In fact, the crystallization of some minerals, such as quartz, orthoclase, and albite (soda plagioclase), seems to be difficult or impossible without the aid of these volatile substances. Since ease of molecular migration in a cooling solution is conducive to the formation of relatively few, large crystals, an abundance of gases and vapors in a magma may function in the same way as a slow rate of cooling. Pegmatitic texture, which is thought to be due to the agency of an excess of mineralizers and particularly of water vapor, is often characteristic of the last portion of a magma to crystallize, because the volatile substances, being for the most part excluded from the composition of the minerals which they help to crystallize, are left in increasing proportion in the residual liquid.

There is still another factor which influences the fluidity of a magma, namely, the proportion of the nonvolatile components. Those magmas (*basic*) which have a relatively high content of lime, iron, and magnesium, and are low in silica, are thinner and more mobile than those (*acidic*) which are high in silica and the alkalis. Basic lavas flow quite freely and sometimes for long distances when they are poured out on the earth's surface, and the magmatic gases are readily given off from them; but acidic lavas are so viscous that the gases escape with much difficulty and generally with explosive violence. It might seem, therefore, that the basic, mobile magmas would consolidate with coarser texture than the acidic kinds, and undoubtedly this is

sometimes true; but rate of cooling and volatile content are so much more effective, at least as far as visible results are concerned, that the degree of control by nonvolatile composition is usually indeterminate. Thus, an acidic intrusive may be of coarser grain than a basic igneous rock into which it was injected.




FIG. 86.—Types of igneous contacts, as seen in cross section. The intrusive rock is blank and the country rock is lined. The contact is straight in A, jagged in B, blocky in C, blocky and matched in D, and sinuous in E.

sinuous, or lobate, jagged, and blocky

In brief, then, the viscosity and crystallization of magmas and the texture of igneous rocks are controlled by various factors of which temperature change and content of volatile substances are generally the most important. The beginner is advised to disregard pressure change and nonvolatile composition since the parts played by these are more difficult to gauge. Furthermore, he is warned not to make comparisons between the textures of different classes of rock and to draw conclusions accordingly. Because a granite happens to be coarse and a diorite is finer, the granite magma did not necessarily cool more slowly or have a larger proportion of volatile constituents than the diorite magma; but if the granite shows variations of texture within its own mass, these may be ascribed in most cases to the control of one or the other, or possibly both, of the factors named; and the same may be said of variations within the diorite.

CONTACTS

120. Shape of Contacts.—Intrusive contacts may be straight, jagged, blocky, sinuous, or lobate. These are shown in Fig. 86. Straight, jagged, and blocky contacts point to the invasion of fissures

by the magma. They signify that the country rock was in its zone of fracture (154), and that probably it was relatively cool as compared with the molten material. In the case of thin injected bodies, such as dikes and sills, the two edges are sometimes *matched*, *i.e.*, indentations on one wall may be seen to correspond to projections of like shape on the other wall (Fig. 86, D); but more commonly small blocks have been broken off and carried away by the magma so that the walls do not match. Sinuous and lobate contacts often indicate that the country rock was within its zone of flowage (154). The difference between the




FIG. 87.—Section of a lava flow resting on older material (vertical ruling). The flow is highly vesicular above, less so below, and is compact in its central portion. Its upper surface is scoriaceous. (Cf. Fig. 33.)

temperature of the country rock and that of the intrusive mass may not have been very great.

The upper and lower surfaces of a lava flow are generally very irregular. Below, the sheet is often cavernous, and above, it may be relatively smooth and ribbed (ropy lava, pahoehoe), or hummocky (pillow lava), or exceedingly rough and jagged (block lava, aa) (Fig. 87). Block lava owes its roughness to the coalescence and increase in size of vesicles at its upper surface and to the breaking of crusts which formed before its flow had ceased.

121. Sharpness of Contacts.—Some contacts are very definite, so sharp, in fact, that one can put the point of a pencil on the exact line (Fig. 88). In other instances there appears to be more or less blending between the country rock and the intrusive (Fig.

89). Sharp contacts may mean either: (1) that intrusion was rapid and the magma was soon chilled against the country rock; or (2) that there was not a strong tendency for the magma




FIG. 88.—Section of a sharp igneous contact between two igneous rocks. The rock on the left is the younger. This is determined by the fact that its texture becomes finer toward the contact, showing that its magma was chilled against the rock on the right, and that here, therefore, its crystallization was impeded. This is an example of a chilled contact zone.

gradually to alter or dissolve the country rock (129); or (3) that, if the magma invaded the country rock by some mode of chemical or mechanical replacement, it did so without filtering into the latter and it removed the products as fast as they were formed.




FIG. 89.—Section of a branching dike and its country rock. The contacts are blended; that is, there is nowhere a sharp division line between the two rocks.

Blended contacts suggest: (1) that the magma may have worked its way into the country rock and there crystallized in thin stringers or in isolated grains between the constituents of the older rock; or (2) that the magma had the property of gradu-

ally breaking down and altering the composition of the country rock. Each of these alternatives points to long-continued magmatic conditions; there could have been no sudden chilling. In other words, the country rock must have been relatively warm.

CONTACT ZONE IN THE ERUPTIVE ROCK

122. Principal Phenomena of the Contact Zone.—The contact zone in an eruptive rock (endomorphie zone) may exhibit the following characters which are more or less dependent upon the influence of the country rock, or, in the case of lavas, of the atmosphere: (1) textural variation; (2) vesicular and amygdaloidal structures; (3) flow structure; (4) fracture structure (214); (5) chemical and mineralogical divergence from the normal or average composition of the eruptive as a whole; (6) schliers and segregations; and (7) inclusions 136 142.

123. Marginal Texture.—Many igneous bodies are of coarser grain centrally than they are near their surfaces. This is explained by the fact that the molten rock after its eruption was chilled by its cooler surroundings, so that its crystallization was hindered (119). For the same reason lavas may be glassy above and more or less crystalline inside. These fine-grained marginal zones are spoken of as *chilled contacts* (Fig. 88).

It is worth while noting in this place that rock is a poor conductor of heat. Hence, in large intrusive bodies the chilled contact zone may not be very thick because, when once the country rock has been heated at the contact to a temperature near that of the magma, further loss of heat is exceedingly gradual, so that crystallization may proceed slowly in the unchilled portion of the magma. Lava flows, although rapidly frozen on the surface, may remain red hot and even liquid for a long time beneath a thin crust because this crust is a poor conductor.

Occasionally intruded masses are even-grained up to their contacts or they may actually be coarser near the margins. Even grain indicates that the conditions of the country rock were so near those of the intrusive that the inner and outer parts of the latter were affected almost alike. For example, the country rock

may have been so warm, either because of its depth or because the magma flowed by it for a long time, that it did not chill the magma. A coarser marginal phase may often be attributed to the local activity, near the contacts, of volatile constituents derived either from the magma itself or from the country rock.

124. Vesicular and Amygdaloidal Structures.—Vesicular structure is characteristic of extrusive sheets, but it may sometimes be found in rocks which were injected under little pressure. The pores may be marginal or central or they may pervade the mass. In sheets of lava (Fig. 87) they are commonly near the upper surface toward which they may become more and more numerous until the rock is scoriaceous or pumiceous. Vesicles near the lower contact of a flow in many cases originated on the upper surface or at the front of the moving lava and were then rolled under (223).

Since amygdales are merely the fillings of vesicles, their forms and relations are the same as those of vesicles.

125. Discrimination between Vesicular Structure and Weather Pits.—Little cavities left by the removal of the grains of a soluble mineral (36) may give to a rock the appearance of a vesicular lava. To discriminate between these weather pits and vesicles, break off a piece of the rock. A short distance in from the surface of the outcrop the weather pits will be seen to have the angular shape of the crystals which were leached out, and, farther in, the original crystals may still be present. Vesicles, on the other hand, will be rounded and empty.

An exception to this statement is the case in which vesicles have been filled with amygdales and the amygdales have been dissolved out by weathering near the outcrop surface. The broken fracture of the rock may show the remaining amygdales. It will then be necessary to apply the rules for distinguishing between amygdales and crystals (126).

126. Discrimination between Amygdaloidal and Porphyritic Structures.—Well-developed amygdales and phenocrysts should be easily distinguished, for amygdales are typically rounded mineral aggregates with concentric structure and phenocrysts

are generally single grains with crystal edges and angles (Cf. Figs. 70, B, and 72). Sometimes, it is true, phenocrysts have had their corners and edges rounded by resorption (magmatic solution) (Fig. 70, C), so that some of them look more like amygdales, but the other criteria just mentioned should be sufficient for their discrimination.

127. Flow Structure.—Flow structure has been briefly described in Art. 117. When it bears a definite relationship to the contacts of an eruptive body, as in the dike in Fig. 90, it may be regarded as one variety of endomorphic effects. On a larger scale, Fig. 91 illustrates flow structure in a stock or batholith.




FIG. 90.—Section of part of a dike and its country rock, showing the relation between the contacts and the flow structure of the dikes.

128. Fracture Systems.—In many eruptive bodies, both intrusive and extrusive, there are fractures that may be more or less regularly disposed and that may bear certain relations to the form of the body, or, in other words, to its contacts with the country rock. Since flow structure, also, is often related to these contacts, it follows that there may be a recognizable—often a very important—connection between the flow structure and the fracture systems within a given igneous body. More will be said on this subject in Art. 215, in the chapter on fractures and fracture structures.

129. Marginal Variations in Composition.—Many eruptive bodies have a gradual change in composition toward their contacts in a way to suggest that the variation must owe its origin to some outside control. We can imagine two general methods by which a magma might be so affected, namely, either by solu-




FIG. 91.—Flow structure in a stock or batholith. (After Balk. See caption for Fig. 75.) In each of the five diagrams, A is a vertical cross section, and B is a horizontal plan. Diagram 1 shows a dome of flow layers. 2. Arch of flow layers, with massive centre. 3. Dome of flow lines (not yet observed in the field). 4. Arch of flow lines. 5. Incomplete arch of flow lines. In 1 and 2, lines with black triangles indicate strike and dip of flow layers. A cross denotes horizontal flow structure. Arrows show pitch of flow lines. Double-barbed arrow denotes horizontal flow lines. In 4, B, the axis of the flow lines (dotted belt) coincides with the axis of the mass if on the right side of A and disregards it on the left of A.

tion and incorporation of some of the country rock, or by some internal process whereby certain mineral components might become separated from others and then segregated near the contacts or away from the contacts, as the case might be. The first and direct mode is *marginal assimilation*; the second, indirect way comes under the head of *differentiation*. Conceivably both might go on simultaneously. The products of assimilation are called *syntectics*, and those of differentiation are *differentiates*. Both processes, requiring high fluidity for their successful operation, might be expected to yield their most marked results in those intrusive bodies that consolidate least rapidly. Accordingly, we find that the best-developed contact zones of chemical or mineralogical variation are in the larger intrusive masses.

There has been much controversy about the relative efficiency of marginal assimilation and differentiation, and the problem is not yet solved¹ (see Art. 137). Without entering into the discussion, we may briefly point out a few criteria for distinguishing between the results of the two processes. Theoretically, if marginal assimilation had occurred to any measurable extent: (1) contacts would have rounded, lobate embayments into the country rock, and other marks of corrosion; (2) there would be some correspondence between the composition of the igneous rock and that of the adjacent country rock; and (3) the zone of chemical modification would have an increasing chemical similarity to the country rock toward the contact. For the case of magmatic differentiation: (1) there need be no evidences of corrosion at contacts; (2) the modified zone would have no special relation to the distribution of various types of country rock, and, therefore, while maintaining its own general characters, it might have a much greater extent than the area of the contact surface of any one of the invaded types of country rock; and (3) the modified

¹ N. L. BOWEN (see Bibliog.) has published papers in which he discusses methods of differentiation: (1) by the gravitative settling of crystals as they are formed in the magma; and (2) by compression, due to the forces of rock deformation, which may squeeze some of the remaining magma from between the crystals of the partly consolidated igneous rock.

zone and the adjacent country rock need have no chemical likeness.¹

In geologic field work it is important to ascertain: (1) whether there are marginal zones of chemical variation; and (2) if such zones do exist, just what the nature of the variation is, whether it is in any way related to the country rock and how it is related to the contact.

130. Schliers and Segregations.—Schliers (*schlieren*) and segregations are sometimes particularly numerous within a few score feet of the contact of large intrusive bodies. They are especially characteristic of the subjacent masses. Schliers are flow layers. In composition they may be similar to some of the main differentiated portions of the frozen magma. Segregations are apparently due to the separation of certain constituents from the magma and their crystallization about isolated objects, such as inclusions.

CONTACT ZONE IN THE COUNTRY ROCK

131. Contact Metamorphism.—Physical and chemical changes induced in rock material by the influence of magma or of lava may be accomplished by heating, by the infiltration of volatile and nonvolatile constituents of the magma, or, occasionally, by the pressure of intrusion. By chemical processes, discoloration, baking, and alteration in composition may be effected. Physical changes include tension jointing (214) and peripheral cleavage. The contact metamorphic zone (exomorphic zone) in which these features may be observed varies in thickness from a fraction of an inch to many hundred yards. It is usually thin adjacent to small intrusives and beneath flows. Its thickness and the extent of the alteration are roughly proportional to the size and temperature of the intrusive body, the duration of flow of the magma between the walls of a conduit, and the structure and composition of the country rock. For example, the roof above a batholith may be altered a long distance, sometimes a

¹ For further details see Bibliog., BARRELL, J., 1907; DALY, R. A., Chapters XI and XII.

mile or more, from the main contact, because batholiths are large and they lose their heat slowly. Likewise the contact zone about a volcanic neck may be disproportionately thick if the outflow of lava continued for a long time. Conduction of heat and infiltration of escaped magmatic substances are more easy along, than across, parallel structures, and therefore the thickest portion of the altered zone in rocks having cleavage, bedding, etc., is apt to be where these structures are perpendicular to the contact (Fig. 92). Finally, when magma is intruded into a rock having a composition very different from its own, the metamorphism is likely to be more intense and of greater extent than when the compositions of intrusive and country rock are similar.




FIG. 92.—Section of an igneous contact between an intrusive rock (blank) and its stratified country rock (lined). The latter has been metamorphosed (stippling) in a wider zone on the left where the bedding is transverse to the contact.

That is why a sedimentary country rock may be more severely altered than one that is igneous.

The physical and chemical features named above are described in Arts. 132–135.

132. Baking.—*Baking* refers to the hardening or toughening of rock material through the influence of magma or lava. Sometimes loose clays and sands are cemented just below a lava flow. Shale may become a very hard, flintlike rock, called hornstone, and quartz sandstone may become quartzite. Baking seems to be a process of cementation rather than compression. It may be due partly to the rearrangement and crystallization of substances already in the country rock, and partly to the infiltration and crystallization of some of the magmatic silica, etc. At exposed contacts in thinly and evenly banded shales, the banding may become obscure or fade away in the baked zone. Similarly, the cleavage of slates may gradually pass over into the irregular

fracture of hornstone. Being comparatively resistant to erosion, these hardened contact zones may form ridges where the same rock, not baked, is a valley-maker.

133. Discoloration.—Discoloration may be caused by a change in mineralogical or chemical composition. Greenish, grayish, or yellowish rocks may be reddened by magma through the dehydration of limonite ($2\text{Fe}_2\text{O}_3 \cdot 3\text{H}_2\text{O}$), or the decarbonation and oxidation of ferrous carbonate (FeCO_3), and the formation of hematite (Fe_2O_3).




FIG. 93.—Degree of contact metamorphism. The intrusive rock is diagonally ruled. A, B, C, and D represent successive stages of increasing contact metamorphism (stippling) in the country rock. The more intense metamorphism is indicated by the closer stippling.

134. Mineralogical and Chemical Alterations.—Alterations more striking than baking or discoloration are common in the contact zones of invaded rocks. The changes are brought about largely through the agency of water vapor and gases, most of which have filtered in from the magma, but some of which may have been in the country rock prior to intrusion. Many of these changes come under the head of pneumatolysis. Even silica and other nonvolatile substances are believed to escape in solution from the magma, assisting in chemical reactions, cementing the rock particles, and forming veins in the open spaces (237). New minerals are formed by the crystallization of substances derived

from the magma, by the breaking down and recrystallization of the original minerals, and by the combining of new and old constituents. Quartz, mica, garnet, andalusite, staurolite, vesuvianite, and tourmaline, are a few of the common species that may be developed in this way. Clay rocks sometimes become spotted in the early stages of metamorphism, the spots or "knots" often being small aggregates of carbonaceous matter. Ordinarily the variety of the new minerals is greater if the original rock was impure, for then there are just so many more substances from which different combinations may be made.

It is important to note, with reference to contact zones showing chemical or mineralogical alteration, that greater changes are produced at high than at low temperatures and that, at different temperatures, the same chemical constituents may unite in different associations to make different minerals. From this it follows: (1) that the country rock near the contact will pass through successive stages of increasing metamorphism as long as it is being heated and otherwise affected by the magmatic agents; (2) that ultimately a given type of country rock will be most altered near the contact and less and less so away from it; and (3) that, other things being equal, the higher degrees of metamorphism existing close to the contact in broad altered zones will be wanting in narrow zones and that consequently a given degree of alteration may be expected nearer the igneous




FIG. 94.—Maps showing relations of cleavage to intrusive contacts. The dash pattern represents the intrusive rock. In A the cleavage is essentially peripheral, probably because it was produced by the hydrostatic pressure of the magma. In B the cleavage was formed prior to the intrusion of the magma.

body in the narrower zones (Fig. 93). As a rule the effects of heat and of the infiltration of the magmatic juices proper are found to have been distinctly antecedent to the effects produced through the invasion of the volatile constituents (pneumatolysis).




FIG. 95.—Section of part of a batholith (blank and stippled) and its country rock (black) in successive stages of consolidation of the former. In A the stippling represents the portion which, having already crystallized, formed an outer envelope surrounding the still molten interior (blank). By further movements the magma was injected into this envelope (B). Black inclusions are foreign; stippled inclusions are cognate.

135. Cleavage.—As a result of eruption, cleavage (fissility) is not common. It is generally a product of dynamic metamorphism (see Art. 222), with no relation to intrusion, a fact which is demonstrated in numberless exposures where the cleavage is *cut across* by the intrusive bodies (Fig. 94). Where it is a consequence of the force of intrusion, it dies out away from the contact and its attitude is directly related to the igneous mass. It is

then roughly parallel to the contact and cases of intersection of this peripheral cleavage by the contact are local and insignificant.

INCLUSIONS

136. Cognate and Foreign Inclusions.—Inclusions have been defined as blocks of rock which were detached from the walls of a magma chamber and were eventually frozen into the resulting igneous rock. It is necessary to point out that not all inclusions are of the rock originally invaded by a magma. While a large body of molten material is undergoing differentiation, its marginal parts are crystallizing, so that at length a stage is reached in which the body consists of an outer hardened shell covering a still molten residuum of different composition. Very often the outer, earlier differentiates are more basic than the inner ones. If the residual magma for any cause is again disturbed and forced to intrude, it will have to invade its own external shell. Relatively acidic, light-colored dikes will penetrate this darker shell and blocks of the latter may be detached and immersed in the magma (Figs. 95, 96). Such blocks, having the same ultimate origin as the magma surrounding them, are called *cognate inclusions*. Inclusions of the country rock proper may be spoken of as *foreign*. Cognate inclusions are sometimes carried up in dikes, sills, etc., and foreign inclusions may be seen in all kinds of intrusive bodies, and even in flows; but both cognate and foreign xenoliths are most extensively developed in batholiths and large injected masses.

137. Overhead Stopping and Intrusive Breccias.—With reference to the large intrusive bodies, the passive rifting of blocks from the walls of the chamber Daly terms *overhead stopping*. He ascribes it to a sort of exfoliation consequent upon the heating and expansion of the wall rock (Fig. 97), assisted by the invasion of dikes (Fig. 98) and sometimes by the movement of the magma. In general the detached blocks sink as the magma remains sufficiently fluid. As the viscosity increases this settling is impeded and finally checked, so that the inclusions which are rifted off just

prior to consolidation can not move far from their sources. The consequence is that the big intrusive bodies may have an outer shell of *intrusive breccia*, in which inclusions, both cognate and




FIG. 96.—Section of part of a batholith and its country rock, C and E. The batholith consists of granite, G, with a basic border phase of diorite and gabbro, D. The diorite and gabbro appear to be older chilled phases of the batholith in which the granite later differentiated and into which the granite was intruded. (Penobscot Bay Folio, No. 149, U. S. G. S., 1907.) (Taken from R. A. Daly's "Igneous Rocks and Their Origin.")

foreign, are very abundant (Fig. 95), and this may pass into an adjacent surrounding cover of country rock ramified by numerous apophyses. If differentiation occurred and the magma was injected at intervals into its hardened portions, the contact zone of intrusive breccia might be very complicated in its nature.




FIG. 97.—Section of a contact between granite (dash pattern) and slate (lined). Fragments of the slate, detached by contact exfoliation, were frozen into the granite as inclusions. (After T. N. Dale.)

138. Characters of Inclusions.—Seen in cross section on the surfaces of outcrops, inclusions appear as more or less irregular patches which may be sharply angular, subangular, well-rounded, lobate with embayments, or shredded (Figs. 99, 100). They may vary in size from a fraction of an inch to enormous blocks measuring several hundred feet in their visible dimensions. Their contacts may be clearly defined or blended for the same reasons that were mentioned in Art. 121. Where sharp contacts and

angular forms are common, marginal assimilation has probably played an insignificant part. Sometimes there is a complete and uniform transition from the surrounding igneous rock to the central, unaltered portion of the xenolith, as if the latter had been in process of absorption when freezing stopped further encroachment by the magma. Foreign inclusions may, of course,

exhibit the same features, original or metamorphic, as the country rock. In them bedding, cleavage, etc., may still be preserved




FIG. 98.—Section showing details of a contact between schist and an intruded igneous rock (dash pattern). The separation of inclusions is here due principally to the invasion of dikes. Observe the relation between the shapes of the inclusions and their schistosity. In which direction do the dikes appear to have penetrated with greatest facility?




FIG. 99.—Shapes and distribution of inclusions (black) in an enclosing igneous matrix (white). A, angular inclusions. Some of the fragments may be seen to have fitted together. B, inclusions with rounded corners, suggestive of magmatic solution. The small inclusion at the extreme right was evidently broken so late that the corners of the fracture suffered no rounding. C, scalloped inclusions, the embayments of the eruptive rock being places where the magma dissolved its way into the inclusions. D, sliver-like inclusions in parallel position. The form is the result of an original well-defined parallel structure in the country rock. The orientation may be indicative of the direction of flow of the magma.

or, on the other hand, they may be baked, discolored, or mineralized. Their contact zones are concentrically arranged, the more extreme changes being in the outer parts. Since small inclu-

sions are apt to be more thoroughly altered than large ones, original structures should be looked for in the latter.



FIG. 100. A rock surface showing basic cognate inclusions in a more acidic matrix. Most of the contacts are irregular, suggesting that the magma was able to dissolve its way into the country rock, but the nearly straight matched contacts of the broad light dike on the left are clearly the result of fracture. They are of somewhat later origin than the irregular contacts. (Cf Fig. 99 B). (About $\frac{1}{4}$ natural size.)




FIG. 101. Vertical section of a contact to illustrate the source of inclusions.

139. Source of Inclusions.— When inclusions in an eruptive are situated near country rock of the same kind, as seen on an outcrop surface (Fig. 101), their source is fairly obvious, although

probably they were not carried directly across from the part of the contact (*b* in Fig. 101) at present exposed. They may have come up from some point on the wall, *bc*, that is now within the rock mass, or they may have come down from a portion of the wall, *ab*, which has been eroded away, or they may have moved along the trend of the contact line. For the geologist they are of particular interest when no country rock remains in the vicinity or when the wall rock that does outcrop is of an entirely different nature. Under these circumstances it is likely, but not absolutely certain, that inclusions in dikes have risen and that those in batholiths, chonoliths, and laccoliths have sunk; in other words, that the parent rock in the first case is below the land surface and that, in the second, it has been removed through denudation. Xenoliths in a batholith which has been broadly uncovered may thus give one a notion of the character of the eroded roof.

140. Discrimination between Inclusions and Segregations.—

The distinction between inclusions and segregations is not always easy or possible. The following characters are generally typical of segregations: (1) relatively small size, often only a few inches across; (2) rather uniform size on outcrops a few square yards or rods in area; (3) oval or circular cross section; (4) concentric arrangement of the constituent minerals; (5) one or more minerals in common with the inclosing igneous rock. On the contrary, inclusions are more frequently of irregular shape and variable size. As pointed out in the preceding paragraph, the larger ones often retain original features. Hence, the true nature of small xenoliths that look like segregations may be determined by comparing their composition and structure with the composition and structure of the outer zones of the larger blocks whose derivation is certain. As for cognate inclusions, there is every gradation between them and segregations, for both are more or less directly related to differentiation.

141. Discrimination between Large Inclusions and Roof Pendants.—In effecting the uncovering of a batholith, denudation isolates the roof pendants, if there were any such (Fig. 102). On a map they look like islands of country rock encircled by the

intrusive rock, exactly the same relations, in fact, as are exhibited by xenoliths in ground plan. Outcrops of country rock in an area which is certainly inclosed by the eruptive rock may belong, then, either to a large inclusion or to a truncated roof pendant. There are some geologists who assert that it is impossible to tell the difference between the two. However, if several of these isolated exposures of country rock are found, and in all of them structures like bedding, cleavage, etc., have a parallel or otherwise orderly arrangement of strikes, they are probably roof pendants. In the case of xenoliths, even when they are very near one another, such structures are apt to have diverse directions and




FIG. 102.—Block diagram of a batholith (white) and its country rock (lined) in successive stages of erosion. At the lower level (front of block) one of the roof pendants, *p*, has been isolated and so looks like a xenolith. Compare the orientation of roof pendants, *p*, and xenoliths, *x*.

no apparent relations, for blocks of country rock that have been detached from the walls of a magma chamber are free to change their positions.

142. Discrimination between Inclusions and Erosion Patches.

Small patches of rock left on a contact that has been laid bare by erosion are sometimes mistaken for true inclusions. These are described in Art. 151.

Another erosion phenomenon which beginners too often confuse with inclusions is an effect of unequal weathering of igneous rocks. Exfoliation, it will be remembered, is a process by which the outer surface of an outcrop spalls or peels off in thin plates. If these spalls come off unequally, first in one place and then in another, the rock acquires a patchy look, for each slab that peels off leaves a scar that has a color somewhat different from the

older surrounding surface. It is these scars that are sometimes taken for inclusions. They are especially common in glaciated regions which have been abandoned by the ice long enough for exfoliation to start on the smooth and polished surfaces. They may be distinguished by these characters: (1) often there are all gradations between the color of the latest scar and that of the original surface, for the spalls come off at different times, and with age the scars fade and so grow more and more like the old surface; (2) search may reveal some chips that have nearly come off and others which have separated so recently that they still lie loose on their own scars; (3) if it is possible to break the rock at the edge of a scar, the fresh fracture will be of uniform color both under the scar and under the old surrounding surface. Familiarity with rocks and minerals under various conditions of weathering is the best guide.

FIELD INTERPRETATION AND CLASSIFICATION OF ERUPTIVE BODIES

143. Shape of Eruptive Bodies.—Both extrusive and intrusive modes of occurrence may be discussed in this connection. Volcanic ash cones owe their slopes to the angle of repose of the pyroclastic débris of which they are composed (246). It may reach 40°. The form of a mass of lava depends in part upon the topography and in part upon the viscosity of the molten rock. Mobile flows spread far and are relatively thin as contrasted with those which are viscous. A cone built of lava poured from a central vent may have an inclination of less than 10°. From this extreme there are all gradations to the type of ejection known as a "spine," a column of lava so rigid that it does not flow at all.

As regards intrusive bodies, their shapes are governed: (1) by the viscosity of the magma, (2) by the structure of the country rock, (3) by the weight of the overburden, and (4) by the manner of intrusion. Thinness, coupled with relatively great extent in the other two dimensions (*e.g.*, many dikes, sills, etc.), implies rapid injection and a highly mobile magma, especially if the country rock appears to have been cool (120, 121) when

it was invaded. A sticky magma would move sluggishly, and slow intrusion would soon be brought to a stop by chilling. Where the country rock was nearly as warm as the magma, thin sheets do not necessarily prove rapid injection. That the country rock was warm and plastic enough to be deformed by the force of intrusion is suggested by the pinch-and-swell form of




FIG. 103.—Pinch-and-swell form of a pegmatite dike in schist.

many pegmatite dikes in schists (Fig. 103), by the local bending of the schist folia against such pegmatite dikes (Fig. 104), and by other phenomena.

The effect of greater viscosity on concordant injection is exemplified in the typical laccolith (Fig. 78), the domical roof of which indicates that the magma, being too sticky to slip in rapidly and far between the beds, heaved them up and arched them by the force of its hydrostatic pressure. Many observed laccoliths are not quite typical, for minor irregularities in the roof and the presence of some inclusions in the igneous rock prove that the act of intrusion was not wholly a process of lifting and wedging, but was assisted by the disruption of blocks from the walls of the chamber. In batholiths this disruptive process (overhead stop-



FIG. 104.—Section of a pegmatite dike cutting the foliation of a schistose rock.

ing) seems to have predominated as is indicated by the marked irregularity of the contact as a whole, frequently by the abundance of xenoliths, and by the usual total lack of correspondence between the attitude of the contact and the attitude of bedding in the roof rock. However, although the shape of the contacts of a batholith must unquestionably be ascribed in part to the separation of inclusions, this does not preclude the possibility that the

roof was uplifted. With wider and more intensive study of these large intrusive masses, evidence is increasing to the effect that upward pressure and upward expansion of the core of magma played a significant role in their emplacement. Such evidence includes doming and arching of flow structure in the intrusive body; systems of tension fractures so disposed that they indicate upward movement of the magma after the outer shell has already consolidated; zones of marginal upthrusts, in steep-walled intrusives, showing the effects of upward and outward expansion of the liquid core; gneissic marginal shells, due to intense mechanical forces of intrusion, etc.¹ The degree to which each of these processes (passive stoping of the roof and active forcible ascent and expansion of the magma) has contributed toward the emplacement of the magma and the ultimate form of the batholith should be investigated, in each case, by careful examination of all available field criteria.

144. General Summary with Reference to the Interpretation of Contact Phenomena.—For ease of reference we may classify here the principal facts presented in the foregoing paragraphs. *Place of intrusion* within the lithosphere, *i.e.*, whether in the zone of fracture or in the zone of flowage, is indicated by shape of contact, sharpness of contact, marginal textures, tension jointing, and shape of the intrusive body. *Manner of eruption* is indicated by shape and sharpness of contacts, presence of inclusions, characters of inclusions, attitude of flow structure, and shape of the eruptive body. Evidences for *kind and amount of assimilation* may be found in shape and sharpness of contacts, marginal variations in the composition of the intrusive rock, shape of intrusive body, and characters of inclusions. Evidences for *differentiation* appear in schliers, segregations, and cognate inclusions, and in marginal variations in composition of the intrusive body. *Rate of injection, rate of flow, and viscosity of magma and lava* are indicated by the shape of the eruptive masses. *Conditions of the country rock at the time of intrusion* are suggested by shape and sharpness of contacts, marginal textures of the intrusive, characters of inclu-

¹ See Bibliog., ROBERT BALK, 1937, pp. 122-129.

sions, kind and degree of contact metamorphism, and shape of the intrusive body.

145. Field Recognition of Eruptive Bodies.—The recognition of modes of occurrence of igneous rocks in the field depends upon a thorough understanding of the definitions given in Art. 116. It is well also to have a notion of the sizes which are characteristic of eruptive bodies (117). Bear in mind that sills are essentially parallel to the bedding of their country rocks; that chonoliths and laccoliths, as distinguished from batholiths, have basal contacts; and that the difference between a sill and a laccolith is principally one of the relations between thickness and lateral extent. There can be no such thing as a sill in a country rock which is not stratiform. For chonoliths, laccoliths, and batholiths, extensive field correlation is necessary because of the great size of these bodies.

Probably the most troublesome problem is the distinction between a sill and a flow which has been buried under later strata, now consolidated. (1) A flow is often vesicular or scoriaceous in its upper portion and may have pores and brecciated structure near its base. On the contrary, a sill is usually free from visible pores; but there are sometimes numerous short apophyses extending into the superjacent strata, and these, when viewed in cross section, may make the upper surface of the sill look as if it were a scoriaceous lava. If longer apophyses can be found, they are among the safest criteria for intrusion. (2) The cavities and depressions of a buried lava flow are generally filled with sediments that have their bedding lamination parallel to the main stratification above. If a sill has many short roof apophyses, the intervening downward projections of the country rock are apt to show more or less contortion. (3) A flow may rest upon beds of volcanic ash or other volcanic debris; yet it is not to be forgotten that sills, too, may be injected into pyroclastic materials. (4) Flows are not uncommonly overlain by sediments that contain angular blocks or water-worn pebbles of the lava. Eroded fragments of a sill cannot be present in the superjacent beds which were invaded by the sill. These overlying beds may seem to contain pieces of the sill rock if the magma was injected upward as a

network of ramifying pipes (Fig. 105). Careful study of this case would show that the seeming fragments of sill rock have chilled margins and that the inclosing rock has a metamorphic aureole round each "fragment." (5) Inclusions of the superjacent beds may be found in sills, but never in flows. (6) The effects of contact metamorphism may be present in the roof strata of a sill, but not in the beds above a flow, provided there is no other outside influence by which such alteration might have been induced.




FIG. 105.—Section of the upper contact between a sill (stippled) and its country rock of slate (lined), showing short roof apophyses which are pipe-like in form. The roundish patches of the sill rock in the slate are sections of these "pipes." (Section about 3 ft. long.)

146. Field Study of Structures of Igneous Rocks.—The two most significant kinds of structure in igneous rocks are flow structure (113) and fracture structure (214). Flow structure antedates fracture structure in time of origin, since the former develops while the rock is molten and the latter, after it has become hard enough to break or shear. For this reason it is best to begin the study of an igneous body by examining and mapping any flow structure that may be discovered in it; then the fracture systems should be mapped; and these should be studied and described in relation to the observed flow structure. Both features are usually best developed near the contacts. Both should be carefully examined on several surfaces of the rock as nearly as possible at right angles to one another. In recording notes and in mapping, discrimination should be made between linear and platy flow structure; also between the different classes of fractures (214). Detailed investigation of these phenomena in the field is important because they are of great assistance in ascertaining the

history and mode of occurrence of the igneous rock bodies with which they are associated.

ERUPTIVE BODIES IN RELATION TO THEIR TIME OF ORIGIN

147. Relative Age.—The age of an igneous rock is dated from the time when it was intruded, or extruded, and was brought into fixed relations with the adjacent older rocks. Thus, every intrusive body is younger than its country rock and every lava flow is younger than the underlying rocks and, if buried, older than the superjacent materials. In field work an important duty of the geologist is to determine the relative ages of the igneous rocks. This may be done in several ways. If, for instance, there are




FIG. 106.—A, intersecting dikes, *ab* being younger than *cd*. B, branching dikes, *ab* and *cd* being of the same age. How is the apparent displacement in A to be explained?

two kinds of dikes, outcrops should be searched until a place is found where one of these dikes cuts across the other (Fig. 106, A). Sometimes two or three periods of injection by the same type of rock may be demonstrated. Branching dikes must not be confused with intersecting dikes (Fig. 106, B). Where but one contact between two igneous rocks is exposed, the younger rock is apt to be progressively finer toward the contact (123). Even if the boundary line is concealed, the relations may occasionally be ascertained by discovering inclusions of one rock in the other, for inclusions are always older than the inclosing matrix.

As regards batholiths and other large intrusive masses, there is probably a long time interval between the consolidation of the outer portions and the freezing of the final residuum. Consequently, in point of crystallization, not only are cognate xenoliths

distinctly older than the surrounding rock, but also certain cognate inclusions may be older or younger than others in the same body. Within a given intrusive mass cognate inclusions are younger than foreign inclusions.

The age of an igneous body with reference to joints, faults, folds, and other structures, should likewise be noted. Straight and blocky contacts, particularly if they correspond to existing joints in the country rock, imply a fracture system antedating intrusion. Tension joints, due to contact effects (214), are clearly subsequent to the eruptive body that led to their origin.




FIG. 107.—Section of a dike, *cd*, which has entered a fault. The fault intersects a series of strata containing a sill, *ab*.

A fault which intersects and displaces an igneous mass is younger than the latter (Fig. 107). A fault that is essentially coincident with a contact may be older or younger than the intrusive. Thus, a region may be dislocated and then invaded by magma along the faults (Fig. 107); or slipping may take place along the contact surface of an eruptive body. In the former case the contact and the fault would be one and the same surface, except perhaps where apophyses had branched into the fault blocks; whereas, if dislocation followed intrusion, places could surely be found where the fault and the contact were not coincident, and any apophyses would be intersected by the fault. On the earth's surface, lava flows and ash cones are sometimes aligned in such a way as to suggest that the magma ascended along a fault. The case may be proved by finding topographic

evidences of displacement along the general trend of the volcanic vents (Chapter VIII).

There are many reasons for believing that intrusion of large magmatic bodies and deformation of their country rocks are more or less synchronous. By definition, the updoming of the roof of a laccolith is accomplished by the invading magma. Batholithic intrusion seems often to have closely followed, or even accompanied, large scale deformation. These phenomena are regarded as parallel effects of the same cause.

148. Geologic Age.—Since igneous rocks do not hold fossils their geologic ages must be fixed by correlating them with sedi-




FIG. 108.—Section of part of a batholith, *b*, and its country rock, *a*, both of which were eroded and overlain by later strata, *c*.

mentary rocks whose age is known. Flows and pyroclastics are of the same geologic age as the sedimentary rocks with which they are interstratified. For intrusives, the following example may suffice to illustrate the method of correlation. In Fig. 108, *b* is intrusive into *a* and pebbles of *a* and *b* are found in *c*. Fossils show that *a* is Cambro-Ordovician and *c* is Devonian. Hence the age of *b* is between Ordovician and Devonian.

ERUPTIVE BODIES IN RELATION TO THE LAND SURFACE

149. Significance of the Exposure of Intrusive Rocks.—The presence of intrusive rocks upon the earth's surface is evidence of the work accomplished by erosion. Sometimes a thick covering has been removed and sometimes a thin one. For magma, in its eruption, reaches various levels within the lithosphere. Most striking is the case of batholiths. In these bodies the magma probably does not rise to within several hundred or even several

thousand feet of the surface except, perhaps, in rare instances (116), so that where subjacent masses are exposed, a thick cover of country rock has, little by little, been worn away and the débris has been laid down elsewhere in some area of deposition.

150. Topographic Expression of Igneous Bodies.—Exposed intrusive bodies are so often more resistant than the inclosing country rocks that usually they have a more pronounced relief. The higher central parts of many mountain ranges consist of batholithic rocks. Unroofed laccoliths may form groups of hills that rise above the surrounding country (Fig. 109). The smaller injected bodies, such as necks, dikes, and sills, are generally more resistant or less resistant than the country rock, and,




FIG. 109.—Section of an interformational laccolith, Bear Lodge Mts., Wyoming. *S.*, syenite porphyry; *M.*, Lower Mesozoic; *C.*, Carboniferous; *Ca.*, Cambrian; *Ag.*, "Algonkian" granite. Length of section, 6 miles. (Sundance Folio, No. 127, U. S. G. S., 1905.)

correspondingly, they may have positive or negative topographic relief (245) (Fig. 110). Horizontal or gently inclined sills and flows are sometimes the protective layers surmounting mesas and cuestas (278).

151. Relations of Contacts to Erosion.¹—The student who has arrived at the stage at which he undertakes his own geologic surveying will be disappointed to find how often important contacts—usually those he most wishes to map—are quite hidden beneath the soil. The reason is obvious. The agents of erosion, obtaining more easy access along these surfaces, wear the rocks down more rapidly, and the depressions then become floored over with débris. In this way a valley may have its position fixed along a single contact (270, B). In other cases, where a weak rock lies between resistant materials, the former may be worn

¹ See also Art. 345.

away, and the valley (or gully) will have its walls situated somewhere near the contacts (Fig. 110, A).

If the rock on one side of a contact is much less resistant to erosion than that on the other side, the weaker rock, whether intrusive or country rock, may be worn away to such an extent that the outcrop surface practically coincides with the contact.




FIG. 110.—Topographic relations of a dike and its country rock, as seen in vertical section. A, dike less resistant than country rock. B, dike more resistant than country rock.

At a certain stage in the erosion, when this coincidence has been all but accomplished, the more resistant rock will be exposed only in small areas where a thin remaining cover of the weaker material has been perforated (Fig. 111, A).

A little later the weak rock will be removed except for a few scattered patches (Figs. 111, B; 112). The perforated spots in the earlier stage and the patches in the later stage are very easily mistaken for inclusions.

To determine whether patches on the surface of an igneous rock are true inclusions or not, look over the whole outcrop and




FIG. 111.—The diagram shows an uneven contact between an igneous rock (dash pattern) and its country rock (lined on front face; black on top and side faces). The front face of each block is assumed to be a surface produced by erosion. In A the remaining layer of the country rock has been perforated, and in B, a somewhat later stage, only a few patches of the country rock are left.

see whether they are distributed on all sides. Erosion patches are limited to those rock surfaces that correspond to contacts. In the earlier stage, above mentioned, the perforation spots can often be enlarged by splitting off some of the layer of weaker rock, and in the later stage the patches themselves can be broken off with a hammer. This weaker rock may be found in place in

greater amount just beneath the soil at the foot of the outcrop or along the strike of the contact surface on other ledges in the vicinity.

On a much larger scale, the exposure of intrusive bodies presents some interesting problems. Consider, for instance, a batholith with an irregular roof. At first all the bedrock in the region is the normal country rock (Fig. 113, A). As denudation



FIG. 112.—Patches of a trap dike (dark gray) still attached to its country rock. Here the dike was the weaker rock. (Cf. Fig. 111.) The largest patch is about 15 in. long.

proceeds, the land surface at length reaches what we may call stage 2. In this stage, although the bedrock is still entirely the roof rock of the batholith, there are a few closed areas in which evidences of contact metamorphism may be recognized. These are the places where cupolas will soon be uncovered (Fig. 113, B). In the third stage several cupolas (stocks) are exposed, each being rimmed by a collar of the metamorphosed country rock (Fig. 113, C, *a*). There may be closed tracts of metamorphosed country rock which cap the shorter cupolas. The outcrop areas




FIG. 113—Successive stages in the exposure of a batholith through erosion. Batholith, dash pattern, country rock, blank where unmetamorphosed, ruled where metamorphosed. *a* is a stock (cupola) surrounded by the metamorphosed country rock.

of the cupolas grow larger and coalesce, as erosion goes on, so that, in the fourth stage, the bedrock of the region consists principally of the intrusive, with here and there isolated tracts of country rock which are, in reality, truncated roof pendants (Fig. 113, D). In the fifth and last stage the land surface is entirely on the batholithic igneous rock (Fig. 113, E).



FIG. 114.—Section of part of a batholith (dash pattern) and its country rock (black). Much of the country rock has been stripped off by erosion, so that the land surface in many places essentially coincides with the roof contact. The valleys have been incised below the contact well into the batholithic mass. (The section is about 8 miles long.)

Possibly there are some regions where the roof contact of a batholith or of a flat-lying intrusive mass (sill, laccolith, etc.) has become the land surface over several square miles. The weaker superjacent country rock has been stripped off except for a few scattered remnants, and the resistant eruptive rock has been only locally incised by streams (Fig. 114). The evidences for this broad scale coincidence of erosion surface and




FIG. 115.—Section of an intrusive body and its country rock. The thickness of the contact metamorphosed zone (shaded) of the country rock is the same on both sides of the intrusive mass (ab and de). The breadth of exposure of this zone is greater the lower the inclination of the contact (ab and cd).

contact include: (1) extensive distribution of like contact phenomena on the outcrops of the eruptive; (2) marked decrease in the variety and intensity of contact phenomena downward in those valleys which cut well into the intrusive body; (3) the isolated remnants of country rock, just referred to, especially if these are clearly sessile upon the eruptive; (4) accumulations of débris of the country rock on the summits of hills and ridges now consisting entirely of the intrusive rock; (5) similarity in shape and other characters between the general configuration of

the topography and visible contacts beneath the remnants of the country rock.

152. Relations of Contact Zones to Topography.—The breadth of an exposed contact zone is seldom equal to the thickness of the zone, because the land surface is usually inclined to contacts at an angle less than 90° (Fig. 115). Instances of this kind should not be confused with cases like that illustrated in Fig. 92. Figure 116 shows two explanations for an observed increase in the degree of contact metamorphism without apparent cause.




FIG. 116.—Vertical sections showing relations of the land surface to the degree of contact metamorphism. Intrusive rock, dash pattern; country rock, ruled. In each case, A and B, the degree of contact metamorphism grows less in going from a toward b, and then increases again, reaching a maximum at b. The explanation is obvious.

153. Effects of Topography on the Shapes of Outcropping Dikes, Sills, and Contacts.—The influence of topography upon the form of outcrop surfaces and layers is most conveniently treated with reference to stratified rocks. Consequently the subject is reserved for Art. 174. The student has only to remember that, when dikes and sills are of comparatively uniform thickness, their exposed edges are related to the land surface in exactly the same manner as are the exposed edges of strata, and that the same comparison may be made concerning regular igneous contacts and surfaces of conformity in sediments.

CHAPTER VII

TILTED AND FOLDED STRATA

DEFORMATION OF ROCKS

154. Fracture and Flowage.—From the time of their origin rocks are more or less disturbed by forces acting within the lithosphere. On a broad scale, the movements which bring about slow changes of sea level (286) demonstrate the operation of these forces; but more striking evidence is furnished by the joints, cleavage, and folds that are so often seen in consolidated rocks. The deformation represented by these and other allied structures may be brought about through fracture or flowage. By flowage is meant a gradual change in the form and internal structure of a rock mass accomplished by chemical readjustment and by microscopic fracture while the rock remains essentially rigid. There is no igneous fusion during the process. The rock does not become molten. Under very great pressure and temperature, such as exist deep below the earth's surface, all rocks yield to stress by flowage rather than by fracture. High temperature and pressure, the presence of moisture, and the nature of the rock itself, are factors influencing this flowage. Nearer the surface rocks are more apt to break; but some rocks may flow even at depths of only a few hundred feet. For any rock subjected to differential pressure we have, then, a *zone of flowage* below and an enveloping shell or *zone of fracture* above. The maximum depth of the zone of fracture for rocks least capable of flowage is placed at about 11 miles.¹ Below that depth all rocks flow if deformed. However, when we speak in terms of all rocks, the outer 11-mile shell of the lithosphere becomes

¹ Bibliog., ADAMS, F. D.

almost entirely a *zone of combined flowage and fracture*, because different rocks vary so much in their susceptibility to flowage when under stress.

Structures produced in the zone of fracture are joints, faults, brecciation, autoclastic structures, fracture cleavage, etc. (Chapter VIII). In the zone of flowage originate flow cleavage, schistosity, gneissic structure, etc. (Chapter IX). Folds (flexures) may result from either fracture or flowage, and very often they are the product of both processes combined.

TERMINOLOGY AND CLASSIFICATION

155. Principal Kinds of Folds or Flexures.—As seen in cross section, the principal forms of tilted and folded strata are as follows:

A *syncline* is a downfold opening upward (Fig. 117, A, D).

An *anticline* is an upfold opening downward (Fig. 117, B, E).

A *homocline* is a group of strata which have a fairly regular amount of dip in the same general direction (Fig. 117, C).




FIG. 117.—Cross sections of types of folds. A, symmetrical syncline; B, symmetrical anticline; C, homocline; D, asymmetrical syncline; E, asymmetrical anticline; F, monocline; G, structural terrace; H, isoclinal anticline and syncline; I, chevron folds; J, resurgent folds; K, fan folds. In A, B, D, and E, σ is the position of the axial surface.

A *monocline* is a step-like bend in otherwise horizontal or gently dipping beds. It consists of a change in the *amount* of dip from gentle to relatively steeper and back again to gentle (Fig. 117, F), but the direction of dip remains essentially unchanged.

A *structural terrace* is a step-like or shelf-like flattening of the dip in more steeply inclined strata (Fig. 117, G). In a certain sense it is the reverse of a monocline.

The term *monoclinal dip* (also called homocline) refers merely to a dip in the same general direction. A homocline may be diversified by several monoclines and structural terraces.

156. Terms of General Application.—Folds are bodies of three dimensions, that is, they have height, breadth, and length, a fact




FIG. 118.—Symmetrical syncline shown in three blocks. *ab* and *cb*, limbs; *de*, axis; *def* axial surface. Note broadening of syncline with depth. (See parallel folds, p. 171.)

which is too easily forgotten because they are usually represented in plane cross sections. Figures 118 and 119 show the directions of the three dimensions of the folds of which only the height and breadth are indicated in A and B, Fig. 117. In each of these diagrams (118 and 119), the fold is symmetrically divided into two essentially equal parts by a vertical surface (*def*), called the *axial surface*.¹ The line where this surface intersects any particular bed or horizon in the folded group of strata is called the *axis*

¹ Often called *axial plane*, though probably never a *plane*, since this surface is warped through the irregularities of folding.

of the fold in that bed or horizon (*e.g.*, *ed*). The two parts of the fold, one on each side of the axial surface, are its *flanks* or *limbs* (*ab* and *bc*, Figs. 118, 119).

In Figs. 117, A and B, 118, and 119, the anticline and syncline are drawn with their axial surfaces vertical. If the axial surface




FIG. 119.—Symmetrical anticline shown in three blocks. *ab* and *bc*, limbs; *de*, axis; *def*, axial surface. Note narrowing of anticline with depth, a feature of considerable importance in petroleum geology. (See parallel folds, p. 171.)

of a fold is inclined, as in Fig. 117, DE, the beds in the two limbs may have very dissimilar dips. It has been customary to describe the former type of fold as *symmetrical* and the latter as *asymmetrical*, referring to the mutual relations of the dips in the two limbs rather than to the geometrical relations of the limbs to the axial surface.¹

¹There is a decided practical advantage in the first definition of symmetry, herein used and commonly understood, because, for the second definition, the whole underground form of the fold must be known, and this is rarely possible. Furthermore, if the whole form is known, terms other than symmetry and asymmetry may be applied to better advantage. Symmetry refers to the *dips* of the beds, and *dips* are measured from the horizontal.

In an asymmetrical fold, the axis does not coincide with the highest part, or crest, of an anticline, nor with the lowest part, or trough, of a syncline (Fig. 120). This is a very important




FIG. 120.—Asymmetrical anticline (left) and syncline (right), seen in cross section; *acb* axial surface of anticline, seen in section; *egf*, same for syncline; *dc*, crestal surface of anticline; and *gh*, trough surface of syncline, both seen in cross section. Any crestal line, or trough line, would be perpendicular, or nearly perpendicular, to the plane of the diagram.

point to remember. In such folds, the line where any given bedding surface meets a horizontal plane may be called the *crest line*, in an anticline, or the *trough line*, in a syncline. The surface that includes the crest lines in successively deeper beds in an anticline is the *crestal surface* of that fold; and the corresponding surface in a syncline may be termed a *trough surface* (Figs. 120 and 121).

Note that the axis of an asymmetrical fold migrates, in successively lower beds, toward the more steeply dipping limb in synclines and toward the more gently dipping limb in anticlines (Fig. 117, D and E). This fact has a bearing on the accumulation of oil and gas in asymmetrical folds.¹




FIG. 121.—Cross section of an anticline with a warped axial surface (*acb*); *dc* is the cross section of the crestal surface.

The upper bend of either a terrace or a monocline may be referred to as the *head*, or *upper break*, or *upper change of dip*, and the lower bend is the *foot* of the terrace or monocline, or the *lower break*, or the *lower change of dip*.

157. Varieties of Folds.—Anticlines and synclines may be simple, composite, or complex. A fold is *simple* when its curve

¹ Bibliog., HEWETT, D. F., and C. T. LUTON, 1917, p. 34.

is simple; *composite* when it consists of smaller anticlines and synclines; and *complex* when its axis is folded, *i.e.*, when the fold is cross-folded. Simple folds are drawn in Fig. 117.

A composite anticline is called an *anticlinorium* and a composite syncline, a *synclinorium* (plural, anticlinoria, synclinoria) (Fig. 122). Whenever a set of small folds is superposed upon a group of larger folds, the former are called *minor* and the latter *major*. All major folds are composite. If the axial planes of the minor folds converge downward in an anticlinorium or upward in a synclinorium, the major fold is called *normal* (Fig. 122, A




FIG. 122.—Synclinoria (A and C) and anticlinoria (B and D).

and B); if the opposite is true, the anticlinorium and the synclinorium are *abnormal* (Fig. 122, C and D).¹

A very extensive uplift, generally anticlinal in its nature, is a *geanticline* or a *regional anticline*. In the same way, a great synclinal area is termed a *geosyncline* or *regional syncline*. Examples of the former are the Arbuckle Mountain Uplift in southern Oklahoma, the Central Mineral Region of Texas, and the Sabine Uplift of northern Louisiana. Examples of regional synclines are the Mississippi Embayment, the Rio Grande Embayment, the Permian Basin of western Texas, and the geosyncline of eastern Texas, just west of the Sabine Uplift.

Where stratified rocks have an average inclination in some general direction over a wide extent of territory, this inclination

¹ Bibliog., VAN HISE, C. R., 1896, pp. 608-612.

is called a *regional dip*. It differs from a homocline in that it may be variously modified by changes in the amount and direction of dip, and even in *reversals* of dip, as long as the average is maintained. These reversals and less conspicuous variations




FIG. 123.—A, dome fold; B, basin fold.

are referred to as *local dips*. They are also called *abnormal* to distinguish them from the regional or *normal* dip. A regional dip is generally the limb of a geosyncline or of a geanticline.

Types of complex folds are the *dome fold* or *dome*, and the *basin fold* or *structural basin*. A dome is anticlinal in two vertical sec-




FIG. 124.—Anticlinal and synclinal canoe folds, represented in part. The axes of the folds are inclined downward (pitch) toward the background.

tions at right angles to one another, and a basin fold is similarly synclinal (Figs. 123, 482). If the folding is much closer, *i.e.*, if the compression has been much more intense in one direction than at right angles to this direction, the folds are much longer in comparison with their width. The elongated basin fold may then

be called a *canoe fold*, and the dome may be called an *inverted canoe fold*, or a *ridge fold* (Fig. 124). Domes and inverted canoe folds are referred to as *anticlinal closures*, and structural basins




FIG. 125.—A complex fold which is synclinal in one section and anticlinal in the perpendicular section.

and canoe folds, as *synclinal closures*, on account of the fact that, when they are represented by structure contours (456), these contours are closed (Fig. 482).

Sometimes a fold, which is anticlinal in one section may be synclinal in the perpendicular section (Fig. 125). Such a fold is termed a *saddle*. It may be an upfold along the axis of a syncline, or a downfold along the axis of an anticline.

A local anticlinal warping on the limb of a major fold or on any monoclinial dip is an *anticlinal bowing*, or *nose*, in reference to the




FIG. 126.—Parallel folding.

fact that contours showing this type of structure bend or bow out toward the direction of the dip (Fig. 482). The corresponding synclinal structure, in which the contours bend in the up-dip direction, is a *synclinal bowing* (Fig. 482). Anticlinal and synclinal bowings pitch or plunge in the direction of the general dip.

Folding may be parallel or similar. In *parallel folds* (also called *concentric folds*) each bed is of approximately uniform thickness throughout its course in both anticlines and synclines (Fig. 126).




FIG. 127.—Similar folding.

The effect of this relation is that the bedding surfaces are not of the same shape. Both upward and downward folds die out.¹ On the other hand, in *similar folds* the bedding surfaces are of similar shape and the beds vary in thickness (Fig. 127). Their limbs are thinned and their axial regions are thickened. Such folds may be persistent upward and downward through a thickness of rock which is very great as compared with the amplitude of the contortions of any one bed.




FIG. 128.—Diagram illustrating the differential movement between adjacent beds in parallel folding.

Deformation in parallel folding is accomplished by adjustment between the beds, and in similar folding, by adjustment within the beds. In both cases the movement is differential. In parallel folding this movement is such that a given bed slides upward against the next underlying bed toward anticlinal axes (Fig. 128). Adjustment within beds is effected principally by rock flowage. It requires more energy than the shearing of strata one upon

¹ The student is here reminded of another way in which an anticlinal fold may die out with depth. See p. 649, where the effects of convergence are described.

another. Hence we find that similar folds are characteristic of the zone of flowage, whereas parallel folds are characteristic of the zone of fracture. Similar folding is common in metamorphic rocks having flow cleavage (Fig. 129). The field classification of folds may be aided by the facts enumerated in Arts. 476 and 477.

158. Size of Folds.—Folds range in breadth from very minute contortions, seen only by the aid of a microscope, to great arches and troughs many miles from axis to axis. Diminutive folds, naturally limited to fine-grained rocks, are always subordinate in that they are superposed upon larger folds. They may



FIG. 129.—Sketch of contorted laminae in a specimen of mica schist. (Length of figure about 1 ft.)

form low, subparallel ribs and furrows on the cleavage surface of a rock, and they are then termed *crenulations*.

Anticlines and synclines are usually lower than they are wide. Exceptions are found only where the strata have been intensely deformed. In folds large enough to map, the dips of the limbs vary from only a few feet per mile to 90° .

159. Competent or Controlling Beds.—The unequal susceptibility of different rocks to deformation by flowage seems to indicate that if a sufficient force were applied laterally (parallel to the beds) to a formation consisting of layers of varying resistance, the individual beds would be affected in different ways; and, as a matter of fact, this is actually the case. In a series of this

kind a strong stratum, if arched up, may tend to support the overlying beds and thus lessen the vertical pressure on the rocks below it. "Willis' experiments on the mechanics of Appalachian structure¹ showed that the thicker, more competent wax layers rise in simple outline under given conditions of pressure and load until they are unable to lift the load farther. Then they crumple and, in crumpling, thicken, enabling them to lift the load higher.




FIG. 130.—Diagrammatic section showing differential movement between competent beds on the limbs of a fold with the development of minor drag folds between them. (After C. K. Leith.)

Thus composite folds are really indications of incompetence. Simple folds are more characteristic of the zone of fracture; the bed is able to lift itself without interior adjustment, and without crumpling; it is competent."² As Leith and others have pointed out, this term, "competence," is one of relative value only. One rock may be competent with respect to a second and incompetent with respect to a third.

When a series of strata is subjected to lateral pressure, there is at first a tendency for the formation of parallel folds. This, as

¹ Bibliog., WILLIS, B., 1892, pp. 241-253.

² Bibliog., LEITH, C. K., pp. 111, 112.

we have seen, means slipping between the beds. If the strata are of different degrees of resistance and the conditions are such that the stronger layers are in their zone of fracture while the weak beds are in their zone of flowage, the readjustment by slipping may be concentrated in the weaker, incompetent layers. The series will then be folded after the parallel pattern, being




FIG. 131.—Drag folds produced in an incompetent bed between two competent strata. (Cf. Fig. 130.) The differential motion at the bedding contacts is indicated by the arrows *e*, *d*, *e*, and *f*. *X* and *Y* show the relative differential movement of the two competent beds. *ab* is a section of the axial plane of one of the drag folds. An anticline is to the right of the figure and a syncline is to the left.

controlled as a whole by the competent strata; but the incompetent beds will bear evidence of flowage either in flow cleavage or in minor folds of the similar type. Minor folds of this origin are primarily the result of the differential movement or "drag" between the competent strata, and they have therefore received the name of *drag folds* (165). Since, in the differential movement between strata, a given bed slips over the subjacent layer in a direction toward the

nearest anticlinal axis, the drag folds are overturned in this direction and their axial planes generally converge downward in the major synclines and upward in the major anticlines (Fig. 130). The axial planes of the drag folds are inclined with the direction of differential movement (Fig. 131).

160. Strike, Dip, and Pitch.—The definitions in Art. 12 hold for folded strata. In Fig. 132, A, the strike is east-west and the dip is 45° S. In Fig. 132, B, the strike is north-south and the dip is W. on the east side of the block and E. on the west side. The axis of the syncline shown in this diagram is horizontal, but in Fig. 132, C, the axis is inclined northward, and a section through *a*, *b*, and *c* shows the angle of this inclination in its relation to the horizontal (Fig. 132, D). This angle is a special case of dip and is known as the *pitch* or *plunge* of the fold. Here, then, we have

a syncline pitching 10° N. It is obvious from the diagrams that the strikes of the limbs of such a fold, the axis of which lies in a north-south vertical plane, are not parallel as in Fig. 132, B. In a syncline they diverge, and in an anticline they converge, in the direction of the pitch.

CAUSES AND CONDITIONS OF FOLDING

161. Causes of Tilting and Folding.—Although a detailed discussion of the causes of deformation of rocks is not within the province of this book, a few words of explanation may not be amiss. There are probably at least seven causes of tilting and folding of strata. These are: (1) settling due to weighting; (2) differential compression; (3) tangential compression; (4) faulting; (5) igneous intrusion; (6) invasion of salt; (7) secondary changes including chemical alteration and unequal weathering.

1. In regions of long-continued deposition there seems to have been a gradual widespread settling of the floor in which the sediments have been accumulating, almost *pari passu* with the sedimentation. This settling, called *isostatic settling*, results in the bending of the strata, already deposited, downward toward the area of maximum subsidence. The inclination of the beds, after such bending, has been termed "initial dip" by Bailey




FIG. 132.—Diagrams of dip, strike, and pitch.

Willis.¹ In a thick series of sediments, it is greater in the lower beds, which have undergone more settling, than in the beds higher in the formation.

2. The compressibility of sediments under load has been mentioned in Art. 72. We may suppose: (1) that the total shrinkage of a thick sedimentary formation will be greater than that of a thin formation; and (2) that the shrinkage of a given formation will be greater the larger the proportion of highly compressible materials (mud, clay, peat) to slightly compressible materials (sand) within the formation.




FIG. 133.—Vertical cross section illustrating the arching of strata over ridges in the basement. These buried ridges or buried hills may have been due to faulting followed by erosion, *a*; exposure of a plutonic body, *b*; differential erosion of hard and soft strata, *c*, *d*.

As a result of unequal compression, individual layers in such a sedimentary formation are likely to be bent or warped. A series of strata resting unconformably upon an uneven basement might thus become deformed so that the beds would sag toward the depressions in the surface of unconformity; or, in other words, they would arch over the original uplands (Fig. 133). This may be the explanation, at least in part, of the structural relations of the Carboniferous strata to the subjacent "Granite Ridge" in central Kansas.² For a similar reason, but on a smaller scale, sand or sandstone lenses within a formation may induce bending of overlying, and even of underlying, more compressible strata.

We have learned that the average distribution of sediments along a coast is such that sands predominate near shore, muds

¹ See footnote, page 66.

² This subject has been discussed at length by SIDNEY POWERS, particularly in papers on buried hills. See Bibliog., POWERS, SIDNEY, 1922; *Ibid.*, 1926.

farther out, and limy oozes beyond the muds (78). In the progress of a transgression of the sea, the mud phase migrates over the basal sand phase. Between the principal sand body and the principal mud body there will be a transitional zone of considerable thickness in which layers of sand and mud will alternate, the mud increasing in amount upward and the sand increasing




FIG. 134.—Vertical section through littoral marine sediments laid down during a transgression of the sea from right to left. Vertical scale exaggerated.

downward in the series. At any given time during the transgression, the proportion of mud to sand, as measured vertically from top to bottom of the growing sedimentary formation, will be greater seaward. Let us assume a hypothetical case, illustrated in Fig. 134. The total thickness of mud and of sand, before compression, at points A, B, and C, is given as follows:

Station	Thickness of formation, ft.	Total sand thickness		Total mud thickness	
		Ft.	Per cent	Ft.	Per cent
A	500	400	80	100	20
B	1,000	400	40	600	60
C	2,000	400	20	1,600	80

Considering only the strata represented in the figure, let us suppose that the sand will suffer 1 per cent vertical shrinkage and the mud 15 per cent vertical shrinkage, of its original thickness, after further transgression of the sea and the deposition of a heavy overburden of younger sediments. The figures will then be as follows:

Station	Original thickness of sand, ft.	Compressed thickness of sand, ft.	Original thickness of shale, ft.	Compressed thickness of shale, ft.	Total shrinkage of formation, ft.
A	400	396	100	85	19
B	400	396	600	510	94
C	400	396	1,600	1,360	244

The total shrinkage of the formation, given in the last column, represents the quantity by which the original surface of the deposit, and, therefore, the beds which were at the surface, are lowered through the effects of the compression, using the foregoing hypothetical values (72).

From A to B a secondary dip of 75 ft. is produced, and from B to C, a secondary dip of 150 ft.

Although these figures are hypothetical, they suggest that the original inclination of the beds in extensive growing deposits may be increased not only by settling of the foundation (see 1, above), but also by the unequal compression of the strata, involving an increasingly great reduction in their thickness away from the source of supply.

3. Probably the folding ordinarily observed in strongly deformed strata is an effect of lateral or tangential compression within the lithosphere, *i.e.*, of compression by forces acting in approximately horizontal directions. Briefly, this compression is thought to be a consequence of strains and stresses induced by the earth's gradual shrinkage. Geologists believe that these stresses slowly increase until finally they somewhere overcome the resistance of the lithosphere to deformation. Then yielding occurs by breaking or by folding. In the earth's history this yielding seems often to have occurred in regions of heavy sedimentation where, already, there may have been some weakening by bending due to isostatic settling (§ 1) and differential settling (§ 2).

The conception has been generally held that the compressive forces have operated essentially perpendicular to the axes of the resulting folds (Fig. 135). That such may not be the case has been recently pointed out in an illuminating article¹ by Warren J. Mead, who shows that overlapping, pitching folds, occurring in groups and with roughly parallel alignment of their axes—a condition frequently found in deformed strata—may be produced by shearing stresses (Fig. 136). Mead writes, "It seems probable that the movements between great earth masses are in the




FIG. 135.—Plaster of Paris positive of folds produced by compression or shortening. The force was applied perpendicular to the length of the folds. (After Warren J. Mead.)

nature of shears rather than simple straight-line compression. In other words, *the application of a compressive force directly toward the point of maximum resistance would be less probable than the development of a couple which would cause what has been called a rotational stress*" . . . He thinks that "most of the faults or folds" in deformed strata "are the result of the riding or dragging of the upper layers by" shearing movements in "the underlying materials."²

4. Flexing produced by faulting may be local, as in the case of drag dips (180, 191); or it may become rather extensive,

¹ See Bibliog., MEAD, WARREN J.

² *Ibid.*, p. 521..

where folds are associated with flat overthrusts, with zones of overlapping faults in the origin of which torsional forces operated, and, finally, in slump faults on the flanks of settling geosynclines (Art. 185).

5. Deformation associated with, and produced by, the intrusion of magma is referred to in Art. 116.




FIG. 136.—Vertical view of reproduction, in plaster of Paris, of folds produced by shearing deformation. The direction of movement is indicated by arrows and the amount of deformation is shown by the shape of the block. (After Warren J. Mead.)

6. In some parts of the world, notably in Roumania, north-eastern Germany, Holland, the Gulf Coastal region of Mississippi, Louisiana and Texas, and the Isthmus of Tehuantepec, there are dome-shaped uplifts of stratified rocks associated with central plugs of salt. These structures are known as *salt domes* (Fig.

137). The salt core generally stands nearly vertical and has a roughly circular or oval horizontal section, measuring from 1,000 ft. to two miles or so in diameter. It extends downward to an unknown depth. In this country wells have penetrated salt more than 3,000 ft. without going out of it, and there are reasons for believing that the plugs in Europe extend downward 15,000 and even 20,000 ft. The sides of the plug dip at angles of 30° to




FIG. 137.—Ideal vertical cross section of a salt dome showing salt, cap rock consisting of upper layer, *a*, chiefly of calcite (limestone), and lower layer, *b*, consisting of gypsum and anhydrite. An older series was intruded and uparched, then eroded, and finally covered by younger beds. Subsequently renewed uplift domed the younger strata.

90° . The salt mass itself is composed of salt crystals which are sometimes columnar, having their long axes essentially in a vertical position. It may be marked by streaks closely resembling the flowage lines in gneisses, and these streaks may be parallel to the sides of the plug or they may be severely contorted, like the structure shown in Fig. 129.

A majority of the Gulf Coast domes are crowned with a so-called "cap rock" varying in thickness up to 1,000 ft. or more,

and consisting essentially of crystalline anhydrite. Associated with the anhydrite may be gypsum, probably an alteration product of the anhydrite, and also limestone or dolomitic limestone, and in some cases sulphur.

Adjacent to the salt, the surrounding sedimentary strata, generally ranging in age from Cretaceous to Recent, have been faulted and turned up at sharp angles against the sides of the plug and have been arched over it where they were deposited prior to the latest thrust of the salt. In some instances proof has been found of a total displacement amounting to 5,000 ft. or over. Recent investigations are more and more clearly demonstrating that the upthrust of many of these domes was intermittent, probably with long intervening periods of quiescence. Beds more recent than the latest thrust of the salt core are not uparched.

Domes like those above described, where the strata have been not only uparched but also punctured by the salt plug, are *piercement domes*.

Geophysics has indicated that there are many *deep domes* below which drilling has not reached the salt plug, which apparently arched a very thick prism of overlying beds without intruding them. These are sometimes called domes of the *nonpiercement* type.

Salt domes are found for the most part in regional synclines (geosynclines) where heavy sedimentation has occurred. Furthermore, they are distributed roughly along lines which parallel the major structural trends of the region.

Although many theories have been proposed to explain the origin of these salt domes, the view most commonly held in this country until the early 1920's was that the salt was deposited from ascending waters. However, serious objections to this theory have been presented.¹ In Europe, where the domes are often laid bare to considerable depths by erosion, and where, consequently, a more certain idea of their structure and origin

¹ Bibliog., ROGERS, G. SHERBURNE; p. 460; also DeGOLYER, E., et al.

can be obtained, geologists have come to believe that the salt was thrust upward into the sediments like a punch, principally by mechanical means, assisted by the ordinary processes of granulation and recrystallization supposed to accompany the development of schistosity in metamorphic rocks (224). The source of the salt is thought to have been in deep-lying salt beds (Lower Miocene in Roumania; Permian in Germany and Holland; probably Jurassic in Mississippi, Louisiana, and Texas), from which it was squeezed upward at points of minimum resistance.

In view of the many features common to our Gulf Coast domes and those of Europe, particularly the unmistakable indications of great mechanical upward force, we may conclude that the origin is similar in each case and that the salt of the Gulf Coast domes has been derived from sedimentary salt deeply buried in bedded deposits. The chief force involved was probably downward pressure of this great load of overlying strata, a force that caused the salt locally to move upward in a semiplastic condition along lines and at points of weakness.

7. In regions underlain by stratified formations which include some soluble members, these members may be gradually dissolved and carried away by subsurface waters. This may cause the overlying strata to sag toward the area of maximum removal by such solution (321).

INTERPRETATION OF TILTED AND FOLDED STRATA

162. Discrimination between Primary and Secondary Dip.—The inclination of layers, when not over 30° or 40° , may be original (73, 246). Sometimes it is hard to discriminate between primary dip and the secondary kind of dip induced by deformation. Ordinarily, laminae which have a primary dip as high as 25° or 30° are cross-beds (84) in the main stratification, and, therefore, they are of limited length. When the geologist is doubtful whether he is dealing with primary or secondary dip, he should examine other outcrops in the vicinity, and particularly large outcrops, since on these the major structure may

be apparent. Cross-lamination is to be expected in eolian and fluvial sandstones.




FIG. 138.—Sections of strata illustrating the relations of primary dip to deformation. A, cross-bedding in its original position, with a primary dip of 30°E . B, the same cross-bedding after it has been tilted eastward through an angle of 30° ; it now has a dip of 60°E . C, the same cross-bedding as that in A after it has been tilted 30° westward; it is now horizontal, in spite of the fact that the strata have been tilted. D, the same cross-bedding as that in A after it has been tilted 60° westward; it now has a dip of 30°W .

Primary dips of lower angle are distinguished with less facility. In general, where cross-bedding is absent, the main stratification of coarse fragmental materials (sand or gravel) may be expected to have an original inclination of 2° to 5° or even 8° . This remark applies to piedmont alluvial deposits, topset beds of small deltas and sand plains, beach deposits, etc. If the rocks of a region belong unquestionably to these types, and if they have dips of these low angles, their inclination is not sufficient reason for assuming that they have been tilted since their accumulation. On the other hand, strata laid down with approximately horizontal attitude, now inclined at a low angle, have probably suffered slight deformation.

To understand how to solve this problem, one must have a knowledge of the manner in which different kinds of sedimentary material are deposited and one must correlate dips and strikes in many outcrops, sometimes over wide areas. Note that a single outcrop with a low dip, or a small group of exposures with low dips, may be situated in the axial region of a broad fold.

163. Amount of Tilting.—Provided beds were accumulated in a horizontal position, their dip is a measure of the angle through which they have been tilted, in any given locality; but if they were laid down with a primary inclination, the amount of their rotation is not correctly expressed by their present dip. Figure 138 illustrates three cases (B–D) where the axis of tilting was coincident with the original strike of the strata when deposited.

164. Direction of Forces.—While it is impossible here to enter into a discussion of the dynamics of folding, a word or two may be said concerning the direction in which forces are supposed to have acted in the formation of folds. A monocline is often the product of a vertical or nearly vertical displacement consequent upon crustal tension; or it may be an effect of local adjustment in the vertical bodily uplift of huge blocks of the lithosphere. In some cases basin folds may be made by downsagging of the area deformed, and dome folds may be due to local upthrust or to peripheral settling. In this connection it is well to bear in mind the possible origin of folds through differential compression (161, ¶ 3). The forces in these instances have acted vertically.

We have already mentioned the two hypotheses for the origin of typical diastrophic folds (161, ¶ 3). According to one the compressive force acted normal to the fold axes and according to the other this force was a component of a shear which operated oblique to the fold axes.

An asymmetrical fold suggests an overthrust force acting from the direction toward which the axial plane dips, *i.e.*, from the side of the less steeply inclined limb (Fig. 139). This force may have been a differential pressure applied through the mass of the folded zone or it may have been a drag consequent upon the over-riding of a more rigid superjacent body of strata (Fig. 131); for there is no reason for assuming that the drag folds must neces-




FIG. 139.—Section of an asymmetrical fold which was formed by forces acting probably in the general direction of the arrows.

sarily be small because they are subordinate in a composite fold. The asymmetrical form of a fold might also be attained by an underthrust from the direction of the steeper limb (Fig. 139), a possibility which should be considered in reference to Mead's hypothesis of subjacent shearing (161, ¶ 3). The condition of asymmetry depends upon a multiplicity of factors, such as initial surface features of the folded tract, original inclination of the strata, relations of force and resistance, and the like.

165. Significance of Minor Folds in Relation to Major Folds.—

Reference is made here only to folds produced by earth stresses. In contorted schists and gneisses, rocks which have undergone severe dynamic metamorphism, the folding is very irregular and




FIG. 140.—Drag folds in an incompetent bed between two competent beds. According to the rule, the competent layer on the left moved up with respect to that on the right. Consequently, these beds must be in the limb between an anticline on the right and a syncline on the left, and the beds on the left must be stratigraphically above those on the right.

all the layers have shared about equally in the deformation. The plications approach the similar type, although not uncommonly one fold may be seen to narrow and die out while beside it another broadens correspondingly. These are actually corrugations on larger folds and the larger ones may be superposed upon still larger ones, and so on. Originating in the same period and under the influence of the same forces, these sets of folds are apt to possess like characters. Their difference lies principally in their dimensions. Naturally we should expect to find that the minor folds pitch if the major fold pitches, and probably in the same general direction. Careful study of these small folds may, therefore, suggest the nature of the larger

structure of a region and serve to guide the geologist in the methods to be adopted in his field investigation (323).

Drag folds produced in the manner described in Art. 159 may help to unravel the major structure. Since their axial planes are inclined with the direction of differential movement, they suggest the position of the major folds (Fig. 140). In a vertical or steeply

dipping series this method also shows which is the top and which the bottom of the beds, for the younger and upper layers are toward the synclinal axes. (See also 228 and 229 on use of cleavage in interpreting folds.)

166. Top and Bottom of Steeply Inclined, Vertical, and Overturned Beds.—It is customary to assume that any layer in a series of strata is older than the overlying beds and younger than the underlying beds. When strata are vertical, their relative age cannot be determined by superposition. When they are steeply inclined this method of reasoning is unsafe, too, for they may have been turned beyond the vertical and thus be overturned. Indeed, in very severe folding, beds may be turned




FIG. 141.—Sections of steeply dipping strata as seen on a horizontal or nearly horizontal surface. The younger (upper) beds in both A and B are toward the south. Explain this fact.

quite upside down (Fig. 117, H), but rocks thus affected would presumably show signs of considerable metamorphism. In the investigation of steeply dipping beds and metamorphosed strata of lower inclination, the geologist must therefore seek criteria other than superposition to demonstrate the true relative order of stratification, or, as it is termed, the stratigraphic sequence (108).

Geologic structures of assistance for this purpose are: (1) regional unconformity, with an associated basal conglomerate (77); (2) local unconformity (81) (Fig. 141, A); (3) curved cross-bedding, concave upward in the bedding and with the upper ends of each set of laminae truncated above by the next overlying set (84) (Fig. 141, B); (4) gradational texture from coarse below to fine above in individual beds or laminae (87); (5) ripple marks, but not in all instances (84, H); (6) the attitude of fossils

(98); (7) fossil footprints; (8) mud cracks (58); (9) raindrop impressions (59); (10) the attitude of drag folds (165), of cleavage (228, 229), and of joints (228).

FOLDS IN RELATION TO THEIR TIME OF ORIGIN

167. Age of Folds.—In a folded series of strata the deposition of the beds antedated their deformation. The folds are younger than the strata. Generally, joints and faults in such a formation are younger than, or contemporaneous with, the folding. They should not be regarded as older than the latter unless there is definite proof of the fact.

The geologic age of folding is determined by correlation with strata of which the geologic age is known. In the district sectioned in Fig. 108, the folding was post-Ordovician and pre-Devonian, for the strata (*a*) are deformed, whereas the overlying series (*c*) is not so. Both folding and erosion, as well as the intrusion of *b*, must have occurred between the two periods of sedimentation.

168. Two or More Periods of Folding.—To demonstrate that rocks have been subjected to two or more periods of folding is difficult if the evidences are sought in a conformable series of beds. Both complex folding and the superposition of small plications upon larger folds are phenomena commonly of contemporaneous origin. Cross-folding, so-called—*i.e.*, the deformation of fold axes—is not a criterion for a second period of folding



FIG. 142.—Section of a surface of unconformity between two series of folded strata. The strata below the unconformity have been through two periods of deformation.

(Figs. 135, 136). Moreover, variations in the intensity of folding, parallel or normal to the main axis, are perfectly characteristic of crustal blocks deformed in one diastrophic period. The only safe criterion for two distinct epochs of folding is found in undoubted cases of angular unconformity in which the younger beds have been folded (Fig. 142). Here the older strata must have suffered from deformation twice, once to account for the angle between the two series, and again, when the overlying

beds were folded. The determination of successive periods of folding requires widespread geologic investigation and careful correlation of the observed facts.

169. Folds That Originate in Unconsolidated Sediments.—

There are several ways in which folds may be produced in beds prior to consolidation. Some such plications fall under the head of contemporaneous deformation (83); others do not. Like cross-bedding and other primary structures, they may be preserved during the lithification of the strata in which they are formed, so that their occurrence is not limited to unconsolidated materials. In any case they are of peculiar interest in denoting




FIG. 143.—Section of contorted fine sand and laminated clay overlain by like sediments which are not deformed. *ab*, line of local unconformity. The shape of the folds indicates that the deforming agent moved from left to right. What is the significance of the fact that the folds die out downward? (Length of section about 2 ft.)

certain conditions under which the sediments were deposited. Ten varieties are described below and an attempt is made to point out criteria which may be of service in their interpretation.

1. A block of ice floating in a lake or in the sea may scrape over the bottom and rumple up the muds and fine sands which are in process of accumulation (Fig. 143). Folds and faults thus produced are examples of contemporaneous deformation. When formed, they are confined to a relatively thin upper zone and they die out downward. Upward the folds are sharply truncated by the surface of erosion made by the berg, and they are overturned in the direction of its motion. Since deposition of the mud or sand continues after the passage of the

ice, the erosion surface is soon buried and so becomes a local unconformity.

A series of beds exhibiting this kind of contortion is usually characterized by fine texture, by thin, uniform lamination, and by general regularity except in the crumpled zones of the type just described. These zones may be few or many, according to the size and number of the bergs which made them. They are not apt to be of great extent in the plane of the main bedding. In formations that exhibit these features, search should be made for isolated boulders (93) and other evidences of the association of ice in the work of deposition.

2. In the forward motion of glacier ice on land the ice may not only erode, but also dislocate, aqueoglacial sediments which have




FIG. 144.—Till overlying folded aqueoglacial strata. *ab* is a line of unconformity. The folding and the erosion, *ab*, were performed by ice moving from left to right (Length of section about 200 ft)

been laid down in front of the advancing ice margin. A thickness of several feet of strata may be affected; the sediments are not limited to uniformly laminated fine sands and clays; and till often rests upon the eroded surface that truncates the deformed beds (Fig. 144). Many examples have been cited, in the literature, of glacial clays, esker and kame gravels, and other bedded deposits, which have thus been scoured and deformed. Overriden clay beds sometimes reveal grooves and scratches on the surface of unconformity, if this has been exposed. Overturned folds and reverse faults show by their attitude the direction from which the ice thrust came. This structure may also be classified as contemporaneous deformation.

3. A structure very similar to 2 is that of outwash beds which were spread out before a *retreating* glacier and were subsequently overridden and deformed by a new advance of the ice. The

time elapsed between the deposition of the strata and their erosion may have been scores, hundreds, or even thousands of years, so that this can hardly be called an example of contemporaneous deformation. The discrimination between the folding and erosion effected by ice moving over its own frontal outwash and the folding and erosion performed by ice moving over the retreatal deposits of an antecedent advance requires careful search for the criteria listed in Art. 111.

4. During the winter season in northern climates, the expansion of the ice covering of ponds and lakes is relieved by crowding of the ice up the beach. This process, for which evidences may be seen in the boulder piles of "walled lakes," may be accompanied by slight erosion and by deformation that may be called contemporaneous, provided the disturbed sediments constitute the beach. In most cases the ice probably rubs up over the beach materials, but it may carry along some sand and gravel which have been frozen into it, or it may push up a ridge in front of it. The overridden layers are apt to be crumpled and dragged forward, so that small folds are overturned landward. They may be truncated above by an erosion surface (local unconformity); downward they grade into the uncontorted beds. At most this folded zone can be but a few feet in thickness, and between winters it is likely to be reworked and spread out by wave action. Normally only a narrow strip of sediments along the beach can be handled in this way; but if water level rises or falls during a succession of years, the effects may be distributed over a much wider belt. Stationary water level would result in excessive disturbance of the same materials; falling water level would result in the exposure of the contorted beds to erosion by rainwash, etc.; and rising water level would bring the deformed zone of each winter beneath the water surface where it might be preserved by subsequent lacustrine deposition.

5. When ice crowding occurs in swamps, muds and organic materials may be contorted on a broad scale.

6. By alternate freezing and thawing, sediments that are ordinarily soaked with moisture suffer repeated expansion and

contraction which may occasion local deformation in them. Properly speaking this would not be *contemporaneous* unless the time interval between the deposition of the sediments and their deformation were comparatively short.

Contemporaneous deformation originating on lake shores, in marshes, and in water-soaked sediments, is not necessarily associated with a capping surface of unconformity produced by the slight shove of the ice. It is much more probable that the folds will die out both downward and upward. They will grade upward into a zone in which any original bedding was destroyed by the upheaval and settling of the loose grains and pebbles.

7. Mud flow is a possible cause of folding in unconsolidated beds. The coefficient of friction is so low in moist clays and muds, especially under water, that slipping may be induced even on slopes of only 2° or 3° . The "flow" may be distributed in the form of contortion through the thickness of one or more beds. As might be expected, the folds are overturned toward the direction of motion. Sometimes this distributed crumpling develops into an actual sliding of the overlying mud or clay along a surface that truncates the tops of the little folds and lies approximately parallel to the bedding. The resulting structure, though closely resembling the contemporaneous deformation due to grounding ice blocks, is likely to be of wider extent in the plane of stratification. Isolated boulders and other evidences for the former presence of ice might serve as a means of discrimination were it not for the fact that there is nothing to prevent mud flow in bodies of water in which icebergs are floating.

8. Valley strata of various kinds, generally fluvialite, may be torn up, folded, and eroded by the sudden deployment of an avalanche. A vertical section would show the heterogeneous avalanche material resting unconformably upon the distorted beds.

9. Removal of mineral matter in solution from a rock which is undergoing decomposition may lead to irregular settling and contortion of overlying strata. Increase of volume induced by decomposition may crowd and fold rocks near the surface. Plica-

tions formed in these ways are not overturned in any particular direction.

10. Monoclinical folds, and sometimes more involved folding, may be produced in unconsolidated beds as an effect of faulting in the subjacent rocks.

In neither 9 nor 10 is local unconformity genetically associated with the deformation, and in neither instance is this deformation contemporaneous, as the term has been defined.

170. Discrimination between Folds Originating before and after Consolidation.—In folded shales, clay slates, and sandstones, and occasionally in other elastics, some difficulty may be experienced in deciding whether minor folds were produced through superficial agencies or through earth stresses, in other words, whether they are to be interpreted as evidences for conditions of sedimentation or for conditions of diastrophic deformation. Unfortunately, there seems to be no constant and striking character peculiar to either class of deformation. Yet certain features may be noted, which are suggestive of one origin or of the other.

In the first place, superficial folds, having an origin unrelated to stresses and strains within the earth's crust, have no direct structural relation to the major deformation in the neighborhood. Herein they differ from minor diastrophic folds, but the fact is not always easy to ascertain. Second, superficial folds are often much more disorderly and involved than diastrophic plications, because there is less opportunity for readjustment under the pressure and confinement of relatively great depths. Again, superficial folds are usually localized in beds which are overlain and underlain by uncontorted strata. Very often the crests of the anticlines are bevelled off by a surface of contemporaneous erosion (iceberg, glacial ice, shore ice, landslide) or by a shear plane (mud flow, etc.), and more rarely the troughs of the synclines at the base of the folded zone are truncated by a shear plane; whereas small diastrophic folds commonly die out gradually upward and downward into the less deformed strata. However, there are exceptions in which, both upward and down-

ward stratigraphically, superficial folds pass into uncontorted beds, and, on the other hand, diastrophic plications may be found in layers that are truncated above and below where there has been shearing of the undeformed beds over the crumpled zone, and of the crumpled zone over the subjacent undeformed beds. Truncation, then, is not a safe criterion.

The discrimination of these two kinds of folds is not a question that is likely to arise in the case of metamorphic rocks, flat-lying lithified sediments, or unconsolidated strata. In schists and gneisses any original plications that may once have existed have probably been masked beyond recognition. Minor contortion in metamorphic rocks is generally diastrophic and is usually of the similar pattern (Fig. 129). Highly crumpled layers or zones in flat-lying, unmetamorphosed strata, otherwise unfolded or only broadly warped, are pretty surely of primary origin. One important exception to this statement must be made: faults in the lithosphere may cause slips and accompanying local crumpling in the superjacent mantle rock.

FOLDS IN RELATION TO THE LAND SURFACE

171. Topographic Expression of Folds.—Provided folds are large enough and provided they are in strata of different degrees of resistance to erosion, they may exercise a marked control upon the form and distribution of hills and valleys. The harder beds stand up as ridges, and the weaker ones underlie longitudinal valleys (see Figs. 406 and 407). After long erosion the ridges may be carved into ranges of hills with intervening transverse valleys. If the axes of the folds are parallel to the general surface of the ground, the ridges and longitudinal valleys will have a parallel trend; but if the axes pitch, the ridges will zigzag back and forth, always pointing up the pitch in synclines and down the pitch in anticlines (Cf. Fig. 124).¹ In denuded dome folds and basin folds, the ridges and valleys are closed concentric curves (Cf. Fig. 123).¹ In gently dipping beds that have been

¹ Salt domes (161) are seldom strongly marked on the earth's surface. Even where the deeper strata invaded by the salt may have been displaced

truncated by erosion, no matter what the shape of the fold may be, the hard layers stand out as *cuestas*, and in steeply inclined beds these hard layers form *hogbacks* (278).

172. Breadth of Outcrop Defined.—The breadth of outcrop of an exposed bed may be defined as the distance between the stratigraphic top and bottom edges of the bed measured on the surface of the ground perpendicular to the strike (Fig. 145, *ab*, *cd*).




FIG. 145.—Sections illustrating variations in breadth of outcrop (*ab* and *cd*) of strata. The thickness of the beds in all four diagrams is the same.

173. Effects of Topography on Breadth of Outcrop.—Figure 145, A–D, will explain more clearly than words how the breadth of outcrop of a stratum may be modified by topographic variations. The essential points to notice are: (1) that breadth of outcrop is least when the surface of the ground is perpendicular to the beds; and (2) that the more obliquely the surface bevels across the beds, the greater is the breadth of outcrop for a stratum of given thickness. (What would be the dip of a bed

many hundreds of feet, the surface expression of the dome may be only a low hill (Fig. 414). Sometimes the ground may be level, or again there may be a depression with or without a lake, probably due to partial solution of the salt plug at its top. The presence of an underlying salt dome may be manifested at the surface by springs of salt water or sulphur water, or by seepages of marsh gas or sulphur gas.

whose thickness is half its breadth of outcrop on a horizontal surface?)

174. Effects of Topography on the Distribution of Outcrops.—

When strata are exposed on an uneven land surface, the trend of their outcropping edges varies according to their attitude. The edge of a horizontal bed bends out round the spurs and in up the valleys (Fig. 146). If it is followed upstream on one side of the valley, it is found to approach and finally cross the stream and then turn back on the other side. Isolated hills in the region may be mesa-like, with the same beds exposed all round (278).




FIG. 146 —Effects of topography on the outcropping edges of horizontal strata.

Vertical strata outcrop in regular bands which trend straight across hills and valleys with no relation to the topography (Fig. 147). If beds are inclined, they outcrop in parallel zigzag belts with elbow-like bends which are situated in the valleys and on the spurs (Figs. 148, 149). In the valleys these bends point down the inclination of the strata, as measured in the general direction of the valley, unless the angle of this inclination is less than the gradient of the stream.¹ In the latter case, which is very rare, the bends point up the inclination. (What will be the effect if inclination of beds and valley gradient are equal?)

¹ If the strata strike perpendicular to the trend of the valley, this "inclination" is approximately the true dip; otherwise it is a component of the dip, taken along the valley trend.

It is to be observed that the foregoing rules, although referring to strata which are theoretically of uniform thickness, are equally applicable to either the top or bottom surface of any given bed,




FIG. 147.—Effects of topography on the outcropping edges of vertical strata.

and to any relatively even surface of unconformity. The distance between the outcrop lines of any two parallel bedding surfaces, *i.e.*, the breadth of outcrop, varies according to the slope of the ground as described in the preceding article.




FIG. 148.—Effects of topography on the outcropping edges of strata dipping downstream.

175. Traverses across and along the Strike.—Unless the underground structure of a district on sedimentary rocks is exceptionally complex and irregular, a brief study of two or three

outcrops should suffice to show in which direction one should walk in order to follow along, or to cross, the strike. In a flat country eroded upon folded strata, and in a hilly country where the strata are vertical, the geologist would keep on the same bed were he to travel parallel to the strike; but if the topography were rugged and the beds dipped less than 90° , he would come on to younger strata in climbing the hills (*a-c*, Figs. 148, 149) and on to older strata in descending into the valleys (*c-a*, Figs. 148, 149), provided, again, that he travelled along the trend of the strike. The object of a traverse along the strike is to assist in determining:




FIG. 149.—Effects of topography on the outcropping edges of strata dipping upstream.

(1) the distribution of the strata; (2) whether the strike curves and so indicates pitching structure (157, 160); (3) whether the strata are continuous or have been faulted (192); and (4) the constancy of the dip of a given stratum.

In traverses across the strike in regions of folded sediments, whether the topography be flat or rugged, successive strata are met. The object of this kind of traverse is to ascertain: (1) the breadth of outcrop; (2) the nature of the folding; (3) the position of anticlines and synclines; and (4) variations in the dip.

176. Sequence of Strata in a Cross-strike Traverse.—As may be noted in Fig. 150, in synclines relatively younger strata, *a*, lie between the older, subjacent beds, *b*, and in anticlines older strata, *c*, lie between younger superjacent strata, *b*. In all cases except where the surface of the ground is parallel to the beds or

where it slopes in the same direction as, and more steeply than, the dip of a series of inclined beds, successively younger strata are traversed in walking across the strike in the direction of the dip.

177. Correlation of Outcrops.—An outcropping stratum which is conspicuously and continuously exposed, or is exposed with only slight breaks in its continuity, can be traced on the ground without difficulty. This is called "walking a bed" (310, 317). When beds are exposed only in isolated outcrops, or in far-separated ledges, these exposures must be carefully studied and correlated with one another to determine their proper relationship. Correlation may be necessary from outcrop to outcrop along the general trend of the edges of the strata, either along the strike, or along the direction of dip, or in some direction oblique to strike and dip. This statement may be understood if the reader will imagine that the sandstone layers in Figs. 146-149 are exposed only in detached outcrops. Rocks may have to be cor-




FIG. 150.—Section illustrating the position of strata in eroded folds. *a*, youngest bed in section; *b*, beds of intermediate age; *c*, oldest exposed bed.




FIG. 151.—Section to illustrate the methods of correlation of strata observed in different outcrops, *a*, *b*, *c*.

related across a fold, as indicated in Fig. 151, where the sandstone outcrops at *a*, *b*, and *c*, are found to belong to the same stratum.

In cases of the two kinds just mentioned, the correlation of outcrops, being over areas of comparatively small extent, may be called *local correlation*. Where the relationship of rocks is studied over or across extensive areas, as in the entire Gulf Coastal Plain, or across the Rocky Mountains, the correlation may be termed *regional* (322).

CHAPTER VIII

FRACTURES AND FRACTURE STRUCTURES

FRACTURES IN ROCKS

178. Relations of Fractures to Zones of the Lithosphere.—

When a mass of rock is not strong enough to resist forces that are tending either to compress it or to stretch it, the rock suffers deformation. The change of form is brought about by flowage in the deeper parts of the lithosphere and by fracture in the upper parts. As pointed out in the foregoing chapter, the zone of fracture for any particular rock seldom coincides with that for another, because rocks differ in their capacity to "flow" under stress. However, since every rock which has been naturally exposed through erosion is within its zone of fracture, outcrops on the earth's surface are invariably and conspicuously traversed by cracks. A large majority of these fissures belong to the class called joints. Other types of rock fracture are faults, fracture cleavage, and breccia structure. Besides these there are certain kinds of fracture which are principally the effects of surface agencies. Such are crescentic fractures of glacial origin, exfoliation cracks along which spalls separate from a disintegrating rock, etc.

FAULTS

TERMINOLOGY AND CLASSIFICATION¹

179. General Nature of Faults.—A *fault* may be defined as a fracture along which there has been slipping of the contiguous masses against one another. Points formerly in contact have

¹ The author has drawn freely from Bibliog., REID, H. F., 1913. In a few cases he has slightly modified the definitions as given therein, but the fact is noted.

been dislocated or displaced along the fracture. Solid rocks or unconsolidated sands, gravels, etc., may be dislocated in this way. Faulting may result from compression, tension, or torsion. Some faults in loose or weakly consolidated clays, sands, and gravels are produced by the removal of a support (201).

In many cases, especially near the earth's surface, the process of dislocation is probably intermittent, although the stresses may be applied continuously and uniformly. This is because the rock does not break until its resistance is overcome. Then it gives way suddenly, and the relief is followed by another period of quiet during which the stresses again accumulate until they occasion another movement, generally on the old fractures. Thus faulting may be accomplished, a little at a time, until the tension or the compression, as the case may be, ceases to be operative. When the release is abrupt, the lithosphere is




FIG. 152.—A fault dying out and passing into a monoclinal fold at its two ends.

jarred and we say that there has been an earthquake.¹ Other things being equal, the greater a single movement is, the more violent is the shock and the farther do the perceptible earthquake vibrations travel from their place of origin. The displacement responsible for an earthquake is seldom more than a few inches, although occasionally it amounts to several feet; yet the sum of all the slipping that has occurred along a fault may be many hundreds or even thousands of feet.

If traced far enough a fault is found normally to die out at its two ends (Fig. 152). Consequently its displacement is apt to be at a maximum near the middle of its length, diminishing toward its extremities. Measured displacements vary from microscopic to many miles, and in length faults range also from microscopic to hundreds of miles.

¹ Not all earthquakes are so caused. Some are due to volcanic disturbances.




FIG. 158.—Map showing distribution of the faults in certain counties in Oklahoma. (Traced from the State Geologic Map.) The numbers on the right are townships north, and those in the lower margin are ranges east. (See Appendix VII.)

In some districts there is a tendency for faults to occur in groups, or zones, within which the individual fractures not only possess many features in common, but also bear definite relations to one another. Thus, in Osage, Creek, Okfuskee, and adjoining counties in Oklahoma (Fig. 153), and likewise in eastern Texas (Fig. 154), there are fault zones in which the separate faults are arranged in overlapping order. Faults (or other features) which overlap in this manner are said to be *en echelon*. These zones usually trend about parallel to the regional strike of the strata. There can be no question that a majority of the faults in such groups or zones are effects of a common cause, which may be local settling over a deeply buried ridge; or, horizontal movement along steeply dipping faults in the basement; or, perhaps more commonly, regional twisting or torsion during uneven uplift or uneven subsidence involved in broad movements of the earth's crust. In the latter case, the twisting was probably such that there was relative tension more or less at right angles to the individual faults, and relative compression roughly parallel to them.¹

180. Terms of General Application.

The characters of a fault are generally

¹ For a discussion of this subject, see Bibliog.: FATH, A. E., 1920; FOLEY, LYNDON L., 1926; LINK, THEO. A., 1929; LAHEE, F. H., 1929, p. 357; and SHERRILL, R. E., 1929.




FIG. 154.—Sketch map showing distribution of major faults, *a* to *i*, in the Mexia fault zone, Texas. Faults *j* and *k* are in the Tehuacana fault zone. These faults are designated by the following names: *a*, Basette; *b*, Powell; *c*, Richland; *d*, North Currie; *e*, South Currie; *f*, Wortham; *g*, Mexia; *h*, North Groesbeck; *i*, South Groesbeck.

different in different places. An illustration of this statement is the varying amount of displacement shown in the fault in Fig. 152. Consequently most of the terms in use refer only





FIG. 155.—Vertical sections of a normal fault (A) and a reverse fault (B). In each figure abc is the dip and bac is the hade of the fault. The wall on the left is the hanging wall and that on the right is the foot wall. If the section is assumed to be perpendicular to the strike of the fault, in each case, bc is the heave and ac is the throw. The arrows indicate the direction of motion of the blocks.

to the part of the fault to which they are applied and not necessarily to the fracture as a whole. This must be kept in mind in connection with the definitions given below.

The contiguous surfaces of the two bodies of rock that have been displaced, in faulting, are called the *walls* of the fault. The upper wall of an inclined or horizontal fault is the *hanging wall*, and the lower one is the *foot wall* (Fig. 155). When referring to these surfaces in contact with one another, or to either one, separately, we may speak of the fault surface or the *surface of faulting*.¹

Although ordinarily fault walls are irregular in their minor details (188; 35, H), when looked at from a large point of view, they may be relatively flat or undulating. Their minor irregularities sometimes give rise to open spaces in which vein minerals may subsequently be deposited. The fracture is not always clean-cut and definite, for there may be more or less crushing of the wall rocks during the act of slipping.

¹ The reader is reminded that the accompanying illustrations are diagrammatic. In the field fault zones may be found instead of the fault surfaces herein figured, and they may have much less regularity in direction and shape. Unfortunately, *fault plane* has often been used for *fault surface*, although, in nature, no fault surface is a plane.

Finely pulverized rock flour of this origin is *gouge*. Coarser material, consisting of fragments of various sizes, usually associated with a more finely crushed matrix, is *fault breccia* (Fig. 156, C). The layer of gouge or breccia is termed the *fault zone* or the *shear zone*.¹ If such a shear zone is present, the walls are separated by the width of the zone. These fault zones may have vein minerals deposited between the fragments (223). The displaced masses on either side of a fault may be called *fault blocks*. A *horse* (Fig. 156, A) is a large fragment of rock broken from one block and caught between the walls of the fault. Sometimes bedding, or some other parallel structure in the fault blocks, has been turned up or dragged against the




FIG. 156.—Sections of faults showing, in A, a "horse"; in B, drag produced by bending, and in C, drag produced by brecciation.

fault walls during the differential movement. Minor folding of this kind is called *drag* (Fig. 156, B). It is frequently well exemplified in faulted unconsolidated beds. It may produce sharp changes of dip and strike (*drag dips* and *drag strikes*) in the vicinity of a fault. The term is also applied by miners to the stringing out of fragments of a disrupted dike, ore body, etc., along the fault (Fig. 156, C). In the actual slipping the blocks may scratch, groove, and polish one another. The scratches are known as *slickensides*. Some geologists apply the name *slickensides* to both the polish and the scratches together.

Fault line, *fault trace* and *fault outcrop* are used synonymously for the intersection of the surface of the ground with a fault.

The words *attitude*, *strike*, and *dip* are used for faults in the same way as for strata (12), and they may be applied to a

¹ Not to be confused with the groups of related faults called *fault zones* (p. 203).

sharp fracture or to a shear zone (Fig. 155). The *hade* of a fault, or of a shear zone, is the complement of the dip, *i.e.*, it is the vertical angle between the plane of the fault and a vertical plane containing the strike of the fault (Fig. 155, *cab*). In the interest of uniformity, when referring to the attitude of a fault, *dip* is to be preferred to *hade*. In other words, it is better to measure the inclination of a fault downward from the horizontal.

181. Kinds of Displacement.—*Displacement* and *dislocation* are words used only with a general meaning in this book. When




FIG. 157.—Displacements of a fault. The upper and lower surfaces of the block are horizontal. The triangles *abc* and *adb* are in the fault plane, *caf*. *ab*, slip; *ac*, dip slip; *cb*, strike slip; *ad*, perpendicular slip. (After H. F. Reid, with modification.)

more accuracy is desirable, *slip*, *shift*, and *separation* may be employed, with or without qualification. *Slip*, or *net slip*, is "the relative displacement of formerly adjacent points on opposite sides of the fault, measured in the fault surface"¹ (Fig. 157). If there is drag or other distortion along the fault, the slip is not equal to the displacement that affects points situated outside the immediate zone of dislocation. This is illustrated in Fig. 158, where *ab* is the slip and *de* is the displacement of the point, *e*, in moving from its former position, *d*. This distance, *de*, is called the *shift*. It is distinctly greater here than the slip. Figure 159 shows another example of shift. "The shift is of

¹ The quotations in this article are taken from Bibliog., REID, H. F., 1913.

greater importance in the larger problems of geology than the slip." "The *separation* of a bed (Figs. 160, 161, 162), vein, or of any recognizable surface, is the distance between the *corresponding surface* of the two parts of the disrupted bed, etc., measured in any indicated direction. The distance must be measured between the *corresponding surfaces* on the two sides of the fault—for instance, between the upper surfaces of the two parts of the disrupted bed or between their lower surfaces—but not between




FIG. 158.—Slip and shift of a fault. The curvature of the beds is drag. *ab*, slip; *bc*, dip slip; *ac*, strike slip; *de*, shift; *fe*, dip shift; *df*, strike shift. The words "dip" and "strike" are used for the components of slip and shift which are parallel to the dip and strike, respectively, of the fault. (After H. F. Reid, with modification.)




FIG. 159.—Shift produced by a multiple fault. *de*, shift; *ef*, dip shift; *df*, strike shift. (After W. Lindgren.)

the upper surface of one part and the lower surface of the other. Moreover, the surfaces considered must be parallel with the general extension of the bed, vein, etc., such as the upper or lower surface of a bed or the walls of a dike.

"The *vertical separation* is the separation measured along a vertical line (Figs. 160, 161).

"The *horizontal separation* is the separation measured in any indicated horizontal direction.

"The *normal horizontal separation* of a bed or other surface is its horizontal separation measured at right angles to the strike of the bed, etc. It is frequently determined from the outcrops of the bed at the surface of the ground; it is then usually

called the *offset* of the bed." If A and B, in Fig. 162, represent the ground plans of oblique faults on a level surface, *be*, and




FIG. 160.—Displacements of a diagonal fault. *ab*, slip; *bc*, vertical separation; *ac = de*, horizontal separation along the strike of the bedding (gap); *ad*, trace of bedding on fault surface; *be*, offset.




FIG. 161.—Displacements of a diagonal fault. *ab*, slip; *bc*, vertical separation; *ac = be*, horizontal separation along strike of bedding (overlap); *ad*, trace of bedding on fault surface; *de*, offset.

not *bd*, would be the offset of the bed. *bd* would be the horizontal separation along the fault strike. *de*, in the same figures, would

be called the *gap* and *overlap* of the bed, respectively; they are measured parallel with the strike of the bed.

"The *perpendicular separation* is the distance between the planes of the two parts of a dislocated bed or other surface measured at right angles to these planes."

"The measures which will be most commonly made are the offset at the surface, and the vertical and horizontal separations in shafts and drifts, respectively" . . .




FIG 162.—Offset, gap, and overlap. A is a plan of the structures which would be seen in the plane *xyz* of Fig. 160; B has a like relation to Fig. 161. *bc*, offset; *de* gap in A, and overlap in B. Observe the symbols for dip and strike of the bedding.

"It is extremely important clearly to distinguish between the slip and shift and the separation. The first two refer to the actual relative displacement of the two sides of the fault, the last to the relative displacement of the surfaces of the two branches of a dislocated bed, etc.

"Movements of one side or of both sides of the fault parallel with the plane of a bed would not alter the separation of the bed, but would materially alter the slip and shift."

By *throw* is meant "the vertical distance between corresponding lines in the two *fracture surfaces* of a disrupted stratum, etc., measured in a vertical plane at right angles to the fault strike. The *heave* is the horizontal distance between corresponding lines in the two *fracture surfaces* of a disrupted stratum, etc., measured

at right angles to the fault strike" (Fig. 155). A vertical fault can have no heave and a horizontal fault can have no throw.

The several terms defined above for the displacement of a fault, measured in various directions, refer to a single line, or a single surface, disrupted and separated in the movement. Because faults may die out upward, downward, or laterally and




FIG. 163.—Cross sections of two faults. In A, the fault dies out upward; in B, it dies out downward. In both cases, as it dies out, it passes into a flexure.

because the broken strata or other rock materials may vary in rigidity, there may be considerable variation in the amount of displacement on the same fault, measured between points formerly in contact, at successively higher or lower levels in the disrupted mass (Fig. 163).




FIG. 164.—A, a dip-slip strike fault. B, a strike-slip dip fault.

182. Classification of Faults.—Faults are classified according to: (1) the nature of their displacement; (2) their distribution; and (3) their relations to disrupted bedding or other parallel structures.

1. In any rock formations a *dip-slip fault* has its net slip essentially in the line of the fault dip (Fig. 164, A); a *strike-slip fault*

has its net slip along the fault strike (Fig. 164, B);¹ and an *oblique-slip fault* has its net slip anywhere between the dip line and the strike of the fault (Figs. 157, 158). A *normal fault* is one in which the hanging wall has apparently slipped down with respect to the foot wall (Fig. 155, A), and a *reverse* (not "reversed") *fault* is one in which the hanging wall has apparently moved up with respect to the foot wall (Fig. 155, B). We say "apparently" because sometimes a normal fault may result from relative uplift of the hanging wall and a reverse fault may be produced by relative depression of the hanging wall (Fig. 165). It is not always true, then, that there is extension of territory by




FIG. 165.—On the left, reverse fault produced by depression of the hanging wall; on the right, normal fault produced by uplift of the hanging wall.

normal faulting, as if tensile stresses had operated, nor that there is contraction of area in reverse faulting, as if due to compression. "Normal" and "reverse" should "be used purely for purposes of description and not for the purpose of indicating extension or contraction, tension or compression, vertical or horizontal forces."² A fault due to gravitative settling, resulting from tension, is called a *rift*.¹ *Thrust* may be reserved for faults that are demonstrably due to compression. Three varieties of thrust are noted by Willis; (a) *break thrusts*, when the fault follows a previously formed tension fracture (Fig. 166); (b) *shear* or *stretch* thrusts, when the break follows the sheared and stretched under-

¹ Although "rift" is used for a tension fault, the displacement of which is due to gravitational subsidence, the term has also been applied to strike-slip faults and to valleys caused by such faults (see Art. 264).

² Bibliog., Reid, H. F., 1913, p. 178.

limb of an overturned fold (Fig. 167); and (c) *erosion thrusts*, when the competent layer carrying the thrust is weakened by erosion at or near the crest of the anticline (Fig. 168).¹ A thrust having a




FIG. 166.—Sections illustrating the origin of a break thrust. The position of the overthrust fault shown in B was determined by the fracture represented in the massive limestone bed in A. (After B. Willis.) Observe that in this kind of faulting, and also in the varieties shown in Figs. 167 and 168, older rocks come to lie above younger rocks.

relatively high angle of dip is a *ramp*. An *overthrust* is any thrust fault having a low dip (large hade) (Figs. 166–168).

Overthrusts are very common in regions of intense folding. Their displacements may amount to several miles.² They have been traced as single faults for as far as 200 miles, or even more.




FIG. 167.—Development of a stretch thrust from an overturned fold. (After B. Willis.)

The overlying block, or *sheet*, is termed a *nappe* (pl., *nappes*), or *decke* (pl., *decken*). Because of successive overthrusting, several of these sheets may be shoved, one upon another, so that they overlap, shinglelike. The surface (foot wall) on which a fault sheet rests is referred to as a *sole*.

¹ Bibliog., WILLIS, B., 1892, pp. 222–223; LEITH, C. K., 1913, pp. 46–48.

² See Bibliog., BEVAN, A., 1929, p. 447; also WILLIS, BAILEY, 1923⁴.

The overlying sheet (hanging wall) of a low-angle thrust fault may be broken by steeply dipping or vertical faults that strike nearly at right angles to the strike of the overthrust fault and have their displacement essentially horizontal. These are strike-slip faults (see ¶ 3, below), which, in this particular association, are called *tear faults*.

Low-angle thrust faults are commonly irregular, and their cross sections may appear as undulating lines (Fig. 216) even




FIG. 168.—Sections illustrating the origin of an erosion thrust. The position of the overthrust shown in B was determined by the land surface condition represented in A, where a weak rock (dark shading) outcrops at the base of a scarp. The force acted from right to left. Erosion is supposed to have continued during the faulting. (After B. Willis.)

when they preserve their original form. However, they may undergo warping or folding, in which case there is some correspondence between flexures in the fault surface and flexures in the folded strata above and below (see *a*, Fig. 211; Fig. 169).

Most of the low-angle thrust faults probably resulted from sliding of the hanging wall *over* a passive foot wall; but similar relations might be brought about by sliding of the foot wall *beneath* a passive hanging wall. The former is *overthrusting*; the latter, *underthrusting*. That overthrusting has probably occurred in most cases is suggested by these facts¹: (1) the relative direction

¹ Bibliog., NEVIN, C. N., 1936, pp. 130-133.

of movement of the hanging wall is usually in the direction of convexity of the trends of associated arcuate folds, and the axes of such folds curve outward, away from the deforming force; (2) there would be less resistance to the lifting and sliding of an




FIG. 169.—Cross section showing successive stages (I to IV) of thrusting in the eastern part of the Canyon Mountain area, Montana. In each stage the dashed line indicates the position of development of the next thrust. Stage I shows the hypothetical condition before thrusting, with two anticlines truncated by erosion. A shear, propagated from the pre-Cambrian (Agn) through the Middle Cambrian shales to the surface at the crest of the northern anticline, gives rise to stage II. A second shear (*de*) cuts through the Madison limestone (Cm) where that formation has been weakened by flexure and erosion (at *d*); and a branch shear from *ab* reaches the surface at *c*. On this the formations above the fault surface are overturned (stage III). In stage IV, further compression has folded the thrust planes, and erosion has produced the present topography. The section in stage IV is about 8 miles long. (After D. C. Skeels, with some modifications. See Bibliog. Reproduced through the courtesy of the author, the *Journal of Geology*, and the University of Chicago Press.)

overthrust mass than to the downward and forward driving of an underthrust mass; (3) the rocks of the overlying sheet being older and more rigid, would be better able to stand the strain of overthrusting than the younger rocks of the foot wall could

stand underthrusting. According to Lovering,¹ if the active wall of a tear fault moved in the same direction as the relative movement of the overlying thrust sheet, this low-angle fault was an overthrust; if in the opposite direction, an underthrust.

Faults on which the blocks rotate during dislocation are *hinge faults*, *pivotal faults*, *scissors faults*, or *rotational faults* (Fig. 170).




FIG. 170.—Rotational fault.

2. An *auxiliary* or *branch fault* is a minor fault ending against the main fault. It may be the boundary of a wedge (Fig. 171, A). Where the main fault is due to tension, the branch is likely to dip more steeply than the main fault, and, where the main fault is due to compression (a thrust fault), the branch usually dips less steeply than the main fault. Faults that cross one another are *intersecting faults* (Fig. 171, B). A *fault complex* is an intricate system of intersecting faults of the same age or of different ages. When several parallel faults are close together and the intervening fault slabs or slices are not distorted, the group may be termed a *multiple fault*. A multiple fault in which the downthrow is on the same side of each component fault, is a *distributive fault*. A multiple fault, consisting of thrust faults, is called *imbricate structure*. It may divide the major blocks in regional overthrusting into minor slices (Fig. 172




FIG. 171.—A, branching fault; B, intersecting faults. Which fault is the older one in B?

¹ Bibliog., LOVERING, T. S., 1932.

3. In strata, a *strike fault* (Fig. 164, A) has its strike parallel to the strike of the beds; a *dip fault* (Fig. 164, B) strikes at right angles to the strike of the beds; a *diagonal fault* is one in which




FIG. 172.—Imbricate structure in the overhanging block (adbc) of a thrust fault (ab).

the strike is oblique to the strike of the beds (Fig. 160–162); a *bedding fault* is parallel to the stratification (Fig. 173); a *longitudinal fault* strikes parallel to the general structure (fold axes, schistosity, etc.) of a region; and a *transverse fault* strikes across such structure.




FIG. 173.—A bedding fault.




FIG. 174.—Section of a fault wedge, abcd.

183. Terms for Fault Blocks.—A wedge-shaped block between two faults is a *fault wedge* (Figs. 171, A; 174). Wedges are some-




FIG. 175.—Block diagram showing a possible explanation for the dislocation of such a wedge as that drawn in Fig. 174. *efg* corresponds to *deb* in Fig. 174. *d* has slipped from *a*, and *f* from *b*.

times indicative of considerable lateral motion (Fig. 175). An upthrown block between two downthrown blocks is a *horst*

(Fig. 176, A). A downthrown block between two upthrown blocks is a *graben* or *fault trough* (Fig. 176, B). In both definitions the movement of the blocks is relative. Thus, in the graben, the middle block may have gone down, or the walls on both sides may have gone up, or all three may have settled with respect to their original position, but the middle one more than the other two. Similar reasoning may be applied to a horst. If




FIG. 176.—Sections of a horst (A) and a graben (B).

the diagrams (Fig. 176, A and B) tension faults, or rifts bound the middle block. Conceivably these faults might dip in the direction opposite to that shown, and they would then be thrust faults, or ramps. A graben might thus be defined as a *rift trough*, or a *ramp trough*, according to the nature of its bounding faults. Again, corresponding nomenclature might be applied to horsts.

a b c

FIG. 177.—Cross section of a deep salt dome (salt plug not reached by deep drilling) where the crest has broken and dropped to form a compound graben, between a and c.

Grabens may occur on or near the crest of broad arches; also, on the crests of domes associated with deep salt intrusion (§ 6, Art. 161), as indicated in Fig. 177. These relations suggest some expansion and settling of the rock masses following the compression, or uplift, that produced the arch. Faults like those in Fig. 154, with downthrow on the side up the regional dip of the strata, may be the down-dip walls of *strike grabens*, which are bounded 2 or 3 miles up dip by tension faults (rifts) that have their downthrow on the down-dip¹ side (Fig. 178).

¹ These references to dip are to the regional dip of the faulted strata.

A block that has been lowered on all sides by faulting or by downwarping or by both processes is called a *basin* (Fig. 179). These terms (*horst*, *graben*, *basin*) are structural in their significance, and they are used irrespective of the topographic form of the block (204).




FIG. 178.—Cross section of a graben (*ac*) that trends essentially parallel to the regional strike (perpendicular to the plane of the page).

When a fault is approximately parallel to the strike of the strata, the block on the side of the fault toward which the dip of the beds is measured may be termed the *down-dip block*, and the other one is the *up-dip block* (Fig. 164, A). Note that the word, dip, in these two terms refers to the inclination of the beds. On the down-dip side of any given stratum, the strike of a diago-




FIG. 179.—Block diagram of a structural basin. The dash pattern represents a hard crystalline rock formation upon which a series of strata (lined) rests unconformably. The strata occupy the basin. The little basin on the extreme left is an *outlier* of the main basin, and the mass of crystalline rocks within the basin, bounded on the right by fault *b*, is an *inlier*. The topography, in this case, was produced by differential erosion acting on the hard and soft rocks of the region, following peneplanation (Art. 261).

nal fault makes an acute angle with the strike of the beds (angle *sdt*, Fig. 162, A) on one side of the fault, and an obtuse angle with the strike of the beds on the other side (angle *dbv*, Fig. 162, A). The block containing the acute angle on the down-dip side of an outcropping bed may be called the *acute-angle block*, and the other, the *obtuse-angle block* (see also Fig. 162, B).

184. Omission and Repetition of Beds Defined.—Erosion after strike-faulting of stratified rocks may bring about the entire elimination of some beds (Fig. 180, A), or, on the other hand, it




FIG. 180.—Sections showing omission (A) and repetition (B) of strata. In A, the beds between a and b are entirely concealed beneath the surface of the ground. In B, beds between a and b are exposed twice in the same succession on the surface of the ground.

may cause repetition of some beds, with the same sequence, on opposite sides of the fault (Fig. 180, B). The first is spoken of as *omission of beds* and the second as *repetition of beds*, respectively.




FIG. 181.—Dip data secured by reflection seismographic work (see p. 755) in an area in south Texas. Note the zone of poor records, indicated by the dashed line, *AB*, which is interpreted as a fault, the dip of which decreases with depth. Note also that the strata dip toward the fault on both sides. Its displacement, though not revealed by these data, is down on the east side (Cf. Fig. 183.)

185. Variations in Dip and Displacement of Faults.—When faults are exposed in cross section over a distance of many hun-

dreds of feet or when their underground form can be ascertained by numerous deep well logs or by seismographic methods, they are often found to change in dip with increasing depth. Thrust faults may steepen with depth (Fig. 169). On the contrary, normal faults—especially strike faults with downthrow on the side down the regional dip of the strata—may reveal a decreasing angle of dip with increasing depth (Fig. 181).

186. Relations of Faults to Folds.—Flexing or folding of strata may be associated with faulting. Figure 152 shows a tension fault passing into a flexure at each end. A fault of this kind may also pass into a flexure either upward or downward. Similarly, a




FIG. 182.—Cross section of a normal fault (*ab*) with upthrow on the regional down-dip side. (The regional dip here is toward the right.) Some flexing, on a relatively large scale, seems to be genetically related to the fault, since the crestal surface (in section, *cd*) of the antiform in the upthrown block is parallel to the fault.

thrust fault may pass into a fold either laterally or upward or downward (Fig. 163). In these cases, bending of the strata no doubt occurred first, and then, with further application of the stress, fracturing followed where this stress was most effective (Fig. 169).

Drag (Fig. 156, B) is another variety of flexing associated with faulting. It is generally very local, but it may assume larger proportions, as represented in Fig. 182.

A very interesting relation between folding and faulting is depicted in Fig. 183, where, for some distance out from the fault, the strata dip in toward it. This condition has been recognized by seismograph (Fig. 181) and then by drilling, in association with many strike faults of the Gulf Coastal Plain. It has also

been observed exposed in mountain districts of considerable topographic relief. Comparison of Figs. 181, 183, and 279 suggests that the tilt of the beds from *a*, *a'*, toward the fault (*b*, *b'*), on the downthrown side, may be genetically associated with this kind of fault that so closely resembles the landslide slip. The thickening of the strata from *a*, etc., toward *b*, etc.,




FIG. 183.—Faulting of the normal type (*ef*), where there is dip of the strata *into* the fault on both sides of the break. (Cf. Fig. 181.)

may mean that sliding on the fault was progressive during sedimentation.

GEOLOGIC EVIDENCES FOR FAULTING

187. Principal Evidences of Faulting.—That faulting has occurred in any locality may be indicated in various ways. Sometimes slickensides or other marks of slipping may be observed on a fault surface exposed by natural or artificial means. More often the evidence is found in the relations of the rock structures on the two sides of the fault when the latter is viewed in horizontal, inclined, or vertical cross section. Or, again, the criteria may be topographic in character. These features, whether geologic or topographic, the field geologist should learn to recognize. He should know how to interpret their meaning, and in order to do this, he must be able to discriminate between them and other features that look like them but are really of very different origin.

The topographic forms related to faulting are described in Chapter XI. Their significance as evidences for dislocation is

pointed out in Art. 210. Following are the more important geologic phenomena:

1. Slickensides, polish, and other features on fault surfaces.
2. Visible displacement of veins, dikes, strata, etc., on opposite sides of an exposed fault line.
3. Zones of breccia.
4. Drag.
5. Discontinuity of linear forms along their general trend.
6. Abrupt termination of structures along their trend.
7. Repetition of strata.
8. Omission of strata.

188. Slickensides and Other Features on Fault Surfaces.—

Slickensides are useful in showing the general line along which the motion took place. On a vertical fault surface, they indicate vertical slipping if they are vertical, horizontal slipping if they are horizontal, and so on; but they do not tell the relative motion, *i.e.*, if they are vertical, they do not show which block moved up with respect to the other. This relative displacement is sometimes indicated by steplike jogs that trend across the slickensides (**35, H**). The student should be careful not to place too much importance on these little irregularities. One or two are not sufficient evidence, but if they are numerous and all face in one direction, then they are fairly conclusive. Polish is of no value as a criterion for displacement.

Slickensides on outcrop surfaces may look like glacial striæ. For the most part, slickensides on any given surface are parallel, whereas striæ generally—not always—vary in direction within 10° or 15° of arc. On steeply inclined surfaces, fault scratches are apt to run up and down, whereas glacial striæ are likely to trend in a nearly horizontal direction. When the scratched surface can be traced to a place where it passes into the rock,¹ it is usually a fault surface; but exception must be made for the rare case in which ancient (pre-Pleistocene) glaciated surfaces are found to have been reëxposed by the partial removal of the overlying younger rock. When the scratched surface is glaciated,

¹ Not merely under superficial deposits, such as till, alluvium, etc.

any overlying material, consolidated or not, is apt to be of glacial or of aqueoglacial deposition. For other kinds of scratches, grooves, and polish, which may be mistaken for slickensides the reader is referred to Art. 35.

Slickensides are not invariably accurate indices of the direction or distance of slipping. Successive movements on the same fault may have different directions, and the grinding and polishing of the last dislocation may have destroyed all traces of earlier slickensides. Thus, the total distance travelled by a point from its first position may be greater than the slickensides would lead one to believe, and the present direction between two points which were formerly in contact may be different from the course along which they acquired their ultimate positions. In making measurements on a given fault the geologist should ascertain, if possible, whether the slickensides are reliable data for obtaining the direction and amount of slip.

189. Visible Displacement of Veins, Dikes, Strata, Etc.—There can be no better evidence for faulting than the case in which the two ends of a dislocated bed, dike, vein, or other structure, are visible where they abut against the fault, also exposed in section (Fig. 155). The geologist will discover few instances in which this kind of evidence is questionable; but he will also find that it is a phenomenon which is seldom seen except on a small scale.

190. Fault Breccia Zones.—This subject is reserved for Art. 223.

191. Drag.—Drag is not observed unless in the immediate vicinity of a fault. It need not be exposed on both sides of the fracture in order to ascertain the direction of displacement, for, normally, if the slipping had a vertical component, the faulted structures are turned up in the downthrown block and down in the upthrown block (Figs. 156, B; 158). However, due to complex conditions of the forces acting and of the consequent displacement, or because of two successive periods of slipping, one up and the other down, on the same fracture, or because monoclinal folding has been followed by faulting with the relative

directions of displacement reversed, instances of faults have been observed where the drag turned up in the upthrown block and down in the downthrown block, except perhaps within a very few feet or a few inches of the actual surface of slipping.¹

192. Discontinuity of Linear Structures along Their General Trend; Offset.—A dip fault or a diagonal fault, intersecting beds or other regular structures across their strike, is usually indicated by some type of offset. For example, a bed which has been dislocated in this way may be traced on the surface of the ground, generally in a series of separate outcrops, to a point beyond which it terminates and some other rock takes its place; but somewhere, to the right or left, the same bed will be discovered, probably




FIG. 184.—Offset produced by a dip-slip fault. Left, without erosion; right, after erosion.




FIG. 185.—Offset produced by a strike-slip fault.

trending in the original direction. The relations are essentially like those described in Art. 189, but here the fault intersection (fault line) is concealed, so that merely its approximate position can be determined.

For the correct interpretation of offset the faulted bed, dike, vein, igneous contact, or other structure must have characters sufficiently distinctive for unquestionable recognition. On the assumptions: (1) that inclined stratified rocks have been dislocated; (2) that the bedding has the same strike and dip on both sides of the fault; and (3) that the land surface is essentially horizontal, the conditions of offset may be classified as follows:

(A) *The fault is a dip fault; there is neither gap nor overlap.* Like effects upon the outcrops of the strata may be produced by dip-slip, oblique-slip, and strike-slip faults, provided the net

¹ See, for example, Bibliog., BRUCKS, ERNEST W., 1929, Vol. I, p. 266.

slip is of the proper amount. Whether the fault is vertical or inclined, the beds are offset toward the direction in which they dip in the upthrown block of a dip-slip fault (Fig. 184), and in the block which moved toward the dip of the bedding in a strike-slip fault (Fig. 185). For an oblique-slip fault (Fig. 186)




FIG. 186.—Offset produced by an oblique-slip dip fault. Left, without erosion, right, after erosion.




FIG. 187.—Offset toward the direction of dip of the beds in the downthrown block of an oblique-slip dip fault. Left, without erosion; right, after erosion.




FIG. 188.—Offset toward the direction of dip of the beds in the downthrown block of an oblique-slip dip fault. Left, without erosion; right, after erosion.

the same statements hold true with the exceptions drawn in Figs. 187 and 188.

(B) *The fault is a diagonal fault.* Like effects on the outcropping strata may be produced by dip-slip, oblique-slip, and strike-slip faults, provided the displacement is of the proper amount. Whether the fault is vertical or inclined, in the case

of dip-slip faults, overlap results from downthrow of the acute-angle block (Figs. 189, 190), and gap from downthrow of the obtuse-angle block (Figs. 191, 192); and in the case of strike-slip faults, overlap results from the movement of the obtuse-angle block in the direction of the dip of the beds, and gap from




FIG. 189.—Overlap caused by a dip-slip diagonal fault. Left, without erosion; right, after erosion.




FIG. 190.—Overlap caused by a dip-slip diagonal fault. Left, without erosion; right, after erosion.




FIG. 191.—Gap produced by a dip-slip diagonal fault. Left, without erosion; right, after erosion.

the movement of the acute-angle block in this direction. The same statements hold for oblique-slip diagonal faults, except in cases analogous to those figured for dip faults.

If inclined stratified rocks have been broken by a rotational dip fault, the beds are offset in the same manner as in a dip-

slip dip fault but the outcrops are broader in the block which has undergone a differential upward displacement increasing in amount in the direction of the dip of the strata (Figs. 193, front block; 194, back block). Exception to this statement




FIG. 192.—Gap produced by a dip-slip diagonal fault. Left, without erosion; right, after erosion.




FIG. 193.—Offset by rotational faulting. Left, without erosion; right, after erosion.




FIG. 194.—Offset by rotational faulting. Left without erosion; right, after erosion.

may be found where the rotation has actually reversed the direction of dip of the beds.

193. Abrupt Termination of Structures along Their Trend.¹—In offset the two parts of a dislocated structure end abruptly against the fault line. If one of the parts were gone the condition would be that referred to in the title of the present article.

¹ Note that the word trend implies outcrop on the land surface.

Under these circumstances, the lost portion of the structure may be concealed under water, under alluvium, under lava, or under a later series of stratified rocks (Fig. 195); or the displacement may have been greater than at first imagined and the "lost portion" may be found by more extended search.




FIG. 195.—Abrupt termination of strata (right) against a fault. The same strata, on the left of the fault, are concealed beneath the body of horizontal sediments. These younger horizontal sediments have been eroded from the right fault block.

In a series of strata which have been broken by a rotational fault and then eroded the beds in one or both blocks may be truncated by the fault. On the assumption that the land is essentially horizontal, these relations may be classified as follows:

(A) *The beds are horizontal in one fault block and are inclined in the other, and the inclined beds strike nearly or quite at right angles to the strike of the fault.* The block with the tilted beds




FIG. 196.—Effects of rotational faulting of horizontal strata. Left, without erosion; right, after erosion.

suffered relative uplift with increasing slip on the side away from which the strata dip. The fault surface is vertical or inclined (Fig. 196). The same relations may be brought about by rotation of a block of tilted strata on a dip fault in such a way that the layers in this block become horizontal; but this case is exceptional.

(B) *On both sides of a fault the beds are inclined in the same general direction, but those on one side strike parallel to the strike*

of the fault and those on the other side strike so that they make an acute angle with the fault line. The beds which are truncated at the fault line are in the tilted block. In Fig. 197, A: (1) if the fault is vertical and the beds dip to the right, the tilted block was increasingly lowered toward *a*; (2) if the fault dips to the right and the beds dip to the right, either the fault dips more steeply than the beds and the tilted block was increasingly lowered toward *a*, or the fault dips less steeply than the beds and the tilted block was increasingly lowered toward *b* (Fig. 198); (3) if the fault dips to the right and the beds dip to the left, the tilted block was increasingly lowered toward *b*. In Fig. 197,




FIG. 197.—Effects of rotational faulting of inclined strata, as seen in plan.




FIG. 198.—Effects of rotational faulting of inclined strata. Left, without erosion; right, after erosion of upthrown block.

B: (1) if the fault is vertical and the beds dip to the right, the tilted block was increasingly lowered toward *b*; (2) if the fault dips to the right and the beds dip to the right, either the fault dips more steeply than the beds and the tilted block was increasingly lowered toward *b*, or the fault dips less steeply than the beds and the tilted block was increasingly lowered toward *a*; (3) if the fault dips to the right and the beds dip to the left, the tilted block was increasingly lowered toward *a*.

(C) *The beds on both sides of the fault are inclined in the same general direction and strike so that they make an acute angle with the fault line* (Fig. 199). On the assumption, above made, that

the land surface is horizontal, these relations are caused by rotation in both blocks; but in nature the same thing is more apt to be due to the fact that the ground slopes.

The abrupt termination of structures along their trend is not necessarily a result of faulting. The same phenomenon is common in association with igneous contacts and lines of unconformity. Furthermore, one should not overlook the fact




FIG. 199.

FIG. 199.—Effects of rotational faulting, as seen in plan.




FIG. 200.

FIG. 200.—Sketch map of a body of inclined strata partly covered by alluvium (white). The middle sandstone bed (stippled) on the right thins out beneath the alluvium and thus looks as if it had been dislocated by a fault, also concealed beneath the alluvium; but the fact that the other beds match across the alluvium cover proves that the suggestion of a fault is incorrect.

that since beds, dikes, veins, fractures, and the like, may come to an end in their original form, within short distances, apparent truncation is not always real (Fig. 200). The natural termination may be concealed and so lead one to infer the presence of a covered fault where no fault exists.




FIG. 201.—Repetition of beds explained by folding, *abcdet*, or by faulting, *saedet*. The stippling represents alluvium which conceals some of the beds and likewise the fault line, if faulting is the correct explanation.

194. Repetition of Beds.—Repetition of beds (184) is a very satisfactory indication of faulting, but it is not conclusive evidence. It may be due to folding where an intervening limb is concealed (Fig. 201), or it may be a consequence of the repetition




FIG. 202.—Repetition of strata caused by erosion (right diagram) succeeding dislocation by a vertical dip-slip strike fault (left diagram). (Cf. Fig. 206.)




FIG. 203.—Repetition of strata caused by erosion (right block) succeeding dislocation by a dip-slip strike fault that dips in the opposite direction from the dip of the broken strata. (Cf. Fig. 207.)




FIG. 204.—Repetition of strata caused by erosion (right block) succeeding dislocation by a dip-slip strike fault that dips in the same direction as the broken strata. (Cf. Figs. 205, 208.)




FIG. 205.—Repetition of strata caused by erosion (right block) succeeding dislocation by a dip-slip strike fault that dips in the same direction as the broken strata. (Cf. Figs. 204, 209.)

of a certain sequence of conditions during the deposition of the beds. Proof that folding is not the cause may often be found by wider field correlation, or, if the true succession of strata is known from observations in the vicinity, by actual measurement across the strike to determine whether there is room for the concealment




FIG. 206.—Omission of strata caused by erosion (right block) succeeding dislocation by vertical dip-slip strike fault. (Cf. Fig. 202.)




FIG. 207.—Omission of strata caused by erosion (right block) succeeding dislocation by a dip-slip strike fault that dips in the opposite direction from the dip of the broken strata. (Cf. Fig. 202.)




FIG. 208.—Omission of strata caused by erosion (right block) succeeding dislocation by a dip-slip strike fault that dips in the same direction as the broken strata. (Cf. Figs. 204, 209.)

of the repeated strata in an intervening limb of a fold. As for the possibility that the conditions of sedimentation were repeated, this is very unlikely, and the more beds there are in the repeated series, the more improbable does this suggestion become.

Figures 202-205 show several methods by which repetition of strata may be produced.

195. Omission of Beds.¹—The ability to recognize omission of beds in the field demands a thorough acquaintance with the stratigraphic sequence (108) in the region; for obviously, unless one knows what strata to expect, one cannot tell whether or not




FIG. 209.—Omission of strata caused by erosion (right block) succeeding dislocation by a dip-slip strike fault that dips in the same direction as the broken strata. (Cf. Figs. 205, 208.)

some beds are missing. In Figs. 206–209 are illustrated several methods by which omission of beds may be produced.

196. Omission and Repetition of Beds Observed in Drill Holes.—When a hole is drilled through faulted strata, and in




FIG. 210.—Vertical section of strata broken by a normal fault which dips in the direction opposite to the dip of the strata. This is the kind of fault characteristic of the Mexia fault zone in Texas. (See Fig. 154.)

such a position that the hole intersects the fault, part of the stratigraphic section normal to the region may be found to be repeated,

¹ See Art. 184.

or, on the other hand, missing. Figure 210 is a vertical section of gently inclined beds, displaced by a strike fault with its downthrow on the side up the dip of the strata (on the west).¹ The normal succession of formations is *u, v, w, x, y*, in order downward from the surface of the ground. Well *a* passed through this sequence. Well *b* missed the lower part of *u*. Well *c* missed all of *v* and parts of *u* and *w*. Well *d* passed directly from a thin section of *v* into *x*, missing *w* altogether. Well *e* missed *x* and part of *w*. Well *b* had the normal sequence as deep as it was drilled, but at a much lower level than the same formations were encountered in well *a*.

In the study of vertical sections by means of well logs (457) an understanding of these relations is essential, for the discovery of a fault may be made on just this sort of evidence, even where there are no indications on the surface of the ground.

By carefully analyzing the relations in Figs. 203-209, the student will note that either repetition or omission of beds may be observed in a *vertical hole intersecting* a normal fault or a reverse fault and whether such fault is associated with repetition or omission of beds on the land surface (assuming this to be relatively flat and nearly horizontal), depending on the particular relations of direction and amount of dip of both the fault and the strata.

FAULTS IN RELATION TO THEIR TIME OF ORIGIN

197. Relative Age of Faults.—A fault is younger than the rocks which it intersects. A fault which is clearly dislocated by an intersecting fault is older than the latter (Fig. 171, B). Yet there are many cases of intersecting faults which are essentially contemporaneous, even though some are slightly dislocated by others. Such faults generally occur in definite sets which, like intersecting joint sets (218), have been formed during one and the same period of deformation. In a given region tension faults are usually younger than compression faults.

¹ See Bibliog., LAHKE, F. H., 1929.

198. Warped and Folded Faults.—Faults have been recorded as folded or warped; that is to say faulting is supposed to have been accompanied or followed by folding or warping. Overthrusts are particularly liable to bending, because, like most folds, they are products of compression, and they may be followed as well as preceded by folding (Fig. 169). Tension faults are less apt to be warped unless the rocks which they intersect are buried and subjected to folding in a later geologic period. Note, however, that the fact that a fault has an undulose shape and looks as if it had been flat and had been bent, is no proof of subsequent deformation. A great many faults originate with such a shape. Indeed, irregular form is more typical than is flatness. Yet in most cases, no doubt, a highly undulose shape of




FIG. 211.—Section of a fault, *a*, which is intersected by a surface of unconformity, *bc*. Since the surface of unconformity and the beds above it have been folded, the irregularity of the subjacent fault is probably also a consequence of deformation. The little patch of stippling (to represent sandstone) in the upper middle part of the diagram was displaced along fault *a* from the crest of the anticline just to the left of *a*.

the fault surface is significant of compression after faulting. One's conclusions must be guided largely by the degree of irregularity exhibited. The surest evidence for warping or folding of a fault includes all the following features in association (Fig. 211): (1) the fault has an undulating form; (2) it cuts a rock formation which has clearly been folded; (3) it terminates upward at a surface of unconformity which separates the dislocated formation from an overlying series of strata; (4) this younger series is likewise folded. In the absence or obscurity of one or more of these structural relations, the conclusion that the undulose fault has been bent after its origin becomes less reliable and it is often safer to believe that the shape is primary.

199. Geologic Age of Faults.—The geologic age of faults is ascertained from their relation to the adjoining rocks. An example is shown in Fig. 69. On many of the major faults, displacement has been recurrent, sometimes through long periods of geologic time, so that they may have to be dated as to both their first and last movements (Cf. Fig. 182).

200. Post-Pleistocene Faults in Bedrock.—In countries which were glaciated in the Pleistocene, signs of postglacial dislocation are sometimes found in low scarps or edges, of a fraction of an inch to a few inches in height, which interrupt the continuity of striated and glacially smoothed rock surfaces (Fig. 212).



FIG. 212.—A small postglacial fault, *ac*, which interrupts the continuity of a glacial rock surface. The edge made by the fault is about $\frac{1}{4}$ in. high.

Although the throw of these faults may be small individually, the total displacement of several on a single ledge, all with the downthrow on the same side, may amount to a number of feet. Demonstration of the origin of these faults subsequent to the

erosive work performed by the ice lies in the facts: (1) that the displaced scratches and grooves on the two sides of the fault clearly match as to their direction, shape, and size; and (2) that the edge of the upthrown block at the fault is sharp, not bevelled off as it would be had the dislocation antedated glaciation.¹

201. Faults That Originate in Unconsolidated Sediments.—Faults may be formed in unconsolidated sediments in all the ways described for folds (169). They are usually reverse faults when the deformation was produced by an overriding mass, and, like the overturned plications, they indicate by their attitude the direction in which the agent moved. If due to settling the faults are commonly normal. Settling may be induced by faulting in the underlying rock (Cf. 169, ¶10), by decomposition of the underlying rock and removal of the products in solution (Cf. 169, ¶9), by mechanical washing out of the finer grains from a bed of sand or gravel, or by the removal of a support, such as

¹ Bibliog., MATTHEW, G. F.

ice. It is possible that many of the small faults in aqueoglacial sands are to be explained by one or both of the last two processes.

202. Discrimination between Faults Originating in Sediments before and after Consolidation.—After faulted sediments have become consolidated, it may be difficult to decide whether the observed displacements were formed before or after lithification.




FIG. 213.—Sections to illustrate the difference between faults which were limited to superficial sediments (A) and those which, although appearing in the superficial sediments, had their origin in the underlying bedrock (B). *ab*, line of unconformity between ancient rock foundation (dash pattern) and sediments which were unconsolidated at the time when they were dislocated. *cd*, original land surface at time of faulting. In both cases this surface was later buried under younger sediments.

1. If such faults are thrusts, they are probably associated with crumpling, and the criteria outlined in Art. 170 for the discrimination of contemporaneous folds may be applied.

2. Gravity faults, occasioned by settling of purely superficial origin and therefore limited to sediments which were unconsolidated at the time of the displacements, are seldom more than a few inches or a few feet in length when measured across the bedding. They are spaced typically at short intervals, their trends and mutual relations are irregular, and they are lacking in definite relations to the axes of diastrophic deformation in the

rocks of the region. A fault of this kind is often slightly blurred because some of the grains of the unconsolidated deposit slipped or rolled a little way along the surface of displacement and so obscured the bedding in a thin layer. Such a layer corresponds to a fault breccia in fractured solid rocks. Usually, not always, it is indistinguishable or absent in muds or clays and their derivatives, narrow in sands and sandstones, and broader in coarse materials. These gravity faults commonly terminate upward where the original surface of the deposit was at the time of dislocation (Fig. 213, A).

3. Faults, either single or multiple, which were produced in unconsolidated sediments by displacement in the subjacent rock, intersect a regional unconformity (Fig. 213, B). In the younger formation, which was unconsolidated at the time of their origin, they exhibit many features like those mentioned for the second group, but necessarily they are definitely related to the faults in the rocks below the unconformity. In the underlying formation they are apt to have clean-cut edges, true breccia zones, and other characters such as develop in the dislocation of consolidated rocks. Sometimes the grains of the younger formation are found to have slipped down into the fault crack in the older formation.

FAULTS IN RELATION TO THE LAND SURFACE

203. Classification of Topographic Forms Related to Faulting.

The topographic expression of faults may be original or subsequent. Original are all those land forms produced by faulting and not so modified by erosion but that their primary characters are still recognizable. These include fault scarps (248), faceted spurs due to faulting (251), fault valleys, fault gaps, and rifts (264), kernbutts and kerncols (254), and horsts, grabens, and structural basins bounded by fault scarps (183). All topographic forms which have been derived through the extensive erosion and consequent extensive modification of original topographic features due to faulting are subsequent. Such are fault-line scarps (250, F), fault-line gaps (270, E), and horsts, grabens, and basins, bounded by fault-line scarps (204).

204. Topographic Expression of Horsts, Grabens, and Basins.

Horsts, grabens, and basins are included in the list just given because, if they are comparatively small, or if their characters are very pronounced, they are recognizable as topographic forms: but ordinarily they are so large and their surfaces are so varied




FIG. 214.—Block diagram of a horst after faulting (A) and after considerable erosion (B). The land of block A is supposed to have been reduced by erosion almost to a plain (peneplain) at the level, *xxx*. Then, after a general uplift, the rivers of the region were revived. They cut away the weak rocks, *w*, much more rapidly than the resistant rocks, *h*, so that the lowlands of block A became the uplands of block B. The scarps in A are fault scarps; in B, fault-line scarps.




FIG. 215.—Block diagram of a graben after faulting (A) and after considerable erosion (B). The land of A was reduced to a plain at the level, *xxx*. After uplift and rejuvenation of the rivers, the weaker rocks, *w*, were eroded away more rapidly than the hard rocks (lined), so that the lowlands of A became the uplands of block B. The scarps in A are fault scarps; in B, fault-line scarps.

in relief that their study can be accomplished only by extensive field investigations. Consequently, although the scarps, valleys, and other land forms are described in Chapter XI, horsts, grabens, and basins will receive consideration here.

A horst has been defined as a relatively elevated block of the lithosphere between two downthrown blocks; that is, in its

original surface form, a horst is a ridge (Fig. 214, A), or, if erosion has modified the block, it has a hilly or mountainous expression, provided the block is a large one. In the same way, the original topographic form of a graben is a lowland which may or may not have an even floor (Fig. 215, A).

If such a valley is bounded by tension faults (rifts), it is a *rift valley*; if by thrust faults (ramps), it is a *ramp valley*. If a region in which there is a graben or a horst is exposed to denudation for a long period, hard and soft rocks may be so distributed in the fault blocks that the relief may become reversed. The horst may




FIG. 216.—Relations of an overthrust fault to the land surface. The figure is drawn as if a single block had been cut and the pieces had been separated a short distance. The land surface (top of the blocks) is represented as flat. Erosion has removed a large part of the older overthrust block (shaded), thus exposing the underlying younger rocks (white). (Cf. Fig. 166.) The base of the shaded formation is the fault, drawn as a full line where still present, and as a dashed line where eroded. The arrows indicate the relative motion of the blocks in the faulting. *a*, a fault outlier; *b*, a fault inlier. Quite commonly in nature fault outliers are hills, and inliers are basins, topographically.

become a lowland and the graben may become an upland (see B in Figs. 214, 215). Likewise, theoretically, the relief of a geologic basin may be reversed.

The student should observe that even if a basin or a graben is still a lowland, and if the horst is still an upland, this seemingly primary form may be of subsequent development. In other words the scarps which bound the basin, graben, or horst, may be fault-line scarps (250, F) which front in the same direction as the original fault scarps.

205. Effects of Topography on the Trend of Fault Lines.—Major faults are more apt to trend along valleys or along the bases of scarps, but where a fault runs across hills and valleys the form

of its outcrop is regulated by the topography in just the same way as is that of an exposed stratum (174). The rules governing the outcrops of vertical, inclined, and horizontal faults are identical with those for strata with like attitudes; and the exceptions are the same. The trace of an overthrust may be highly complex and irregular (Fig. 216).

206. Inliers and Outliers Produced by Erosion of Faults.—

Like low-dipping strata, the outcrop lines of overthrusts are very involved and sinuous in lands of marked relief. Cases are known in which the overlying (overthrust) block (decke, or *nappe*) has been locally perforated by erosion so that the lower block has become uncovered (Fig. 216, *b*). An isolated exposure like this has been termed a *fenster* (German, window). With reference to the main mass of the overridden block, a *fenster* may be called a *fault inlier*. In analogous fashion, a remnant of the upper, overthrust block, separated by erosion from the main area of this block and surrounded by the worn surface of the lower block, is termed a *klippe* (pl., *klippen*), or *fault outlier* (Fig. 216, *a*) (Cf. Fig. 179).

207. Effects of Faulting on Streams.—A and B in Fig. 217 show two cases in which dislocation has occurred across the channel of a stream. If downthrow is on the downstream side of the fault, the stream will incise its course in the upthrown block and will build a small alluvial fan in front of the scarp (Fig. 217, A). This process will continue until the river's channel is reduced to a uniform grade. Following relative upthrow of the downstream block (Fig. 217, B), the fault scarp serves as a dam above which a lake may be impounded. The lake will rise until it spills over at the old channel. The outlet will then be degraded until the lake is drained and any sediments which may have been spread over its floor will be incised.

208. Displacement Relative to Sea Level.—When we say that one fault block has moved up or down with respect to another, we do not imply anything as to the actual change of position computed from sea level. Slickensides and measured relative displacements do not solve this problem. Both fault blocks may be

lowered, but if one sinks more than the other, the latter appears to have been raised. For ancient faults it is practically impossible to determine the true change of position. Recent earth movements can be studied by levelling. A comparison between old and new triangulation records may establish results as to uplift or downthrow with respect to sea level. This is really the only satisfactory method, although certain physiographic features, when observed not too far from the coast, may be significant. For instance, where there is evidence that a late young topography, adjacent to the coast, has had its valleys suddenly aggraded from the shore line inland to a fault scarp which shows




FIG. 217.—Relations of faulting to streams. A, upthrow on upstream side of fault; B, upthrow on downstream side of fault. A lake has formed upstream from the fault in B.

downthrow toward the sea, the seaward block has probably been depressed with respect to sea level. In this, as in other problems, the correlation of geologic and physiographic phenomena is of great importance.

209. Original Inclination of a Fault Scarp.—The average inclination of a fault scarp may be less than the dip of the fault (or faults) either because the displacement is a distributive fault or because the scarp has been lowered by erosion. Professor Wm. M. Davis suggested a physiographic method of determining in a rough way how steep a dissected scarp may have been before it was modified by erosion.¹ If the fault had been very steep, as in Fig. 265, a talus would probably have accumulated at the base of the scarp between the notches, and this rock waste would have been conspicuous in front of each triangular facet for a long time during the erosion of the fault block. The absence

¹Bibliog., DAVIS, W. M., 1909, p 754.

of a talus with these relations would therefore indicate that the scarp was originally of comparatively low inclination, perhaps not much over 30° or 35° (246). However, we might assume that, for a steep fault, slipping might have been intermittent through a period sufficiently long to permit erosion to keep the scarp reduced to a low angle and to remove the waste.

210. Topographic Forms as Evidences of Faulting.—None of the land forms listed in Art. 203 can be accepted as *prima facie* evidence for faulting. Perhaps the most significant are rifts, kerneols, and kernbutts, and certainly: (1) scarps which interrupt the continuity of slope on constructional surfaces (248); (2) local abnormal changes in stream courses associated with transverse scarps or rift valleys in the banks on either side (207); and springs in linear arrangement. But rift valleys, kernbutts, and kerneols are not always easy to recognize; scarps, faceted spurs, gaps, and valleys may originate in other ways than by dislocation; and springs may be arranged in linear fashion where a water-bearing stratum comes to the surface in a long narrow belt. Faceted spurs may be made by glacial scour or by marine erosion (251); valleys may be eroded upon belts of weak rock, or along lines of igneous contact and of unconformity (270, B); erosion scarps often look very much like fault scarps (248), and raised beaches, river terraces, etc., may resemble low fault scarps in unconsolidated gravels or in other loose deposits (252-257). A common fallacy is to ascribe joint-faced erosion scarps to faulting. Such scarps are especially numerous in glaciated lands and they may be very striking in their regularity and in their extent. They are often the plucked sides of roches moutonnées. As in the case of many of the geologic structures mentioned in the preceding pages, these topographic forms suggest the possibility of faulting, but they do not prove it. Before they can be attributed to faulting, the geologist must demonstrate that there is no other reason for their being. In other words, he must be able to discriminate between them and other similar features of the land surface. For the comparison between like topographic forms, the reader is referred to Chapter XI.

JOINTS

TERMINOLOGY AND CLASSIFICATION

211. Definitions.—Well-defined cracks in a rock divide it into blocks. If, along such a crack, there has been no slipping of one block on another, or if one block has slipped only a very little against the other, the crack is termed a *joint*. Slight displacement may sometimes be seen when, for instance, a pebble in conglomerate has been split by a joint and the pieces have subsequently been cemented together in their altered position by vein material. The blocks between adjacent joints, or blocks bounded by joints, are called *joint blocks*. Their breadth depends upon the *spacing* of the joints. The opposing surfaces of two blocks at a joint are the *walls* or *surfaces* of this joint. Short or long, straight or curving, regularly or irregularly distributed, joints display great variety of character. They may be arranged in definite *sets*, all those belonging to one set having the same general direction. Often the fractures of one set are better developed than those of the other set or sets in a locality, and we then call the former the *master joints* or *major joints*. The strike and dip of a joint may be taken on the outcropping edge of the crack, or, if one block has been removed, upon the joint wall that still remains *in situ*.

212. Classification.—Theoretically, joints may be classified according to whether they have been formed by compression, tension, or torsion. Since torsion is a special case involving both tension and compression, it will not be included here. Due to compression are: (1) irregular cracks induced by the expansion of rocks consequent upon chemical alteration; (2) diagonal joints in igneous rocks; and (3) probably a majority of the regular joint systems in stratified rocks. Tension joints include: (1) irregular cracks formed in the shrinkage accompanying certain kinds of rock alteration; (2) hexagonal columnar structure and associated fractures due to cooling; (3) cross joints in igneous rocks; (4) small local cracks, opened in folding, in the upper parts of some anticlines and less often in the lower parts of synclines; (5) gash

joints transverse to cleavage in sheared rocks; (6) fractures clearly associated with tension faulting; (7) cracks due to the drying of muds, clays, and argillaceous limestones.

To say whether the origin of this or that joint or set of joints is to be ascribed to tension or to compression is not always possible. The criteria are too indefinite and the problem is often too complex for solution. Typical tension fractures bear on their surfaces evidences of pulling apart, of disruption. From their walls project the grains or pebbles or other physical constituents of the broken rock, and each projection on one joint surface is matched by a hollow from which it was torn on the other surface. Thus, tension cracks characteristically have rough, granular walls. On the other hand, joints arising from compression are really shear surfaces along which there has been a small differential gliding of the blocks. Such fractures cut across pebbles and large grains indiscriminately, so that the joint walls are apt to be comparatively smooth. Mathematical flatness and smoothness are prevented by the imperfect elasticity of rocks and by other interfering factors. More significant than these surface features in determining the nature of the causal force are the larger relations to folds or to adjacent igneous bodies. These will be mentioned below in describing the more important types of joints.

DESCRIPTION OF JOINTS

213. Primary Fracture Systems in Igneous Rocks.—In igneous rock bodies several kinds of primary fracture are recognized. These are primary in the sense that they originate through forces acting during what may be called the emplacement period of the eruption. These classes of fracture include the columnar and transverse jointing observed in many flows and some thin intrusive sheets (Art. 214); and the following six kinds of fracture, usually rather definitely related to flow structure in the larger eruptive bodies: (1) cross joints, (2) marginal fissures, (3) longitudinal joints, (4) diagonal joints, (5) flat-lying primary joints, and (6) flat-lying normal faults (Art. 215).

lines (113). They are of tension origin. Flow structure must be present for their designation. Where they pass down into the




FIG. 220.—Diagram to illustrate bending of weak and strong material and attendant development of marginal fractures or joint fans. In A, a weak substance protrudes in the direction of the arrow, between stationary walls to the left and right. The zones of intense lengthening (between the dashed lines) are relatively narrow, as shown by the curvature of the three lines. Under suitable conditions, tension joints open within these zones, approximately normal to the lines of local elongation. In nature the marginal fissures near intrusive contacts are due to a similar lengthening of the magma. In B, the material is stronger than in A. The zone of bending is wider, the elongation per unit area less intense. Fractures within the border zones are more widely spaced, and the dip is steeper. In C, a strong substance is bent. Distinct zones of bending disappear, and a continuous symmetric arch results. The fractures are arranged in a broad fan. The fans of tension joints in massifs are believed to form under similar conditions; hence, they are steeper than marginal fissures and reach from one end of the massif to the other. (After Robert Balk, *Bibliog.*, 1937, p. 102. See caption for Fig. 219.)

more massive part of the igneous body, where flow lines may be wanting or indistinguishable, they are called *tension joints*; but, to be so classified, their relationship to the true cross joints must

be established. If the flow lines form an arch or dome in the igneous mass (Fig. 91), the cross joints will be arranged in a fan (Fig. 219). This fan of cross joints may extend into the country rock, which suggests that the wall rocks as well as the intrusive suffered some stretching or elongation in a direction normal to these joints (Fig. 219).

The steep border regions of some large intrusions are accompanied by systems of aplite and pegmatite dikes, quartz veins, and fissures, which dip into the igneous body at angles between 20 and 45°. These belong to the class of *marginal fissures*, probably caused by local stretching involved in the upthrust of the eruptive mass (Fig. 220).

Quoting Balk,¹ "In border zones where flow structures are vertical, these fractures have distinct dip angles, whereas true cross joints would lie horizontal. . . . In nature . . . steeply dipping flow layers and flow lines represent the earliest stage; marginal fissures dip gently into the intrusive because they were formed a little later—*i.e.*, the magma had stiffened somewhat during their period of origin. . . . A broad fan of cross joints (or tension joints) is superposed, in general, to all other elements, being the expression of slight bending or arching in a highly rigid material." Figure 219 gives a diagrammatic picture of these relations.

Longitudinal joints, or *strike joints*, are steeply dipping fracture surfaces that strike parallel to the flow lines. They are not so smooth as cross joints.

Diagonal joints are steeply dipping fractures that tend to lie at angles of approximately 45°, or more, to the trend of the flow lines. They may therefore occur in two sets, although locally one or the other set may not be developed. These joints are regarded as shear planes produced by compression normal to the trend of the flow lines.

Primary flat-lying fractures may occur in sheetlike intrusions. Their origin may have been aided by approximately horizontal floors or roofs (of the chamber invaded by the magma) or by

¹ Bibliog., ROBERT BALK, 1937, p. 101.

low-dipping flow layers; but they are not limited to associations of this kind. Care must be exercised in discriminating between these primary fractures and the joints opened by exfoliation (216).

Flat-lying normal faults (Fig. 221) "are so arranged that the sum of all displacements along them widens an intrusive horizontally. . . . The strike of these faults may vary, but the




FIG. 221.—Association of flat-lying normal faults with marginal fissures and thrusts. Along steep contacts (left and right), marginal fissures prevail. They lengthen the massif upward and outward. The flat-lying normal faults (center) distend the intrusive horizontally and seem to develop especially near subhorizontal contacts. In some instances, the expansion along these fracture systems seems to be caused by continuous intrusion of magma into the core of a massif. (After Robert Balk, *Bibliog.*, 1937, p. 107. See caption for Fig. 219.)

azimuth of the slickensides on them is parallel to that of the flow lines."¹

216. Sheet Jointing in Massive Rocks.—Sheet structure, sheet jointing, or sheeting may be seen to good advantage in granite and other massive, homogeneous rocks. The joints are broadly undulating and are roughly parallel to the surface of the ground. They divide the rock into flat sheets, or into lenticular slabs that lie so that the thick part of one rests upon the thin ends of two underlying lenses (Fig. 222). The vertical spacing of the blocks,

¹ *Ibid.*, p. 107.

i.e., the thickness of the slabs, increases downward. The fracturing is believed to be due to relief of pressure, and consequent vertical expansion, through removal of the overlying rock by erosion.¹

When sheet jointing is present in massive sedimentary rocks considerable care is sometimes necessary to distinguish between it and stratification. Even granites and other igneous rocks that are well sheeted may look very much like strata from a distance.




FIG. 222.—Vertical section of sheeted granite. The joints or sheets inclose roughly tectonic slabs of the rock between them.

217. Columnar and Transverse Jointing Not Related to Igneous Eruption.—Sun cracks are an example of original or contemporaneous hexagonal columnar jointing (58). The tendency to open along the old fissures may persist even through the long period of burial and lithification of the mud, so that, when the consolidated rock is finally exposed by erosion, joints may form along the ancient sun-crack surfaces. These inclose short, roughly hexagonal columns just as the sun cracks did. Perpendicular to the bedding surfaces the columns fade away downward but terminate abruptly upward. (Why?) These revived original fractures are seldom found. They have been noted not only in mudstones but also in limestones that have suffered exposure to the atmosphere at intervals during their accumulation.

218. Intersecting Joint Systems in Stratified Rocks.—In the stratified rocks of any district joints may be seen striking in all the directions of the compass, but among these a large proportion usually fall into two or more distinct sets. These are the major joints, and it is these that the following description concerns. The minor fractures are merely the outcome of the complex conditions of force and resistance that must obtain in a

¹ Bibliog., DALE, T. N., 1907; pp. 30-38.

strained series of variable beds. Probably the majority of joints in stratified rocks are the result of compression or of torsion, seldom of simple tension.

1. Compression along a single axis may produce two, four, or more joint sets, and there is a tendency for fractures in intersecting sets to be perpendicular to one another and for all the sets to be approximately at 45° to the direction of compression (Fig.




FIG. 223.—Compression joints, in conjugate sets, made by forces acting in the direction of the arrows. ab would be the approximate strike of beds folded by these forces. In A both sets of fractures are strike joints; in both sets are diagonal joints. All four might well be produced in a single rock mass. They are shown separately here merely for comparison.

223). Two sets of joints thus mutually related are called *conjugate sets*. All such joints (compression joints or shear joints) are likely to show on their surfaces indications of slight shearing, and close inspection may reveal minute displacements between the severed parts of fractured objects in the rock. In a region of folding, if two joint sets only are well developed, both may strike roughly parallel to the fold axis (*strike joints*), or at an average angle of 45° to this direction (Cf. A and B, Fig. 223). If parallel to the axes, these joints dip so that they converge above anticlines and below synclines (Figs, 224; 225, A). If the joints

strike oblique to the fold axis (Fig. 223, B), they will have a nearly vertical dip. The first condition, A, is best developed where vertical relief is comparatively easy upward and the second condition, B, where relief under the compression is more easy in a roughly horizontal direction. It is possible also for joint systems to result from compression acting along the fold axes in the condition of strain for the formation of complex folds (157).

If, through this *minimum* compression, fractures arise striking perpendicular to these lines of force, their average strike will be nearly in the plane of the dip of the main folds. They will be *dip joints*. Their dips will approach 45° .

For the significance¹ of certain kinds of compression joints in folded strata, refer to Art. 228.

2. Torsion, like compression, may give rise to two, four, or more sets of joints that bear similar relations to one another and that tend to make an angle of 45° with the axis of twisting. Torsional stress probably accompanies the warping and compression that produced complex folds. Since torsion involves both compression and tension, fracture systems related to both conditions of stress may develop.




FIG. 224.—Block diagram of a thin, weak bed (*ab*) between two thick, strong beds. The fractures in the strong beds are strike joints formed by compression. Those which are parallel to the bedding are bedding joints. In the weak bed the curved fractures are fracture cleavage, and the five short cracks are gash joints formed by tension. (After E. Steidtmann, with modification.)




FIG. 225.—Sections of folded strata intersected by strike joints. In A the fractures are compression joints, and in B they are tension joints.

3. Sometimes tension may lead to the formation of cracks at the crests of anticlines and less often at the troughs of syn-

¹ See also Bibliog., BUCHER, WALTER H.

clines, where stretching results from folding; but it is doubtful whether joints of this nature are common. In simple folds tension joints strike parallel to the fold axes, and in complex folds there are two sets, one striking parallel, and the other transverse, to the axes. These joints, unlike the fractures made in analogous positions by compression, dip so as to diverge above anticlines and below synclines (Fig. 225, B).

According to Cloos,¹ tension joints perpendicular to fold axes are common. He compares them with cross joints in igneous rocks, since, in both cases, they are essentially normal to the direction of greatest elongation (fold axes; linear flow structure).

Gash joints are short, local tension fractures (Fig. 224).

The geologist may take for granted that lithified, flat-lying strata have nearly always suffered broad-scale warping, although in small areas no dip may be apparent. These "horizontal" beds are commonly intersected by two main vertical joint sets approximately perpendicular to one another. Extended field work in some regions has demonstrated not only the existence of broad undulations in such strata, but also the fact that the two master fracture sets strike respectively perpendicular and parallel to the axes of the low folds and dip so as to converge above anticlines and below synclines. For these particular areas, then, the joints would seem to be of compressional origin. In distinctly folded rocks conspicuous joint sets are more numerous and more closely spaced, and their study is correspondingly more difficult.

No individual joints, not even the master ones, are continuous for long distances. When a fracture ends it is usually replaced, on one or the other side, often with a few inches or a few feet of overlap, by other joints having the same trend. In strata of variable resistance, joints in one bed often end abruptly against an adjacent bed or they may turn and pass through the latter bed in a different direction.²

¹ Bibliog., CLOOS, ERNST, 1937, p. 74.

² For important papers on joints see Bibliog., MEAD, WARREN J., 1920, and BUCHER, WALTER H., 1920-1921.

INTERPRETATION OF JOINTS

219. Interpretation of Joints.--Careful field investigation of joints may assist in the interpretation of local and regional geologic structures. Take, for example, hexagonal columnar jointing (214). We know that the columns are apt to develop perpendicular to the igneous contact at which their growth commences. Therefore, if a rock has vertical columnar jointing, the contact is probably horizontal, and if the columns are horizontal the contact is vertical. If such columns are present, they are apt to be vertical or steeply inclined in recent lava flows, perpendicular to the adjacent strata in sills and laccoliths, and in dikes that cut stratified rocks they are parallel or inclined to the bedding.

In proportion as the columnar structure is less perfect, the transverse joints become more conspicuous. They may be of use because of their approximate parallelism with the contact. Following is an actual example: A certain outcrop of trap was intersected by what appeared to be a very complex system of joints. Upon close examination one fracture set seemed to be better developed than the rest. It had a definite trend and the cracks belonging to it were, many of them, continuous for several yards. They had a strike between N 10° W. and N. 10° E. and a dip of about 50° eastward. There were several other less prominent joint sets more or less perpendicular to the master set. Knowing that trap occurred in this region generally in straight-edged dikes and assuming that the fissures were of the tension class, the geologist inferred that the master set corresponded to the transverse variety of joints, that the contact might have approximately the same attitude, and that, therefore, search should be made on the eastern and western edges of the outcrop. By removing the sod here and there this conclusion was proved to be correct. The country rock was found, the igneous rock was shown to be a dike, and the attitude of the dike was obtained. The value of this method lies, not in its

infallibility, for it is by no means certain, but in its suggestiveness where contacts are hidden.

In field studies of the larger eruptive bodies, the geologist should investigate and map both flow structures and fracture systems in order to ascertain their mutual relations. From such data he should be able to learn a great deal concerning the form of the igneous body, the nature and attitude of its contacts, and the mechanics of its emplacement (Art. 444).

In regions of folded strata, whether the folds are broad and low or are close and indicative of strong deformation, the master joint systems usually exhibit a marked degree of regularity over an area much more extensive than the individual folds. Consequently, if carefully mapped and properly interpreted, they may reveal valuable information as to the history and larger structural features of the regional geology.

JOINTS IN RELATION TO THEIR TIME OF ORIGIN

220. Age of Joints.—From what has been stated above certain important conclusions may be drawn: (1) Joints having different attitudes may be of the same age, whether they are intersecting or not. (2) If, in homogeneous rocks, the joints of one set, *A*, are relatively short and always terminate against the fractures of another set, *B*, *A* may be younger than *B*. (3) If joints in a given bed terminate abruptly against an overlying bed, they are not necessarily older than the latter; rather they are almost surely younger. (4) Conjugate sets of joints in folded strata striking at approximately 45° to the direction of maximum compression are essentially contemporaneous with the folding. (5) Joints due to the cooling of an intrusive rock are younger than the adjacent country rock (214). (6) Joints due to the cooling of a lava flow are younger than the underlying rock. (7) Joints that are due either to drying or to cooling are essentially contemporaneous with the origin of the material in which they occur. (8) In the larger igneous bodies, cross joints, marginal fissures, diagonal joints, and other fracture systems belong to the later stages of intrusion when the magma had already become too

viscous to flow but while it was still under the stresses involved in its emplacement. To these statements may be added the following: (9) Joints may be synchronous with cleavage (*q.v.*). (10) Compression joints may be contemporaneous with compression faults (*q.v.*), and tension joints may be contemporaneous with tension faults (*q.v.*).

The geologic age of joints may sometimes be ascertained by their relations to dikes. For instance, in a certain region where late Carboniferous strata were folded before the Triassic period commenced, the beds were abundantly cut by several prominent sets of fractures. Parallel with these fractures and showing every sign of having been intruded into some of them, are numerous dikes of Triassic age. Obviously the joints are pre-Triassic and




FIG. 226.—A line of unconformity, *ab*, which indicates by its form that the older formation (dash pattern) had vertical and horizontal joint sets prior to the deposition of the overlying sediments.

post-Carboniferous, and they must, therefore, have been contemporaneous with the folding, or a little later.

Joints were no doubt developed near the earth's surface in the past just as they are today, and we might, therefore, expect to find signs of old fracture systems at surfaces of regional unconformity. However, it would require a shrewd geologist to prove that existing cracks in the underlying formation (below the unconformity) are old fissures reopened and are not joints of the same series as those in the overlying younger formation. More satisfactory evidence is necessary. This may be found where the old joints were filled, previous to the first erosion period, by vein material or by dikes, or later, at the close of the erosion period, by sediments belonging to the overlying formation.¹ By their shape and relations to the surface of unconformity, these joint fillings may indicate something of the original character and

¹ It must be clear that the old fissures were not opened along faults.

arrangement of the fractures in which they were formed (Fig. 226).

JOINTS IN RELATION TO THE LAND SURFACE

221. Relations of Joints to Erosion and Topography.—Joints are the commonest kind of fractures in rocks. In promoting erosion they are of the utmost importance, for they serve as channels for waters that cause decomposition, they facilitate the wedge action of ice in disintegration and in glacial quarrying, and they invite concentrated attack by abrasive agents. Many erosional processes are accomplished by the removal of joint blocks. The surface configurations of ledges, cliffs, and mountain summits are generally conditioned by joints. Indeed, it has been demonstrated that the pattern of drainage and topography in a region often reveals a marked dependence upon the existing fracture systems. Thus, the elbow turns in many young streams are not infrequently due to a shift of the current from one joint set to another. The student should be on the lookout for this kind of topographic control, not only in the field, but also by comparing joint directions as plotted on a contour map with the pattern of rivers, lakes, and divides.¹

FRACTURE CLEAVAGE

222. Definition and Origin.—*Rock cleavage* has been defined by Leith as a "structure by virtue of which the rock has the capacity to part along certain parallel surfaces more easily than along others."² He goes so far as to include within the definition such primary parallel structures as bedding, flow structure in igneous rocks, etc. Ordinarily, however, in speaking of rocks, geologists apply the term "cleavage" to secondary structures only. This is the sense in which it is used in the present book.

Cleavage in rocks—also called *fissility*—may be induced by fracture or by flowage. The discussion of flow cleavage is reserved for Chapter IX. *Fracture cleavage*, also called *fissility*, may be regarded as a special case of jointing or of faulting in

¹ Bibliog., HOBBS, W. H.

² Bibliog., LEITH, C. K., 1905, p. 11.

which the displacements are minute and the "blocks" are thin sheets. Not infrequently it occurs in two or more intersecting sets that divide the rock into small polygonal blocks. In thin sections, for microscopic examination, fracture cleavage is seen to consist of true fissures (Fig. 227). Sometimes the microscope reveals columnar or platy minerals distributed in the planes of the fracture, with their long dimensions parallel to it, so that they




FIG. 227.—Microscopic section of fracture cleavage (diagonal) crossing flow cleavage (horizontal). (After T. N. Dale.)

give the appearance of flow cleavage (*q.v.*). They may have acquired this arrangement by growth after the origin of the fracture cleavage or by rotation of the parallel mineral grains of flow cleavage into parallelism with a subsequent fracture cleavage.

For further details on fracture cleavage refer to Chapter IX.

BRECCIAS AND AUTOCLASTIC STRUCTURES

223. Definition and Classification.—The term *breccia* (pron., bretchia, not breck-chia) is derived from a root which means to break. As far as its origin is concerned, it might be applied to a rock which is intersected by closely spaced joints, but this use is not accepted. The word is best employed for rocks which have the following qualifications: (1) the rock consists of an unsorted


mass of angular fragments contained in a matrix of the same or of different material; (2) these fragments have acquired their angularity through breaking, not by abrasion; (3) the materials may have been somewhat shifted from their position before breaking, but ordinarily the change of position is not great. To these qualifications there are some exceptions which will be noted below. The class of breccias includes fault and other friction breccias, talus breccias, breccias resulting from change of volume, explosion breccias, flow breccias, and intrusive breccias.

1. To friction breccias belong fault breccias and shatter zones caused by mechanical stresses acting through the earth. They grade into cataclastic structure, a microscopic kind of brecciation present in many gneisses and schists. Both compressional (thrust) and tensional (gravitational) faulting may cause irregular fracturing by the grinding of the blocks against one another, and sometimes the fragments may show evidences of rubbing (46). By excessive attrition due to shearing such fragments may become more or less rounded. The matrix of a friction breccia generally consists of the same substance as the larger fragments but in a more finely pulverized condition. Friction breccias such as those just described are called *autoclastic* ("self-broken") rocks. In general, as contrasted with normal elastics, they are apt: (a) to consist of homogeneous material like that of the adjacent rocks; (b) to contain a large proportion of vein cementing substance; and (c), when in strata, to trend across the bedding; but none of these criteria is decisive.

Under friction breccias may be put certain fracture structures of superficial origin. Breccia structures may result from overriding ice. The disrupted material may have been solid rock or unconsolidated gravel, sand, or mud, temporarily cemented by interstitial ice (94). Evidences of associated glacial deposits and signs of ice abrasion should be sought. Landslide *débris* and breccia structures caused by other kinds of gravity slipping of essentially superficial origin may also be listed here.

2. Since talus *débris* is the product of a disruptive process it is properly classified as a breccia; but it differs from friction breccias

in that the fragments accumulate many feet or even several hundreds of feet from their source. Coarse-grained rocks may suffer rounding by disintegration so that the talus fragments may lose their angularity. Criteria for consolidated talus are: (a) the materials show different degrees of weathering; (b) the matrix is of the same materials as the larger blocks; (c) the deposit is



A



B

FIG. 228.—Breccia structures. A, agglomerate; B, flow breccia. In B many of the fragments seem to have fitted together and to have been separated by only a little distance. This is because they were broken essentially *in situ*. The fragments in A were thrown by volcanic explosion some distance from the place of their shattering.

often associated with other sediments as a basal accumulation above a regional unconformity; (d) the deposit is banked up against a cliff (usually buried if the talus is consolidated rock). The materials of talus are homogeneous or heterogeneous, depending upon the nature of the cliff rock from which they were derived.

3. Rocks may be broken as well as folded (9 in 169) by change of volume effected by decomposition. Breccia structure of this

origin does not in itself cause removal of the fragments. If they remain essentially in place, they constitute a mass which grades down into the subjacent unshattered rock of the same kind. Being for the most part only slightly dislodged, they can often be seen to have once fitted together. There are no signs of faulting. Interstitial material between the fragments is in relatively small amount and is apt to be foreign.

4. Tuff and agglomerate are varieties of breccia, the fragments having been broken and thrown up by volcanic explosion. The larger blocks in agglomerate may be of lava or of the country rock which was pierced by the conduit, and the matrix may consist of tuff, with or without finely comminuted country rock (Fig. 228, A). Vein cementing substances are common. The best criterion for pyroclastics, aside from their lithologic characters, is their interstratification with recognized lavas.

5. Flow breccias (Fig. 228, B) are formed by hardening and breaking of the surface of a lava sheet while still flowing. The fragments and the matrix are of the same material, the matrix having frozen about the fragments from a molten condition. Various lava structures are usually present both in the fragments and in the matrix.

6. The process of intrusion may be accompanied by brecciation of the country rock, or brecciation by some other method may be followed by invasion of the shattered zone by magma, and in either event the injected magma will congeal as a matrix round the fragments of the country rock. Plutonic differentiates may harden and then be broken by movements of the residual magma which subsequently freezes about the inclusions. Again, by magmatic stoping, blocks split from the roof of a magmatic chamber (batholith, etc.) may be preserved as angular masses in the marginal parts of plutonic bodies. All these are ordinarily classed as intrusive breccias (plutonic breccias, shatter breccias, neck breccias, etc.) (refer to Arts. 136-139). The only rocks with which they are likely to be confused are flow breccias. Their recognition depends upon the determination of the matrix rock as unquestionably intrusive in its relations.

CHAPTER IX

METAMORPHIC ROCKS

METAMORPHISM IN GENERAL

224. General Conditions and Effects of Metamorphism.—It has been pointed out in Art. 154 that the lithosphere is divisible into a lower zone of flowage and an upper zone of fracture. All through the lithosphere water is present, but it is in relatively small amount in the lower zone. In the upper zone it occupies fractures and other open spaces. From the zone of flowage upward to a level near the earth's surface, called *ground-water level* or the *water table*, the rocks are saturated with moisture. Above the water table is a thin shell which has a variable water content and in which the principal movement of the water is downward. This outer shell of the zone of fracture is known as the *belt of weathering*, for processes of weathering are here predominant. Since the water table may fluctuate, rising in wet weather and falling in dry seasons, and since, locally, it may even reach above the earth's surface, as seen in ponds and rivers, the belt of weathering has a thickness which varies from zero to several hundred feet. The saturated rocks between the water table and the zone of flowage are in the *belt of cementation*, so called because many substances dissolved in the belt of weathering are carried down and deposited in this underlying region, thus cementing grains together and filling open spaces. It is here that most vein deposits originate (Chapter X).

All rocks are more or less subject to alteration if the conditions under which they were formed are changed. Such alteration is called *metamorphism*. It may be induced chemically or mechanically. *Gases and liquids, heat, static pressure* (simple downward pressure), *differential pressure*, and *duration of time* are the impor-

tant factors concerned in both chemical and mechanical changes. On account of the different conditions existing at various depths within the lithosphere, different chemical processes assume chief importance in the zones and belts referred to above. In the zone of fracture, oxidation, hydration, and carbonation prevail, the first being particularly characteristic of the belt of weathering and the other two, of the belt of cementation. Complex silicates break down and simpler, less dense minerals form. These processes are therefore said to be *katamorphic* (κατά, *down*, and μορφή, *form*) and the zone is called the *zone of katamorphism*. In contrast to this, reactions in the zone of flowage may involve deoxidation, dehydration, and decarbonation. Here silicates are built up, and the great pressure leads to the formation of denser minerals and a compact crystalline structure. This is known as the *zone of anamorphism* (ἀνά, *up*, and μορφή, *form*).¹ According to definition, any kind of alteration that any rock has undergone, whether *katamorphic* or *anamorphic*, comes under the head of *metamorphism*, but there are many geologists who prefer to restrict the meaning of this term so that it does not include weathering. It will be used in this restricted sense in the present book.

Four important processes leading to change of the conditions under which rocks originate are erosion, sedimentation, eruption, and mountain building.

1. Through erosion rocks that were once at great depths are brought into regions of lower temperatures and pressures than those which prevail farther down in the lithosphere.

2. Sedimentation works in the opposite direction. Materials accumulated on the earth's surface, volcanic products, and high-level intrusive bodies (after their crystallization) suffer a gradual increase in temperature and pressure as they become more and more deeply buried, and ultimately they may enter the influence of *anamorphic* conditions. The weight of the overlying rocks is to be regarded as a simple downward static pressure which

¹ The reader is referred to Bibliog., LEITH, C. K., and MEAD, W. J., for a general discussion of the subject.

induces little or no rock flowage. Hence the new minerals that develop are apt to be those with equidimensional forms (*e.g.*, garnet) or, if they are bladed or tabular (hornblende, staurolite, ottrelite, biotite, etc.), they grow in all sorts of positions (Fig. 229). This is *static metamorphism* (Cf. 4, below). The increasing weight of accumulating sediments may sometimes so far compress the strata, vertically, that there is some differential lateral slipping and the consequent growth of mica plates parallel to this slight motion (Cf. 4, below) (See Arts. 72, 161 ¶2).



FIG. 229.—Metacrysts of hornblende in a gneissic rock. The metacrysts were formed after the development of the parallel gneissic structure. (About $\frac{1}{8}$ natural size.)

3. Through intrusion of magma or overflow of lava the adjacent materials may be heated, invaded by gases and liquids, and otherwise affected. Of the several agents concerned, pressure is usually of least importance. For the most part the alterations are chemical and mineralogical and they are often of the anamorphic type, even within the zone of katamorphism. They come under the head of *contact metamorphism* (131-135).

4. The forces which give rise to folds and compressional faults in the processes of mountain building are very effective agents of metamorphism. At any given point in a rock subjected to differential pressure, the forces may be regarded as resolvable into three components at right angles to one another. These may all

be unequal (three-dimensional stress), or two may be equal and the third greater or less than the others (two-dimensional or plane stress). A rock under this kind of unequal compression may be deformed by fracture or flowage. The metamorphism is said to be *dynamic*.




FIG. 230.—Lens of quartz granules in schist. (Enlarged 15 diameters.) The curving lines represent layers of mica, which wrap round the quartz. The lens originated through crushing of a large quartz grain. The mica was formed by recrystallization of substances which were present in the rock before metamorphism.

Rock cleavage (fissility) (222) is a common result of dynamic metamorphism. That which is developed in the zone of fracture is *fracture cleavage*. In the lower zone, flowage is itself a metamorphic process. It leads to the origin of *flow cleavage*, a struc-




FIG. 231.—Microscopic sections of cleavage structure developed through rock flowage. In A the biotite (black) is arranged with its laths all parallel and the quartz grains (white) have a slight tendency to be elongate parallel to the mica. In B there are three different minerals, all of which are oriented in parallel position. Which rock would probably have the better cleavage? (B is after Blackwelder and Barrows.)

ture consequent upon the parallel orientation of platy and columnar minerals and of minute lenticular aggregates of grains (Figs. 230, 231). This parallel arrangement of the mineral constituents is called *foliation*, and rocks having this internal structure are *foliates*. Locally, along surfaces of slipping, a parallel

arrangement of minerals may be produced in the zone of fracture. Flow cleavage is called *slaty cleavage* when it is so perfect that the rock splits into thin plates of uniform thickness, and it is called *schistosity* when the rock splits easily, but not always very



FIG. 232.—Microscopic section of "sliced" feldspar (white) in mica schist. (After C. K. Leith.)

regularly. Rocks exhibiting these features are called slates and schists, respectively. Micas are the commonest of the thin, flat minerals that give rise to flow cleavage. They often cause a distinct sheen on the broad surfaces of the cleavage fragments.




FIG. 233.—Side view of a specimen of gneiss having parallel linear structure. (Cf. Fig. 234.)

Many schists have the mica flakes distributed in wavy lines (seen in cross section) which alternately meet and separate, and so inclose lenticular areas in which the constituents other than the mica predominate. These lenses range from less than an inch to

many feet in length. A *gneiss* is a metamorphic rock in which a banded distribution of its constituents is more conspicuous than a parallel orientation of the individual grains. Many gneisses contain feldspar, quartz, and mica, so that they look like granitic rocks, especially if their banding is not pronounced (233). In



FIG. 234.—End view of a specimen of gneiss having parallel linear structure. (Cf. Fig. 233, another view of the same specimen.)

gneisses, foliation is not so well developed as in schists.

Flow cleavage is produced, *i.e.*, rock flowage is accomplished, by granulation, recrystallization, and rotation, thus: (1) Brittle minerals are crushed and the aggregates of minute fragments are flattened in planes at right angles to the maximum stress (Figs. 230, 232). This is *cataclastic structure*. (2) From the old constituents new minerals are built and these are apt to be species with tabular or columnar shapes (Figs. 231, 232). If tabular, they grow with their flatness normal to the maximum stress, and if columnar, they grow in various directions, in planes normal to the maximum stress (*plane schistosity*), or, if the mean and maximum forces are approximately equal (plane stress), such crystals may develop with their lengths parallel and in line with the minimum stress (*linear schistosity*, *parallel linear structure*) (Figs. 233, 234). Minerals like quartz and calcite may or may not display elongation of grains, but, even when the grains are roughly equidimensional, they may reveal orientation of their crystal axes, if examined under a polarizing microscope.¹ (3)

¹ Crystals of the various minerals that compose rocks have definite properties in fixed directions, or related to fixed directions, within them, and these directions, called *crystallographic axes*, can be studied by examining thin slices of the minerals with a special type of microscope. Properties

Old or new constituents may be rotated into approximate parallelism.

After flowage has ceased, and static conditions have been resumed, heat, moisture, etc., may still continue to operate and so produce minerals without parallel arrangement. These will lie scattered in various positions through the schist or slate, that is to say, the features of static metamorphism will be superposed upon those of dynamic metamorphism. Often these later crystals are large and conspicuous. Being of origin *subsequent* to that of their inclosing matrix, they are termed *pseudophenocrysts* or *metacrysts*, and the structure is *pseudoporphyritic* (Fig. 229).

Quartzite and marble are not infrequently seen interbedded with schists, yet as a general rule neither displays much evidence of flow cleavage. Both may originate under either static or dynamic conditions, through pressure or through contact metamorphism. In quartzite that was formed under dynamic conditions, the quartz grains are usually a little longer than wide, and they are oriented in parallel position, but the elongation is not enough to be recognized by the eye. The massive character of marble is probably to be accounted for by the ease of recrystallization of calcite. Under static conditions following the cessation of differential pressure, the calcite readily recrystallizes without linear arrangement of its grains. If impurities are sufficiently abundant in these rocks, minerals such as the micas, amphiboles, etc., may be developed with distinctly parallel orientation in dynamic metamorphism, but without orientation in static metamorphism.

In the foregoing paragraphs, we have referred to "parallel orientation" of mineral constituents of rocks having foliated structure. A better term would be "subparallel orientation," for actual parallelism is rare, except in very small sections. The important feature is the tendency toward parallelism, or the approximation to parallelism, which is well expressed by the

thus definitely related to these crystal axes are referred to as *vectorial* properties.

term "preferred orientation," which, as defined by Knopf and Ingerson,¹ describes the spatial relations of the individual grains and also implies that these relations were effected through movement within the rock at the time of its origin.

Preferred orientation is applied to *any* rocks in which the constituents acquired orientation as a consequence of movement within the rock during its origin. Thus, the term includes orientation of the phenocrysts in certain igneous rocks; orientation of clastic flakes or mica in sedimentary rocks; orientation of micas, hornblende crystals, quartz grains, etc., in metamorphic rocks; etc.

As suggested in previous statements, preferred orientation includes dimensional orientation, *i.e.*, orientation of grain shape, and also crystallographic orientation (orientation by crystal vectorial properties), as in the constituents of many quartzites, gneisses, marbles, etc. *Rock fabric* is a term used to include not only the pattern and granularity exhibited by the shape of the constituents but also the pattern made by the orientation of the internal crystal structure of the individual grains.

The study of rock fabric, as thus defined, is *petrofabrics*, which is beyond the scope of this book. However, we do want to emphasize this fact, that, just as minor folds and cleavage may be of great assistance in interpreting the nature of major folding, so also the microscopic examination of rock fabric may serve to unravel problems in structural geology. This the student should keep in mind in case he wants further evidence that may bear on his field studies and conclusions.

In the words of Knopf and Ingerson,² "The purpose of the final microscopic analysis of the internal grain structure of the rock is to block out an accurate ground plan by which to check and, if necessary, to modify the interpretation of megascopic structure as determined from field evidence. This kind of analysis may wipe out many futile speculations as to whether such and such joints are tension joints or shear joints, whether a

¹ See Bibliog., KNOPF, ELEANORA BLISS, and EARL INGERSON, 1938, p. 7.

² Bibliog., Ibid., p. 27.

given schistosity has developed at 45 or 90° to the direction of applied force, whether a given structure is the result of tangential shearing stress or of compression. An intimate and exact knowledge of rock fabric and of the movements that formed the fabric has already been acquired by the use of this tool and has thrown much new light upon the processes of sedimentation, ore deposition, rock deformation, and metamorphism."

Several kinds of metamorphism have already been mentioned. Such are static, dynamic, and contact metamorphism, anamorphism, and katamorphism. *Regional metamorphism* is a term often used in contrast with contact metamorphism, because the latter is generally rather local; but this distinction is unfortunate for alterations caused by intrusion are sometimes very extensive in their distribution. It would be less confusing further to qualify the word "regional" by "static," "dynamic," or "contact," when the discrimination is necessary.

STUDY OF ROCK CLEAVAGE

225. Relations of Flow Cleavage and Fracture Cleavage.—

Fracture cleavage may originate in rocks which have not been below their zone of fracture, or it may be developed in rocks which have already been folded and had a flow cleavage induced upon them in the zone of flowage and which have later been subjected to further compression in the zone of fracture. In the latter case the fracture cleavage is nearly always preceded by minute folding (crenulation) of the older flow cleavage. These relations are represented in Fig. 235. In rocks which have had fracture cleavage induced upon them and then flow cleavage, the earlier cleavage is destroyed.




FIG. 235.—Three ways in which fracture cleavage, *ab*, may develop by deformation of a preexisting flow cleavage.

226. Discrimination between Flow Cleavage and Fracture Cleavage.—When fracture cleavage occurs in several sets, the planes of parting are equally good in different directions, whereas if flow cleavage is found in intersecting planes, one set is usually much smoother and better developed than the other.¹

227. Discrimination between Bedding and Cleavage.—(One of the mistakes which many of the old-time geologists made and which students are very apt to make at first, is to confuse cleav-




FIG. 236.—Relations of flow cleavage and compression joints to deformation. The diagrams are supposed to be drawn on the edge of a bed, as seen in section. A, before folding; B, after folding. The square and circle of A become a rhombus and an ellipse in B. In its proper position in the fold, aa' in B should be vertical. The bedding and the line bb' would then be inclined toward the left. B has been placed in its present position to emphasize the relations between it and A. The lines bb' in B indicate the positions of compression joints and fracture cleavage which may be produced in the deformation. cc' , the direction of greatest elongation of the rock, is the position for flow cleavage. (Cf. Fig. 237.)

age with bedding. The error is most natural, for on weathered rock surfaces both structures may look much alike. But cleavage, in its superficial expression, often appears as parallel fractures, whereas bedding consists of parallel layers of different textures and often of different colors. The parallel layers of foliation (flow cleavage, schistosity) are due to parallelism of constituents, especially mica, rather than to parallelism of adjacent layers of varying texture and composition. The strike and dip of cleavage may be recorded on a map, but on such a map there must be clear indication which symbols are for cleavage and which for stratification.

¹ For further distinctions between the two varieties of cleavage the reader is referred to Bibliog., LEITH, C. K., 1905, p. 125.

228. Relations of Cleavage and Bedding in Folds.—It has been stated (157) that in parallel folding adjustment is accomplished by the shearing of contiguous strata on one another. Each bed on the limb of a fold slips on the next underlying bed *toward the nearest anticlinal axis*. This differential movement has a tendency to produce cleavage planes or joints either parallel to the stratification or at an acute angle to it (Figs. 236, 237). In the latter case the cleavage planes “lean toward the direction of motion.” They dip so as to converge upward in anticlines, like the axial planes of drag folds (159, 165). When beds differ in their competency, cleavage may be developed in this way in the weaker layers only (Fig. 237). It may change a little in direction where it




FIG. 238.—Relations of flow cleavage to folds.




FIG. 237.—Section of alternating competent and incompetent strata in the limb of a fold. The beds dip to the left. The weak layers have flow cleavage, parallel to cc' ; the strong layers are intersected by two sets of compression joints, parallel to aa' and bb' . (Cf. Figs. 224, 236.)




FIG. 239.—Section of vertical strata. 1 and 3 are competent beds; 2 is an incompetent bed with cleavage.

approaches the contacts between beds of different resistance (Fig. 224), and its average attitude in one stratum may vary several degrees from its average attitude in an adjacent stratum.

In similar folds, with which flow cleavage is usually associated, since both are produced in the zone of flowage, this cleavage may be extensively developed with a uniform dip regardless of its position in the folds. It is approximately parallel to their axial planes (Fig. 238). Hence, while it is nearly or quite perpendicular to the bedding in the axial parts of the folds, it may be essentially parallel to the bedding on the limbs. As a matter of fact these are the relations which exist on a much smaller scale between minor drag folds and cleavage when both structures occur together (Cf. Figs. 140, 239). It would seem, then, that the major folding and its associated monoclinial cleavage might be concomitant effects of a powerful control, such as the overriding of a great rock mass in the process of overthrusting, just as the drag folds are a smaller product of differential shearing between separate beds.

229. Uses of Cleavage in Geologic Interpretation.¹—The relations between bedding and cleavage as described in the last section are useful as criteria in the interpretation of geologic structure. An outcrop in which cleavage is perpendicular to the bedding is probably near the axial region of a fold, and one where cleavage is inclined to the bedding at an acute angle is probably in the limb of a fold. Of great importance in this connection are the two rules which have been stated before with reference to parallel folding, namely: (1) the cleavage planes lean in the direction of differential movement between adjacent beds (Fig. 237); and (2) this differential motion is such that any bed slips over the next underlying bed upward toward anticlinal axes (159). By the application of these rules the geologist can tell on which limb of a fold an outcrop is situated, and which are the upper and lower beds in cleaved vertical strata. Thus, in Fig. 239, at the contact *a-b* the cleavage cracks in bed 2 lean toward *a* and so indicate that 1 moved over 2 in this direction. Similarly, 3 slipped along 2 toward *c*. This section, then, must be a part of a limb between an anticline on

¹ See Bibliog., LEITH, C. K., 1913, p. 129, the source for many of the following statements.

the right and a syncline on the left. Successively younger beds are crossed up to the axial region of the syncline in passing from right to left across the outcrops (Cf. 166). "Cleavage in a slate area may strike east and west and dip south at an angle of 45° . The inference is that here are similar composite folds with east-west trend and axial planes dipping to south; further, that the structure was developed by the relatively northward movement of some overlying competent rocks which have been removed; finally this inferred major control suggests a major anticline to the north."¹

230. Distortion of Original Structures, Fossils, Pebbles, Etc.- Of the two kinds of metamorphism, static and dynamic, the



FIG. 240.—Section of the trunk of an ancient tree (*Sigillaria*), flattened by simple compression. (About $\frac{1}{3}$ natural size.)

former is least apt to blur and destroy original structures in a rock. Pebbles, fossils, and such lithologic features as ripple-mark and cross-bedding are little, if at all, altered in shape, except in so far as they are flattened by compression of the rock as a whole (Fig. 240). Indeed, the lithologic structures may be made more conspicuous by the growth of new minerals in layers or lines such as to emphasize contrasts. Dynamic metamorphism, and especially rock flowage, has a marked distorting effect. In similar folding, beds are thinned on the limbs and thickened in the axial regions (157). Sometimes strata are irregularly thinned and thickened so that they "pinch and swell," as seen in cross section. Pinching may go so far that a bed which was once continuous now consists of a series of detached lenses.

Obviously distortion which can have these results must seriously modify the forms of original minor structures. The laminae in cross-bedding may be folded (Fig. 241) or their curvature may be flattened (Fig. 242).² In proportion as they suffer

¹ Bibliog., LEITH, C. K., 1913, p. 132.

² Schists sometimes have a wavy streaking of their constituents in thin lines that may be mistaken for cross-bedding.

deformation, their usefulness in determining stratigraphic sequence lessens (166); and the same is true of ripple-mark. Pebbles may be squeezed into spindle-shaped rods (linear schistosity) (Figs. 20, 21) or they may be flattened into thin sheets




FIG. 241.—Section of deformed curved cross-bedding in vertical strata. By the rule stated in Art. 166, in which direction would one go to find younger strata?

(plane schistosity), the deformation in both cases being accomplished by rock flowage. Fossils also may be distorted (Figs. 243, 244), and unfortunately only a little shearing is enough to deprive them of their value so far as this depends upon the recognition of species.



FIG. 242.—Section of curved cross-bedding which has been somewhat flattened by compression.

In the deformation of any lithologic feature, all stages may exist between very slight change and very great change (231), and in rocks that have been intensely metamorphosed such original features may have been obliterated. Thus, curious though it may seem, the distinction between sheared quartz veins and sheared quartzite pebbles may be almost impossible in

cases of extreme metamorphism. Lithologic structures in igneous rocks may likewise be deformed, but here one must be careful not to confuse phenomena due to magmatic flow with




FIG. 243.—Part of a fossil frond deformed by shearing. The midrib of the leaflets once had the positions *a* and *b*. By the shearing the leaflets above have been shortened and rotated toward the left, *a'*, and the leaflets below have been lengthened and rotated toward the right, *b'*. (About $\frac{1}{2}$ natural size.)

those which are of truly metamorphic nature (233). If possible it is good policy for the beginner to postpone studying highly




FIG. 244. —Deformed impression of the shell of a *Spirifer*. (About natural size.)

metamorphosed rocks in the field until he has first become familiar with the primary characters of sediments and igneous rocks.

DEGREES OF METAMORPHISM AND ORIGIN OF METAMORPHIC ROCKS

231. Degrees of Dynamic Metamorphism in Clastic Sedimentary Rocks.—Like contact metamorphism, dynamic metamorphism exhibits various degrees of intensity (134). To be sure there is great complexity in the latter type of alteration on account of many factors, such as the composition and texture of the rock, yet certain stages can be recognized. (1) The first indications of metamorphism, as seen in hand specimens, are a poor secondary cleavage and a faint gloss on the cleavage surfaces, both due to the presence of a little white mica (sericite or paragonite) in fine laths that have roughly parallel orientation. (2) When shearing has been somewhat more intense, the white mica laths have more perfect parallelism and there are more of them, so that the rock cleavage is better and the sheen on the fracture surfaces is more conspicuous. Sometimes other secondary minerals, like biotite and ilmenite, are found, although these may have originated under static conditions after the cessation of rock flowage (page 269). Fossils are somewhat distorted. Pebbles are slightly, if at all, deformed, but they have thin coats of mica. (3) In what may be called the third stage, secondary cleavage is good and is often consequent upon the parallelism, not only of the white mica, but also of ilmenite, biotite, etc.; that is, all these cleavage minerals grew during rock flowage. Fossils are much distorted. Pebbles, too, are distorted and are thickly coated by white mica. (4) Maximum metamorphism is represented in the fourth stage. Original structures and fossils are largely obliterated and pebbles have been very much deformed. All the minerals in the rock are secondary.

These stages are not sharply defined, nor do they hold for all classes of rock. As they have been described above, they are applicable to many metamorphosed clastic sediments. Other things being equal, flowage is easier in mudstone than in sandstone and in sandstone it is easier than in conglomerate; that is to say, under similar conditions of pressure, etc., mudstones may

acquire a higher degree of metamorphism than sandstones, and sandstones reach a higher stage than conglomerates.

In this connection should be mentioned the alterations of carbonaceous materials, such as coal and petroleum, which may be associated with sediments. These substances react under compression much more readily than do shales, and they may react under both static and dynamic forces. Peaty or coaly materials consist essentially of fixed carbon, volatile hydrocarbons, other volatile substances, such as water, sulphur, etc., and nonvolatile impurities classed as "ash." With increasing compression, probably assisted by moderate heat, the volatile components gradually pass off, thus resulting in an increasing proportion of fixed carbon to remaining volatile hydrocarbons. In any coal, the ratio of the fixed carbon to the fixed carbon plus the volatile hydrocarbons, expressed in percentage, is known as the *fixed carbon ratio* of that coal. The proportions of these ingredients are determined in the laboratory by proximate analyses.

This process of metamorphism is undoubtedly in part dependent upon the abundance and openness of avenues by which the volatile constituents can escape.

In general, within a given coal-bearing formation, the fixed carbon ratio is found to increase downward from the earth's surface, to be somewhat greater on anticlines than on adjacent synclines, and to be relatively high near faults.¹ In two unconformable coal-bearing formations, the fixed carbon ratio is higher in the older formation.

Apparently there is a more or less definite relation between the characters of petroleum in its native state and the degree of metamorphism to which its containing rock formation has been subjected.² The greater the metamorphism, and, therefore, the higher the fixed carbon ratio of any coal which may be present in the formation, the lighter is the associated petroleum, i.e., the

¹ See Bibliog., FULLER, M. L., 1920.

² This relation was first described by DAVID WHITE. See Bibliog., WHITE, DAVID.

greater is its gravity expressed in degrees Baumé. This rule, however, may have many exceptions, for the reason that petroleum compounds are usually fluid and are capable of extensive underground migration. The consequence is that heavy *residual* petroleum substances may occur in a rather highly metamorphosed formation, and *vice versa*, an abnormally light migratory petroleum compound may be found in a series of beds containing coal having a low fixed carbon ratio.

We wish to point out again that these changes in coal and petroleum, if recognizable, are commonly found as indices of metamorphism in sedimentary rocks which have not suffered enough alteration to exhibit even the lowest degree of metamorphism in the associated shales. Sericite does not appear in the latter until the fixed carbon ratio of the coals is very high.

232. Discrimination between Metamorphosed Sedimentary Rocks and Metamorphosed Igneous Rocks.—The facility with which the original classification of a metamorphic rock can be ascertained depends largely on how much the rock has been modified. Seldom is this problem insoluble. Even in cases of extreme metamorphism there are generally some characters, physical or chemical, local or regional, which give intimation of the primary nature of the rock. Some of the more useful points of distinction are noted below.

(1) An important field evidence is an observed gradation in the exposures of a rock from its highly metamorphosed condition to less altered phases where its source is recognizable. In deformed sediments the least altered portions are likely to be found in the axial regions of the folds. (2) Look for original structures that are surely identifiable, such as contacts in the case of igneous rocks, and pebbles, fossils, cross-bedding, etc., in sedimentary rocks. Faults and unconformities must not be mistaken for igneous contacts (312). (3) Original textures, such as porphyritic texture, may be preserved. (4) Igneous rocks may be uniform over large areas; sedimentary rocks often have a regular and continuous banding. (5) Intercalation of beds of limestone or quartzite is good evidence for sediments, but

sometimes calcite and quartz veins may be misinterpreted for beds. (6) Graphite may be sparsely distributed through an igneous rock or it may occur in veins. However, if it is uniformly disseminated in distinctly argillaceous or quartzose layers, or if it forms beds intercalated between such layers, it and its associated rocks are probably of sedimentary origin. (7) Great preponderance of quartz is characteristic of some sediments. Confusion may arise in the case of sheared quartz veins and highly quartzose pegmatite dikes. For other criteria, which are mostly microscopical and chemical, the reader is referred to Trueman and to Leith.¹

233. Discrimination between Primary and Secondary Gneisses.—Primary gneisses are igneous rocks which possess a foliation produced before crystallization was complete. Secondary gneisses are those which acquired their structure through true rock flowage and not through the viscous flow of a stiff magma. Certain characters of primary gneisses, useful as criteria for distinguishing between the two classes of rock, are noted in the following quotation from Trueman:² “Field evidence: Banding in apophyses from the gneiss parallel to the walls and at an angle to the schistosity of the inclosing rock; dikes of pegmatite belonging to the same magmatic series as the gneiss and either parallel to the gneissic structure and foliated with it or cutting the gneissic structure and undisturbed; lack of sharp contact between the acidic and more basic portions of the gneiss, indicating high temperature during the solidifications of the different bands; presence of inclusions of foreign rocks, which are but slightly deformed, in a matrix of well-banded gneiss; presence of distinct bands of widely different composition, none of which may show evidence of shearing; flow-like curves of the banding, some of which may close in a circle.

“Mineralogical evidence: Presence of minerals formed characteristically only from igneous melts and arranged in a manner impossible of formation from solid rocks by metamorphism, *e.g.*,

¹ Bibliog., TRUEMAN, J. D.; LEITH, C. K., 1913.

² Bibliog., TRUEMAN, J. D., p. 231.

nepheline and olivine; textures due to crystallization from an igneous melt."

234. Relative and Geologic Age.—Since metamorphosed rocks were once typical sediments or typical igneous rocks, their age relations are in general similar to those of the rocks from which they were derived. That these relations are more difficult to recognize in their case, however, is suggested in the preceding paragraphs.

The geologic age of metamorphic rocks can seldom be determined directly by fossil contents. Ordinarily it must be obtained by correlation with other rocks whose age is known.

235. Original Depth of Metamorphic Rocks.—A rock which has characteristics due to rock flowage must have once been within its zone of flowage. A comparatively weak rock, like shale, may have undergone anamorphic changes at a moderate depth; but if all the rocks in a formation, even the more resistant types, have flow cleavage or other features unquestionably of anamorphic origin (not contact metamorphism), probably these rocks were altered in the zone of flowage, that is, below the region where both fracture and flowage are possible. On the assumption that the upper part of the zone of flowage is several miles below the earth's surface (154), this would mean that these rocks have been exposed through the erosion of a cover of that thickness.

CHAPTER X

MINERAL DEPOSITS

MINERAL DEPOSITS IN GENERAL

236. Terminology and Classification.—A mineral deposit is a natural concentration of one or more mineral species. The concentration may be brought about by sedimentary, igneous, or metamorphic processes. Such deposits are *primary* if they still preserve their original characters and relations to adjoining rocks, and they are *secondary* if they have suffered partial or complete chemical or mechanical alteration since their origin. In the formation of a secondary deposit the materials often change their position. With reference to the time of their origin as compared with that of the inclosing rock (country rock), primary bodies are either *contemporaneous* (*syngenetic*) or *subsequent* (*epigenetic*). The contemporaneous varieties are further divided into those which are *igneous* and those which are *sedimentary*. Subsequent mineral deposits include *open space deposits* and *replacement deposits*. Secondary deposits, produced by various processes of erosion, may be concentrated by chemical or mechanical means.

It is not the author's purpose to enter into detail concerning mineral deposits. All classes are abundantly represented by ores, *i.e.*, by deposits which are of economic importance, and therefore, if the student wishes full information on the subject he should consult books devoted to economic geology.¹ We are here interested particularly in structural and field relations. With respect to the different types noted above, all discussion of contemporaneous primary mineral deposits and of secondary mineral deposits will be omitted from this chapter. Igneous primary deposits, resulting from processes of magmatic differen-

¹ See SPURR, J. E., "Geology Applied to Mining," McGraw-Hill Book Company, Inc., 1926; also GUNTHER, C. G., and R. C. FLEMING, "The Examination of Prospects," McGraw-Hill Book Company, Inc., 1932.

tiation and segregation, answer to statements made in Chapter VI; sedimentary primary deposits are merely beds which, in general, have structural and field relations like those described for stratified rocks in Chapter V; and many of the facts outlined in Chapters V and IX are applicable to secondary mineral deposits. The only types left for description here are open space and replacement deposits.

STUDY OF SUBSEQUENT MINERAL DEPOSITS

237. Origin of Subsequent Deposits.—Underground waters whether they have descended into the lithosphere from the




FIG. 245.—Section of an open space vein. The mineral numbered 1 was deposited before that numbered 2. The black represents spaces still unfilled. *ab* is the hanging wall and *cd* is the foot wall. The stippled part of the country rock adjacent to the vein has been metasomatized.

earth's surface or have been given off by intruded magmas, contain a variable proportion of mineral substances in solution. In their circulation these waters may come under certain influences which induce the deposition of some of the solutes. Precipitation may be caused by cooling, by the mingling of different solutions, by chemical reactions between a solution and the rock through which it is passing, and in other ways. The

same is true of gaseous solutions which probably emanate from magmas in considerable quantities (134). In the zone of fracture the precipitated minerals may incrust the walls of open spaces and line them with layer upon layer until the openings are partly or wholly filled. Thus originate open space deposits (Fig. 245). Under certain circumstances mineral-bearing solutions may attack a rock, removing its constituents in solution and precipitating new ones by a process of substitution or replacement. This is also

known as *metasomatism*. Such *replacement deposits* may be formed either in the zone of fracture or in the zone of flowage. Metasomatism is often associated with intrusion as one of the important phases of contact metamorphism (Fig. 246).

Although any rock may be altered by replacement if the conditions are favorable, some kinds are much more susceptible than others. Limestone is one of the types that are metasomatized with comparative readiness (Fig. 246). Fossils are often preserved because their constituents have been replaced by more




FIG. 246.—Vertical section of a contact metamorphic deposit. Ore, black; altered country rock beyond ore, stippled. The alteration was induced by the intrusion of the quartz monzonite. The ore is almost entirely limited to the limestone. (After W. Lindgren.)

stable compounds. Not uncommonly the wall rocks of open space fillings are more or less metasomatized in the vicinity of these deposits (Fig. 245).

238. Forms of Subsequent Mineral Deposits.—Subsequent mineral bodies with tabular or sheetlike form and genetically associated with fractures are called *veins* (Fig. 245). They may originate by the filling of a fissure (joint, fault, cleavage plane, etc.) or by more or less replacement of its wall rocks, or by a combination of both processes. Simple open space fillings of any variety naturally have the shape of their inclosing chamber or fissures. Examples are amygdales (page 118); geodes, which are incrustations in cavities a few inches in diameter; and gash

veins, occupying gash joints (Fig. 224) and some other kinds of tension fractures. Stalactites and stalagmites are peculiar types belonging to the group of open space deposits. Replacement bodies are usually very irregular in shape. This is true even of replacement veins, although in the main they are tabular. Veins of any kind may widen or pinch; they may turn in their course, branch, and sometimes form networks; indeed, as a class they display every conceivable irregularity. In schistose rocks they are frequently lenticular.

239. Distribution of Subsequent Deposits.—The fillings of primary open spaces are limited in their distribution to the rocks in which the chambers were present; *e.g.*, amygdales in certain lavas. Deposits in secondary openings, especially fissure fillings, are found in nearly all rocks. They are exceedingly common. Such deposits bear the same relations to geologic structures (folds, contacts, strata, etc.) as do the joints or faults in which they were formed. Sometimes they may be localized in particular rocks. Thus, in a folded stratified series, fissure veins may be found only in the harder, more brittle members which suffered prominent fracturing (159), whereas the less competent beds, which were deformed by flowage, are barren or have only thin, poorly defined veinlets.

Replacement deposits are apt to be associated with igneous contacts or with fractures, shear zones, or other structures which functioned as channels for the mineralizing solutions. Like open space deposits, they too may have a distribution restricted in certain regions to special kinds of rock. Their localization may be caused by some definite control over the migration of the solutions, or to the fact that the altered rocks were relatively very susceptible to metasomatism under the influence of the particular solutions in circulation at the time; *e.g.*, some limestones.

240. Composition of Subsequent Deposits.—The composition of veins and other subsequent deposits is exceedingly varied. Among the commonest constituents are quartz, calcite, epidote, pyrite, chalcopyrite, hematite, barite, prehnite and, the like. Ore-bearing veins generally consist of one or more minerals which

have a commercial value associated with other substances, known as *gangue minerals*, which have no value. Within the gangue the ore minerals may be disseminated as fine particles, or distributed in threads, or segregated in masses, or otherwise arranged. Although ore minerals are sometimes native, as gold, copper, platinum, and mercury, they are usually sulphides, oxides, carbonates, sulphates, chlorides, or other compounds.

241. Size of Vein Deposits.—In thickness veins may range from a fraction of an inch to many yards, and in length they may range from a fraction of an inch to several miles. Many have been followed downward to depths of 3,000 or 4,000 ft.

242. General Field Relations of Veins.—The attitude of a vein is referred to in the same terms as that of a fault, a dike, or a bed. Strike, dip, and hade are used with the same significance as defined in Art. 180. A majority of veins have dips steeper than 50°. When a vein is inclined the wall above it is the *hanging wall* and that below is the *foot wall* (Fig. 245).

The geologic age of a mineral deposit is determined by correlation with fossiliferous strata or with other rocks whose age has been established.

With reference to their relations to the land surface, veins may be more resistant or less resistant to the influences of weathering than their wall rocks. If stronger, they project as ridges. When small and numerous, they give to an outcrop a ribbed surface or a honeycombed appearance according as they are in parallel or intersecting sets. If they are less resistant than their country rock, they weather down below the general level and become covered with their own residual débris (gossan, etc.).

The trends of outcropping veins conform to the rules which have been set forth in Art. 174 for strata.

243. Discrimination between Open Space Deposits and Replacement Deposits.—No infallible rule can be laid down for ready discrimination between open space and replacement deposits. There is generally some alteration in the walls of open space deposits and, on the other hand, replacement

bodies may be situated along fissures which conducted the mineralizing solutions. Every gradation exists between the two classes. Nevertheless there are certain features which are especially characteristic of one group or the other, and these, when properly interpreted, may be of considerable assistance as distinguishing marks. (1) Usually, not always, replacement deposits have rather indistinct or blended contacts and open space deposits have sharply defined boundaries. (2) Open space bodies ordinarily have a banded or crustiform structure parallel to the walls of the original chamber, this being due to the deposition, one upon another, of successive layers of




FIG. 247.—Section of a replacement mineral deposit (white) containing isolated blocks of the country rock in their original position.

varying mineral composition. Banding, if present in replacement deposits, is rarely symmetrical. (3) Replacement veins are apt to be less regular in shape than fissure veins. The latter often exhibit matched walls. (4) Blocks, or “horses,” of the wall rock, completely detached and with their original structures unchanged in position, have been isolated by replacement of the intervening rock (Fig. 247). If detached fragments of the wall rock are found in an open space deposit, they usually touch one another and they have altered their position as shown by the various orientations of their structures.

244. Discrimination between Veins and Dikes.—In their field occurrence dikes and veins are very much alike. Typically they are sheetlike and their irregularities of shape are of similar nature, so that they cannot be distinguished by their form and

structural relations. As for their manner of origin, there is a complete gradation between them. Vein materials are deposited from solutions. Dikes are formed by the consolidation, usually the crystallization, of magma in which is present a variable quantity of gases and vapors. The greater the proportion of these mineralizers, the more mobile is the magma and the more nearly does it resemble a hot solution from which certain types of vein are precipitated. Pegmatite dikes (or veins) are on the border line in the classification. Pegmatite apophyses from granitoid bodies often verge into true quartz veins at their outer extremities.

From these facts it is evident that a satisfactory code of rules for the discrimination of dikes and veins cannot be made. There are too many exceptions. However, texture, lithologic structure, and mineral composition are often helpful guides. Dikes are usually compact without visible open spaces, and not uncommonly they have porphyritic texture. Chilled margins are typical of many. On the contrary, veins are apt to have open spaces into which numerous crystal ends project (drusy cavities), and they may have a banded distribution of their mineral constituents parallel to the walls. Perhaps the most important criteria are mineral composition and especially the relative proportions of the different species. There are certain minerals which, while sometimes found in dikes, are of much more frequent occurrence in veins; and *vice versa*. For example, characteristic of veins are calcite, epidote, and the other minerals cited in Art. 240, and species more typical of dike rocks are feldspar, hornblende, augite, biotite, and muscovite. Yet, even in this case, great care must be exercised not to confuse calcite, epidote, and the like, in veins with the same minerals occurring as secondary constituents of dike rocks.

CHAPTER XI

TOPOGRAPHIC FORMS

LAND FORMS IN GENERAL

245. Land Forms and Their Recognition.—Hills, valleys, plains, beaches, cliffs, and the like, are classed as *topographic forms* or *land forms*. Although most of them are products of the erosional and depositional agents which are working at the earth's surface, some have been made through the operation of subterranean forces. To the latter category belong volcanoes, lava flows, fault scarps, etc.

Of the topographic forms resulting from erosion, those which project upward (hills, etc.) are *positive*, and those which have the nature of depressions are *negative*. Those which are direct effects of wearing down are *destructural*, and those which have been built by processes of accumulation are *constructional*. Destructural land forms are immediately dependent upon the relative resistance of the materials eroded. Underlying structure is of secondary account, although it naturally governs the shape and distribution of the topographic elements. Constructional forms are nearly always situated in regions lower than the sources of the materials. This, of course, is because the products of erosion are generally carried downward.

The ability to recognize land forms is not only indispensable for the geologist, but it is also a valuable acquisition for persons engaged in many other pursuits. One should be able to tell the difference between valleys made by ice and those made by rivers; between hills of eolian, glacial, or volcanic origin; between plains built by rivers and plains due to the work of waves; and so on. The criteria are included for the most part among the following characters of topographic forms: (1) surface features; (2) general

shape, including ground plan and profiles in significant directions; (3) position with reference to topographic surroundings; (4) internal structure; and (5), for constructional deposits, the characters of constituent grains or fragments.

SLOPES

246. Significance of the Inclination of Land Surfaces.—Topography may be said to consist of sloping surfaces. Even plains have some undulations, and those which are essentially flat often

SCALE IN MILES

FIG. 248.—Profile section of Mauna Loa, a lava cone. (After C. E. Dutton.)

have an inclination one way or another. The slope of any such surface is a feature which deserves an explanation, for it is related to the mode of development of the topographic form with which it is associated.

Land surfaces may be on consolidated or on unconsolidated rocks. The average inclination of the surface of a lava sheet, or a lava cone, is indicative of the original viscosity of the liquid rock. Very mobile lavas spread far and have a slope which may be as low as 3° (Fig. 248). Surfaces eroded on bedrock often owe their inclination to a balance between the rates of passive weathering and of active corrosion. Their case will be taken up in more detail below. Any destructional surface which approximately coincides with the stratification of dipping beds is called a *dip slope*. It is due to natural stripping of an overlying weak stratum from an underlying resistant layer (278, C).

Surfaces on unconsolidated sediments may be either destructional or constructional. In the case of stratified deposits, a




FIG. 249.—Profile section of a slope on loose gravel. *abc*, angle of repose. The larger boulders may accumulate at the foot of the slope, although the reverse may be true where these large fragments disintegrate on the upper part of the slope instead of rolling to the base.¹

¹ BEHRE, JR., CHARLES H., "Talus Behavior above Timber on the Rocky Mountains," *Jour. Geol.*, Vol. XLI, 1933, p. 624.

surface coincident with the bedding is probably constructional, and one intersecting the bedding is probably destructional. The most important angle of slope in unconsolidated deposits is that known as the *angle of repose* or *angle of rest*. If sand or gravel has been held up by a support, and this support be removed, the



FIG. 250. Profile of a volcanic cinder cone. The breadth at the base is a few hundred feet (After J. S. Diller.)

sediments will slump down of their own weight and will continue to slide until friction between the particles prevents further slipping. The vertical angle between a horizontal plane and the




FIG. 251 - A, profile of a bluff in loess; B, profile of a bluff in till. The upper steep slope in B is due to rain erosion; the lower more gentle slope is due to a balance between deposition by rainwash and landslides, on the one hand, and erosion by rain, on the other hand.

surface in which sliding ceased is the angle of repose for these materials (Fig. 249). The maximum angle of repose for coarse gravels consisting of angular fragments is about 35° . Even 42° has been recorded. Volcanic lapilli and ash may stand with slopes of 35° to 40° (Fig. 250). The angle of repose for rounded gravels is lower. For mixed sand and gravel and for sand alone, 28° to 30° is common. Damp sand can stand more steeply than dry, and angular

sand more steeply than well-rounded sand. The angle of repose for sand is somewhat higher under water, provided there is no current, for a current can easily reduce the slope to a much lower inclination. Clay, loess, and similar materials, which are capable of a sort of semiconsolidation, may stand in vertical cliffs (Fig.

251), but, when well soaked with water, mud and clay may slide on slopes of only 2° or 3° . In fact, the relative quantity of water between the particles of any kind of mantle rock has a very significant bearing on the angle above which the material will begin to slide. This is important in considering mass movement (3). On many hill slopes, often of moderate inclination, there is a constant tendency for downhill creep, a process that is usually intermittent, being facilitated by moisture and frost. Figure 252 illustrates several evidences for creep.




FIG. 252.—Common evidences of creep. A, moved joint blocks; B, trees with curved trunks concave upslope; C, downslope hending and drag of bedded rock, weathered veins, etc., also present beneath soil elsewhere on the slope; D, displaced posts, poles, and monuments; E, broken or displaced retaining walls and foundations; F, roads and railroads moved out of alignment; G, turf rolls downslope from creeping boulders; H, stone line at approximate base of creeping soil. A and C represent *rock creep*; all other features shown are due to *soil creep*. Rather similar effects may be produced by some types of landslides. (Reproduced from Sharpe's "Landslides and Related Phenomena" by permission of Columbia University Press. See Bibliog., Sharpe, C. F. Stewart, 1938, p. 23.)

CLIFFS

247. Cliffs in General.—To vertical or very steep faces of rock and partially consolidated sediments are given such names as cliffs, scarps, escarpments, precipices, bluffs, etc. The word cliff will be used here in a general sense. The more common varieties may be classified as follows:¹

¹ Fingerted spurs (251) are not included.

KEY FOR THE IDENTIFICATION OF CLIFFS

If a cliff

A. Bears scratches and grooves which

1. Trend principally along the cliff, either horizontal or with a low inclination, the cliff was probably made by glacial abrasion (250, D).
2. Trend up and down the slope, being vertical or steeply inclined, the cliff may be a fault scarp (248) or a landslide scar (250, G).

B. Bears no scratches or grooves, but is rough on account of the separation of grains or joint blocks (34), and

1. Evidence is found of dislocation (faulting) of bedrock structures,
 - a. And of topographic forms, along the cliff, the latter is probably a fault scarp, somewhat weathered (248).
 - b. But not of topographic forms, along the cliff, the latter is probably a fault-line cliff (250, F).
2. No evidence of dislocation is found along the cliff, the latter
 - a. being situated along an existing shore line or, if not so situated, being associated with a wave-cut bench at its base (256), this cliff is a wave-cut cliff (250, A).
 - b. Not being associated with a shore line or with a wave-cut bench, and if
 - (1) The cliff truncates a particular stratum or layer in a series of eroded horizontal or inclined layers, this cliff is an erosion scarp produced largely by weathering (34).
 - (2) The cliff is the front edge of a recent lava flow, this cliff may be original (249).
 - (3) The cliff is the inclosing rim of a crater or of a caldera, and intersects rocks of volcanic origin, this cliff may be a consequence of volcanic explosion, or of the infall of blocks from the sides, accompanied or not accompanied by fusion at the base, or by these processes in coöperation (266).
 - (4) The cliff is not related to any particular kind of rock, but
 - (a) Forms the wall of a river valley (or channel), this cliff is probably due to weathering assisted by basal undermining accomplished by the river (250, B).
 - (b) Forms the wall of a glacial valley or of a cirque, the cliff may be the result of glacial scour, somewhat weathered, or of glacial sapping (250, D and E).
 - (c) Forms the lee side of a *roche moutonnée*, the cliff is probably a result of glacial plucking (250, E).

248. Fault Cliffs.—Fault scarps are cliffs of varying height and length, formed by faulting. The scarp always fronts upon the lower land of the downthrown block. Most fault scarps, espe-

cially the high ones, are the result of recurrent dislocation along the same surface of fracture or along close, parallel fractures. The shape of the original scarp depends upon the topography of the land mass that was broken. If the ground was level, the cliff is pretty regular in height (Fig. 253), but if a rugged surface was intersected by a fault transverse to the trend of the ridges and valleys, the scarp crest zigzags up and down (Fig. 254). In some cases the scarp may be the actual fault surface, but generally all marks of slipping are destroyed by weathering soon after their exposure. Fault scarps in sands, gravels, and




FIG. 253 — Fault scarp interrupting a level land surface. A, hypothetical condition before erosion; B, aspect after moderate erosion. Talus cones have accumulated at the base of the fault cliff.

the like, are seldom steeper than the angle of repose, because such materials are prone to slump (Fig. 255).

When on alluvial cones and other deposits with definite constructional slopes, fault scarps may be distinguished from abandoned shore-line cliffs (286) by their lack of relation to the contours. Shore-line features follow the contours (Fig. 256).

249. Volcanic Cliffs.—The front edges of lava flows are often abrupt and may be fairly straight for many hundred feet, so that they resemble fault scarps. Indeed, it is sometimes a difficult matter to determine whether or not such a steep face in lava is a product of faulting. Evidence for the continuation of a line of displacement must be sought beyond the edge of the lava flow. The inner rims of explosion craters might also be mentioned here. They are steep slopes on which are usually exposed



FIG. 254.—Fault scarps in a mountainous region (After W. M. Davis)




FIG. 255.—Fault scarp in gravel, produced by a displacement in the underlying bedrock. The slope of the scarp is the angle of repose of the gravel.




FIG. 256.—Contour map of an alluvial cone at the base of a mountain range. The dashed lines indicate the relations between the contours and the hypothetical positions of an abandoned shore line, *aa*, a tilted, abandoned shore line, *bb*, and an interrupted fault scarp, *cc*.

the truncated ends of the outward dipping ash deposits and interbedded flows which constitute the volcanic cone. They are distinguished with some difficulty from the bounding walls of volcanic sinks (264).

250. Destructional Cliffs.—Erosion cliffs include sea cliffs, river cliffs and bluffs, cuesta scarps, ice-scoured rock walls, ice-quarried cliffs, fault-line cliffs, and landslide scars. Some are made by weathering, some by abrasion, and some by both. Ordinarily one may assume that a cliff exists either because it is still in process of formation or because it was made so recently that the forces of erosion have not yet had time to erase it.



FIG. 257.—Profile section of a sea cliff. *ab*, overhang; *bc*, undercut, or notch; *cd*, wave-cut bench.

—A. Sea cliffs are maintained by cutting at the base. In hard rock the *locus of attack*, or place where the waves do their principal work, is seen in an undercut, or notch, at about high tide level (Fig. 257). From time to time joint blocks are dislodged from the overhanging rock by frost or by other agents of disintegration. Where weak dikes or strata offer less resistance to the onslaught of the waves than do the adjacent rocks, fissures and cliffs may be cut landward. This is a case of differential erosion. In materials like till, which are apt to slip if undermined, the cliff may be steep, but rarely has the compound nature of undercut and overhang (Fig. 251, B). Gravels and sand slump to their angle of repose just as fast as they are attacked below.

—B. River cliffs are cut by the lateral swinging of the stream. In respect to basal undercutting, dislodgment of blocks from the cliff face, and relation of materials to slope and form, they correspond to sea cliffs. Wherever streams are rapidly incising their channels in horizontal strata of varying resistance

to erosion, the valley walls usually consist of alternating vertical cliffs on the more resistant rocks, and talus slopes with the angle of repose on the weaker strata (Fig. 258). This type of valley wall may be seen in the Colorado Canyon.




FIG. 258.—Profile section of a valley in alternating strong and weak horizontal strata; *a* and *b* weather back equally fast; *d* weathers more slowly than *b* and, therefore, a rock bench is developed at *f*; *c* is so thin that the talus (black) overlaps the base of *b*. (Cf. *e*.)

—C. Cliffs like those just mentioned may form the sides of mesas and buttes (Fig. 259). Each hard layer serves as a protective cover for the underlying softer rock. To some extent erosion may undermine the weak stratum beyond the edge of the strong, but if undermining goes too far, masses of the overlying rock fall off. Thus, while the cliff or escarpment is gradu-




FIG. 259.—Profile section of a mesa. *a*, remains of a weak stratum, nearly worn away; *b*, alternating strong and thin weak beds; *c*, weak stratum with its edges covered by talus (black).

ally worn back, its steepness is maintained as long as the hard stratum, or cliff-maker, stands well above the level attained by the streams of the region when they reach grade (281). If the layers have a low inclination (say up to 20° or 25°), the escarpment is called a *cuesta face* or a *cuesta scarp*, and the cliff-making rock is spoken of as a *cuesta-maker*.

—D. The ice of mountain glaciers scours deep the valleys through which it moves and, in so doing, greatly steepens the valley walls. This is called *oversteepening* (Fig. 260). Such

oversteepened, ice-scoured rock walls are polished and striated unless postglacial weathering has effaced the marks of glaciation. In the latter event the origin by ice abrasion may be demon-




FIG. 260.—Transverse profile section of a glaciated valley (*aca*). *nba*, valley before glaciation; *ada*, original surface of ice. Note the shoulders at *a*.




FIG. 261.—Profile section of the ice-sapped cliff, *ac*, and the ice-scoured floor, *cd*, at the head of a glacial cirque. *t*, talus (of postglacial origin).

strated by other signs of glacial erosion in the vicinity, or by associated glacial deposits.

—E. Ice-quarried cliffs (Fig. 261) are quite different from the preceding type. At the head of a mountain glacier, where

abrasion is little or nil, alternate thawing and freezing operate exactly as does the frost action of disintegration, but on a larger scale, and blocks are riven off along the joints. These blocks of rock settle into the ice (Fig. 262) and are slowly carried away by the glacier. If long continued, this process of *sapping* or *quarry-*





FIG 262 — Same as Fig 261 with the ice restored to its original position, *ac*, rock wall from which alternate thawing and freezing of water loosen blocks that settle into the ice. At *b* is a deep crevice known as the *bergschrund*, which is commonly observed at the head of a glacier and which may facilitate the entrance of water. *cd* is the scoured rock floor over which the ice moves.

ing may develop cliffs up to many hundreds of feet in height, but they are not exposed, except to a certain extent within the *bergschrund*, until after the glacier has dwindled away and disappeared. They form the walls of cirques (270, H).

Smaller cliffs of somewhat similar origin may be seen on *roches moutonnées*, and on hills of like nature, where moving ice detached or *plucked* joint blocks from the lee sides of the rock masses over which it rode (278). *Sapping* or *quarrying* is

accomplished entirely by the passive process of wedging, whereas plucking, although more or less assisted by wedging, is largely dependent upon the overriding of a moving body.

—**F.** Fault-line scarps are erosion scarps developed along lines of faulting. They are not direct effects of displacement.



--b

FIG. 263.—Development of fault-line scarps, as seen in cross section. A, fault scarp. (Cf. Fig. 253, B.) If the land were eroded to the level *aa* and were then uplifted, the weak rock, *m*, would be removed more rapidly than the resistant rock, *o*. Hence a fault-line scarp would be produced in *o*, facing *m*, as shown in B. In the same way, following erosion to the level *bb* (see A), uplift would result in the formation of a fault-line scarp in the resistant rock, *n*, facing the weak rock, *p*, as depicted in C. The black is talus.

They are phenomena belonging to a second cycle of erosion (285). The original fault scarp was eroded to low relief, the land was then uplifted and a second cycle was inaugurated, in which weaker rocks on one side of the fault were worn away more rapidly than more resistant rocks on the other side. Thus, a scarp was developed along the line of faulting. Two conditions are pos-

sible: the lower land toward which the fault-line scarp faces may be (1) on the block which was the downthrown side of the fault (Fig. 263, C) or (2) on that which was the upthrown side (Fig. 263, B). In other words, a fault-line scarp may face the same way as the original fault scarp or in the opposite direction. Figure 264 represents a fault-line scarp formed in the first cycle of erosion.

—G. Landslide scars are the bare surfaces left by the fall of masses of rock or of unconsolidated materials. The greatest dimension of a landslide scar is generally up and down the slope (267, F).



FIG. 264.—Section of a fault scarp and a fault-line scarp. Strong beds, ruled; weak beds, blank; talus, black. *a* has been worn back faster than *c* because the weak rocks are exposed in *a*. Before the faulting, the strong rock stratum at *a* and *c* was continuous.

Here, also, might be mentioned the scars left by mudflows, although these scars are likely to be broad in area, with relatively low bounding edges and on lower slopes than the sites of landslide scars. At the down-slope side or end of a mudflow scar will be found the mudflow débris.

251. Faceted Spurs.—Let us consider the topographic development of a fault scarp in a land mass that was essentially level before its displacement. Take “the ideal case of a faulted block of homogeneous structure whose faulting has progressed at a slow and relatively uniform rate, so that the sides of the ravines that are eroded in it shall be weathered back to graded slopes about as fast as the fault block is raised . . . In an early stage (Fig. 265, A) the low fault scarp is notched by ravines whose location and length are determined by the site of pre-faulting inequalities in the upper surface of the block. Adjacent ravines have not yet widened sufficiently to consume the edge at the top of the block between them. In a later stage (Fig. 265, B) the

block is raised higher, the ravines are worn deeper and farther back, some of them being larger than others. Nothing of the upper front edge of the block now remains, for the flaring walls of the ravines now meet in a sharp ridge crest that rises backward from the vertex of a *triangular facet on the block front*,¹ toward the top of the block. In the third stage (Fig. 265, C) the block is raised still higher, and the ravines have become still longer and deeper; at this stage the mountain crest might become




FIG. 265.—Dissection of a fault scarp. (After W. M. Davis.) A, displacement moderate; gorges short; part of the original front edge of the uplifted block remains. B, the same region after more displacement and erosion; none of the front edge of the uplifted block is left; the fault scarp still persists in a series of triangular facets. C, spurs and deep ravines in the uplifted block after further displacement and erosion. The upper surface of the block is not shown in C. Actually, the spur facets would have suffered some erosion in B, and more in C, and the slopes of these facets would tend, therefore, to decrease (Fig. 266).

serrate, and its back slope would be well dissected. The long, sharp-crested ridges between the larger front ravines are still terminated by triangular facets, very systematic in form and position, with their bases aligned along the mountain front. The spur sides and the facets themselves will have suffered some carving, as is shown in Fig. 266, where some of the terminal facets are enlarged. The moderate dissection of the large facet by small ravines results in the development of several little basal facets along the fault line, where they form the truncating terminals of several little spurs. These basal facets are of importance in this stage of dissection, for they have suffered the least change of any part of the mountain front.

"We are thus led to conclude that the features of special significance as the necessary result of long-continued faulting,

¹ The italics in the quotation are not original.

persistent into the recent period, are, first, the sharp-cut, narrow-floored valleys which have already been considered; and secondly, the large and small terminal facets of the spurs, whose bases show a notable alignment along the mountain front.




FIG. 266.—Dissected terminal facets of main spur. Drawn on a larger scale than Fig. 265. (After W. M. Davis.)




FIG. 267.—Triangular facets due to wave erosion. *ABCD*, initial shore line at time of submergence; *DKF*, cliff facet cut back in spur *DEF*; *FGH*, spur platform fronting its cliff facet, *FLH*, after withdrawal of the water. (After W. M. Davis.)

"If faulting be supposed to cease after the stage of Fig. 265 is reached, the valleys will widen without much deepening at their mouths, the spurs will be narrowed, and the truncating terminal facets will in time be so far consumed that the spurs will become pointed."¹

Faceted spurs may be made also by glacial erosion, or by wave erosion upon a submerged ridge-and-valley topography along a

¹ Bibliog., DAVIS, W. M., 1909, pp. 745-747.

lake shore or a sea coast. If the ice should retreat or if the lake waters or the sea should withdraw, these triangular spur terminations might be mistaken for fault facets. Wave-cut triangular facets, however, would rise from the inner margins of triangular wave-cut benches (256) (Fig. 267), and the valleys would show evidences of aggradation succeeded by rejuvenation, caused, respectively, by the advance and later by the retreat of the waters. Triangular facets made by ice are sometimes found terminating the ridges between adjacent tributary glacial valleys where they enter the trunk glacial trough (Fig. 268).




FIG. 268.—Triangular facets due to glaciation. The lowland in the foreground is part of a broad trunk glacial valley. (Drawn from a photograph, after F. H. Moffit.)

In this case marks of ice scour (32, 35, 36) are generally present on the walls and floors of the valleys and on the facets, and more or less glacial *débris* is distributed in the neighborhood.

A more complex type of faceted spur is developed by a series of transverse, essentially parallel step faults. On such divides downdropped strips of the old upland surface may be preserved at different levels (254).

BEACHES

252. Classification and General Characters.—All constructional shore-line deposits, built principally by the work of waves and longshore currents, and consisting of sand or of pebbles and boulders, are herein classed as *beaches*. Under this head may be listed barrier beaches, bay-head or pocket beaches, spits, bay-mouth bars, tiebars, and cusped forelands.

Along a coast where the mainland is very low (coast of elevation), the waves break some little distance offshore. They




FIG. 269.—Barrier beach and lagoon (Great South Bay) south of Long Island N. Y. The overlap of Fire Island Beach south of Oak Island Beach indicates transportation of sand in the direction of the arrow. Shaded dry land, stippled sand beach, unshaded land area marsh (Isip quadrangle N. Y.)

churn up the bottom sand and build up a *sand reef* or *barrier beach* (*offshore bar*) (Fig. 269), between which and the main shore there is a strip of quiet water called a *lagoon*. Reefs of this kind are well represented along the Atlantic coast from Long Island southward. Along steeper coasts, where the shore line is comparatively straight, a beach often lies at the foot of the sea cliff, forming a thin cover over the wave-cut bench.




FIG. 270.—Bay-head beach (stippled) consisting of wave-washed sediments. The land is to the left. The arrows show the direction of transportation. Sea cliffs are represented by short dashes.

Beach construction on irregular coasts is varied. At the heads of the bays there is a tendency for the accumulation of debris worn from the neighboring headlands. These deposits are *bay-head beaches* (Fig. 270). Sometimes currents sweeping by headlands or islands distribute the rock fragments and sand in *spits* which tail off into deep water (Fig. 271). Spits may be hooked, or re-curved (Fig. 272). If a spit or a barrier beach




FIG. 271.--Spit (stippled) at the head of Bolinas Bay, Cal. (Tamalpais sheet, Cal.) In which direction were the materials of the spit transported?




FIG. 272.—Willoughby Spit, Va. (Norfolk quadrangle, Va.-No. Car.)




FIG. 273.—Merced Lake, Cal., a bay closed by the forward growth of a spit. (San Mateo and San Francisco sheets, Cal.)




FIG. 274.—Mecox Bay, I. I., a bay closed by the landward advance of a barrier beach (Sag Harbor quadrangle, N. Y.)




FIG. 275.

FIG. 275.—Lynn Beach (the long narrow stippled area) connecting Nahant (shaded areas on the south) with the mainland (NW. shaded area). Lynn Beach is a tiebar (*tombolo*). Nahant once consisted of two islands, now themselves united by a tiebar. (Boston Bay coast, Mass.)




FIG. 276.

FIG. 276.—Three varieties of cusped foreland (stippled). The mainland is shaded. In A and C the forelands inclose lagoons. The arrows indicate current directions.

finally closes in the entrance to a bay, it is termed a *bay-mouth bar* (Figs. 273, 274). If it is carried out so far as to join an island with another island, or with the mainland, it is a *tiebar* (Fig. 275). A *cusped foreland* is a triangular point of land, often inclosing a small triangular lagoon, built out from a shore line by currents (Fig. 276).

In general beaches are coarser at the top than they are near the water. Sea beaches often consist of pebbles above high tide level, grading downward into sand, and, below low tide level, into mud. On very low, shelving shores, mud flats are exposed at low tide. Coarse pebble beaches are usually situated near cliffs from which the materials are supplied. A sand beach may have its surface diversified by ripple marks, rill marks, wave marks, and other features which have been described in Chapter IV.

BENCHES AND TERRACES

253. Definitions and Identification.—Benches and terraces are relatively flat, horizontal or gently inclined surfaces, sometimes long and narrow, which are bounded by a steeper ascending slope on one side and by a steeper descending slope on the opposite side. Both forms, when typically developed, are steplike in character. By increase in breadth they grade into plains. Not uncommonly the term *bench* is used to denote forms in solid rock, and *terrace*, forms in unconsolidated materials, but this distinction is not always made.

KEY FOR THE IDENTIFICATION OF TERRACE-LIKE LAND FORMS

The land surface has the form of a bench or a terrace. If

- A. The terrace-like form is definitely related to horizontal strata in the underlying bedrock, being situated between two abrupt slopes or cliffs which truncate relatively hard strata, it is probably a bench or a step produced by differential erosion (256).
- B. The terrace-like form is not definitely related to horizontal strata in the underlying bedrock, and
 - 1. Is situated along an existing shore line, beachlike, usually just above high water level, it may be a wave-built terrace or an ice-pushed terrace (255).

2. Is not situated along an existing shore line, but

a. Is situated on a valley side or a hillside, and

(1) Has a rather irregular shape, seldom with a flat or level surface, and although, perhaps, appearing on the flanks of several adjacent hills (or mountains), never follows up the intervening valleys, the terrace-like form may be a fault bench or terrace (254).

(2) Has a shape which is conspicuous for its regularity, generally with a comparatively flat surface, and

(a) With the appearance of having been *built out upon* the original sloping surface, the terrace-like form may be a marginal terrace (255), or a river terrace (257), or one of several varieties of abandoned beach (252, 286), in any case bounded downhill by a relatively steep slope.

(b) With the appearance of having been *cut into* the original sloping surface, the terrace-like form may be a wave-cut bench (256) or a wave-cut terrace (257), in either case bounded uphill by a steep wave-cut cliff (250) at the base of which wave-worn pebbles and boulders may be present.

(c) With the appearance of having been *both built out upon, and cut into*, the original sloping surface, the terrace-like form may be an abandoned wave-cut bench or terrace (cut in) in association with an abandoned offshore terrace (built out) (286).

b. Is situated on the floor of a valley, it is probably a river terrace (256, 257).

254. Fault Benches.—Irregular benches are produced on the sides of hills and mountains by certain kinds of faulting. These are *fault benches*. Their surfaces may be undulating or hummocky and need not be horizontal along their length. There may be a slight depression—indeed, sometimes quite a marked saddle—between the outer edge of such a bench and its inner edge where it meets the hillside (Fig. 277). Lawson has called the outer, ridge-like edge a *kernbut*, and the inner sag a *kerncol*.¹ Two explanations for the origin of these features are illustrated in Fig. 278. Such benches are not to be confused with similar forms of landslide origin and, therefore, purely superficial (Fig. 279). Benches like that in Fig. 279 may be produced on a smaller scale, either singly or in steplike groups, by slumping.

¹ *Bibliog.*, LAWSON, A. C., 1902-1904, pp. 331 *et seq.*

255. Constructional Terraces.—Constructional terraces include offshore terraces (also called wave-built terraces), marginal deposits and abandoned beaches.

An *offshore terrace* (Fig. 280) is a deposit of sand which is built out into deep water by the combined action of waves and currents. It




FIG. 277.—Map of a hillside ridge made by faulting. (After the California State Earthquake Investigation Commission.)





FIG. 278.—Two explanations for the origin of kernbutts and kerncols. In A the mountain flank consists principally of pre-faulting land surface, and the uphill side of the kernbut is the fault surface (lined). In B the mountain flank is chiefly fault surface (lined), and the uphill side of the kernbut is the pre-faulting land surface.

trends parallel to the shore. The materials are dumped over its outer edge. Its upper surface is a continuation of the shore bench or wave-cut bench with which it is associated. Shore terraces are not exposed except by sufficient subsidence of the water level.

Wave-built terrace is a term sometimes given to the upper coarser portion of a beach where the waves have thrown the pebbles up in low ridges parallel to the shore line and a few feet above mean high water level. An




FIG. 279.—Bench caused by a landslide. aa, original profile; bb, profile after slipping; cc, surface of slipping. (After M. L. Fuller.)

ice-pushed terrace is made along some lake shores by the thrust of ice up the beach. Similar features have been observed on the shores of fiords and inlets of the sea in northern latitudes.

During the later Pleistocene, when the ice was fast melting away, gravels and sands were sometimes deposited between withering ice tongues and the adjacent valley walls. After the complete disappearance of the ice, these deposits were left as terraces on the hillsides. While, for several reasons, they are not common, the chance of their existence should not be forgotten when studying terraces in regions of past glaciation.




FIG. 280.—Shore-line features. *ab*, sea cliff; *bc*, wave-cut bench; *cde*, wave-built terrace; *fgh*, outline of land surface before wave erosion; the same surface lies beneath the terrace; *g*, a stack.

Beaches and other associated shore-line deposits which have been abandoned by the water body at whose margin they were formed, may constitute terraces which may be difficult to distinguish from river terraces. They are discussed in a separate section (286).

256. Destructional Benches and Terraces.—Wave-cut benches, canyon benches, plateau steps, and river terraces may be described in this category.

The *wave-cut bench* (*marine bench*) usually has a rock floor and terminates inland in a marine cliff and seaward in a shore terrace (Fig. 280). It is made by the gradual landward erosion of the cliff and may be more or less covered by a thin layer of rock debris. Stacks (278, F) may rise above the bench near its inner margin. If the land rises or the sea level falls, such a bench becomes *abandoned* (283). Its associated terrace will be quickly destroyed, wholly or in part, and a new sea cliff and sea bench

may be cut into the rocks. The abandoned bench will then be bounded both landward and seaward by sea cliffs (Fig. 281). It may be incised by streams that traverse it to the new shore line.

Marine erosion of *unconsolidated* rock materials may produce a similar wave-cut bench, but the *sea cliff*, at the head of the bench, or fringing residuals corresponding to "stacks," may be less pronounced than in solid rock and may lack the undercut or notch at the base. Forms analogous to those just described may be developed by the action of waves along lake shores; and successive stands of lake level, during a long period of shallowing of the




FIG. 281.—Profile section of abandoned (probably elevated) wave-cut cliffs and benches. Stippled, talus; ab, outline of land before erosion; H.T.L., high tide level. The oldest bench is 1, the next is 2, and the youngest is 3.

lake waters, may result in several such groups of abandoned shore-line features on the slopes forming the lake basin.

In regions of horizontal strata the walls of deep valleys may be steplike. The cliffs between the *treads* or bench levels are in hard strata. In each case the upper surface of the hard layer roughly coincides with the tread above the cliff (Fig. 258). These are *canyon benches*.

Where erosion has greatly broadened benches like those just described, they are called *steps* (German, *stufe*) (Fig. 282). They are characteristic of the high plateaus of western America. Exact counterparts of these steps, as far as their origin is concerned, are the *cuesta* in low-dipping strata and the *hogback* in steeply dipping strata (278, C).

If the *downward* cutting by a river becomes retarded for one reason or another, *lateral* cutting may become predominant, and, by virtue of the swinging and migration of the meanders of the

river, a long narrow plain may be formed, beveling across rocks and structures below (261). Provided the stream now undergoes *rejuvenation*, which means a return of the preponderance of downward over lateral cutting, it will erode below the level of this plain, parts of which will be left as *river terraces*; and, if this process is repeated, there may be several sets or pairs of such terraces, rising steplike above the present level of the river, or of the river flood plain. If, during any period, the meanders swing all the way over to the original valley side, the older (higher) terrace (or terraces) on this side may be destroyed. Also, if




FIG. 282.—Steps, or “stuffs,” made by erosion of alternating strong (stippled) and weak (blank) horizontal strata.

there are numerous tributary streams, these may cut into the terrace remnants, finally leaving only a series of narrow, nearly level-topped spurs as evidence of the former terraces. Eventually these, too, might disappear. Note that, whether these river terraces are carved out of consolidated or unconsolidated rock materials, this fact may not at once be apparent because there is nearly always a thin layer of river alluvium (mud, sand, or gravel) covering the destructional surface of the terrace.

257. Degradation and Aggradation of Rivers.—Erosion by streams, including both downward cutting and sidewise, or lateral, cutting, is called *degradation*. Building of deposits by stream action is *aggradation* or *alluviation*. The development of river terraces, as above described (256), depends mainly on an alternation of the preponderance of downward cutting and of lateral cutting; but terraces may likewise be formed through alternation of degradational and aggradational processes. There are several reasons why degradation may succeed aggradation.

- (1) In its normal development a river constructs an alluvial plain

in its lower course. The surface of this plain is above the level to which the stream can cut in a later stage. Subsequently, therefore, the river incises its channel in the alluvial deposit and, by meandering, may broaden its flood plain (260, A) until only remnants of the old, higher plain are left. These remnants appear as terraces on either side or on both sides of the flood plain. They are usually not very conspicuous features. (2) Much more striking are the terraces formed by the downcutting of a stream into thick alluvial deposits which it laid down during a period when it carried an excessive load. Many of the rivers of northern




FIG. 283. - River terraces. Black spots at the terrace cusps represent bedrock exposures. *abc*, former level of terrace gravels.

regions were thus overloaded by abundant *débris* derived from melting ice in the waning stages of glaciation. With the disappearance of the ice, the supply decreased so much that aggradation gave place to degradation. Terraces made in this way may be preserved for long periods of time when the river, in swinging from side to side, encounters projections of the bedrock below the alluvium. The rock outcrops are generally situated near the terrace cusps (Fig. 283). (3) If the volume of a stream is augmented while the load remains unchanged, the stream will incise its channel. (4) By uplift of the land, rivers may be rejuvenated and so forced to cut into their old alluvial deposits.

PLAINS

258. Terminology and Identification.—Land forms which are comparatively flat and of low inclination and which are not better classified under the head of benches or terraces are placed here under *plains*. They vary in area from a few acres to many

square miles. While their continuity may be interrupted by isolated hills or by occasional valleys, flatness is their predominating quality.

KEY FOR THE IDENTIFICATION OF PLAINS

The land surface is a flat, or nearly flat,¹ plain which may be horizontal or gently inclined. If

A. The materials beneath the plain are till, the plain is a till plain (260, D).

B. The materials beneath the plain have a stratiform structure with which the plain is essentially parallel, and these materials consist principally of

1. Superposed lava sheets, often with intercalated beds of volcanic ash, etc., the plain is of volcanic origin (259).

2. Stratified muds, sands, or gravels, and if

a. The plain constitutes the floor of a basin which

(1) Is intermittently more or less covered by shallow alkaline lakes, the plain is probably a playa (260, F) and is situated in the lower central part of a desert region.

(2) May or may not be flooded from time to time, and which is bordered by such shore-line phenomena as beaches, deltas, wave-cut cliffs, etc., now all abandoned and more or less destroyed, the plain may be the floor of an old lake (260, E).²

b. The plain borders a range of hills or mountains away from which it slopes downward with an inclination of 5° to 8° at its upper margin, this angle decreasing inversely as the distance from the range, the plain may be a piedmont alluvial cone or a piedmont alluvial plain (260, A).

c. The plain constitutes the floor of a valley along which a stream flows, the plain may be a valley train (260, C) or a flood plain (260, A).

d. The plain borders upon a lake, down to which it has a gentle inclination, and

(1) Is local, being situated at the mouth of a stream which empties into the lake, the plain is probably the exposed upper surface of a delta (260, B).

¹ Such a flat plain need not be continuous. It may be incised by valleys or broken by faults, or perhaps diversified by an occasional volcanic cone, sessile upon its surface; but provided its original character is still recognizable, its remaining visible portions may be classified as if it had not been modified since its origin.

² Such features may be found in valleys which were once basins produced by some temporary natural barrier (266).

- (2) Is continuous round a large fraction or the whole of the periphery of the lake, and is underlain by mud or clay, the plain may be an exposed portion of the lake bottom at time of low water.
- e. The plain borders upon the sea, down to which it has a gentle inclination, and
- (1) Is local, being
 - (a) Situated at the mouth of a stream and not being inundated except, perhaps, in rare instances and then only at its outer margin, the plain is probably the exposed surface of a delta (260, B).
 - (b) Part of the floor of a bay, and being inundated at high tide, the plain is probably an estuarine flat (260, E).
 - (2) Is continuous for many miles along the coast and is not inundated at high tide, the plain may be a coastal plain (260, E).¹
- f. The plain, having a gentle southward inclination, is bordered on the north by an irregular hummock-and-hollow topography of glacial origin (refer to the key in 274), it may be a frontal apron or a sand plain (260, C).
- g. The materials beneath the plain are rocks of various kinds and often with diverse structure, and these rocks and structures are truncated by the plain, the latter may be a plain of marine denudation, a graded river flood plain, a peneplain, or a plain of arid denudation (pediment) (261). Note, however, that in many cases, such destructional plains are thinly veneered with gravel or other loose sediments that conceal the typical erosional features and thus make them look like constructional plains.

259. Volcanic Plains.—Volcanic plains are the surfaces of broad sheets of lava or of volcanic ejectamenta. They may be many square miles in area. They are usually diversified by other volcanic forms.

260. Constructional Plains.—River flood plains, alluvial cones, piedmont alluvial plains, delta plains, glacial frontal aprons, outwash plains, valley trains, till plains, lake-floor plains, estuarine flats, coastal plains, and playas are all constructional in their mode of origin. Swamps might also be listed here, but they are treated in Art. 262. All have been built up in one way or another.

¹ A coastal plain may consist of isolated portions at the heads of the bays on an irregular coast which has suffered only a small emergence.

—A. Plains of several kinds are constructed by rivers. When a stream has its volume diminished (as by evaporation in deserts) or has its efficiency lowered by a decrease in its velocity, it may become overburdened with detritus so that it will have to deposit part of its load. *Aggraded flood plains*, characteristic of mature rivers (281), are alluvial flats which are often covered by water at times of flood. When the waters subside a new layer of sediment is deposited on the plain. On piedmont slopes streams are forced to deposit where they pass out from their steeply graded mountain valleys on to broad lowlands. Each stream builds an *alluvial fan* or *cone*, a gently sloping deposit (Fig. 284), which focusses at the point where the stream leaves the mountains. Ordinarily the channel is not so deep but that

FIG. 284.—Radial profile section of an alluvial cone. The distance from *a* to *b* is about 8 miles.

the stream can break out at times of high water and take a new route on a lower part of the cone. When deposition has gone too far in one place there is a shift in the water course to a new position, so that the cone is formed symmetrically, banked up against the mountain side. In arid regions these fans are built intermittently largely by torrential outbursts and by mudflows. If these cones coalesce, they make a piedmont alluvial plain, or, in arid regions, a *bajada* (pronounced *bahada*), which spreads like an apron along the front of the range. A *bajada* is characterized by a succession of groups of radiating dry channels, each group focusing at the head of its fan. The radial profile is concave upward (Fig. 284). "Parallel to the mountain range the convexities of the component fans impart to the *bajada* an undulating surface."¹

—B. A delta is a familiar type of river deposit. It is made where a stream loses carrying power by passing into a body of water with little or no current. Topographically it consists

¹ BLACKWELDER, ELIOT, "Desert Plains," *Jour. Geol.*, vol. 39, 1931, p. 136.

of three parts (Fig. 285): (1) a broad, gently sloping upper surface most of which is above the level of the quiet water body; (2) the steeper front slope which is submerged and has the angle of repose of materials under water; and (3) the submerged muds




FIG. 285.—Radial profile section of a delta, *abc*, top surface, of which *ab* is exposed and *bc* is submerged; *cd*, front slope; *de*, prodelta clays and muds.

and silts (*prodelta clays*) which extend out in a gently undulating sheet from the foot of the front slope. Deltas are described here because the exposed portion, (1) above, is conspicuous as a plain. On this surface the river may split into distributaries which reach the front at different points on the periphery (Fig. 286, A). The plan of a delta depends on several factors among which the presence or absence of longshore currents and variations in the load transported by the river are important. Were it not for these disturbing factors the delta would be semicircular in outline. Longshore currents sweep away much of the material dumped by the stream, and so truncate the delta (Fig. 286, B). When the load of the river is diminished, the several distributaries may temporarily degrade their channels, bear the resulting sediments to the front, and drop them there as small deltas. This makes the main delta lobate.¹

Highly irregular delta fronts show that river construction dominates over wave erosion. Delta structure has been described in Art. 84.

¹ Bibliog., SMITH, A. L.



8

FIG. 286.—A, lobate delta with distributaries. B, a delta which has had its form modified by a current flowing in a direction up the page, as the figure is drawn. In each case the mainland is on the left and the water body on the right of the shore line.

C. The construction of outwash plains was an important accomplishment of aqueoglacial waters just outside the margin of the continental ice sheet. Frontal aprons, valley trains, and glacial delta plains were so formed. *Frontal aprons* correspond to alluvial plains. They consist of sands and gravels which were



FIG. 287.—Ideal radial section of a glacial delta plain showing its relation to the ice mass and the water level. Both ice and lake were temporary. *ab*, esker channel; *b*, head of delta plain; *d*, front of delta plain at water level; *o*, backset beds; *st*, line of unconformity between rock floor and overlying unconsolidated deposits. (After W. M. Davis.)

spread out in front of the ice. Their length is parallel to the ice margin and they often head against frontal moraines. The largest ones were made south of the main terminal moraine. Probably those portions of the loess plains of central United States which were water-laid constitute parts of very large outwash plains. *Valley trains* are nothing more than restricted frontal aprons. They are valley floor deposits of sand and gravel laid down by heavily overloaded streams that flowed from the melting ice. Some of them are many miles long. Many have since been terraced. *Glacial delta plains* were built by aqueoglacial streams in temporary lakes. For their construction the ice front must have been stationary (277, E). Subsequently they were exposed by the natural draining of these lakes. There are a great many




FIG. 288.—Map of the Barrington delta plain, R. I. Stippled, esker and delta plain; vertical ruling, brick clays, largely marsh land; horizontal ruling, water. Scale, approximately 1 in. to 1 mile. (After J. B. Woodworth.)

of them in New England, New York, etc. They consist of the three parts mentioned above for modern deltas. The prodelta clays are now often covered by marsh. At their northern edge, these delta plains usually terminate in ice-contact slopes where

formerly the deposits rested against or upon the ice (Fig. 287). Often an esker north of a delta plain marks the course of the original stream (Fig. 288). Any of these outwash plains, consisting chiefly of sands and gravel, and deposited by water in proximity to glacial ice, may be called *sand plains*. Some sand plains are *pitted* by kettle holes (267) and some show the old stream channels, or *creases*.

—D. Till plains are produced by more or less uniform deposition of till, usually in lands of low relief. The ice must retreat at a fairly constant rate, for otherwise the *débris* is apt to be heaped up in morainal ridges. The till of these plains is no doubt partly subglacial, partly englacial, and partly superglacial. In sections the deposit is seen to have no stratification (66).

—E. While silts and muds are in process of accumulation on the floor of a lake there is a tendency to fill depressions and thus to make the bottom more even. The same thing may be said of sea floors. If the lake is drained or evaporated away, the exposed floor will be a *lake-floor plain*. In section the underlying deposits will be seen to be very fine and evenly stratified (86). They may carry fresh water fossils. If the floor of a bay is laid bare at low tide we speak of it as a *mud flat* or an *estuarine flat*. If the land should suffer relative uplift with respect to sea level, a larger area of sea floor would be exposed as a *coastal plain*. Where there is gradual exposure of sea-floor deposits, inflowing rivers are likely to be aggraded, and so it happens that extensively uplifted coastal plains consist, not solely of littoral and marine sediments but of littoral and marine strata interbedded with fluvial or river-laid deposits (78; 84, F; 86).

—F. *Playas* are level plains underlain by clays, locally alternating with salt and gypsum, deposited in broad shallow ephemeral lakes in basins in desert regions. Deposition is intermittent. It is accomplished by inflowing mud-laden streams after local cloudbursts. Drought of many months duration may succeed a short period of accumulation, and in this dry

season the muds may crack and peel under the sun's rays and undergo a considerable amount of eolian erosion. While dry, playas are often whitened by a crust of soluble salts. (Where did these salts come from and why are they found here?) Some playas, marking the loci of discharge of groundwater by evaporation, are soft and wet most of the time.

261. Destructional Plains.—The plain of marine denudation, the graded river flood plain, the peneplain, and the plain of arid denudation (pediment), are the principal members of this group. The *plain of marine denudation* is merely an enlarged marine bench (256), a level area cut by the waves. Its distinguishing characters are as follows: (1) a sea cliff surrounds any residual stacks or other elevations that rise above the plain; (2) there is a scanty covering of wave-worn pebbles and beach sand; (3) the surface bevels across rock structures. The sand and gravel, being poor supporters of plant growth, are not likely to be densely covered by vegetation even in old uplifted plains.

A *graded river flood plain*, or "river grade plain"¹ is really a destructional plain, beveling across structures in the bedrock that is concealed by a veneer of river deposits. Such a plain is commonly narrow, its width being determined by the breadth of the meander belt (see footnote, page 367), for the planation is accomplished largely by side cutting as the stream meanders. The graded river flood plain may easily be mistaken for the aggraded flood plain (260, A), which, however, has a much thicker underlying deposit of alluvial material than in the former.

A peneplain² (*penc*, almost) is a nearly flat or broadly undulating land surface produced by normal subaerial erosion, that is, by erosion which is accomplished chiefly by the work of

¹ Bibliog., BLACKWELDER, ELIOT, 1931, p. 134.

² We have retained the original spelling, *peneplain*, instead of the revised spelling, *peneplane*, which is found in some recent textbooks, because William Morris Davis, who first used the term, intended to convey the idea, not that the land had been worn down almost flat or almost level but that it had been almost, rather than completely, worn down. His emphasis was on degree of denudation of the peneplain rather than on approach to a horizontal plane.

rivers assisted by weathering. A stream-made topography passes through a series of stages of development, known as youth, maturity, and old age (281). The valleys, at first narrow, become broad; the hill slopes grow gentler; the relief as a whole becomes less and less rugged; and finally the rivers with their branches, aided by weathering, reduce the land to an almost level plain. This is the peneplain. It is the ultimate stage of




FIG. 289.—A represents the section of a peneplain upon rocks of varying hardness and with complicated structure. B is the same region after moderate uplift, revival of erosion, and removal of the weaker rocks to a level below that of the old peneplain which is now preserved in the hill tops. *a*, schists, intruded by *b*; *c*, basal conglomerate laid down unconformably on *b* and overlain by sandstone, *d*, and shale, *e*. C shows a peneplain beveling inclined strata. D represents the same region after uplift and erosion. Here the harder rocks, *a*, *b*, and *c*, form cuestas.

the erosion cycle. A true peneplain has the following characters: (1) the relief is very low, but there may be a few scattered residual hills (monadnocks) which have not yet been cut down to the level of the surrounding country; (2) the streams meander at grade (281) in broad, shallow valleys; (3) thick residual soils carpet the interstream areas, for slopes are so low that weathering is more rapid than removal of the débris; (4) the surface of the plain bevels across the underlying rocks without regard to variations in their hardness and structure (Fig. 289, A). Peneplains on nearly horizontal strata are difficult to determine as such, but the geologist usually finds that, by travelling

across the plain in certain directions he traverses different strata or formations which successively come to the surface (Fig. 289, C). A peneplain is first completed near the sea coast and its development progresses inland, for rivers generally reduce the land to late stages of erosion in their lower courses long before they have lost even their youthful appearance up in the hill country. A peneplaned surface of great extent is rare because erosion becomes excessively slow in advanced maturity and old age. Relative depression of the sea level, tilting, crustal warping, and other changes may interrupt the cycle of erosion before it has reached its normal conclusion.

If a peneplaned land mass is uplifted with respect to sea level, a new cycle is inaugurated. Beginning at the shore line and cutting headward, the rivers will incise their channels as young valleys below the upland surface. They will have a new base level (281) toward which they will work. As time goes on, the upland area, the old peneplain, will be diminished until, in the mature topography of the new cycle, it is represented perhaps merely by the crests of the hills. Yet it will still be called a peneplain—a *dissected peneplain*. It will be recognized by the fact that a majority of the hills rise to about the same level (Fig. 289, B, D). In the distance it will be indicated, though not demonstrated, by the "even sky line." We say "not demonstrated," for an even sky line in a hilly topography may be due to the dissection of some other kind of plain, or it may be the result of differential erosion on strata which have been folded so that the anticlinal crests reached approximately to the same level. The student must take great care to investigate each case by itself before concluding that he has discovered a peneplain.

The third type of destructional plain, the plain of arid denudation or mountain pediment,¹ is limited to desert regions. It is a product of stream wash, sheetfloods² and rill wash, with lateral

¹ Bibliog., KEYES, C. R.

² A sheetflood is a broad, shallow sheet of running water, which rises rapidly, generally following a cloudburst, and soon subsides again and disappears. Temporary streams of this kind are characteristic of some

cutting predominating, assisted by removal of the finer *débris* by the wind (deflation). Students of desert conditions have shown that many square miles of nearly level country in arid regions are really floored by bedrock concealed by only a thin veneer of rock waste. During storms and during the movement of the sheet-flood, this rock waste is carried forward and, in its transportation, it accomplishes erosion; but, after wind or flood subsides, it comes to rest for a while until the next storm urges it forward again. In this manner a plain may be worn on the bevelled edges of rock strata so that the relations resemble those of true pene-



FIG. 290.—Ideal cross section of a bolson. *ab*, exposed mountain flanks in process of erosion; *bc*, pediment, meeting *ab* with abrupt change of slope; *bc* is thinly veneered with rock waste, which is shifted intermittently toward lower part of basin *eddc*, where it may accumulate. The floor of the basin, under alluvium (black), may be irregular instead of smooth, as shown. In special cases, a bajada of coalescing fans may be built out from the mountains, covering the lower part of *ab* and the upper part of *bc*.

planation. Residual hills and ranges ("island mounts") of relatively resistant rock may rise as monadnocks above the plain of arid denudation (268, A).¹

Because of its veneer of rock waste, the pediment may be confused with the bajada, especially since the bajada may grade downward into a pediment. However, in contrast with the undulating profile of the bajada, parallel to the mountain front, and its series of groups of radiating drainage channels, the pediment is a nearly flat plain, slightly concave upward, with a nearly level profile parallel to the mountain front, and its drainage consists of braided stream courses.

semiarid regions. When heavily loaded with mud and other rock *débris*, the sheetflood becomes a mudflow which may be a powerful agent of transportation of huge boulders (Bibliog., BLACKWELDER, ELIOT, 1928).

¹ For a detailed comparison between erosion features in arid and humid climates, see Bibliog., DAVIS, W. M., 1930.

Broad, closed desert basins flanked by mountains, which are fringed by bajadas and pediments, passing centrally into flat playas, are referred to as *bolsons* (Spanish for *purse*) (Fig. 290).

SWAMPS

262. Definition and Classification.—A large proportion of the land surface receives its moisture in the form of rain, snow, hail, dew, or frost, but there are some places which are watered by springs, and there are others which are periodically or occasionally flooded. Whatever may be the source of supply, the water ordinarily passes away within a very short time. Some of it runs off over the ground in thin sheets or in little rills; some of it sinks into the soil and into fissures in the bedrock, and so becomes groundwater; part of the underground water combines with part of the *run-off* to form streams; and, last, a considerable quantity of moisture is evaporated. These modes of removal may be referred to as drainage (including run-off and streams), percolation, and evaporation. Thorough drainage may be prevented by the levelness of the land; percolation may be impeded by a relatively impervious soil, subsoil, or underlying bedrock, or by a thick mat of plant roots and plant remains; and evaporation may be checked by a dense foliage. If, in any region, these processes are incompetent to carry away all the water that is supplied, the ground may become swampy and perhaps stay so for an indefinite time. A *swamp* may be defined as a land area where the soil contains an excess of moisture.

A majority of swamps are nearly or quite level, yet the soil on mountain sides and hillsides is sometimes soggy either because of the constant downslope percolation of moisture from melting snow fields above or because of a local subsurface discharge of underground water. These may be termed *hillside swamps*. *Coastal plain swamps*, like the Everglades, owe their existence primarily to their flatness and consequent poor drainage. Although they are situated on uplifted portions of the sea floor, they are usually fresh, most of the original salinity having long ago disappeared. *Delta-plain swamps* and *river flood-plain*

swamps are due as much to frequent overflow as to their levelness. In glaciated countries inland swamps are often the sites of lakes which have been choked by vegetation and soil, or they are located upon a clayey subsoil that does not allow free percolation. The latter variety is not uncommon on the prodelta clays of glacial sand plains (Fig. 288). The lake-basin bogs are sometimes called *muskegs*. Portions of the tundra in northern climates are kept saturated by melting snow. Small boggy places may be found even in deserts. For instance, the ground is moist and there is generally some vegetation in the vicinity of springs, and at points where intermittent streams sink into the ground, or where they come near the surface in their subterranean course. A swampy belt may be situated in soil that conceals a bedrock fault, if the fault serves as a conduit for ascending underground waters. Along sea coasts several kinds of salt marsh are recognized. Some are caused by the filling of lagoons with mud, sand, and plant remains (283); others are due to the slow uplift of the sea floor; and others, on the contrary, are indicative of subsidence. The evidence for the origin of this last type rests on these facts: (1) the marsh deposit is relatively thick and consists of mud mixed with the relics of plants (mostly grasses) which can exist only if they are moistened by salt water for a short period each day; (2) this marsh deposit rests upon a floor which was once undoubtedly under subaerial conditions; and, (3) the present upper surface of the marsh is just within reach of the high tide.

In many cases the origin of a swamp is suggested by its topographic surroundings, but whenever possible corroborative proofs should be looked for in the structure of the marsh deposit itself. This can be done with an instrument for cutting test holes.

VALLEYS AND BASINS

263. Terminology and Identification.—The word *basin* is here used for topographic depressions which are rimmed round on all sides. They may be deep or shallow, large or small, and they may or may not contain water. *Valleys* are topographic depres-

sions that are open, although in some cases their floors may be diversified by small basins. They may or may not be occupied by streams.

In attempting to draw up a table for the recognition of valleys and basins, it has been thought best to treat them separately, as follows:

KEY FOR THE IDENTIFICATION OF TOPOGRAPHIC BASINS

The land has the form of a basin, being rimmed on all sides. If

- A. The basin, after careful investigation, is found to be due to the direct effects of faulting (204) or of tilting or warping of the underlying rocks, it is a tectonic or diastrophic basin (264, 265).
- B. The basin is due to the damming of a valley by a barrier of lava, morainic débris, ice, mudflow, or landslide débris, or if it is situated near the sea coast and is separated from the ocean merely by a sand or gravel beach, it is a barrier basin (267).
- C. The basin is not the consequence of diastrophism or of the construction of a barrier across a valley, and
 1. Is entirely rimmed by bedrock,¹
 - a. Being generally shallow and
 - (1) Venceder by a thin deposit of transported (wind-blown) dust or sand, it may be a wind-scoured basin (268).
 - (2) Covered by a deposit of residual material, it may be a basin due to some localized process of weathering (268).
 - b. Being comparatively deep, but generally not so deep as it is wide or long, and if it
 - (1) Has steep inward facing walls which are rough and irregular and have no scratches or grooves, or, if exhibiting such marks of abrasion, have them trending up and down, the basin may be a volcanic crater (266), or a caldera (266), and the surrounding rock is probably lava.²
 - (2) Has walls which are steep in some places and of gentler declivity in others, showing marks of abrasion which trend, for the most part, along the walls and parallel to the length of the basin, the latter is probably an ice-scoured basin (268).
 - c. Having a depth generally equal to, or greater than, its horizontal dimensions, and if it

¹ Sometimes this fact is obscure because the bedrock is more or less covered by surface débris.

² The lava may have intercalated beds of volcanic ash, etc.

- (1) Has smooth, often polished, rock walls which may bear irregular circumferential grooves, the basin may be a large pot-hole (36).
- (2) Has walls which are rough or, if somewhat smooth, have vertical channels due to solution (35), and is in limestone, the basin may be the upper end of a sink hole (269).
2. Is entirely rimmed by unconsolidated materials, and
 - a. Is situated at the crest of a conical hill which consists of volcanic ash, etc., the basin is probably a volcanic crater.
 - b. Is situated in an irregular hummocky land area which is
 - (1) Underlain by glacial till, the basin is probably a kettle hole in a moraine (267).
 - (2) Underlain by rather poorly stratified gravel and coarse sand with subangular pebbles predominating, the basin is probably a kettle hole associated with kames and eskers (267).
 - (3) Underlain by fine, cross-bedded, wind-blown sand, the basin is probably a "blow-out" (268), or less probably a constructional depression, between sand dunes (267).
 - c. Is situated on a nearly flat plain, which is
 - (1) Underlain by well-bedded, often cross-bedded sands, not infrequently overlain by gravel, the basin is probably a kettle hole in a glacial delta plain or a frontal apron (267).
 - (2) Underlain by gravel, sand, or mud, the basin being crescentic in form and associated with a meandering stream, the basin is probably a deserted meander (267).

KEY FOR THE IDENTIFICATION OF VALLEYS

The land surface has the form of a valley. If

- A. The valley has rock walls,¹ and
 1. Its floor bears evidence of glacial abrasion, with more or less glacial deposition, and its cross section is U-shaped, the valley is probably of glacial origin (270, G, H).
 2. Its floor bears no evidence of glacial erosion or deposition, and it is
 - a. Definitely related to, or controlled by, the underlying rock structure, in this respect, that
 - (1) The valley crosses or intersects a ridge across its trend,
 - (a) The ridge being a cuesta, the valley is a transverse valley and is probably "consequent" in the sense that its stream originally flowed down the constructional surface of the dipping beds.

¹ This fact is not always clear at once, for the bedrock may be more or less concealed by surface debris.

- (b) The ridge being a hogback or a similar exposed edge of a steeply dipping stratum or other layer, the valley may be some variety of gap (264, 270, E).
- (2) The valley trends along the course of one or more of a series of parallel rock layers, it is a longitudinal valley and may be
 - (a) Due to corrasion, particularly if the underlying rock is not markedly soluble, or
 - (b) Due to solution, if the underlying rock is soluble, *e.g.*, limestone (270, D).
- (3) The valley is situated above a fault (single or multiple), this valley may be a rift (264) or a fault-line valley (270, B).
- (4) The valley is bounded on one side by a fault scarp or a fault-line scarp, this may be a fault valley (264), or a fault-line valley (270, B), respectively.
- (5) The valley is bounded on both sides by fault scarps or by fault-line scarps, this valley may be situated upon a graben, or upon a horst of which the relief has been reversed by erosion (304).
- b. Not definitely related to, or controlled by, the underlying rock structure, it is probably a river valley in a region of complex geologic structure or in a region of horizontal strata.
- B. The valley lies between a rock wall on one side and a wall of unconsolidated materials on the other side, this valley is probably a result of construction, and the unconsolidated materials may belong to a moraine (267, E), an esker (277, C), etc.
- C. The valley has walls of unconsolidated materials, and
 - 1. Lies between two typical constructional deposits (two moraines, two eskers, an esker and a drumlin, etc., etc.), the valley is of constructional origin (267).
 - 2. Interrupts the continuity of an otherwise essentially flat surface, the valley may be a stream channel
 - a. Associated with the upbuilding of the deposit (channels on alluvial cones, deltas, etc., and creases; refer to 267).
 - b. Of purely destructional origin (270, F), (rainwash gullies, etc.).

264. Fault Valleys and Basins.—In faulting the blocks may be tilted in such a way that a depression lies at the base of the fault scarp (Fig. 265), or a block may slip down between two opposing fault scarps (Fig. 215, A), or a block may be left between two other blocks that have been uplifted. Sometimes long, relatively narrow depressions or *rifts* are formed along lines of

multiple fracture (Figs. 291, 292). The San Andreas rift¹ in California, along which differential horizontal movement occurred in the earthquake of 1906, is "a trough coinciding in general trend with the Coast Ranges, but crossing various mountain ridges obliquely, or even following their crests. In detail it comprises many small ridges and hollows, approximately parallel but otherwise irregularly disposed, and evidently caused by splintery dislocation. Streams zigzag more or less about the ridges, and the hollows contain many small ponds and marshes."² This rift is traceable for several hundred miles. On this subject, refer also to Art. 204.

Another possible phase of fault valley is the *fault gap*, a depression between the offset ends of a ridge developed on a resistant rock layer that has been displaced by a transverse fault (Fig. 293). *Fault-line gaps* are more common than fault gaps (270, E).

In volcanic regions roughly circular or oval depressions, called *volcanic sinks*, may be formed by broad-scale downfaulting of the land surrounding an old vent. The settling may be caused by subterranean removal of lava which had served as a support. These sinks are bounded by steep fault scarps upon which slickensides or other evidences may sometimes be found, indicating the direction of the slipping (35, 188). The floor of a volcanic sink is of much larger area than the cross section of any associated vent.




FIG. 291.—Drainage map of the Bolinas-Tomales valley, Cal. Heavy broken lines, crests of bounding ridges; light broken lines, limits of rift topography; T, Tomales Bay; O, Olema Creek; P, Pine Gulch Creek; B, Bolinas Lagoon. (After the California State Earthquake Investigation Commission.)

¹ In this usage the word *rift* seems to include both the depression due to faulting and the fault or faults, but it does not imply the kind of displacement. See p. 211.

² Bibliog., GILBERT, G. K., 1909, p. 48.




FIG. 202.—Profile section of Bolinas-Tomales valley. Vertical and horizontal scales are equal. *RR*, limits of rift; *P*, valley of Pine Guleh Creek, running SE.; *O*, valley of Olema Creek, running NW. (After the California State Earthquake Investigation Commission.)




FIG. 203.—Diagram of a fault gap, *g*, caused here by horizontal movement on a vertical fault, *f*, with consequent displacement of the ridge of hard rock, *A*.



FIG. 204.—Dunes and dune hollows. Contour interval, 20 ft. (Lakin sheet, Kan.)



FIG. 205.—Section of a glaciated valley with lateral moraines (stippled). Talus (black) has partly filled the small valleys between the moraines and the bedrock (vertical lining).



FIG. 206.—Moraine and outwash-plain topography in Union Co., N. J. The eastern half of the map shows ground-moraine topography. The rough line of country just east of meridian $74^{\circ}24'$ is a terminal moraine. The land sloping westward from the terminal moraine is an outwash-plain. Heads are represented by horizontal ruling. (After R. D. Salisbury and W. W. Atwood.)

265. Basins Caused by Tilting and Warping.—Some basins, usually of large size, have resulted from tilting or warping of a topography that may be flat or irregular. In this manner, through diastrophic agencies, sags may be produced in a previously even land surface, or low ridges may be uparched across original drainage courses.

266. Volcanic Basins.—By volcanic outbursts craters are formed, either as holes in more or less level ground (pit craters), or as cup-shaped depressions on the summits of volcanic peaks. The floor of such a crater is of the same size as the cross section of the vent through which the explosions occurred. Explosion-made depressions of considerably larger size than the accompany-




FIG. 207.—Characteristic terminal moraine topography. (Passaic Folio, N. J.-N. Y., No. 157, U. S. G. S., 1908.)

ing associated volcanic vents are called *calderas* (sing., *caldera*) (Cf. volcanic sink, Art. 264). Lakes may gather in the craters of extinct volcanoes.

267. Constructional Valleys and Basins.—When deposition by wind, water, ice, or vulcanism is irregular, or when natural barriers are thrown up across valleys, constructional valleys and basins may result. Basins, some constructional and some destructional, are typical elements in the topography of dune areas (Fig. 294). Valleys may be formed between parallel morainal ridges of mountain glaciers, or between the lateral moraines (277, E) and the adjacent valley walls (Fig. 295). They may be formed also between parallel ridges deposited by a continental ice sheet. Terminal moraines especially are characterized by numerous hollows of all sizes and shapes (Figs. 296, 297). At the ragged edge of the melted ice sheet, outwash sands and

gravels (kames, eskers, sand plains, etc. (277)) may be spread round and even over detached ice blocks, which, by subsequent melting, leave depressions (kettle holes, ice-block holes) to mark their sites (Figs. 298, 299). When such kettle holes are in outwash plains (260, C), dry channels or *creases* may sometimes be seen to extend out from them, channels by which water was con-



FIG. 298.—Section showing a mass of ice, *a*, surrounded by aqueoglacial deposits, and a kettle hole, *b*, resulting from the melting of a similar projecting ice block. (After M. L. Fuller.)

FIG. 299.—Section showing a block of ice (*a*) covered by aqueoglacial deposits, and a kettle hole, *d*, formed by the melting of a similar buried ice block. Under the kettle hole structureless sands, *c*, occupy the space of the melted ice. (After M. L. Fuller.)

ducted away from the melting ice block. If the wash deposit did cover the ice, melting caused the materials to sag and so more or less destroy their internal structure. The sides of the resulting kettle hole may have any inclination between 0° and 30° or 35° (angle of repose), according to

how much sagging there was, and there can be no accompanying drainage creases on a surrounding outwash plain. If a kettle hole has a notably flat, even floor, it has probably been alluviated.

Barrier basins are produced by natural damming. Landslide debris, or mudflow debris (both types of rapid mass movement), may choke up a narrow valley for a while and a lake may be formed upstream from it. Many of the lakes in glaciated countries lie in hollows behind morainic barriers (Fig. 300, A). Ice itself has sometimes served as a temporary dam, particularly in the valleys of northward-flowing streams. Two bends of a meandering stream sometimes meet, and the stream, breaking through the narrow neck, adopts the shorter course. The deserted meander, at length



B

FIG. 300.—Section to illustrate the nature of glacial lake basins. A, lake retained by moraine dam; B, lake held in rock basin.

silted up at its cut-off ends, becomes an oxbow lake (Fig. 301). When a side stream brings down more detritus than the main stream can handle, the latter may be ponded upstream from the confluence; and, *vice versa*, if a river carries an excess of load, it may aggrade its bed and impound the lower reaches of its




FIG. 301.—An oxbow lake in the site of a deserted meander of the White River, Indiana. Contour interval, 20 ft. (Princeton sheet, Ind.-Ill.)

branches just above its confluence with them. (Under what topographic conditions might these events occur?) Another type of barrier basin may be made by a sheet of lava which blocks a main valley, or, by moving down a main valley, dams up the side valleys. Barrier basins include lagoons (283) and bays which have been closed in by bay-mouth bars (252).

268. Destructional Basins.—Basins of destructional origin are comparatively rare. Some are made by ice, some by wind, and some by unequal weathering. In glaciated districts these rock basins are not infrequently occupied by lakes which may be very deep (Fig. 300, B). The process by which they are gouged out by the ice is often called *overdeepening*. On their rocky rims are unmistakable signs of their glacial origin, in striae, grooves, and numerous knobs or *roches moutonnées* (278, E). *Wind-scoured basins*, i.e., basins maintained or developed by deflation of the finer rock waste, are shallow, but they may cover large areas, sometimes many square miles in extent. They are characteristic of deserts. At irregular intervals their lower central parts may become the sites of broad, shallow sheets of water called *playa lakes*, which quickly gather and almost as quickly evaporate, leaving mud flats, or *playas*, to mark their sites (260, F). Destructional hollows carved out by wind in dune areas are called *blow-outs*. Their sides are often steep and intersect the bedding of the adjacent dunes. Shallow basins are sometimes produced by unequal weathering (chiefly decomposition) in uniform rocks or by differential weathering in rocks of varying resistance where the surface of the ground is too level for thorough drainage. Moisture, collecting in the hollows, maintains a luxuriant vegetation and, with the help of soil acids, brings about the decay of the underlying rock. Such basins may broaden more rapidly than they can deepen, for decomposition is greatly retarded by increase of depth.

269. Destructional Sinks.—The word *sink* is applied to vertical holes in the ground, which lead downward into subterranean passages and chambers that have been formed by the solution of a soluble rock. It should not be confused with the volcanic sink (264), which is of diastrophic origin. Sinks are generally limited to countries where limestone underlies the soil and the climate is humid (Fig. 302). They are of two kinds: some are produced by the caving in of the roofs of subterranean chambers, and others are channels which were opened up along joints and which have been enlarged through solution by descending surface

waters. The cave-in type of sink reveals signs of fracture on the edges of the hole, generally increases in diameter downward




FIG. 302.—Sink holes in limestone. The depressions are situated on the NE.-SW. diagonal of the map. Contour interval, 100 ft. (Bristol quadrangle, Va.)

from the surface, and contains shattered débris of the roof rock on the cave floor beneath the opening (Fig. 303, A). On the




FIG. 303.—Sections of sink holes. In A the roof has fallen in; in B the upper opening has been made entirely by solution.

other hand, solution sinks often flare, funnel-like, at the surface, and the edges and walls of the hole bear marks of corrosion, not of fracture (Fig. 303 B) (Chapter II)

By gradual lateral solution of the upper layer, or layers, a sink may expand into a broad, shallow, nearly circular depression. A land surface that consists of many sinks, with irregular divides between them, is called a *karst topography*.



FIG. 304.—Section on of a valley due largely to the disintegration of the weaker rocks which are principally sandstones and shales. Here granite, *a*, and the massive Bighorn limestone, *cd*, form the uplands. The section is roughly 1,500 ft. long. (Cloud Peak-Fort McKinney Folio, Wyoming, No. 142, U. S. G. S., 1906.)

270. Destructional Valleys. A. In General.—Valleys carved by erosion differ very greatly in respect to size, shape, and pattern. In size they grade down into grooves (*q.v.*). Their shape may be considered in terms of their profile sections, their longitudinal sections, and their plan. These characters depend upon a number of factors, the most important of which are the agent of erosion, the nature of the material or rock eroded, and the stage of erosion (280).




FIG. 305.—Section across the Appalachian Mts. in Virginia. The principal valleys are situated on limestone. The ridges are on sandstone and quartzite. *a*, Shenandoah limestone; *b*, Martinsburg shale; *c*, Juniata formation; *d*, Tuscarora quartzite; *e*, Lewistown limestone; *f*, Monterey sandstone. (Monterey Folio, Va.-W. Va., No. 61, U. S. G. S., 1899.)

—**B. Valleys of Differential Erosion; Contact Valleys.**—Where rocks differ in their resistance to erosion, the weaker ones become the sites of valleys and lowlands, while the stronger ones remain as uplands. It may be that the difference in resistance is merely mechanical, the weaker ones perhaps being softer or more closely jointed, or the weaker rock may be more soluble or otherwise more easily decomposable than the hill-maker (Figs. 304, 305). Valleys are often opened up along the outcrop-

ping edges of such surfaces of weakness as igneous contacts, upturned unconformities, conformable bedding contacts, and faults (Fig. 306) (see 171, 204). These may be called *contact erosion valleys*, and those on fault lines are further defined as



FIG. 306.—Geologic section illustrating valleys situated upon contacts as follows: a. intrusive contact; b. unconformity; c. conformable bedding contact; d. fault. Note that the contact localizes the valley, but often because resistant and weak rocks are there in juxtaposition.

fault-line valleys. The fault-line gap is a special variety of fault-line valley.

—C. **V-shaped Valleys.**—Gully, gorge, ravine, and canyon, are all general names applied to destructional valleys with comparatively steep sides. Those which are stream-made are characterized by two important features: they are V-shaped in




FIG. 307.—A river valley showing overlapping spurs. The line at the top of the vertical ruling is a profile line, the ruling being a section of the ground.

cross section, and their plan is more or less sinuous or zigzag, so that a person standing near the stream and looking along the valley cannot see far because of overlapping upland spurs (Fig. 307). The breadth or angle of the V is largely dependent upon the stage of erosion (280). In young valleys it is narrow and relatively deep. In valleys which are said to be in early maturity

it is broader, and it opens wider and wider and becomes more and more shallow as maturity advances to old age.

—**D. Solution Valleys.**—The V-shaped types of valley just described are due to corrasion. In moist climates soluble rocks, like limestone, may wear chemically with greater facility than they wear mechanically. The resulting *solution valleys* are often broadly U-shaped in cross section, and their trend parallels the outcrop of the soluble rock. There is the possibility that these valleys may be confused at first glance with those of glacial origin; but, in general, solution valleys are seen only south of



FIG. 308.—The Delaware Water Gap, from Jenny Jump Mt. The high ridge in the background, interrupted by the gap, is Kittatinny Mt. Its top marks the level of an ancient uplifted peneplain. (After W. M. Davis.)

the limits of continental glaciation. Within the glaciated area examples may be found of valleys started by solution, but subsequently deepened by ice abrasion.

—**E. Destructional Gaps.**—A short valley which opens across a ridge and connects lowlands on opposite sides of the ridge is termed a *gap*. The fault gap has already been described and figured (264).

Under certain conditions a river may be forced to incise its course as a narrow gorge in a hard rock ridge while it opens out a broad lowland in the less resistant rocks on each side. This gorge is called a *water gap* as long as the stream flows through it (Fig. 308); but if, for any reason, the water is diverted, the original water gap becomes a *wind gap*. A gap, whether or not containing a stream, is called a *fault-line gap* provided it is due primarily to erosion and is located along the line of outcrop of a

dip fault or a diagonal fault that intersects the ridge-making rock layer (Fig. 309).

—**F. Valleys and Channels without Streams.**—Two cases have already been noted of channels which have been abandoned by the streams that made them. These are the wind gap (**E**) and the glacial crease (**267**). Further comment on them is unnecessary; but there are several other types of channel, gorge, or valley, which are temporarily or permanently without streams.




FIG. 309.—Origin of a fault-line gap. A, a region after faulting and before erosion; B, the same region after erosion to a plain at the level aa; C, the same region after revival of erosion and removal of the weak rocks to the level bb. The fault-line gap is at x in C. Hard rocks are black.

By differential weathering steeply inclined dikes and strata may be eroded so much faster than the rocks on each side that clefts and even considerable valleys may be produced. Often there is no stream in these depressions. The rock waste is removed by rainwash or, in dry countries, by the wind.

In deserts dry channels or *arroyos*, some of them many feet deep, are normal features in

the landscape. Occasionally these arroyos are filled by roaring torrents which are supplied by cloudbursts in adjoining mountains, but the water runs usually for only a short time because it soon sinks into the ground or is evaporated. The typical arroyo has a flat floor and almost, if not quite, vertical walls, for the effects of the excessive erosion performed by the torrents are scarcely modified in the intervals between successive floods.

Alluvial fans in dry regions are built intermittently. The streams pass into the loose sand or gravel far up on the deposit and abandon their lower channels except at times of heavy rainfall in the mountains. Shallow depressions are common on allu-

vial plains where the streams, in their meandering, have deserted their former courses.

Above the level of saline lakes, in relatively low places in the rims about their basins, abandoned outlets may exist by which the lake waters once drained out. More common, however, are the abandoned channels in lands which have been under the influence of continental glaciation, channels which served for a while as main drainage lines for the glacial waters (Fig. 310).



FIG. 310.—An abandoned stream channel, formerly an outlet of a glacial lake. The Syracuse and Binghamton Division of the railroad follows the channel. Contour interval, 20 ft. (Syracuse sheet, N. Y.)

They were made where the lower, older valleys were blocked by ice or moraine and the water was forced to follow new routes. They often start at the level of abandoned shore lines, showing that they were the outlets of temporary lakes. Some of these gorges were subsequently buried under later drift, but those that were not so filled display many of the normal characters of destructional stream courses, except that they are often out of harmony with the present drainage systems.

—**G. Glaciated Valleys.**—Glaciated valleys have been scoured either by mountain glaciers or by ice sheets. In both cases it is probable that many of the valleys were formerly made by streams and were then modified by ice. The glaciated valleys of mountain districts are characterized by several or all of the following features: (1) the transverse profile is U-shaped, not

V-shaped as in a majority of stream valleys; (2) the valley is straight or broadly curving, without overlapping spurs; (3) its rock walls are steep (oversteepened stream-valley walls) and are more or less polished, striated, and grooved by ice abrasion; (4) the ice-scoured walls sometimes terminate upward in an obtuse angle or *shoulder* above which the mountain slope is less steep; (5) the valley's longitudinal profile is broadly steplike, the *treads* being of gentle grade and sometimes holding lakes in rock-rimmed or moraine-dammed basins, and the *risers* being




FIG. 311.—Longitudinal profile section of a glacial valley in the Sierra Nevada, Cal. *ab*, cirque wall; *c, d, ef*, lakes; *gh*, tread; *hi*, riser; *jk*, head of alluvial cone at foot of mountains. The vertical scale is twice the horizontal scale.

steep, ice-plucked cliffs, sometimes well nigh impassable (Fig. 311); (6) the rock floor of the valley bears evidence of powerful ice abrasion in polish, striæ, grooves, etc., and is often irregular with roches moutonnées; (7) ground moraine and recessional moraines (277, E) rest on the valley floor, and lateral moraines are plastered up against the valley sides; (8) tributary valleys usually enter at levels considerably above the main valley floor (271).

Valleys overrun by ice sheets do not possess so many distinguishing marks of their origin. Their profile is U-shaped if they happened to trend about parallel to the ice motion, but those which lay athwart this direction often suffered plucking (and therefore steepening) on the side toward the source of the ice and abrasion (hence reduction of slope) on the other side (Fig. 312). Although an ice sheet tends to straighten original

valleys parallel to its advance, although it polishes, striates, and grooves their floors and walls, and here and there scours out rock basins or forms *roches moutonnées*, it does not have a special propensity to oversteepen these walls, or to produce *shoulders*, or to erode *giant steps*. There are no true lateral moraines. In fact, the distribution of morainic material shows regional rather than local control. Outwash sediments very often cover the bedrock floors of these valleys, sometimes to considerable depths.

Glaciated valleys may lose their distinctive marks so that there may be some trouble in distinguishing them from solution valleys




FIG. 312.—Transverse profile of a valley overrun by an ice sheet in the direction of the arrow. *abcd*, profile of valley before ice erosion.

on the one hand, and from certain mature stream valleys on the other hand. For instance, weathering may remove *striae* and other tokens of glacial abrasion, and, in mountain valleys, talus accumulations may obscure the U-profile or conceal morainic deposits. As with solution valleys, so too with U-shaped mature stream valleys, they are not found in areas which have suffered continental glaciation because there has not been time enough for their development since the ice retired. All such original valleys in the glaciated area were modified by the ice.

—**H. Cirques and Drift Hollows.**—At its head the valley made by a mountain glacier normally opens out into a broad half-amphitheater bounded by steep precipices on all sides except at the junction with the valley. This is a *cirque*. Its floor resembles the floor of the associated valley in bearing evidences of very powerful ice abrasion, but its walls, unlike those of the valley, are generally free from marks of scour. They are cliffs made by sapping (250). They are bounded by joint faces.

The earliest phase of the cirque is to be seen in the small drift hollow on a hillside. During the day the snow melts. At night

the water freezes in the interstices of the underlying rock and wedges off a few small chips. The next day these chips are washed away down the slope. Thus, as the process (called *nivation*) is repeated from day to day, the snowdrift comes to rest in a hollow of its own making. When the drift hollow grows larger it becomes a small cirque and the deeper snow changes to *névé*.

Landslide scars (250, G) may partially resemble glacial cirques, especially where well developed by repeated slides from the same




FIG. 313.—View of a glacial hanging valley on the south side of Nunatak Fiord, Alaska. (From a photograph, after R. S. Tarr and B. S. Butler.)

place on the mountain side and also where the bedrock is relatively soft and therefore not likely to preserve for long the marks of glacial abrasion.

HANGING VALLEYS

271. Definition and Classification.—A *hanging valley* may be defined as a valley whose floor “is not in even adjustment with the bottom of the lower depression with which it unites.”¹ Between it and this lower depression—valley or basin as the case may be—there is a steep, generally precipitous slope over which the stream of the hanging valley plunges. (1) A majority of hanging valleys owe their origin to glaciation (Fig. 313). This is because a trunk glacier cuts its bed to a lower level than

¹ Bibliog., RUSSELL, I. C., p. 76.

do its tributary glaciers, and when the ice disappears the tributary valleys are left hanging above the main valley. In like manner cirques may be hanging. However, there are methods other than ice erosion, by which valleys may be made to hang. (2) If waves wear back a coast line more rapidly than the inflowing rivers can cut down their channels, the latter become hanging with respect to sea level (Fig. 314). (3) A river may erode faster than its side streams so that their valleys are made to hang with respect to the main valley. (4) Finally, if a fault crosses a




FIG. 314.—A hanging valley resulting from rapid wave erosion.

valley, the part of the valley in the upthrown block may be hanging above the lowland of the downthrown block, provided the displacement was more rapid than the stream erosion. From the foregoing it is clear that any kind of a valley may become hanging under the proper conditions.

CAVES AND NATURAL BRIDGES

272. Caves.—Caverns in lava, which result from the very irregular way in which viscous lava moves, may be classed as volcanic. Most caves are destructional. Among these, the largest are formed by solution of limestone where the water table (224) is low and the products of solution are carried away in underground streams. The Mammoth Caves of Kentucky and the Carlsbad Cavern of New Mexico are well known examples.

In regions of horizontal strata weathering may locally gnaw back the weak rock underlying a cliff-maker and thus produce broad, shallow caves. Of somewhat similar nature are undercut

caves formed at the base of an abrasion cliff, where winds, stream currents, or waves, deliver their most efficient attack. Such caves are especially liable to occur in weak rocks or along joints or faults that invite concentrated erosion.

273. Natural Bridges. Natural bridges may be found in irregular lava sheets. The majority, like caves, are destructional products of denudation, and as such they are merely a later stage of cave erosion. They are remnants of cave roofs of which the main portion has fallen in or has been eroded away. Consequently, they may result from solution or from abrasion. Some are cut by wind and some by water. In regions of flat-lying strata, the undercut soft rock on opposite sides of a divide may at last be removed, leaving the hard capping layer to span the opening.

HILLS, RIDGES, AND OTHER POSITIVE LAND FORMS

274. Terminology and Identification. - According to the definition previously given (245), positive land forms include hills, ridges, pinnacles, and any other relief forms which project upward and are surrounded on all sides by lower land.¹ Following is a key to aid in their identification:

KEY FOR THE IDENTIFICATION OF POSITIVE LAND FORMS

If the land surface has the form of

- A. An isolated knoll or hill, not much longer than wide, and, in general,
 - 1 With its height less than its ground plan dimensions, and
 - a. The underlying rock materials are unconsolidated, consisting of
 - (1) Volcanic ash, scoriae, bombs, etc. (sometimes associated with flows), with their bedding parallel to the slopes of the hill, the latter is probably a volcanic cone (276).
 - (2) Glacial till (65), the hill is probably a drumlin, if it is more or less oval in ground plan and (usually) has its length nearly parallel to the glacial striae on bedrock in the vicinity (277, B).
 - b. The underlying rock materials are consolidated, and consist of
 - (1) A particular rock association composed of
 - (a) Lava in flows (sometimes interbedded with volcanic ash, etc.), the flows being parallel to the surface of the hill, the latter is probably a volcanic cone (277).

Islands are not treated here as a separate class.

- (b) Flat-lying strata, the hill is
 - (a₁) A mesa if its top is flat (**278, B**).
 - (b₁) A butte if its top is peaked (**278, B**).
- (c) Igneous rock which has the shape of a neck, cutting across the rocks of the surrounding region, the hill is probably a volcanic butte (**278, B**).
- (2) Not necessarily a particular rock association, and if
 - (a) The rock knob or hill is more or less well rounded and
 - (a₁) Has glacial scratches and grooves on its surface, the knob or hill is probably a *roche moutonnée* (**278, E**).
 - (b₁) Has no glacial scratches or grooves, but shows evidence of the separation of spalls or slabs from its surface and is more or less surrounded at its foot by talus of these spalls, the hill is probably an exfoliation dome (**278, D**).
 - (b) The knob is usually rugged, and is surrounded by a wave-cut cliff and bench, it is probably a stack (**278, F**).
- 2. With its height often several times greater than its ground plan dimensions, the elevation may be a stack (**278, F**), a rain pillar (**278, G**) or any sharp, pinnacle-line remnant of erosion (**278, H**).
- B. A definite ridge, usually many times longer than wide, and either continuous or broken by transverse valleys, and if
 - 1. The underlying rock materials are unconsolidated, consisting of
 - a. Loose boulders with no, or little, intervening finer *débris*, the ridge may be a boulder belt (**277, E**), or a winter talus ridge (**277, G**), or a wave-built terrace (**255**).
 - b. Glacial till, the hill is probably a moraine of one kind or another (**277, E**).
 - c. Rather poorly stratified sand and gravel, many of the pebbles and boulders being subangular, the ridge may be an esker (**277, C**) especially if it is associated with kames and kettle holes (**277, D**).
 - 2. The underlying rock materials are consolidated, consisting of inclined strata which dip nearly parallel to the land surface on one side of the ridge, but are truncated by the other side of the ridge, the latter may be a *cuesta* or a *hogback* (**278, C**).
- C. A group of hummocks and hollows, generally with a relief of 150 ft. or less and the underlying materials, which are unconsolidated, are
 - 1. Fine, cross-bedded sands, the hummocks may be dunes (**277, A**).
 - 2. Coarse sand and gravel, rudely stratified, the hummocks may be kames and the hollows kettle holes (**277, D**).
 - 3. Unstratified, heterogeneous *débris*, the deposit as a whole may be of glacial till, or it may have been produced by landslide, earth flow, mudflow, or rock glacier (**277, B, E, F**).

D. A range of hills or mountains, with intervening valleys, the hills are the interstream divides left in the process of erosion of the valleys which have been incised into a broad upfaulted or uparched land mass.

275. Fault Mountains.—*Block mountains* are ridges due to faulting. Ordinarily one slope is gentle (back slope) and the other is steep, the latter being a fault scarp (248). Since the uplift of a block mountain is generally slow and erosive agents are constantly working, the ridge is seldom seen as an unbroken unit. It is usually dissected by valleys, and, when very old,



FIG. 315.—Geologic section of Marysville Buttes, a group of hills resulting from the denudation of a volcanic cone. *a*, alluvium resting on volcanic tuffs; *b*; *c*, Tertiary sedimentary rocks; *bdb*, hypothetical original profile of volcano. (Marysville Folio, Cal., No. 17, U. S. G. S., 1895.)

it becomes a low range of hills (Fig. 265). The same remark applies to the horst (204).

276. Volcanic Cones.—A volcanic peak consists principally of volcanic materials—lava, or ash and other fragmentals, or lava and fragmentals interbedded. Typically it is conical in form, often quite symmetrical, and if sufficiently recent, it may have a crater at its summit. Its slopes may vary between 2° or 3° and 40° (246). Denudation may eventually destroy the crater and reduce the original elevation of the peak (Fig. 315).

277. Constructional Hills and Ridges.—Constructional hills and ridges built of materials derived through erosion include dunes, drumlins, kames, eskers, several types of moraine, landslide hummocks, and winter talus ridges.

—A. In arid regions, along the shores of seas and lakes and along or near the courses of streams that vary greatly in volume, *dunes* may be constructed if there is an abundant supply of sand and if winds are prevailingly strong and from certain definite directions (onshore in case of seas and lakes). Sand dunes vary greatly in shape, probably depending upon the relations between wind strength, wind direction, and available supply of sand. In

Fig. 316 are shown several types of dune in horizontal plan. Some are crescentic (Fig. 316, A) with the horns opening *with* the wind (called *barchans*). Others are roughly crescentic or parabolic, but with the convex curve of the dune facing *with* the wind (Fig. 316 B). Others are almost sprawling, with




FIG. 316.—Sand dunes, in plan. The graphic scale represents 500 ft. for A, B, and D, and 4,000 ft. for C and E. For all five types of dune, as here represented, the prevailing wind blows from left to right.

fingerlike lobes extending to leeward, and with irregular windward edges (Fig. 316, C). Some are ridgelike, elongate across the course of the wind, and these may have fingerlike lobes to leeward (Fig. 316, D). And, finally, some are long, subparallel, and elongate *with* the prevailing wind direction (Fig. 316, E).

Sand dunes are usually in groups. Their heights are commonly between a few and 200 or 300 ft., though they may be considerably

higher. The windward slope is gentle and the lee slope is steeper, with an angle of from 25 to 35° (Fig. 317). Sand is blown up the gentle slope and is dropped over the crest, whence it slides down the lee slope.

In areas where clays are broadly exposed (tidal flats, playas, etc.) and where, after occasional moistening, they then undergo a period of desiccation, their upper layers may crack and curl, and strong winds may sweep away chips and pellets of the clay (Art. 94), piling these up in dunes where further progress is impeded. This may be within the clay-belt area, or at or near its lee margin. During the next rain, the particles soften and coalesce, and, in the ensuing dry spell, the clay hardens and so tends to build up compact mounds.¹



FIG. 317.—Profile section of a dune taken in the direction of the wind (see arrow). *a*, *b*, and *c* correspond to the same letters in Fig. 316.

Sand dunes and clay dunes may be grassed over and covered with vegetation to such an extent that their identity is very obscure. Examinations should then be made for their internal structure (84, G).

—**B. Drumlins**² are hills consisting of glacial boulder clay (till). At the time of Pleistocene continental glaciation, they were formed under the ice while it was in motion, and so they have a trend parallel to its direction of flow. In some regions the slope toward the source of the ice is lower than the lee slope (Fig. 318), and in other regions it may be steeper (Fig. 319). In plan, drumlins are typically oval, although irregularities in shape are not uncommon (Fig. 319). Few have a relief of more than 200 ft. While some were evidently built round projecting rock ledges, many have no such rocky cores. In cross sections isolated strata may occasionally be seen in the till, and these may

¹ See Bibliog., COFFEY, G. N.; PRICE, W. ARMSTRONG, 1936, p. 226.

² Bibliog., ALDEN, W. C.




FIG. 318.—Longitudinal (A) and transverse (B) profiles of a drumlin. The arrow points in the direction of ice motion. (After W. C. Alden.)



FIG. 319.—Drumlins in Wisconsin. The ice moved a little west of south. Contour interval 20 ft. (Waterloo sheet, Wisc.)

be contorted (95). At the time of their formation drumlins are thought to have been between 5 and 30 miles north of the ice front. As for their distribution, they are numerous in many



a. 320.—Map of North America showing area covered by the Pleistocene ice sheet at its maximum extension. (Pascia Folio, N. J.-N. Y., No. 157, U. S. G. S., 1908.)

states within 100 miles or so north of the southern limit of Pleistocene glaciation (Fig. 320).

—C. *Eskers* are relatively long, narrow, winding ridges of mixed sand and gravel. In longitudinal profile their crests are seen to be sinuous (Fig. 321, A). They range in height from 10 or 15 ft., to 100 ft. or even more. They may cross valleys or bend round hills, seldom more than 200 ft. above the valley floor.

Usually they terminate in outwash plains (260, C). Cuttings in them show that they consist of somewhat waterworn, rudely stratified materials. The pebbles range up to 18 in. or 2 ft. in diameter and are typically subangular, although sometimes pretty well rounded. These esker ridges were laid as stream bed deposits in channels in the ice during the retreat of the glacial sheet. Their shape, their structure, and their relations to outwash plains, prove that the ice was stagnant when they were formed. After the supporting ice walls melted away, the deposits slumped down to the angle of repose for gravel (246). It is on




FIG. 321.—Longitudinal (A) and transverse (B) profile sections of an esker. B is drawn on a somewhat larger scale than A.

account of their rapid accumulation and their later settling that their stratification is generally so poor.

—D. *Kames* are similar to eskers in composition, structure, and origin, but in shape they differ. Instead of being long, narrow ridges, they are more or less oval or irregular knolls and hummocks. They were deposited in irregular openings in the ice. Eskers and kames are associated with kettle holes.

—E. Ridges and irregular deposits laid down by ice are spoken of as *moraines*. Some are associated with valley glaciers and others with ice sheets. Lateral, medial, terminal, and recessional moraines are made by valley glaciers. *Lateral moraines* are built of *débris*, part of which falls upon the ice as talus from the mountain sides, and part of which, having been carried for some distance within the ice, is returned to the surface by shearing or by surface melting (ablation). When the glacier

shrinks by excessive melting, it leaves these lateral moraines as embankments on either side of the valley. They consist of till or of great agglomerations of bowlders (65). They may rise above the valley floor to heights of over 1,000 ft. Frequently there is a descent of a few score feet from the crest of the moraine to the original valley side. A readvance of the glacier front, if of great extent, may destroy the moraines of the earlier advance; but if the advancing ice tongue is not so large as the first glacier, lateral moraines of the second may be constructed, terrace-like, against the inner sides of the older moraines (Fig. 322). On



FIG. 322.—Lateral and ground moraines deposited in two successive advances of a valley glacier.

account of the tendency of glacier termini to oscillate up and down their valleys, this superposition of lateral moraines is not uncommon, and care must be taken to discriminate between the minor variations of one ice epoch and the much more significant effects of distinct glacial epochs. The two sets of moraines shown in Fig. 323 might belong to two ice oscillations during one glacial age were it not for the fact that criteria other than relative position proved them to represent two glacial ages widely separated by an interglacial interval (111).

When two ice streams coalesce, the inner lateral moraines of the two unite to form a *medial moraine* downstream from the point of junction. Medial moraines are very rarely left on the floor of the valley after the disappearance of the ice. They are not so well marked as lateral moraines and they are more apt to be modified or destroyed by subsequent stream erosion.

At the front of the ice, as at its sides, a great deal of detritus is deposited. Some of this *débris* accumulates in a *marginal* or *terminal moraine*, and the rest becomes aqueoglacial material in

so far as it is handled by water derived from the melting of the ice. Terminal moraines, composed of till or of boulder heaps, are curved with the convex side pointing down the valley. In the recession of the glacier a distinct marginal moraine may be




FIG. 323.—Sketch map showing the distribution of moraines deposited in two successive advances of a group of valley glaciers. (After W. W. Atwood.)

formed every time the front pauses in its migration. These are often termed *recessional moraines* (Fig. 324). Many such may be built in a single valley. Terminal moraines often unite with the contemporaneous lateral moraines. Where glaciers deployed upon broad piedmont slopes, terminal and lateral moraines may be finely developed.

Terminal and recessional moraines are also formed by ice sheets, both piedmont and continental. In origin they are

similar to the deposits of the same name made by mountain glaciers, but in form they may be more hummocky, and they are



Heavy moraines



Light moraines



Outwash



FIG. 324.—Diagrammatic sketch map of a glaciated valley, showing lateral and recessional moraines, several blocked tributary streams, and the head of a valley train. (After W. W. Atwood.)

of much greater size. They may consist of till or of loose boulders (boulder belts). Either because an ice sheet, advancing over an uneven topography, may migrate farther in the valleys than on the uplands, or because of subsequent unequal wastage of the ice, the front of the sheet may become lobate, and, as a consequence, its marginal or frontal moraines will be lobate. In North America the southward convex curves in the terminal moraine often indicate relatively low land in a northerly direction.

—F. A deposit of landslide debris has a very irregular, hummock-and-hollow topography, and is generally situated at the base of a steep slope on which the original scar of the slide may be seen. In its plan it may show evidence of having spread out at the time of the fall. Landslide deposits may resemble morainal accumulations in their surface features, in the chaotic arrangement of their materials, and in the occasional presence of scratches on some of the rock fragments, but confusion is

likely to arise only when they are in valleys that look glaciated. In this event they may often be distinguished by their local and

irregular distribution as compared with most moraines, and by the fact that their materials are of the same rock as that on the mountain side *above* them. In unglaciated valleys no other suggestions of ice action will be found. In valleys that were formerly glaciated, the landslide materials have probably slumped down over any morainal *débris* that happened to be in the way. Other constructional forms, which may have either a hummock-and-hollow topography or an irregular ridgelike shape, are the deposits of earth flows and mudflows and rock glaciers (3; 250, G).




FIG. 325.—Diagram showing mode of formation of a winter talus ridge. (After E. Howe.)

—G. In mountain regions, snow banks lead to the formation of *winter talus ridges* (Fig. 325). Rock fragments slide down the snow surface and accumulate at the foot of the drift. In summer, after the snow has melted away, a curving ridge of rock fragments remains, convex away from the source of the slide. If the snow banks of successive winters are smaller, a series of concentric talus ridges may result.

278. Destructional Hills and Ridges.—Destructional hills and ridges are outstanding topographic forms which owe their existence to the deeper erosion of the land that surrounds them. That they have not been worn to a lower level is often due to the superior resistance of the materials of which they are composed, but it may be merely because they are interstream areas or *divides* which have not yet had enough time for their complete erosion. This class of elevations may be regarded as including sharp pinnacles, small rocky knobs only a few hundred square feet in area, and larger peaks and ridges. The following forms

will receive consideration: monadnocks, mesas, buttes, cuestas, hogbacks, exfoliation domes, roches moutonnées, stacks, and rain pillars. Mention is made of nunataks, baraboos, and steptoes.

—A. By long continued erosion a land surface may be reduced to an almost level plain (261, 281), but there may still be a few hills, which, having as yet escaped final destruction,



FIG. 326.—Sections of buttes. A and B, buttes consisting of horizontal strata. B has been more eroded than A. C, volcanic neck. A thin talus cover lies on the edges of the weaker strata in each of the diagrams.

rise conspicuously above the plain. These are *monadnocks*. The term connotes nothing in regard to form or structure; it means merely a residual of an old topography standing above a plain of subaerial erosion.

A similar residual type in arid regions is the *island mountain*, or *island mount* (German, *Inselberg*)¹ (284).




FIG. 327.—A *cuesta*. *ab*, back slope or "outer lowland," approximately a dip slope; *bc*, escarpment with its base covered by talus; *cd*, "inner lowland." Hard strata are stippled.

—B. A *mesa* is a flat-topped *table mountain* consisting of horizontal or nearly horizontal beds and bounded on all sides by steep erosion scarps (34, 250). Mesas sometimes occur as outliers of plateau steps (256). When erosion has reduced a mesa so far that there is practically nothing left of the original flat upper surface, the hill is called a *butte* (Fig. 326). Steep-sided hills consisting of relatively hard igneous rock are likewise

¹ A term proposed by W. Bornhardt. See DAVIS, W. M., 1912, p. 366, and *ibid.*, 1930, p. 6.

termed *buttes* (Fig. 326, C). Many mesas and buttes are monadnocks.

—C. If strata of varying hardness are tilted at a low angle, say between 10° and 20° , erosion will develop ridges or *cuestas* on the resistant rock layers. From the crest line of a *cuesta* there is a steep descent in one direction and a gentle descent in the opposite direction (Fig. 327). The steep slope is the *cuesta face*, an erosion escarpment, and the gentle one is the *back slope* of the *cuesta*. The latter is nearly a dip slope. In beds inclined at angles higher than 20° the slopes of an




FIG. 328.—A hogback, due to the slower erosion of a resistant stratum (lined).

erosion ridge developed on a hard rock layer have angles of inclination which are more nearly equal. The side corresponding to the *cuesta face* (across the stratum) becomes less steep and the back slope, about parallel with the beds, becomes steeper. A ridge of this type is a *hogback* (Fig. 328). Evidently, then, there are all gradations between the plateau step in horizontal strata (Fig. 282), through the *cuesta*, to the hogback in beds with a relatively steep dip.

—D. Rounded knobs or *domes* are sometimes produced in the erosion of granitic rocks, conglomerates, etc., by exfoliation (33). They may range from a few feet to several hundred feet in height. At the base of a hill of this origin the talus consists largely of great spalls of which some may be seen on the hillside in all stages of separation from the parent rock.

—E. In glaciated regions many of the rounded rocky knobs and hills were so made by ice abrasion. Glacial striae, polish, and grooves, on their surfaces bear witness to this fact, but on high hills and rarely in other places, postglacial disintegra-

tion may have destroyed these evidences. These rounded rock knobs and hills are called *roches moutonnées* (sing., *roche moutonnée*). They have a more gentle slope on the side from which the ice thrust came and a steeper, ice-plucked slope on the other side (Fig. 329).

—F. Along rocky coasts there are sometimes outstanding projections of rock, *stacks* or *chimneys*, which have been separated from the sea cliff by the concentrated attack of the waves round and behind them. They are still bedrock in the sense that they are in place. They rise from the wave-cut bench (256) from which they will ultimately be razed (Fig. 280).




FIG. 329.—Profile section of a *roche moutonnée*, showing thrust side, *ab*, and lee side, *bc*. Arrow indicates ice motion.

—G. Relatively soft, fine-grained strata, containing scattered pebbles, or perhaps concretions, may be cut into by the force of falling rain. About any one of these pebbles the matrix may be worn away until the pebble at length rests as a cap on the top of a pillar of the less resistant material. Such *rain pillars* may reach heights of several feet.

—H. Pillars (*hoodoos*) may be developed by the erosion of horizontal strata of varying hardness in regions where most of the rainfall is concentrated during a short period of the year. Below hard layers the soft materials may be so far worn away that columns of the latter remain capped by remnants of the overlying resistant rock. The height of the pillar depends in part upon the thickness of the weaker stratum.

—I. Three or four other forms may be mentioned here, although they have no particular relation to destructional or constructional origin. These include the *nunatak*, the *steptoe*, and the *baraboo*. A *nunatak* is an island of bedrock in a glacial field, a hill projecting through, and entirely surrounded by, the

ice (Fig. 330). A *steptoe* is a similar island of bedrock in a lava flow. The lava spread out round the hill and froze about it (Fig. 331). Finally, a *baraboo* is a monadnock which has been buried by a series of strata and subsequently reëxposed by the partial erosion of these younger strata.




FIG. 330.—A nunatak, *c*. *aa*, ice; *bb*, bedrock.

A hill or mountain of older rock, entirely surrounded, but not covered, by any kind of later sedimentary deposit, has been referred to as a *lost mountain* or an *island hill*,¹ a term which to some extent conflicts with the more restricted definition of *island mountain* or *inselberg* (278, A). Robert T. Hill states² that the term *huerfano* (Spanish for orphan; pronounced ware-fa-no, with the accent on the first syllable) is frequently applied to




FIG. 331.—A steptoe, *c*. *aa*, lava; *bb*, bedrock and soil which were overflowed by the lava.

mountains of this character in southwestern United States and Mexico. These terms—*steptoe*, *baraboo*, *island hill*, *island mountain*, *inselberg*, and *huerfano*—are not in general use, but since they do occasionally appear in the literature and since they do refer to special cases, they have been included in the present chapter.

¹ E. W. SHAW, on p. 489 in "Preliminary Statement Concerning a New System of Quaternary Lakes in the Mississippi Basin," *Jour. Geol.*, 19, 1911.

² In a conversation with the writer.

CHAPTER XII

TOPOGRAPHIC EXPRESSION

TOPOGRAPHIC EXPRESSION IN GENERAL

279. Mutual Relationship of Topographic Forms.—The study of topography cannot stop at the description and interpretation of land forms as mere isolated phenomena. Not only must we be able to recognize these individual elements, but also we must be able to interpret their meaning as they appear in their mutual relations. The various relief features of a region as a whole are the product of some common cause or interacting causes. Their shape and distribution are dependent partly upon the underlying geologic structure, partly upon the number and kind of geologic agents which have been engaged in their formation, and partly upon the length of time during which they have been under the control of these agents. Using the term *topographic expression* with reference to the general appearance of a land area,¹ we may say, then, that topographic expression is conditioned by three important factors, namely, geologic structure, erosion process, and stage of topographic development. In the succeeding pages topographic expression in its relation to these three factors will receive some consideration, though by no means in an exhaustive way. Topographic development will be treated first; then the association of unlike types or facies of topography, which were produced in successive cycles, and, last, valley pattern, which depends chiefly upon underground structure. In studying a land surface from this broad standpoint, the geologist should never lose sight of the fact that the topographic elements must always be examined individually before they can be explained in their ensemble.

¹ We may speak, likewise, of the topographic expression of a particular kind of rock or type of structure.

CYCLES OF TOPOGRAPHIC DEVELOPMENT

280. Definition.—No land forms are strictly permanent. Wind, water, and ice are constantly engaged in modifying the configuration of the ground. In the change successive stages of development are recognized, and these are called youth, maturity, and old age. The sequence, from the beginning of youth to late old age, is known as a *geomorphic* or *physiographic cycle*. As a matter of fact, old age is seldom attained, for the process of erosion becomes increasingly slow as the cycle advances and various accidents and interruptions interfere with the work (285). Since each agent of erosion operates in its own peculiar way, there are several different kinds of geomorphic cycle. There are the *normal* or river cycle, the cycle of mountain glaciation, the cycle of marine erosion, and the cycle of arid erosion.

281. Cycle of River Erosion.—No river can cut its channel more than a few feet below sea level because its speed is quickly reduced as soon as it empties into the sea. A few hundred feet inland the stream cannot cut even as low as sea level, for there must be some slope to enable it to flow. Carrying out this line of reasoning, we find that there must be a slope for the course of every river, below which further erosion is no longer possible. When any stream has cut down to this critical slope it is said to be *at grade*, and the ocean level is termed *base level*. Probably grade has never been attained by any river, for as time goes on a stream must have a constantly diminishing load, and a diminishing load will enable it to cut nearer and nearer to sea level, so that its grade will be a constantly vanishing quantity; but for purposes of general description grade may be regarded as something having a fairly definite value.

Streams that have not yet reached grade are apt to have waterfalls where they cross hard rocks, and lakes where they flow through basins. They are then said to be young and their valleys are in an early stage of erosion. In this condition they are actively cutting downward and headward. For a time a lake may serve as a *local base level* (Fig. 332), reducing the inflowing

streams to *temporary grade*, but at last the lake will be drained and the streams will renew erosion toward a new grade. In like manner, a resistant rock may bring the stream above it to a temporary grade (Fig. 333).




FIG. 332.—A lake as a local base level. *ab*, temporary grade determined by the lake, *cd*; *bc*, delta; *de*, portion of original slope of stream channel; *ef*, upper part of stream profile which is being cut downward to a grade determined by a base level to the right of the diagram. As soon as *e* reaches *d*, by headward cutting, the draining of the lake will begin.

While the stream in its youth is eroding its channel, weathering, soil creep, earth flow and landslides cooperate to lower the valley walls. At first the walls are comparatively steep and the V-section is narrow (Fig. 334). As grade is approached vertical erosion becomes slower, and with the slackening of this process, weathering and mass movement relatively gain in speed, so that




FIG. 333.—Profile of a stream channel, showing how a hard rock layer, *cb*, retards the erosion of the channel upstream from *b*. *b* is a local base level.

the V broadens, *i.e.*, its angle becomes more obtuse. When at grade the river is said to be mature. If all the streams in a region are at grade, the topography is mature. The valleys are broad, there is no sharp dividing line between hills and valleys, and there are no waterfalls and lakes.

From the inception of maturity, lateral erosion becomes more effective than downward cutting. The river builds a flood plain on which it meanders. On the outer curve of each bend the

current erodes and on the inner curve it deposits. The beginning of maturity marks the end of the distinct V-section of the valley (Fig. 334, E). During maturity the hills are lowered, the valley grows broader and shallower, the flood plain also broadens until it is much wider than the meander belt,¹ and oxbow lakes result from the coalescence of meanders (267). Without any sudden change river and valley pass into old age and so complete the normal cycle of erosion. When the uplands have all been reduced to low swells and all the streams meander on broad flood plains, the topography as a whole is old (261).




FIG. 334.—Changes in the profile section of a valley from youth to old age. A, initial stage. BB, youth. CC, late youth. DD, early maturity; here the shoulders once at a and f, have practically disappeared. EE, middle maturity; the stream has built a flood plain. FF, late maturity. GG, old age; the profile is that of a peneplain. HH, base level. becd, section which was cut by the stream; abc and def, sections removed by weathering. Under certain conditions the part of the hill slope below the original position of the shoulder (in CC) may become broadly concave upward in DD and subsequent stages.

Summarizing with reference to the cycle of erosion of streams and valleys: youth is marked by relatively steep valley sides, occasional waterfalls and lakes, and a V-shaped transverse section of the valley; maturity is characterized by a meandering stream, absence of lakes and waterfalls, a flood plain which is not much wider than the meander belt, and a rolling hill-and-valley topography; and, old age is characterized by broad, shallow valleys; broad flood plains, much wider than the meander belts, and the presence of numerous oxbow lakes.

The foregoing description applies more especially to the cycle in regions which have a normal rainfall and a fair covering of vegetation. Where the rainfall is deficient and the vegetation

¹ The part of a flood plain between two lines tangent to the outer bends of all the meanders is called the *meander belt*.

seant, the topographic history approaches that of the arid cycle (284). Furthermore, the differences in the relative resistance of the rocks to erosion may distinctly modify the topographic forms at any particular stage in the cycle. For instance, in areas underlain by approximately horizontal strata, the hard layers may preserve steep cliffs at their outcropping edges from youth even into late old age of the district (Cf. 278, B).

282. Cycle of Mountain Glacier Erosion.—As with rivers, so with mountain glaciers, it is possible to recognize a progressive change in the topography according to the amount of erosion to which the region has been subjected. Imagine an upland on which glaciers are beginning to make themselves manifest. The first work of erosion will consist of the carving of drift hollows and then of small cirques. As the process goes on, the cirques will grow larger and will lead out to glacial valleys. That portion of the old upland which has not yet been touched by ice abrasion will constantly diminish in area, for, by headward sapping, cirques on the opposite sides of a divide will approach one another. Thus the upland will become *scalloped* (Fig. 335, A). To a less degree the divides between adjacent valleys that open in the same direction will grow narrower as the valleys are scoured deeper and wider. If glacial erosion continues long enough, adjacent cirques may meet in sharp-edged ridges, and the old upland will then remain only in isolated areas (Fig. 335, B). At a still later stage the last remnants of the upland will disappear and all the divides will be knife-edge ridges rising at junction points into abrupt peaks (Fig. 335, C).

283. Cycle of Marine Erosion.—There are two phases of the cycle of marine erosion, that for coasts which have been elevated with respect to sea level and that for coasts which have been depressed. The elevated coast may at first be characterized landward by a coastal plain which slopes gently to the water's edge and then continues with the same inclination beneath the water. The shore line is relatively straight and monotonous. Since the water is shallow, the waves are forced to break some little distance offshore, and where they break they




FIG. 245.—Stages of erosion accomplished by mountain glaciation. A, youth; B, early maturity; C, late maturity. In A, C the stippled areas are snow banks and small glaciers. (A and B from the Cloud Peak quadrangle, Wyo.; C from the Bishop quadrangle, Cal.)

churn up the bottom sediments and pile them up seaward as an offshore bar (Fig. 336, I and II) (252). Between the bar and the mainland is a lagoon of clear salt water. The shore is now in a young stage. Meanwhile the waves cut deeper and they begin to cut into the seaward side of the bar; winds blow the dry sands of the bar over into the lagoon; and streams




FIG. 336.—Development of a shore line of elevation. *Z*, zone of initial wave attack; *B'*, *B''*, *B'''*, offshore bar; *C*, original shore line; *D'''*, dunes; *L*, lagoon; *M*, marsh. (After W. M. Davis.)

carry mud and sand into the lagoon from the land side. Thus, two important changes are in progress: the bar is migrating landward and the lagoon is filling up. Gradually plants take root in the shallowing lagoon which eventually becomes a marsh. Over this marsh the bar travels, usually as a body of sand dunes; and at length the edge of the marsh is exposed on the sea side of the bar, that is, on the beach (Fig. 336, III). It is recognizable as a dark band of peat, and very often lumps or *boulders* of peat, more or less rounded by the waves, may be seen on the beach. Finally, there comes a time when the bar has crossed the entire

width of the marsh and has advanced on to what was the land side of the lagoon while the latter existed. The shore line is now mature (Fig. 336, IV). It is still nearly straight, but it has a low cliff or *nip* where the waves are cutting into the original coastal plain. The fact is that the waves, by this complicated process, have so far deepened the water that they now break against the shore instead of far out as formerly. They have moved their locus of attack to the land. Henceforth, during maturity, they may cut inland, but the process will slacken and the land will probably suffer elevation or depression and so start a new cycle before the cliff and its accompanying bench have been made large enough to deserve the title, old age. In this process, waves and currents have operated to develop a profile of equilibrium analogous to grade in river erosion. The slope of the bench, as seen in this profile, will vary with such factors as the strength of the erosive agents and the nature of the rock materials undergoing erosion.

If the emerged coastal plain is relatively steep, it may be bounded landward by an old abandoned sea cliff, and soon after uplift (early youth) it will be bounded seaward by a new cliff, for the waves will break against its seaward margin instead of offshore, as in the case where the plain slopes very gently seaward. This new sea cliff will be cut landward, and the width of the plain will diminish, through youth, until with maturity the younger cliff will have been carried back to the older cliff, and the emerged coastal plain will have been destroyed, as such, and beveled down to a wave-cut bench (Fig. 337).¹

When a land area is depressed relative to sea level, the sea enters the valleys of the drowned land and the new shore line is irregular in proportion to the unevenness of the topography at the time of submergence. The headlands and islands are more strongly attacked by the waves, and the débris, distributed by currents, finds lodgment here and there in bays or on the lee sides of promontories and islands. This is the youthful condition of the depressed coast. Spits, tombolos, bayhead beaches,

¹ See Bibliog., PUTNAM, WILLIAM C.

baymouth bars, etc. (252), are abundantly represented. In the lapse of time the islands are demolished, the headlands are




FIG. 337.—Development of an emerged relatively steep coastal plain, where the land mass is bordered by deep water close to shore. (After Putnam, with permission of the *Journal of Geology* and the University of Chicago Press. See Bibliog., Putnam, W. C., 1937, p. 848.)

cut far back, and the bays are well filled with sediments, partly marine and partly dropped by inflowing rivers, so that the shore

line becomes nearly straight (Fig. 338). This is maturity. Old age is approached, as in the case of the elevated coast, by long continued landward erosion of the coast by the waves.

Lake shores may undergo the same types of erosion as sea shores, but the existence of a lake is generally too short for the complete development of its shore.

284. Cycle of Arid Erosion.--As has been pointed out by W. M. Davis,¹ there is no radical difference, in arid regions as




FIG. 338.—Development of a shore line of depression. *A*, initial shore line; *B*, shore line in youth; *C*, same in maturity; *D, E, F*, deposits made by rivers. (After W. M. Davis and W. H. Snyder.)

compared with humid regions, between the prevailing erosional processes nor between the fundamental characteristics of the topographic forms developed by these processes. The main differences are in degree rather than in kind.

For consideration of the cycle of arid erosion, we may assume an initial land form consisting of uplifted fault-block mountains, with intervening valleys and basins. The principal agents and processes of erosion will be disintegration; wind scour and wind transportation; and especially concentrated abrasion, transportation and intermittent deposition performed by stream

¹ Bibliog., DAVIS, W. M., 1930.

wash, sheetflood wash, and rill wash, locally affecting areas irregularly distributed, but in the long run more or less equally affecting all parts of the region. Landslides, mudflow, and soil creep also play an important role in lowering slopes and in furnishing waste for transportation. Because of the absence, or paucity of vegetation, detritus is coarser, in relation to the time or period of development in this cycle, than it is in the case of erosion under a humid climate.

During the earliest stages in the cycle of arid erosion, stream valleys and branch valleys develop; the uplands are vigorously dissected; and the products of erosion are carried out on to the valley or basin floors. Streams tend to cut down to a grade which will have a slope depending on distance of transport, amount and size of material carried, etc., and the same may be said of sheetfloods and rill wash. By these methods of erosion of running water, assisted by the important process of deflation, a rock-floored plain is carved out of the front of the mountain mass, an apron-like plain, sloping basinward. This is known as a *pediment*. One of the striking features of arid physiography is the pediment, thinly and discontinuously veneered with sand and stony waste, and usually cut out of the same rock materials as the adjacent mountains themselves. This plain, the pediment, is the homologue of the peneplain in humid climates. In the lower central parts of the basins, where sedimentation prevails, are shallow lakes, playas, and salinas. (See Fig. 290.)

Under the conditions just described, the region may be said to be in youth. As erosion progresses, the pediment flanking each mountain mass is extended, encroaching more and more upon the uplands, and adjacent basins may at length coalesce. "Maturity will be reached when the drainage of all the arid region becomes integrated with respect to a single aggraded basin base-level, so that the slopes lead from all parts of the surface to a single area for the deposition of the waste" . . . "There will appear . . . large rock-floored plains sloping toward large waste-floored plains; the plains will be interrupted only where parts of the initial highlands and masses of unusually resistant rocks

here and there, survive as isolated residual mountains" (Inselberge, or island mountains) . . . "In so far as the plains are rock-floored they will truncate the rocks without regard to their structure"¹ (261, 278, A). With further extension of the pediment, an old age stage may be conceived at which all island mountains will have disappeared and only a monotonous undulating plain remains.

TOPOGRAPHIC EXPRESSION DEVELOPED IN TWO SUCCESSIVE CYCLES

285. Topographic Unconformity Defined.—*Topographic unconformity* is a term applied to land surfaces which consist of two




FIG. 339.—Topographic unconformity. A gently rolling preglacial land surface has been invaded by ice which has produced a series of steep-sided cirques. The land is in an early mature stage of glacial erosion. (After W. W. Atwood.)

parts that are out of adjustment with one another. This condition is brought about by an interruption in the ordinary course of an erosion cycle. For instance, rivers and agents of weathering may have produced a late mature topography which is then uplifted and subjected to mountain glaciation. If the invading glaciers disappear before they carry their erosion beyond youth, the area will show two kinds of topography: (1) the mature upland incised by (2) the new glacial valleys, and these two topographic phases will be out of harmony with one another, that is, they will be topographically unconformable. Their relation will be that of *topographic unconformity* due to an *interruption* in the normal cycle (Fig. 339). The same mature upland,

¹ Bibliog., DAVIS, W. M., 1909, pp. 303, 304.

incised by streams with young valleys of a new cycle, would be another case of such unconformity. (Profile B, Fig. 334.) Abandoned shore lines (286) are a third illustration of topographic unconformity.

286. Abandoned Shore Lines.—Shore-line features—beaches, bars, reefs, benches, and the like—originate for the most part at or near the level of the lake or sea where they are formed. If the water level rises a few feet, relative to the land, they will be submerged; but if it suffers relative lowering, they will be left stranded, as it were, some distance above the new shore line. They are then said to be *abandoned*. Such shore lines are too often called *elevated* before substantial evidence has been brought forward to prove that the land rose, rather than that water level was lowered. *Abandoned* is a better epithet for it implies nothing as to the manner in which the change in relative water level was effected. A shore line may be abandoned, in the case of the sea, either by actual uplift of the land or by actual depression of the sea, and, in the case of lakes, either by differential tilting of the land such that at one end the lake floor is more or less exposed, or by lowering of the lake as a whole through draining or evaporation (Fig. 340). Whatever the real cause may be, the results are essentially the same. These abandoned shore-line features are in topographic unconformity with the adjoining land forms.

If relative depression of water level sets in after a long period of constancy, and continues at a uniform rate until it is succeeded by another long interval of constant water level, there will be only one belt of abandoned shore-line forms, those of the first period of fixed water level. Probably no other evidence of wave or current action will be seen in the zone between this old shore line and the present one. In other words, for the development of shore-line features there must be a stand of the water level, and the longer this stand, the more pronounced will be the shore-line forms. If a long-enduring great uplift is interrupted by pauses, each pause will be represented by a belt of abandoned shore-line features (Fig. 281). Naturally, the older, higher ones will bear evidence of most subaerial erosion.




FIG. 340.—Shore terraces exposed by the lowering of an ancient lake. Near Dove Creek, Utah. Map above, view below. (After G. K. Gilbert; drawn by G. Thompson.)

Occasionally lakes are impounded on the upstream side of natural barriers which have been built across valleys (267). Landslide *débris*, morainal material, and even ice itself, may temporarily block up a valley in this way. While such a lake is in existence, various shore-line features, both constructional and destructional, may be formed. Beaches may be built; a small *nip* (bench and cliff) may be cut in original unconsolidated




FIG. 341.—Insequent drainage pattern. (Trent River quadrangle, N. C.)

deposits of the valley side; and inflowing streams may construct deltas. After the barrier has been cut through, or, in the case of ice, has melted away, the lake will be drained, and small beaches, deltas, wave-cut benches, etc., may be seen on the slopes of the valley through which, perhaps, a stream now flows. If ice served as the dam, the shore-line phenomena end abruptly at the former site of the ice front.

With regard to the field study of abandoned shore lines, the geologist should note that their original characters are usually

more or less concealed by vegetation and by erosion. Their recognition depends, first, upon a knowledge of the typical features of shore-line phenomena in their natural position, and likewise upon the ability to distinguish between them and topographic forms of similar appearance (253). River terraces are especially apt to be mistaken for abandoned lake beaches. How-




FIG. 342.—Rectangular drainage pattern controlled by joint and fault systems. (Elizabethtown sheet, N. Y.)




FIG. 343.—Rectangular drainage pattern controlled by folded strata. (Monterey sheet, Va.-W. Va.)

ever, river terraces are not associated with abandoned deltas which extend out from their outer margins (Fig. 340), and river-laid gravels are usually mingled with more sand and fine clastic material than are beach gravels. The latter are relatively *clean*. Also, beach materials grade from pebbles and boulders at the inner margin to finer pebbles and sand toward the outer margin (78), whereas river terrace gravels exhibit no such regular gradation.

TOPOGRAPHIC EXPRESSION IN ITS RELATION TO GEOLOGIC
STRUCTURE

287. Valley Pattern.—Valley pattern,¹ or what commonly amounts to the same thing, drainage pattern, depends on the




FIG. 344.—Radial drainage pattern of the Black Hills of Wyoming and South Dakota. The range is situated principally in the upper half of the map. (After N. H. Darton.)

distribution of bedrock, the attitude of stratiform rocks, the arrangement of surfaces of weakness, such as joints and faults, and on a number of other structural features. Consequently it

¹ See Bibliog., ZERNITZ, EMILIE R.

may be used to assist in the interpretation of geologic structure as well as in the study of land forms.

Young streams, flowing on a nearly level plain or upon irregular superficial deposits of indefinite form and structure, are likely to wander here and there in following the irregularities of the ground. This type of drainage is called *insequent* (Fig. 341). A rectangular, or trellis-like pattern may result from the control of a rectangular joint or fault system (Fig. 342), or from the influence of tilted or folded, alternating resistant and weak strata (Fig. 343). By the updoming of a relatively flat area, a radial




FIG. 345.—Dendritic drainage pattern. (Wartburg sheet, Tenn.)

drainage may be induced (Fig. 344). If the radial streams intersect concentric belts of hard and weak rocks, this pattern may be taken as substantial evidence for there having once been such an updoming. The dendritic (treelike) arrangement of rivers and their branches is most common, and is characteristic of regions where structural controls are not exaggerated (Fig. 345).

In many parts of the country, where soils are mostly residual and where the underlying rocks are gently folded strata, hills and divides may roughly correspond with domes and anticlines, and valleys, with basins or synclines. Under these circumstances it is often a question whether the beds have sagged, as erosion proceeded, and thus have produced what might be termed *false structures* (321), or whether the inclinations of the beds are

true structural dips which controlled the direction and pattern of the drainage. Where folded structure does govern the drainage, the control is effected principally by the harder layers which resist erosion and tend to hold up the land surface. The smaller streams are likely to exhibit the closer relation to the dip, for the master streams not only may cut downward irrespective of the structure, but also may swing sideways out of the area of any possible original control. This statement may apply whether the main drainage is consequent or superposed.¹

¹ A *consequent stream* is one having its course controlled by, and its direction essentially parallel to, the dip of the underlying strata. A *superposed stream* is one which acquired its course on a formation now mostly eroded away and which had this course superposed upon the underlying formation irrespective of the structure of the latter formation.

CHAPTER XIII

TOPOGRAPHIC MAPS AND PROFILE SECTIONS

FEATURES SHOWN ON TOPOGRAPHIC MAPS

288. Classification of Features.—A *topographic map* is one that shows the size, shape, and distribution of features of the earth's surface. On the topographic maps published by the U. S. Geological Survey¹ these features are classified in three groups: (1) *relief*, including hills, valleys, plains, cliffs, and the like; (2) *drainage* or *water*, including seas, lakes, ponds, streams, canals, swamps, etc.; and (3) *culture*, including many of the works of man, such as towns, cities, roads, railroads, boundaries, and names. Relief is printed in brown, drainage in blue, and culture in black. In addition to these, on some maps, forests are indicated by a green tint. The significance of the conventional signs employed² is often given in a key either on the back of the map or in the right margin. Such a key is called a *legend*. In it the various signs are arranged in a column with those for relief above, those for drainage next, and those for culture at the lower part of the table. Each symbol or line is inclosed in a small rectangle, and all the rectangles are of equal size. If the student has to prepare a topographic map of any kind, he will do well to make the legend for it according to the scheme just outlined. In any case the map must have a legend.

289. Contours.—Relief may be represented on topographic maps by contour lines, by tinting, by hachures, or by shading. In some cases a combination of two or more of these methods is adopted. We shall concern ourselves only with contour maps,

¹ Lists of these maps for each state may be obtained from the Director, U. S. Geological Survey, Washington, D. C.

² Bibliog., SALISBURY, R. D., and ATWOOD, W. W.

since these alone can be used for making satisfactory measurements of height, slope and distance.

A *contour* is a line drawn through points having the same altitude. The shore line at mean sea level is called the contour of zero elevation, mean sea level being taken as the datum plane from which other contours are measured. A contour represent-




FIG. 346.—Contour map of a land area bordering a shore line. If sea level were to rise 40 ft., the shaded portion of the present land would be submerged and the new shore line would be the present 40-ft. contour. The hill south of *a* would become an island.

ing an elevation of 20 ft. is the line of intersection of the land surface with a horizontal plane 20 ft. vertically above mean sea level. If the sea were to rise 20 ft., the new shore line would coincide with this contour. In the same way, if the sea were to rise 40 ft., the new shore line would coincide with the 40-ft. contour (Fig. 346); and so on. When the contours thus indicate differences of level of 20 ft., the vertical distance of 20 ft. is

termed the *contour interval*. Other contour intervals, such as 50, 100, 200, and 250 ft., are sometimes chosen instead of 20 ft., but ordinarily only one contour interval is used on a given map.

Certain contours are printed more heavily than others. When the contour interval is 20 ft., the 100-ft. contours are heavy (Fig. 346). A broad contour line of this kind may be called an *index contour*, for it is labelled here and there along its length by a small number which denotes its elevation above mean sea level.

If sea level were to rise, the water would extend up the valleys and so form bays, while the hills and ridges would become headlands. Some hills, having been entirely cut off from the mainland, might become islands. In the present connection the significance of these facts is that: (1) contours bend or "loop" upstream in valleys; and (2) the upper contours on hills are relatively short, closed curves. Hollows without outlets are also indicated by closed contours, but they are distinguished from hill contours by having short hachures on the inner (downslope) side of the line (Fig. 294).

290. Scale.—The scale of a topographic map is usually noted in the lower margin. It may be expressed in several ways. For instance, it may be denoted by such a statement as, "one inch = one mile," or it may be represented graphically by a measured straight line as in Figs. 346 and 347. Again, the scale may be expressed as a ratio or a fraction, the latter being known as the *representative fraction* (R. F.). Thus, if the scale is 1:125,000, or 1/125,000, this means that the distance between any two points on the map is 1/125,000 of the actual distance between the originals of the two points on the earth's surface; or, to put it in another way, a map 6 in. long on a scale of 1:125,000 shows an area $6 \times 125,000$ in. = 11.8 miles long. The scale of 1:63,360 is equivalent to the scale of 1 in. to 1 mile. Most of the Geological Survey maps are constructed on one of these scales: 1:62,500, 1:125,000, or 1:250,000. Maps on the first scale are *15-minute maps*, those on the second scale are *30-minute maps*, and those on the third scale are *degree maps*, referring to minutes or degrees

of latitude and longitude covered by the maps. On the scale of 1:62,500, 1 in. on the map represents a distance a little less than 1 mile; on the scale of 1:125,000, 1 in. represents a little less than 2 miles; and on the scale of 1:250,000, 1 in. represents somewhat less than 4 miles.

291. Direction.—Compass directions are sufficiently indicated on many maps by meridians and parallels of latitude. On large-scale maps; however, a full arrow is commonly drawn, properly oriented, pointing to true north, and a half arrow, intersecting the full arrow in its center, for magnetic north (Fig. 346). The angle between these two arrows should be marked, and also the date when the observations were made, for the magnetic variation changes from year to year (322).

292. Requisite Data on a Completed Contour Map.—The more important features of contour maps have been described above. A contour map is not complete unless it has a name, is accompanied by a legend, and has designated upon it the scale, the contour interval, the datum plane from which the contours were measured, and compass directions.

293. Aerial Photographic Maps.—The subject of aerial photographs and their use as maps is reserved mainly for Chapter XVII. Such photographs, taken from a considerable height, looking vertically downward, are essentially topographic maps. They display in remarkable detail the form and distribution of features of the earth's surface. When properly prepared, they can be accurately contoured, and they can be used for measuring distances and slope angles, but these operations require the use of certain precise instruments in the hands of trained specialists.

PROFILE SECTIONS

294. Nature of Profile Sections.—A *profile section* is a diagram showing the shape of the surface of the land as it would appear in vertical cross section. A profile section consists of four lines which completely inclose a space (Fig. 348). They are the profile line, the base line, and the two end lines. The profile line, which

is the top line in the diagram, represents the intersection of a vertical plane with the land surface. The base line is drawn horizontal and is chosen at a convenient distance below the lowest point of the profile line. The end lines are perpendicular to the base line.

The position of a profile section should always be indicated by a line, called a *line of section*, on an accompanying map (AB, Fig. 347), for a section has no practical value unless its location is known. The line of section is really the top line of the section as seen in plan.




FIG. 347.—Contour map of a land area of moderate relief. Diagonal ruling, lake; AB, line of section.

Every profile section has a horizontal scale, measured in units on the base line, and a vertical scale which is measured in units of elevation perpendicularly above the base line. If these two scales are the same, the section is said to be *drawn to natural scale*. Sometimes the vertical scale is *exaggerated*, i.e., it is made two or more times as great as the horizontal scale (Figs. 348, 349). Exaggeration is useful for profile sections of lands of very slight relief merely to emphasize the positions of hills and valleys. Ordinarily natural scale should be employed. Unless accurate measurements are to be made, the vertical scale may be 1 in. to 5,000 ft. if the horizontal scale is approximately or actually an inch to a mile (1:62,500 or 1:63,360). This is so near to natural scale that it is satisfactory for most purposes, and it

has the advantage that the contour interval is commensurable with the vertical scale.

295. Construction of a Profile Section.--Let us suppose that a profile section is to be made along line *AB*, Fig. 347. Lay the straight-edge of a sheet of paper along *AB* and mark a dot on it at each point where a contour is crossed by *AB* and a small caret




FIG. 348.—Profile section along line *AB* in Fig. 347. Drawn to natural scale.

at each point where a stream is crossed by *AB*. Connect the dots for the upper contour on each hill by a curved line (*h*, Fig. 348), to show where the hills are situated. In the same way connect dots representing the two margins of a lake (*l*, Fig. 348). It is well also to label some of the index contours by their elevation numbers. Upon a piece of profile paper, ruled with coördinates to $\frac{1}{20}$ in., draw $XY = AB$ for the base line of the section.




FIG. 349.—Profile section along line *AB* in Fig. 347. Vertical scale three times as great as horizontal scale.

Transfer the points, carets, etc., to *XY*, marking them lightly with a lead pencil. The first three of these points are lettered *a*, *b*, and *c*, the summit contour is *h*, and the stream is at *s* (Fig. 348). Since $XY = AB$, obviously the horizontal scale of the section is equal to that of the map. If we let $\frac{1}{20}$ in. = 20 ft. for the vertical scale, this section will be drawn to natural scale.

The lowest point crossed by AB happens to be at the lake where the elevation is somewhat less than 180 ft. Therefore, 100 ft. above sea level would be a convenient elevation for the base line. Sea level itself may be chosen if preferred. The first contour cut by AB is the 240-ft. line, represented by a on XY . Make a dot vertically above a on the coordinate for 240 ft. Vertically above b , the position of the 260-ft. contour, mark a dot on the 260-ft. coordinate. Similarly, mark a dot on the proper coordinate above each point on XY . Connect these points by a curved line, MN , which is the profile line of the section. Note that the hilltops are a little higher than 260 ft., but not so high as 280 ft.; that the stream channel is lower than 200 ft., but not so low as 180 ft.; and that the lake surface is below 180 ft., but above 160 ft.

296. Enlargement of Profile Sections.¹—Profile sections may be enlarged by multiplying both the vertical and horizontal scales by the same factor. This may be done in two ways. Suppose that the section of Fig. 348 is to be enlarged twice. Draw a base line double the length of AB (Fig. 347) upon a piece of profile paper. As described in the preceding article, mark on the edge of a sheet of paper the positions of the contours and streams intersected by AB . Lay this paper against the base line so that the point, A , will coincide with the left end of the line. Then transfer the contour positions in such a way that the space between each two adjacent points will be doubled, that is, the spaces, beginning at the left, will be equal to $2Xa$, $2ab$, $2bc$, and so on, in order (Cf. Fig. 340). Having set off all these points, continue as in Art. 295, but with a vertical scale of $\frac{1}{2}_0$ in. = 10 ft. instead of $\frac{1}{2}_0$ in. = 20 ft.

The second method is illustrated in Fig. 350. For convenience only half the length, XO , of the section in Fig. 348 is here enlarged. Lay off the base line $XZ = 2XO = 2AB/2$, as in the first method. From X draw $XW = AB/2$, making an angle of 60° with XZ . Mark on XW the contour and stream positions, as explained in Art. 295, from X to W . Draw ZW , and from each

¹ A section, and also a map, loses in accuracy in proportion as it is enlarged.

of the points on XW draw a line to XZ parallel to ZW . These lines will intercept distances on XZ just double the distances which they intercept on XW .

Enlargement may be accomplished more readily as follows: Let XW , Fig. 350, represent the line of section on the map. Place the paper, on which the enlarged section is to be plotted, so that the base line, XZ , of this section (drawn as many times longer than XW as the desired enlargement) is at an angle to




FIG. 350.—Diagram illustrating a method of enlarging a profile section. $XZ = 2XW$
 $XW = XY/2$ in Fig. 348.

XW , as shown. Draw WZ , and, parallel to it, draw lines through other points to be transferred from XW to XZ .

INTERPRETATION OF CONTOUR MAPS

297. Direction of Ascent and Descent.—In studying a contour map one may want to ascertain whether one would go up or down hill in crossing contours in a certain direction. This may be done either by noting the elevations of the index contours which are successively crossed or by observing the general arrangement of all the contours without particular reference to those which are numbered. The latter method is often preferable where index contours are not crossed or where the map is so obscured by various features that finding and tracing the index contours is difficult. This second method is simple enough if it is remembered: (1) that the contours bend upstream in valleys. (Figs. 346, 347), and (2) that the ground must rise away from stream courses.

In crossing a valley the last contour met before reaching the stream is the first one to be passed on the other side of this stream. Similarly, the highest contour on a divide between two streams must be crossed twice without meeting any intervening higher or lower contour. Ordinarily divides are characterized by knobs or hills which are shown by closed contours. The innermost of such closed contours is the highest. The divide summit is a little higher, but less than a contour interval higher, than this uppermost contour. Obviously the position of the divide summit between two adjacent valleys must be determined in order to avoid the mistake of estimating too great an ascent in passing up from the valley floor.

298. Elevation of a Given Point.—Suppose that one wants to know the elevation of a certain point on the map. The point



FIG. 351.—Ideal profile sections of slopes.

may be: (1) on an index contour; (2) on a light contour; or (3) between contours. In the first case (*a*, Fig. 347) the elevation of the point may be found by following the index contour along to the nearest number which gives its height above mean sea level. The second case is illustrated by *b* in Fig. 347. To obtain the elevation of this point, first determine the elevation of the nearest index contour, here 200 ft., and whether the point is uphill or downhill from this index contour. In the figure, *b* is on the second contour uphill (see stream) from the 200-ft. line. Since the contour interval is 20 ft., *b* is 2×20 ft. above 200 ft.: i.e., its elevation is 240 ft. above sea level. The third case is left for the student to explain. In Fig. 347, *c* may be taken as the point.

299. Spacing of Contours.—Figure 351 illustrates the relations of contour spacing to the steepness and form of a sloping surface. *A*, *B*, *C*, and *D* are profile sections of slopes. *A* is steep; *B* is relatively gentle; *C* is convex upward; and *D* is concave upward. *XY* is the base line for all four. The vertical lines are drawn

from the intersections of the profile lines with the elevation coördinates. The spaces between the verticals are equal to the distances between the contours on a map representing these slopes. This diagram shows that, with a given contour interval: (1) contours are more closely spaced on steep slopes than on gentle slopes; (2) contours are more closely spaced at the base of a surface which is convex upward, and near the top of a surface which is concave upward. When several contours run together into a single line, this line indicates a cliff, or, if the scale of the map is small, a very steep slope.

300. Distance between Two Points.—In Fig. 352, *abc* is the profile of a hill. On a contour map the distance from *a* to *c* over the hill would be shown by the length of the straight hori-




FIG. 352.—Profile section of a hill to show relations between base line and profile line.

zontal line *de*. *abc* may be called the *original* of its projection, *de*. Stated in general, any line that crosses contours on a map represents a distance shorter than the actual distance along the original of that line on the earth's surface. An approximation to the real distance between two given points may be obtained by constructing a natural scale profile section between them and measuring the profile line; but this method cannot be quite accurate because contour maps can be approximately correct only at the contours. Within the limits of two adjacent contours the ground may slope uniformly or it may be irregular.

301. Visibility.—From a contour map it is possible roughly to determine whether certain points, lines, or areas, are visible, in the field, from a chosen station, always on the assumption that there is little or no vegetation in the region to obstruct the view. In the first place we state the rules that: (1) on a convex land surface where the contours are spaced more closely at the bottom of the hill than near the top (299), points are not intervisible;

and (2) on a flat surface, or on a concave surface (299), points are intervisible, in both cases (1) and (2) *in directions across the contours*.

To find out whether a distant point, *C* is hidden or not, from the observer's position, *A*, by an intermediate high point, *B*, draw a horizontal line on a chosen scale to represent the distance




FIG. 353.—A, Topographic contour map. Contour interval, 50 ft. The observer standing at *A* and looking westward (toward the left) can see the area not shaded west of Box Creek, provided the land is not forested. The shaded areas are determined by constructing skeleton profiles on lines *AB*, *AE*, *AG*, *AM*, and *AN*, as illustrated by the two profiles in the lower cross section, B.

between *A* and *C*, and measure off the distance *AB* on this scale on the horizontal line. Let the lowest of the three points lie in the horizontal line. Choose a convenient vertical scale and plot the proper positions of the other two higher stations, on this scale, above the horizontal line. Draw a straight line from *A* through *B* toward *C*. If *C* lies above this line (the line of sight), *C* is visible from *A*. If it lies below the line of sight, it is not visible from *A*.

In ascertaining what areas may be visible from a given station, *A*, skeleton profiles of the type just described may be constructed from *A* across all adjacent critical points, such as hill tops and low points on gaps between hills, and the points at which these lines of sight meet the more distant topography may then be connected by a flowing line (Fig. 353).

302. Inclination of a Slope.—The inclination, grade, or gradient, of a sloping surface or of a sloping line may be expressed as a ratio, as a percentage, or as an angle measured in degrees




FIG. 354.—Diagram showing the methods of measuring a slope.

from the horizontal. Let Fig. 354 be a profile section of a sloping surface, *ac*, and suppose that $ab = 10$, and $bc = 50$, no matter in what units. i is the angle of inclination of the surface. In travelling the horizontal distance $cb = 50$, one would ascend a vertical distance $ab = 10$. The ratio ab/bc , or, in this example, $10/50$, is an expression for the gradient of the inclined surface. It may be spoken of as a grade of 1 in 5. If the division indicated in the ratio is performed, and the decimal point in the quotient is moved two places to the right, the result will be in percentage. In the present case $10/50 = 0.20$. By moving the decimal point two places to the right, we find that the surface has a 20-per cent grade.¹

¹ Equivalent angles and per cent grades are tabulated in Appendix XI.

CHAPTER XIV

GEOLOGIC SURVEYING

PART I. GENERAL OBSERVATIONS

NATURE OF GEOLOGIC SURVEYING

303. Definition and Aim.—*Geologic surveying*, a term practically synonymous with geologic field work or field mapping, is the systematic examination of any region for geologic information. Its purpose may be economic or purely scientific. If economic, the investigation may be somewhat limited in its scope, the object being merely to study the phenomena which bear directly on some particular problem; but it is becoming more and more evident that the broader the range of any field examination, the more accurate and otherwise satisfactory the results are likely to be, for the interrelations of geology are numerous and intricate; and it is further true that the broader and more varied has been the training of a geologist, the more efficient he is in analyzing any kind of restricted geologic problem, be this theoretical or practical.

304. Uses of Geologic Surveying.—Geologic surveying is fundamental to all geologic knowledge. Its uses are, therefore, numberless. It assists the engineer in determining the location and cost of tunnels, bridges, aqueducts, reservoirs, dams and many other structures. It facilitates the work of the prospector. It shows the farmer what kind of soil he may expect to find in one place or another. It provides valuable information in reference to mining, quarrying, and the production of oil and gas. One of its principal advantages is that it locates for the manufacturer the most accessible sources of his raw materials and so enables him to obtain them at a relatively low cost. Finally, it yields to the

scientist facts by which he interprets the structure and history of the earth.

305. Diversity of Surveys.—There are many conditions which regulate the nature of geologic surveys. Work is apt to be difficult in swampy regions, on heavily forested land, and in places where the soil cover is thick and extensive. Marked relief and high altitude increase the physical labor of exploration, and certain climates seriously handicap the geologist. Accessibility to towns and railroads is a significant factor. If the field area is far removed from civilization, a large supply of provisions has to be transported across country and travel is difficult. Where topographic maps have already been published, geologic work can be done more easily and more quickly than where such maps are poor or wanting. Then, again, there are such factors as the time at the disposal of the geologist, the scale on which the geologic mapping is to be done, and, finally, the nature of the problem itself. The consequence is that geologic surveys are very diverse in respect to their needed equipment, their thoroughness, and their manner of execution.

306. Scope of Geologic Field Work.—Geologic field work usually involves: (1) the study and interpretation of rocks, topographic forms, etc.; (2) the determination of the location of points or outcrops where observations are made; and (3) the plotting of these points or outcrops, and of other geologic data, on a map. The interpretation of rock structures and topographic forms we have already discussed at some length in the foregoing pages of this book, but there remain a few facts of general significance to be mentioned in the present chapter. The nature and use of instruments for geologic surveying will be discussed in Chapters XV and XVI. Airplane mapping is described in Chapter XVII.

STUDY OF OUTCROPS

307. Most Likely Places for Exposures.—The best places in which to look for exposures of bedrock are precipices, hilltops, steep hillsides, stream beds, and coasts, along railroads and roads, and in artificial excavations. Cuts in unconsolidated materials

may be sought along the banks of streams, along coasts, roads, and railroads, and in artificial excavations.

308. Examination of Outcrops.—The beginner is often at a loss as to the best manner of attacking a rock exposure. The writer has always advised his students to start by quickly walking round and over an outcrop which they have just found, before attempting to take any notes. In this way they soon gain a general idea of the rocks and structures which are exposed, and they are better able to decide what parts of the rock should be examined in more detail. Unless this plan is followed much time may be wasted. For instance, one may spend several minutes trying to determine the attitude of a sedimentary rock where its bedding is obscure, whereas further search on the same outcrop may reveal a place at which the bedding is distinct and easily studied. This method of rapid reconnaissance followed by detailed examination is recommended, on a larger scale, for the geologic investigation of extensive areas (326).

309. Discrimination between Boulders and Outcrops.—Care should always be taken not to mistake large, half-buried boulders, such as are common in glaciated districts, for outcrops of true bedrock. A safe rule to follow is, never accept as bedrock anything that is small enough to be a boulder, but this is unsatisfactory because there are many places in which large exposures are very scarce and where the small ones are exceedingly useful. It is better to spend some time in studying the questionable rock and correlating it with its surroundings. Bedding, joint systems, cleavage, schistosity, etc., are apt to have similar, though not necessarily exactly the same, character and arrangement in adjoining outcrops of bedrock, whereas in scattered boulders such structures are usually very variable, especially in trend.

310. Tracing Outcrops.—The mapping of veins, dikes, and stratified rocks is best accomplished if these rocks are continuously exposed so that they may be easily followed. However, continuous exposure for long distances is rare. It may be observed sometimes where there is great dissimilarity in the resistance of the rocks to erosion, the stronger ones then con-

stituting scarps (Fig. 327) or ridges (Fig. 328), and the weaker ones the adjacent soil-covered slopes or lowlands. The thicker the alternating hard and soft members of a series of sediments are, the more pronounced the ridges on the harder layers are likely to be. If the resistant beds are relatively thin, or if the difference in resistance of the several members of a series is not marked, there is more chance that the harder rocks will be locally covered with soil.

Where the edge of a bed, dike, or vein, is more extensively covered than it is exposed, the following or *walking* of the outcrop may be very difficult. Under these circumstances the approximate position of the concealed rock may often be indicated by a particular variety of soil, or by a characteristic type of vegetation, or by the topography. As an example of the last, hard beds in a nearly horizontal sedimentary formation may be indicated on the hillsides by topographic benches which are continuous with occasional outcrops of the bench-forming rock. Mapping of distinct belts characterized by certain species of vegetation not only may assist in charting the distribution of rock bodies but also may roughly reveal the direction and amount of dip of sedimentary formations. Another aid in tracing concealed rocks is the occurrence, in some districts, of moist ground or a line of springs along the contact of a lower less pervious rock and an upper more pervious rock (see also Art. 312).

The *walking* of beds is often an essential procedure in the mapping of low-dipping strata (411, ¶ 4; 415).

311. Importance of Contacts.—Contacts (14) are of the utmost importance in the construction of geologic maps, sections, and diagrams, as well as in the interpretation of underground structure and geologic history. This cannot be too strongly impressed. It is, therefore, obligatory upon the geologist: (1) to find the position of contacts in the field, and (2) to map them with as much accuracy as circumstances will allow. These *circumstances* are factors such as the time available and the degree to which a boundary line may be concealed under superficial *débris*.

312. Discrimination between Igneous Contacts, Unconformities, and Faults.—Sometimes the relations between two adjoin-

ing rock bodies are so obscure that difficulty is experienced in deciding whether their mutual contact is an igneous contact, an unconformity, or a fault. Two specific instances should be noted, in which one of the three possibilities may be discounted: (1) if both bodies are sedimentary, their contact cannot be igneous; and, (2) if both bodies are intrusive, they cannot meet in a surface of unconformity. In all other cases, including that of an intrusive mass against an extrusive rock, the mutual surface may be any one of the three types of contact. The problem must be approached with a clear understanding of what features are to be looked for in association with faults, unconformities, and igneous contacts, and then the region must be diligently searched for whatever evidence it has to reveal. Several phenomena that may be misinterpreted are mentioned below.

1. The trend of the boundary line cannot be accepted as a safe criterion. Igneous contacts, faults, and unconformities, may all outcrop in lines that are straight, undulating, or very irregular, although, generally speaking, igneous contact lines, particularly of subjacent bodies, are more commonly irregular, and fault lines and lines of unconformity are more often broadly undulating.

2. Apophyses of an intrusive may extend into the country rock, but sometimes they are conspicuous for their absence. In any event one should look for them. In the case of unconformities, the younger rock may have filled fissures or chasms in the old land surface. Such a filling, if of sedimentary materials, can hardly be misinterpreted; but one of lava might be mistaken for an apophysis, especially if the flow were overlain by lithified strata (145). As for faults, there can be no finger-like projections of the rock of one block into the other unless the displacement occurred close to a preëxisting igneous contact or unconformity (147).

3. Angular or subangular fragments of country rock may be contained in an eruptive body near the contact. Likewise angular, subangular, or rounded fragments of the rocks below an unconformity may constitute the lower layers of the overlying formation. However, an intrusive breccia has an igneous matrix,

whereas the matrix of a basal conglomerate is sedimentary. For the special case of sills, see Art. 145. Contrasted with intrusive breccias and basal conglomerates, fault breccia zones are relatively narrow and they are composed of pieces of the rocks from both walls (223).

4. An intruded country rock may reveal evidences of more or less contact metamorphism, both by heat and by pneumatolysis, and these effects are usually proportional in their intensity and kind to their distance from the contact (131, 135). Also, the eruptive may exhibit textural and other variations which are dependent in character upon the distance from the contact (123). Such conditions are not to be expected in association with unconformities. Faults sometimes serve as conduits for volatile substances rising from underlying magmatic bodies, and these gases and vapors may considerably alter the wall rocks on both sides, so that effects in some degree resembling those of contact metamorphism may be produced.

313. Location of Contacts Buried under a Soil Mantle.—A contact hidden under surface debris may be located by observing the distribution of rock chips and fragments in the soil derived from the underlying bedrock. Precision depends upon: (1) the inclination of the ground; (2) the thickness of the soil cover; (3) climatic conditions; (4) the trend of the contact line; and (5) the regularity of the contact. The steeper the slope of the ground and the thicker the mantle rock, the farther the loose materials may slide from their source before they work up to the surface where they may be seen (Figs. 252, 355). If the inclination is less than 25° , sliding is usually not great enough to occasion serious error in fixing the location of the contact. Climate has various effects. Of these as important a one as any is the action of frost in facilitating soil creep. When a straight contact line runs directly up a slope, its location may be accurately determined by the soil method. If it is either oblique to the slope or parallel to the contours, allowance must be made for factors (1) and (2), above noted. Its actual position is higher than is indicated in the mantle rock. Bends and angles of an irregular

contact line are exaggerated by the distribution of rock fragments in the soil. This method proves useful in locating any kind of concealed contact, provided the rocks on either side are unlike one another.




FIG. 355.—Ideal profile sections to illustrate the downhill migration of rock waste in the soil. Shaded, bedrock; blank, soil. Rock fragments reach the surface of the soil (*c* to *b*) a shorter distance downhill where the slope is moderate (*ab* in A) than where the slope is steep (*ab* in B); and, on a given slope, they reach the surface a shorter distance downhill where the soil is thin (*ab* in B) than where it is thick (*a'b'* in B). (Cf. Fig. 252.)

314. Sinuous Contacts in Low-dipping Beds.—In regions where the strata have low dips, and the topographic relief is low, pronounced swings in a contact may indicate anticlinal structure if an older formation is partly included between or within a younger formation, and synclinal structure if the reverse is true (Fig. 356). The swings must not be confused with the normal downdip bending or looping of the contacts (and outcrop belts) in valleys (174).

315. Location of Eruptive Contacts.—The line at which an igneous rock touches its country rock on the surface of an outcrop may be hard to distinguish, even though exposed, either because the two rocks are of like color and texture, or because

surface staining due to weathering has unpaired an original contrast in hue. There is only one thing to do in this case, and that is to scrutinize the rock surface very carefully. Form the habit of examining one rock inch by inch in a direction toward the other, and then you are not likely to miss the dividing line, provided it is visible. Error is most apt to be made




FIG. 356.—Map of a contact between two conformable formations. The dip is about 50 ft to the mile southeastward. At *a*, a shallow synclinal depression is suggested, and at *b*, an antichinal uplift. Why is this so?

where, by local scaling or exfoliation, relatively fresh surfaces of rock are laid bare next to older surfaces that look different because they have been exposed for a much longer time. Do not let some crack or the edge of a conspicuous stain mislead you into calling this the contact, and, on the other hand, do not be too prone to conclude that a contact is blended and that for this reason no line is present (121).

Whether or not the boundaries of an igneous body are concealed, they may often be located and traced by the phenomena of contact zones. Thus, if an igneous rock displays a regular diminution in the size of its grains in a definite direction, its contact is likely to be found in this direction. In Art. 219 is explained the value of flow structures and fracture systems for this purpose. Great abundance of inclusions in an igneous rock may signify proximity to the contact, especially to the roof of a large intrusive body (batholith, etc.). When once the geologist has made out the characteristic variations of the contact zones in a given region, he may use this knowledge in seeking the same contact where exposures are poor or infrequent. By the degree of baking, discoloration, or mineralization observed on outcrops of the country rock, he may be able to tell roughly how far he is from the eruptive body (152).

316. Obscure Bedding.—There is hardly need to say that sedimentary rocks should always be examined for their bedding, for if this cannot be found, the attitude of the strata and other important facts cannot be determined. Stratification may be difficult to see on a rock exposure either because the materials were accumulated under very uniform conditions (65), or because the rock was metamorphosed (230, 231), or because of surface discoloration. Although, occasionally, sediments are devoid of bedding, perfect uniformity is of rare occurrence. The rock which at first sight appears to be structureless is almost sure to reveal some degree of lamination upon careful scrutiny. When studying an outcrop which is seemingly of even texture, look for sandy streaks in conglomerates, for pebbly or fine sandy streaks in sandstones, for very fine sandy laminae in mudstones, and for impure streaks in limestones and chemical deposits.

317. Determination of Strike and Dip of Strata.—Wherever strata are exposed, the attitude of their bedding should be found (316). In general, we may say that dips of two or three degrees and less are more conveniently recorded in feet of vertical descent per mile of distance than in degrees (Appendices XII–XV). Such dips are difficult to read by clinometer. They are deter-

mined by finding the elevation, above sea level or above some assumed datum, of scattered points on some chosen *key horizon*, such as the top or bottom of a particular bed. In the field an effort is made to trace or *walk out* the key bed (310). Sometimes it may disappear, either because it has been eroded away, or because it dips below the surface. If it has been removed by erosion, elevations may be determined on some other bed, stratigraphically lower, and to these elevations may be added the stratigraphic interval between this bed and the key horizon in order to obtain elevations on the latter. If the key bed dips below the surface of the ground, its position may be ascertained from the records of borings deep enough to reach it (Art. 458), or the stratigraphic interval between it and some higher bed, which *can* be mapped, may be subtracted from elevations on this higher bed to obtain elevations on the key horizon.

Ordinarily, where dips are very low, as above described, field mapping is accomplished principally by either the barometric method (382-399) or the plane table method (400-414; 415), and the geologic structure is represented by a contour map (456). Aerial photographic maps are also used for this kind of work (Arts. 423, 424).

If dips are greater than two or three degrees, they are usually read by clinometer (334). The actual process of taking strike and dip would be simple enough if it were not for the fact that bedding surfaces are more or less irregular and rarely conform with the surfaces of outcrops. To avoid error the compass should never be placed against the rock. Always stand off a few feet and endeavor to gain a correct notion of the strike and dip by a single observation for a length of several feet of outcrop rather than for only a few inches. Where dipping beds are exposed on a horizontal rock surface, the trend of their edges is their strike; but if they are exposed on an inclined rock surface, as they are 99 times out of a 100, the geologist must appeal to his geometric imagination. The same statement holds for dip, since outcrop surfaces exactly perpendicular to strike are rare. Four possible cases are illustrated in Fig. 357. For convenience the structure is shown in diagrams of rectangular blocks, but it

must be remembered that these are unavoidably much more regular than natural outcrops. A, B, and C, in Fig. 357, represent three instances in which the dip might be taken as 30° S. and the strike as E.-W. if only the face *abcd* were seen; but an examination of another surface, *bcfe*, proves that Fig. 357, A, alone answers to this suggestion. In Fig. 357, B, the eastward inclination of the strata on face *bcfe* indicates that the real dip (steepest inclination) is southeastward and the real strike is northeastward; and in Fig. 357, C, the westward inclination of the beds as seen on face *bcfe* shows that the real dip must




FIG. 357.—Relations of dip and strike of bedding to outcrop surfaces.

be southwestward and the real strike northwestward. Figure 357, D, is another case which may arise. It will be noted in all these examples that observation on at least two outcrop surfaces, not parallel to one another, and preferably as nearly perpendicular to one another as possible, is requisite in order to arrive at a correct inference as to strike and dip. The chief aim is to ascertain the position of the plane of stratification. Points *x*, *y*, and *z*, in each diagram, determine this plane. This follows from Plane Geometry. If, on a curved or highly irregular outcrop surface, pebbles be placed at three points, not in the same straight line, on the outcropping edge of a given layer, these pebbles may help to visualize the plane of the bedding.

On a small scale this illustrates the principle involved in dip determinations made by geometric analysis of elevations found by careful methods of field surveying on three separate outcrops of the same bed. For example, suppose that a given stratum is exposed at *A*, *B*, and *C*, these being at the apices of a triangle and being so spaced that *A*, is 500 ft. from *B*, and *C* is 400 ft. from both *A* and *B*. The elevations on top of the same bed at *A*, *B*, and *C*, are determined to be 200, 210, and 230 ft. respectively, above sea level. By the solution of triangles, the true dip may be obtained. It will lie in a direction from *C* toward a point between *A* and *B*, and nearer to *A*. This method of finding dip is more accurate than the measurement of local dips by clinometer, where dips are very low. It eliminates the minor variations, common in folded beds, and especially it reduces the errors which may result from local settling (488, 319 321). We cannot too strongly warn the field geologist to guard against mistaking original dip (73), cross-bedding (319), and the results of soil creep and other mass movements (3, 321), for dips caused by actual secondary deformation of deep-seated origin.

318. Degree of Accuracy in Taking Strike and Dip of Strata.—The accuracy with which dip and strike should be read depends upon the nature of the problem in hand and upon the character of the folding. In regions where dips are low, averaging, let us say, 5° or 6°, fold axes are apt to be irregular in trend. The strata are warped and strikes vary notably. In such cases dips should be read with an error of less than 1°, and strikes should be taken with care. On the other hand, where high dips point to intense deformation, an error of two or three degrees in dip or strike is unimportant, for the actual variations in the beds themselves amount to this or even more within short distances. In this case pains should be taken to obtain correct averages, rather than to make absolutely accurate local readings.

319. Cross-bedding.—Several types of cross-bedding have been described in Art. 84. In studying outcrops of strata with the purpose of determining the dip, great care must be exercised lest cross-bedding be mistaken for true bedding. This confusion is less apt to occur in steeply dipping strata than in gently

dipping strata, and the relative error in the resulting structural interpretation is generally less in the former than in the latter. One should remember that the transverse laminæ in a cross-bedded stratum may be several, or even many, feet long, so that sometimes an outcrop may expose nothing but these cross laminæ (Fig. 358). In regions of low-dipping beds, the wisest course is to ascertain the structure, not by attempting to read strikes and dips at obscure or unreliable outcrops, but by deter-




FIG. 358.—Vertical section of a series of irregularly bedded, nearly horizontal sandstones and shales. The portion (lightly drawn) above *ab* has been eroded away. The black represents soil. If only the rocks between *ab* and the dashed line *c* were exposed, the cross-bedding might be mistaken for true bedding.

mining the elevations at well distributed points on some chosen bed (key horizon) and then drawing structure contours in reference to these established points (317, 456). This method of representing structure by contours also eliminates, to a considerable degree, errors which may be occasioned by such causes as are described in Arts. 320 and 321.

320. Bevelling of Outcrops.—In the erosion of some kinds of rock, especially of rather soft sandstones, the upper portion of



FIG. 359.—Vertical sections of thick sandstone beds (stippled), which have been bevelled at their outcrops by erosion. The true attitude of the bed in each figure is shown by *a*; a possible erroneous idea of the dip, due to the bevelling, is indicated by *b*. The black is soil.

the outcrop may be bevelled off so that the exact position of the upper surface of the bed is rather hard to determine (Fig. 359). This is a source of error which must be considered particularly in districts where sandstones are the only satisfactory beds to

use in mapping and where mapping is done by contouring a key horizon (456).

321. Settling of Beds.—Superficial dips, which have no relation to the true structural dips of a region, are very common effects of uneven sagging and settling of sedimentary rocks. This settling is usually manifested in the exposed harder rocks (Fig. 360). It may be caused by the gradual washing away of an underlying clay or silt, or by the removal of an underlying soluble material such as salt or limestone. On hillsides, a sagging of the beds toward the valley is often seen in regions of moderate folding. Every precaution should be taken lest these false dips




FIG. 360.—Cross section of strata dipping toward the right, *a*. Observations at the outcrop of the limestone bed might lead one to suppose that the dip is to the left, *b*, where sagging of the outcrop has been caused by erosion. The black is soil. (See also Fig. 252).

be misinterpreted for true dips. Where the object is to obtain elevations on a key horizon (317), possible errors, which may be occasioned by settling, may be reduced by eliminating the more doubtful outcrops, or by estimating and allowing for the probable amount of settling.

322. Field Correlation.—In order to obtain satisfactory results in field work, correct correlation of the outcropping rocks is essential. The reader can easily understand that very serious errors may be caused by mistaking one rock for another, which may *look* like the first, but actually may be quite different. Especially where dips are low and where, therefore, structure is mapped by contours on a key horizon, a mistake in the correlation of the strata may introduce errors in the plotted structure. The geologist should take advantage of any features which may help him to recognize and distinguish one rock from another.

Rocks are correlated principally by reference to: (1) their lithologic character; (2) their topographic expression (footnote, page 364); (3) the nature of the vegetation which grows upon their derived soils; (4) their stratigraphic sequence; and (5) their fossil contents.

1. In the first place, a rock is recognized by its classification as igneous, sedimentary, or metamorphic. It may further be marked by a conspicuous color; by its chemical composition; by its texture; by its lithologic structure, such as cleavage, lamination, etc.; by containing concretions recognizable by their form; or, perhaps, by yielding water, oil, or gas at its outcrop. The formations above and below a surface of regional unconformity may sometimes be distinguished by the different degrees of metamorphism which they exhibit.

Features of the kind just cited are helpful, but not final, in correlation, for occasionally—referring to sedimentary rocks—two strata may so closely resemble one another that the geologist may *jump* the beds in crossing an area where there are no outcrops, that is, he may map one bed thinking he is mapping the other. On the other hand, the characteristics of a rock may so far change, laterally along the bedding (91), that two separate outcrops of one and the same bed may perhaps be entirely unlike, even though they are not far apart.

2. Topographic expression may be of great assistance in correlation, since, if a rock keeps its general nature, it will usually affect the topography in the same way wherever it is exposed to erosion. Thus, a hard limestone is likely to crop out in distinct ledges, or, at least, it will probably cause a bench or a ridge, whereas a weaker rock is likely to make valleys.

3. The vegetation is apt to be different according as the soil may be derived from an underlying shale, limestone, sandstone, or other rock. The particular flora characteristic of a certain rock must be learned for each new locality, but, once known, it may be serviceable in problems of correlation.

In the last two cases (§§ 2, 3), the geologist must watch for possible variations in the nature of the rock, for lithologic

variations are bound to be more or less definitely reflected by changes in the topographic expression and the type of vegetation.

4. Strata may be correlated in reference to their stratigraphic sequence. In Fig. 151, page 199, the similar order of like beds—conglomerate, sandstone, and shale, from below upward—suggests that these three beds are the same at the three outcrops. If, at the three localities, the conglomerate were found to rest unconformably upon an older rock formation, this relation would still further establish the correlation of the three beds.

5. Some fossil species, or fossil genera, are found through a considerable stratigraphic range, whereas others are much more limited in their distribution across the bedding. A species which is characteristic of a definite geologic horizon, and occurs only in beds at that horizon, is called an *index fossil*. Such a fossil species may be of great value in the correlation not only of different exposed parts of the bed in which it is found, but also of overlying and underlying strata which may be referred to this bed. Sometimes not one fossil, but a group of fossils, is characteristic of a stratum or series. By way of example, in Fig. 151, the outcrops of sandstone might be recognized as belonging to the same bed because of containing the same fossil species or group of fossil species at *a*, *b*, and *c*.

Like the other criteria for correlation, fossils are not always dependable. Judgment must be exercised in their use. The same stratum, which may be rich in organic remains in some places, may have few or none in other places. Not uncommonly several beds in a formation hold the same fossil species. This causes no trouble in the correlation of the formation, but it may lead to mistakes in the identification of a particular bed which has been chosen as a key horizon for mapping.

Another source of error, applying rather to regional than to local correlation, is lateral change in fossil floras and faunas. This important feature is too often overlooked. One has only to compare the conditions and types of modern life, as they vary from place to place, to appreciate the fact that lateral variations

are to be expected in fossils within a given bed or formation of the same geologic age. On account of some original barrier, very different fossil groups may be found in beds of the same age at localities not far distant from one another.

Again, with the transgression or regression of sedimentary deposits (78), floras and faunas may have been forced to migrate along with their shifting environment. The result is that we may have a transgression of a fossil flora or fauna diagonally across a formation or group of formations, much as a basal sandstone may diagonally cross successively higher and younger formations. For this reason we may sometimes find the same fossils in beds of different age at more or less widely separated localities.¹

323. Attitude of Contorted Strata.

—A word of caution may be given in reference to taking the dip and strike of contorted strata. Figure 361 is a local vertical section of two layers in




FIG. 361.—Section of two layers in a contorted schist. The section is drawn looking north.

a series deformed by minor similar folding. The small folds are from 1 to 5 ft. from crest to trough and the dips of their limbs are approximately 48° W., *aa*, or 82° E., *bb*. Yet the general inclination of the strata is neither 48° W. nor 82° E. It is indicated by the double-headed arrow and is about 33° W. Evidently dips which are measured on the limbs of minor folds cannot be used for the major structure. The same is true, but to a less degree, of strikes. In dealing with highly crumpled sediments the geologist must be careful to discriminate between principal and subordinate folds, and he must not record angles for the minor folding, which he intends to use in sections and maps of the major structure.

324. Attitude of Eruptive Contacts.—The position of an igneous body with reference to horizontality and to structure

¹ For a more lengthy discussion of this subject, the reader is referred to Bibliog., GRABAU, A., Chapter XXXII.

in the adjacent rocks can be ascertained by studying the attitudes of its contacts. The dip and strike of flows and of uniform dikes and sills may be obtained by clinometer and compass just as in the case of strata (317). It is important to remember, however, that even the straightest intrusive sheets, as




FIG 362 --Apparent offset in two outcrops of a dike of which the strike, where observed is parallel to the front edge of the block V-pattern dike rock in section, stippling alluvium

seen in cross section (vertical, horizontal, or inclined), not uncommonly have jogs or elbow-bends, the effect of which, if the bends are all on the same side, is like that of transverse faults with the offset always in the same direction. One part of the sheet may be far out of line with another part (Figs. 362, 363).

In obtaining the trend or the inclination of very irregular contacts, like those which are typical of many batholiths, chono-




FIG 363 --Explanation of the apparent offset shown in Fig 362 the soil having been removed and the top of the block being represented as a horizontal plane

liths, etc., the degree of precision necessary must be determined by the geologist. Just how much he may generalize the line depends largely upon the scale of the map on which he is plotting. For instance, he may disregard local turns and angles 150 or 200 ft. deep if his map is on a scale of 1 mile to an inch. Nevertheless, observe that this statement does not signify that the details of such a contact are not to be studied. Not only should they be carefully examined, but also their shape and other characters should be illustrated by large scale plans and sketches made in the field.

After a contact has been located for a considerable distance and its line of outcrop plotted on a topographic map, its general attitude may often be made out from an inspection of this map, as explained in Art. 475.

Attention is here called to Art. 152, where mention is made of the value of field studies of flow structure and of fracture systems in and adjoining intrusive igneous bodies.

SCHEDULE FOR FIELD OBSERVATIONS

325. General Data to Be Observed and Recorded.—Many of those who are engaged in geologic work, particularly in the earlier years of their training, find that a table of the facts which should be looked for in the field is often very helpful. Excellent schedules may be found in Hayes' "Handbook."¹ They refer to the description and interpretation of land forms, to petrology, geologic structure, glaciers, and glacial deposits, ores, building stones, and other materials of economic worth. For general purposes, however, the following outline may be found useful.

SCHEDULE FOR GEOLOGIC SURVEYING

TOPOGRAPHY.—Note: Relief; shape and arrangement of uplands and lowlands; relations of topographic forms to rock distribution; destructional or constructional origin; evidences for agents and processes of erosion and for stage of development in erosion cycles; effects upon human activities.

Rocks.—1. *For any outcrop*, note: Color, luster, grain, and irregularities of surface; shape, size, and arrangement; distribution with relation to topographic forms.

2. *For any rock*, note: Its texture, mineral composition, name, kind and degree of weathering, and the color of its fresh fracture; relations to other rocks as regards structure and age.

(a) *If an igneous rock*, note further: Mode of occurrence; attitude (for dikes, sills, etc.); fracture systems; lithologic structures (flow structure, schliers, primary gneissic structure, segregations, etc.); contact relations; contact metamorphism; and, inclusions (kind, shape, size, arrangement, and source).

(b) *If a sedimentary rock*, note further: Mode of occurrence (bed, lens, elastic pipe, elastic dike); attitude; breadth of outcrop; degree of consolidation; composition, shape, size, and arrangement of constituents in fragmental rocks; lithologic structures (cross-bedding, ripple-mark, mud

¹ Bibliog., HAYES, C. W.

cracks, local unconformity, contemporaneous deformation, etc.); kinds, attitude, distribution, and abundance of fossils; and stratigraphic sequence.

(c) *If a metamorphic rock*, note further: Kind and degree of metamorphism; any preserved original structures (see igneous and sedimentary rocks, above); secondary lithologic structures (slaty cleavage, plane schistosity, linear schistosity, gneissic structure, etc.); attitude of structure; relations of original structures to secondary structures; classification of original rock before metamorphism.

(d) *If a vein*, note further: Its shape, size, attitude, and relations to the wall rock and to the topography; species, arrangement, and relative amount of mineral constituents.

STRUCTURES.—1. *For unconformities*, note: Kind, extent, and nature of surface; relations of the two unconformable formations; kind and source of basal sediments of the younger formation; age relations.

2. *For folds*, note: Shape; dimensions; classification; major or minor; parallel or similar; with horizontal or pitching axis; relations to topography; relations to rocks; relations of minor to major folds; age relations.

3. *For faults*, note: Extent, attitude, shape, classification as far as can be observed; slickensides, gouge, brecciation, drag, etc.; exposed rocks on each side of fault line; amount and direction of visible displacement; relations to other structures (bedding, folds, joints, etc.); relations to topography; age relations.

4. *For joints*, note: Extent, attitude, shape, spacing, regularity, classification; rocks affected; relations to other structures; relation to topography; age relations.

The foregoing outline will probably not fit all cases, for geologic relations are almost infinite in their variety. The best rule is, search for anything and everything of geologic interest and record all you see. Do not overlook surficial deposits merely because they are unconsolidated. All earth features are but parts of a whole, and you can never tell when seemingly trivial things are going to furnish decisive evidence for the solution of important problems.

GENERAL SUGGESTIONS

326. Beginning a Field Problem.—A few words may be added here in reference to beginning field problems. Some facts concerning the equipment and management of large parties and professional surveys may be found in Hayes' "Handbook."¹ Ele-

¹ *Bibliog.*, HAYES, C. W.

mentary studies, let us say undergraduate field work, should be approached without any previous knowledge of the locality. In this way the student can be trained to observe on his own initiative. More advanced work, of postgraduate grade, and all professional work, should be preceded by reference to the available geologic literature on the region. It is important to learn all that is possible of the results of earlier investigations before going into the field. The geologist should know where to look for the writings of others. For this purpose the "Bibliography of North American Geology," published by the United States Geological Survey, is of inestimable service.¹ Other valuable lists of books and shorter papers are usually given as bibliographies accompanying such publications.

In the search for information on an area to be examined in the field, one should give consideration to the following points:

1. The name, character and geologic age of each of the formations exposed.
2. The names and geologic ages of formations which may underlie the exposed formations.
3. The structural and genetic relationships of these formations.
4. The average or approximate thicknesses of sedimentary formations.
5. The normal or average regional dip of such formations.
6. The amount and direction of any thinning or thickening which may have been recognized in sedimentary formations.
7. The topographic and physiographic conditions in the region, and the relations between these conditions and the various formations.

Passing over the details of equipment, preparation of the notebook, choice of hotel or camping site, etc., we are brought face to face with the actual field work. What is the best thing to do first? To plunge right in at the outset and make a careful traverse is a rather blind proceeding. It has to be done some-

¹ This Bibliography comprises the following Bulletins of the U. S. Geological Survey; 746, 747, 823, 834, 858, 869, 892. See also the Annotated Bibliography of Economic Geology, published by Economic Geology Publishing Company since 1929.

times, but only when time is very short or when the work is to be restricted to a definite route. Ordinarily several hours or days, depending upon the magnitude of the problem, should be spent in going over the area rapidly, for by such a reconnaissance one can learn enough about the frequency of exposures and about the nature of the rocks and probable underground structure to enable one to plan a systematic mode of carrying out and completing the entire investigation. Several days may be saved in this way. After the preliminary reconnaissance the geologist may continue with the more detailed surveying according to one or another of the methods outlined in Chapters XVI and XVII.

327. Collecting and Trimming Specimens.—In these days of sedulous laboratory study comparatively little can be learned of the true nature of rocks in the field. Hence the necessity of collecting specimens. Judgment must be exercised in doing this. Do not bring in chips from the surface of a weathered exposure. Get as fresh a fragment as possible, for the classification of a rock cannot always be made from the products of its decomposition. Representative samples, typical of the rock, should be selected. If time is pressing, irregular fragments may be collected. Otherwise the specimens should be trimmed to a flat rectangular shape, either 4 by 5 by 1 in. or 3 by 4 by 1 in. They are then called *hand specimens*. The width and length should be measured with considerable exactitude, but the thickness may be somewhat variable.

In trimming use the *flat* end of the hammer head. Break the fragment down until its dimensions are half an inch or so greater than they are to be in the completed specimen. Finish by striking it on its edges, not on its faces (Fig. 364). In this way chips fly off sideways, and from both faces at the same time, the fragment is trimmed to a thin straight edge, and the strain of the impact is taken up by the width or length of the specimen instead of by its thickness.

If a rock is to be thoroughly studied it must be examined by the petrographic microscope and must be chemically analyzed. For the microscope thin sections have to be cut. Therefore, in order to avoid sawing into the hand specimens, a geologist usually

takes, in addition to these, a small chip of every rock that he thinks will need to be sectioned. Of any rock that he considers deserving of chemical analysis he collects several pounds; but chemical analysis is seldom undertaken, unless with some special object, on account of the expense.

Hand specimens and chips *must* be wrapped in paper bags to prevent their scratching and bruising one another. A badly bruised specimen is almost worthless. A label bearing the name, number, and locality of each specimen should be wrapped up with it. Do not mark the specimen itself. *Labelling must be done at the time of collection.*

328. Taking Photographs.—In many respects photographs are the most valuable means of geologic illustration. Miniature cameras, especially the better grades, are excellent for recording many features that might be overlooked, or might be slighted, in the field notes. Original photographs can be enlarged and used to illustrate finished reports. For distant photography, the best results can be obtained only by employing special films and ray filters. Stereoscopic and panoramic views are very much worth while. Kodachrome may be used to record the colors of rocks, soils, and vegetation.

Do not take a picture merely because it shows something within your area of investigation. Choose only such views as have a definite bearing on the subject in hand. It is best to photograph very irregular rock surfaces on a dull day, for the shadows made by projecting edges and corners on sunny days appear on the print as black patches. Not infrequently contact lines and other rock structures are exposed on granular, pitted, ribbed, or scratched surfaces. If one's aim is to bring out the grain, ribs, etc., take the picture on a bright day when the sun is rather low so that these minor irregularities will cast shadows; but if the structures are to be emphasized, the photograph should be made on a cloudy day.



FIG. 304.
Hammer
head, *b*,
and rock
specimen,
a, in proper
position for
trimming.

In spite of the fact that the subject of the picture should be of geologic interest, the view should be taken in such a way as to secure an artistic balance. Experience has demonstrated that the balance is best attained in the following manner: Imagine that the field of the picture is divided by two vertical lines and two horizontal lines into nine equal spaces (Fig. 365). These lines, and particularly the intersections of these lines, are the strong parts of a picture. One should aim, therefore, to place the camera in a position such that: (1) the prominent upright lines or objects (trees, edges of cliffs, etc.) in the view will fall along the vertical division lines (*aa*, *bb*, Fig. 365); (2) the prominent horizontal lines or objects (horizon line, etc.) will come on the horizontal division lines (*cc*, *dd*, Fig. 365); and (3) the principal centers of interest or the conspicuous centers of




FIG. 365.—Strong lines and points in a picture.

light or of shadow will be at the intersections of the division lines. It is not necessary that there should be features in the picture coinciding with all the division lines and their intersections, but merely that those important objects which are present should be arranged as above described.

329. How Much Shall Be Undertaken in the Field?—“How much

shall be undertaken in the field?” is a question which deserves consideration. An inexperienced geologist is often tempted to do little more than tramp over the ground and record what he sees at the moment, leaving the rest to be done in the office after the field season closes. This is very poor policy. When this man, two or three weeks or months later, sits down to prepare his geologic maps and reason out the geologic structure, he will soon discover that he cannot remember just where he saw this thing or just how that one looked. Indeed, either he may have to go back to the district next field season or he may have to write a report that is lacking in certain details, some of which, perhaps, are very important.

The moral of this is that you should accomplish in the field all that is possible. Make your geologic maps and sections, and draw your sketches, plans, and block diagrams. They do not have to be finished for publication. They may be done—in fact, they should be done in the field—in pencil, black or colored. You will find that this preliminary drawing will be of the greatest assistance in showing you what you have omitted and what you should reëxamine, if possible, before you leave the region. Write a summary of your notes every night, or at least at the end of every week. This will stimulate new ideas and reveal deficiencies or errors of interpretation which may need attention before the completion of the work.

330. Degree of Accuracy in Field Work.—Brief mention has been made of the question of degree of accuracy to be sought in field work (305, 318, 324). This is an important matter for consideration in advance of, and during, most kinds of field exploration. It also applies to the preparation of the final maps. Rules worth remembering are: (1) For any map no greater degree of precision is desirable or necessary than is commensurate with the scale of the map; and (2) For any map no set of data need be charted in the field by a method more precise than the methods applied in charting the other sets of data for this map.

Possibly these statements are obscure. To be specific, where low-dipping formations are to be contoured (289) with a contour interval of, let us say, 50 ft., application of a field method of mapping elevations to a final limiting error of 1 or 2 ft. would be waste of time; An error of as much as 10 ft. would not be serious. And, similarly, for such a map, too great exactitude in horizontal location of points used for contouring would not be warranted. The whole endeavor should be to see that vertical and horizontal controls, the location of geologic features, and the scale of the final maps and sections are all reasonably related to one another in degree of precision or, to express it in another way, in permissible limit of error.

These remarks are made here so that they may be kept in mind in reading the chapters that follow (Arts. 363, 365, 366, 397, 398, 399, 409, 415, 417).

CHAPTER XV

GEOLOGIC SURVEYING

PART II. INSTRUMENTS AND OTHER EQUIPMENT USED IN GEOLOGIC FIELD MAPPING

331. The Compass and Clinometer. -The compass, with its clinometer attachment, is indispensable for geologic field work. The *Gurley* and *Brunton* compasses are the types most commonly employed.

The *Gurley compass* is provided with a square metal base, a pendulum (swinging) clinometer, folding open sights, and a rectangular spirit level. The edges of the base are bevelled, two being graduated in inches, and two in degrees of arc for use as a protractor. With the sights turned up, this instrument may serve as a short open sight alidade (347). The pendulum clinometer is excellent for reading dips, but is not always satisfactory for determining slopes.

The *Brunton compass* is comprised of an ordinary compass, folding open sights, a mirror, and a rectangular spirit level clinometer. It cannot be employed as a protractor and it is unsatisfactory as an open sight alidade. The clinometer, which is operated by a short arm on the back of the compass box, serves better for taking slope angles than for taking dips.

332. Use of the Compass.—Direction and strike (12) are measured by means of the compass. Concerning the use of this instrument, there are certain rules and facts with which the beginner must familiarize himself at the outset.

1. Degrees for direction and strike are read on the *outer* circular dial.

2. In taking direction or strike, hold the compass so that its face is horizontal and its "length," i.e., the line between the

letters, "N" and "S," on the dial, lies in the direction of the strike (Fig. 366, A, arrow).

3. When the needle is at rest it points in a constant direction for any given locality. Hence readings should be made from one or the other end of the needle, and not from the letters "N," "E," "S," or "W," printed on the dial. Thus, in Fig. 366, A, the compass length, or line between the letters "N" and "S," lies in the NW. and SE. quadrants and thus indicates a NW.-SE.




FIG. 366.-- Diagrams to illustrate the use of the compass. Dotted line, "length of compass"; dashed line, true north-south line.¹

direction. This is suggested by the position of the needle between "N" and "W," and between "S" and "E."

4. Strikes and directions are to be recorded exactly as one reads the compass. If the instrument is in the position shown in Fig. 366, A, and one is looking in the direction of the arrow, the north end of the needle, being the nearest end to this line of sight, should be noted first. Next should appear the angle or number of degrees between the needle and the required direction, and finally is written the direction in which this angle was measured *from the needle end*. If the angle is 30° in this case, the strike is N. 30° W.

5. All readings are made from north and south, or sometimes from north only, but never from east or west. Thus, the strike

¹ Note that the letters "E" and "W" are reversed so that the needle will lie between the letters which designate the quadrant in which the bearing is taken.

mentioned in the last paragraph would not be recorded W. 60° N. A direction 30° east of south may be written S. 30° E. or N. 150° E., but not E. 60° S.

6. A bearing made as just described is spoken of as *magnetic*. There is nearly always a correction which has to be made for this compass reading because the needle seldom points to the *true north*. The compass north (*magnetic north*) may lie a variable number of degrees to the east or west of the true north. East of the zero isogonic line (Plate I) magnetic north is west of true north (west declination), and west of this line magnetic north is east of true north (east declination). Suppose, in Fig. 366, A, that true north is 15° to the east of magnetic north (and, therefore, that true east is 15° south of magnetic east, etc.); the true bearing is then $30^{\circ} + 15^{\circ}$ to the west of true north, or N. 45° W., instead of N. 30° W. Similarly a magnetic bearing of S. 30° E. would become a true bearing of S. 45° E. If the compass reads N. 55° E., as in Fig. 366, B, obviously one must subtract the correction of 15° and the true bearing is then N. 40° E. Likewise, S. 55° W. would be corrected to S. 40° W. All cases are covered in the following rules: If true north is to the east of magnetic north, to all magnetic bearings in the NW. and SE. quadrants add the correction, and from all magnetic bearings in the NE. and SW. quadrants subtract the correction. If true north is to the west of magnetic north, add the correction to NE. and SW. readings and subtract it from NW. and SE. readings. Additions and subtractions are algebraic. (How would you correct a magnetic bearing of N.-S.? of E.-W.?)

Since the magnetic variation is not the same for different localities and since it changes gradually from year to year in any given locality, one must ascertain the proper correction for any place in which geologic field work is to be performed (Plate I).

7. Be scrupulously careful not to have your hammer or any other steel near the compass while making observations. Magnetic ore, steel nails, electric wires, etc., seriously affect the needle.

In reading directions, the sights of the Gurley and Brunton compasses increase the accuracy of the results. The Gurley,

however, must be placed on a horizontal support, such as a plane table, whereas a Brunton can be held in the hand. This is a distinct advantage of the latter instrument, where a plane table is not desired. To read the direction to a distant object, hold the Brunton compass level, with the mirror nearest you and the pen sight away from you. The sight should stand vertical and the mirror should be tilted at such an angle that the sight and the distant object can both be seen reflected in it. With the reflected object and the slot in the sight both bisected by the cross-hair in the mirror, read the compass angle and so determine the required direction (4-6, above.)

333. Setting the Compass.—In both the Brunton and Gurley compasses the dial can be so adjusted that, for a given locality,




FIG. 367.—Diagrams illustrating the method of setting the compass dial for true readings. Dashed line, true north-south line.

true instead of magnetic bearings may be read directly. In Fig. 367 the dashed line represents the direction of true north, here assumed to be 20° to the east of magnetic north (the north end of the needle). As shown in Fig. 367, A, the magnetic reading is due north and south, and the corrected reading is N. 20° W., for the "0" on the dial is 20° to the west of true north. If the dial is turned in the compass box 20° to the west, and the needle and box are in the same relative position as in Fig. 367, A, the bearing when read directly will be N. 20° W. (Fig. 367, B). *i.e.*, the "0" on the dial will now be 20° to the west of the needle. Hence, the rule for setting the compass is this: rotate the dial through an angle equal to the magnetic declination (the angle

between magnetic and true north), *westward* if true north is to the *east* of magnetic north, and *eastward* if true north is to the *west* of magnetic north. Do not overlook the fact that magnetic declination is usually different in different regions.

334. Use of the Clinometer.—The clinometer is used for measuring vertical angles of slope and dip. The compass box must be held with its plane vertical. If the clinometer is of the pendulum type, the angle will be indicated on the inner, nearly semicircular scale, where the swinging pointer comes to rest. If the clinometer is of the friction type, as in the Brunton, the angle will be read on the inner semicircular scale opposite the zero of the vernier, after this has been properly set as described below.

1. In taking the dip, hold the compass vertically with its length parallel to the outcropping edge of the stratum and its face in a plane *perpendicular to the strike*. "Care must be taken to have the eye as nearly as possible in the extension of the plane whose inclination is being measured, and to sight on a horizontal line,"¹ *the strike line*. If the compass is a Brunton, while holding it with its plane vertical and perpendicular to the strike, and with its long edge apparently coinciding with the bedding, turn the clinometer arm until the bubble in the longer level is centered. Then read the angle of dip on the inner dial.

2. In recording dip, the vertical angle from the horizontal and the direction of inclination must be noted. Dip is always measured *downward*. If the strike is E.-W., then the dip may be either northward or southward. If the strike is N. 50° E., the dip may be northwestward or southeastward. It is necessary to give only the quadrant in which the dip lies, for the exact direction can be determined from the strike, since the *direction* of the dip is always perpendicular to the strike. A record of a strike of N. 25° W. and a dip of 45° (downward) toward the NE. is written, N. 25° W.; 45° NE. Observe that the 45° NE. does not mean N. 45° E.; it signifies a vertical angle of 45° in a general northeasterly direction.

¹ Bibliog., HAYES, C. W., p. 24.

A Brunton compass may be employed in other ways. To find the angle of a slope, while looking up or down the slope, hold the Brunton with its plane vertical and parallel to the direction in which you are making the observation, and with the mirror farthest from you. Open the sight at right angles to the plane of the compass and have the mirror about three-quarters closed. Look simultaneously through the open sight and the peep hole near the base of the mirror at a point, up or down the slope, which is as high above the ground as your eye, and bring the point, the

VERTICAL ELEVATION




FIG. 366.—Determination of thickness of inclined beds. (After D. F. Hewett.)

center line of the open sight, and the cross-hair of the mirror into alignment. Then, without changing position, turn the clinometer arm until the bubble in the longer level is centered, *as seen in the mirror*. The angle of slope will be indicated at the point on the inner dial of the compass opposite the zero of the clinometer vernier scale.

Sometimes the Brunton may be used to verify a supposed slight dip or slope. In this case, set the vernier scale with its zero against the zero of the inner dial, and sight at the questionable dip or slope across the top edge of the compass as above described. The supposed dip is proved to exist if the bubble does not move to the center.

The Brunton may be of service in measuring the thickness of inclined beds. In Fig. 368, "the geologist stands at A, the base

of the section to be measured. The clinometer level of the Brunton compass is turned to equal the angle of dip of the beds. When, therefore, the observer looks through the sights, he observes a spot on the ground that is the distance $AC = BD$ stratigraphically higher than the point A at which he stands. Now $BD = AC = AE \cdot \cos$ of the angle of dip $= AE \cdot \cos x$, and AE is constant for each observer. If, therefore, he prepares a table such as that given below, in which $AE = 5.25$ ft. he can readily determine the proper unit for each degree of dip."¹ From A he will go to B and repeat this procedure, and so on to the top of the section. The sum of the distances, equivalent to $AC = BD$, will be the required thickness.

TABLE OF THICKNESS VALUES FOR STEPPING WITH INCLINED SIGHT¹

Dip = x	$AC = AE \times \cos x$	Dip = x	$AC = AE \times \cos x$
0	5.25	22	4.86
2	5.24	23	4.83
4	5.24	24	4.79
6	5.23	25	4.75
8	5.20	26	4.72
9	5.18	27	4.67
10	5.16	28	4.63
11	5.15	29	4.59
12	5.13	30	4.54
13	5.11	32	4.45
14	5.09	34	4.35
15	5.07	36	4.25
16	5.04	38	4.14
17	5.02	40	4.02
18	4.99	42	3.90
19	4.96	44	3.77
20	4.93	46	3.64
21	4.90	48	3.51

¹ After Hewett, *op. cit.*

335. The Locke Level.—The Locke level consists of a straight metal tube or barrel about 5 in. long and $\frac{3}{4}$ in. in diameter, See Bibliog., Hewett, D. F., 1920, pp. 383, 384.

which the observer holds horizontal as he looks through it. Attached near one end is a small spirit level, to be held uppermost when the instrument is in use. Under the level tube, inside the barrel, is a mirror which covers one-half the field of vision, up and down. It (the mirror) is inclined at such an angle that the observer can sight through the barrel at a distant object, and, at the same time, see the bubble reflected in it. When the bubble is bisected by the horizontal cross-hair, a distant object which appears to be opposite the middle of the cross-hair is at the same level as the observer's eye, provided the instrument is in adjustment. The geologist should know the height of his eyes above the ground.




FIG. 369.—Profile section of a slope, illustrating the method of finding difference of elevations by hand level.

The Locke level may be employed as indicated in Fig. 369. *ag* is a hill slope. Standing at *a*, and being careful to hold the level so that the bubble is centered, the observer looks through the tube at some point, *b*, at the same elevation as the instrument; *i.e.*, *a'b* is horizontal. He then proceeds to *b*, noting the distance *ab*, and repeats the process at *b*, looking toward *c*. The height of the instrument, *aa'* is known. Hence the elevation of *g* above *a* is, in this case, *6aa'*.

336. The Abney Level.—The Abney level (or pocket altimeter) has a graduated vertical arc in addition to the tube and spirit level. With the arc set at 0° it can be employed just like the Locke. The Abney can also be used as a clinometer. In Fig. 370, *abcd* is a slope with a change at *b* and another at *c*. The observer stands at *a* with the instrument at *a'*, and, sighting through the tube at *b'*, at the elevation $bb' = aa'$ above the

ground, he simultaneously rotates the spirit level until the bubble is centered. The angle of the slope, $\angle b'a'f$, may then be read directly from the graduated arc. The height of b' above b is generally estimated from a by eye. It may be obtained with greater precision if an assistant at b holds a rod known as a *grade rod*, having the proper length, aa' , indicated upon it. At b the observer sights at c' and reads the slope angle, $\angle c'b'g$. Notice that these readings are always made at changes of slope. At c he would sight forward to a position on another change of slope, and so on.




FIG. 370.—Profile section of a slope, illustrating the method of finding slope angles by clinometer.

337. The Telescopic Hand Level.—The telescopic hand level is essentially a hand level provided with lenses for magnification of distant objects and with stadia hairs for estimating distances. At the end held away from the observer it can be focussed on the object, and at the end nearest the observer's eye it can be focussed on the stadia hairs. These hairs are usually spaced on the ratio of 1:100, *i.e.*, so that an object 10 ft. high and 1,000 ft. distant will appear to be just included between the two outer (stadia) cross-hairs. Consequently, if the horizontal distance between the observer and the object is known, the height of the object can be determined; and if the height of the object is known, its distance can be obtained. By the use of a graduated rod, held at the distant station by a rodman, fairly precise measurements of horizontal distance can be made.

338. Adjustment of Hand Levels.—Any hand level may be tested for its accuracy as follows: choose two trees, fence posts, or other objects at about the same level and several hundred feet

apart. On one, set a mark which will be visible from the other. Hold the level at this mark and carefully sight at the other tree (or fence post, etc.), noting a point which is cut by the cross-hair while the latter bisects the image of the bubble. Go to the second tree and, with the level against the observed point, sight back at the mark on the first tree. If, now, the bubble is not bisected by the cross-hair, the level is out of adjustment. To correct, turn the screws at the end of the level tube until the apparent error in the position of the bubble is halved. Go back to the first tree and repeat, if necessary.

339. Comparison of Hand Levels.—The Abney level is seldom used in ordinary geologic field work. Of the Locke and telescopic (stadia) levels, the latter is more accurate than the former for short sights, provided, of course, that the instruments are in perfect adjustment. In the case of either instrument, the relative error is similar for short or for long sights, but the absolute error is greater for long sights.

340. The Aneroid Barometer.—An aneroid barometer is a case containing a metal vacuum chamber which responds to differences in atmospheric pressure. By a mechanism within the case, changes of pressure are communicated, very much magnified, from the vacuum chamber to an index needle which rotates over a circular dial. In view of the fact that atmospheric pressure diminishes with increasing altitude above sea level, the dial is provided with an outer scale in feet of elevation and an inner scale in inches of mercury. The smallest subdivisions of the former scale are usually 10 or 20 ft. Smaller values may be estimated.

Some instruments have the scales fixed, with the zero of the scale in feet opposite 31 on the inch scale, whereas others are constructed so that the outer scale is movable against the inner. If the geologist has an aneroid of the latter kind, he should be careful to *keep the zero mark in feet against 31 in.* Otherwise he may introduce considerable errors into his readings for the reason that the divisions of the altitude scale are not of uniform size, but are progressively smaller from zero to the upper registry

of the instrument. Under normal atmospheric pressure, 31 in. represents an elevation of 890 ft. below sea level. The zero point of the altitude scale was chosen arbitrarily as equivalent to 31 in. on the pressure scale so that the needle would seldom, by rises of atmospheric pressure (388), go as low as zero. If atmospheric pressure should rise to more than 31 in. a negative elevation would be indicated on the scale in feet.

Aneroids are made in sizes varying from about 2 to 6 in. in diameter. They register up to 2,000, 3,000, 5,000, 6,000, 10,000 ft., etc. One registering to 5,000 or 6,000 ft. is generally most satisfactory in regions where elevations above sea level are not over 4,000 ft. Under no circumstances should a barometer be used at altitudes near the limits of its registry. Hence, the geologist who expects to undertake barometric work should ascertain the probable range of elevations in the district to be investigated.

For all geologic work, the barometer must be reliable. Few aneroids are good enough. Before an instrument is selected for purchase, it should be carefully tested. This may be done in several ways as follows:

"1. Gently tap the glass case with the fingers. The needle should jar slightly, not too freely, and should return to the same point at which it stood before being disturbed. If it stops now at one place and now at another, after successive tappings, while it is held always in the same position, it is unreliable.

"2. Read the instrument, carry it to an upper floor in a building, or 30 or 40 ft. up a hill; read it; return to the starting point and read again. Two or three minutes after arriving here the needle should record the same elevation as at first, provided the ascent and descent were made within 5 or 6 minutes. Go up to the upper station once more, wait a minute or two, and read. Any considerable differences in the elevations recorded at the same station, especially if these differences are unrelated, usually indicate a poor barometer. The pause after reaching the station is to allow for a possible lag.

"3. Take out the new barometer on a day's traverse and compare its readings with those of another barometer known to be reliable. In doing this observe that both barometers may not show the same elevations, estimated from zero, nor equal amounts of rise and fall, but both should rise together and fall together, and *after the readings have been corrected (388, 391)*, the elevations obtained by both instruments should be approximately the same for the same station."¹

Since an aneroid is always a delicate instrument, it should be handled with care. It should be carried where it will not be severely jolted and where it is subject to as little variation in temperature as possible (388). In reading the instrument, hold it horizontally in the open palm of your hand. Do not grasp it.

341. The Paulin Altimeter.—A special type of aneroid barometer, called a Paulin altimeter, has been devised to overcome, as far as possible, some of the instrumental defects² of the ordinary aneroid. We cannot go into the details of construction here. Suffice it to say that, while "the ordinary aneroid may be likened to a spring balance where the reading of weight depends upon the proportional elongation of the spring," the Paulin altimeter "is comparable to the type of scale used in laboratories or for other accurate weighing where known weights are placed on one pan and the object to be weighed is placed on the other, the true weight then being determined by adding to or subtracting from the known weights until the 'tendency pointer' is at zero on the scale."³ Except for some differences in the method of reading the elevations, the Paulin altimeter is handled like an aneroid barometer. Corrections for temperature, weather conditions, and diurnal range must be made in using either instrument (388-398).

342. The Barograph.—A barograph may be described as a self-recording aneroid barometer. The movements of the

¹ Bibliog., LAHEE, F. H., 1920, p. 151.

² Such as frictional resistance in the operation of the mechanical parts, elastic hysteresis, and lag.

³ Bibliog., HILL, RAYMOND A., -1929.

vacuum chamber, caused by variations in atmospheric pressure, are communicated to an arm which carries a pen. This pen, which is constantly filled with ink, rests on a piece of specially prepared ruled paper wrapped round a drum which revolves by clockwork. The motions of the pen are thus recorded on this paper. At the end of each day the record is removed and a new piece of paper is substituted. Barographs are made in different sizes. A small one is almost useless for geologic purposes (390, ¶ 8), because the divisions on the ruled paper are too small for careful reading of pressure variations. A large instrument, if any, is the only kind that should be used, but this has the disadvantages of bulk and weight.

343. The Watch.—An ordinary watch is absolutely essential in some types of field work (383). It ought to be of workmanship sufficiently good to insure its proper running, with ordinary care, while the geologist is in places where no repairs can be made. A wrist watch is most convenient.

344. The Plane Table.—A plane table is a drawing board mounted on a tripod in such a way that the board can be turned horizontally, when the table is set up, without moving the tripod. Geologists ordinarily prefer boards 15 by 15 in., 18 by 18 in., or 18 by 24 in. The small size is convenient for some kinds of reconnaissance work (413). The 18- by 24-in. board is the best size for mapping unsectionized country and for mapping a single township, on the scale of 2,000 ft. = 1 in., in sectionized country (Appendix VII), since, in the latter case, there is room for the title, legend, etc. (443). The 18- by 18-in. size is useful in sectionized country where several townships must be mapped and the maps must later be fitted together.

The paper for the map may be attached to the board by thumb screws or thumb tacks.

The plane table may be used oriented or unoriented. When *unoriented*, the table is set up at a given locality without reference to directions. It serves merely as a page in the notebook, but is a more convenient support for the map. Lines between stations are plotted by protractor with respect to north-south and

east-west coördinates ruled on the map sheet. An *oriented plane table* is set up at every station in exactly the same position relative to true or astronomic bearings (332), and lines between stations are plotted by sight alidade (347) or telescopic alidade (348). Some plane tables have a compass needle for orienting, sunk in the board at one edge. More often, however, the board is not provided with such a needle, for the Gurley compass (331) or the alidade may serve the same purpose if this instrument is properly placed on the map.

345. Paper for the Plane Table.—On account of the fact that paper consists of fibers, it generally expands and contracts unequally in different directions. To overcome this tendency, plane table paper is mounted on cloth, or two or three thicknesses of paper are mounted together with the fibers in the different sheets in different relative positions. The most satisfactory type is made of two sheets of paper with a sheet of cloth between them (double mounted egg shell paper). This may be used first on one side and then on the other. The surface should be slightly rough, hard enough to take a 7-H or 8-H pencil line, and slightly tinted to lessen the glare of the sunlight. The sheets should be cut to the dimensions of the plane table. Often several sheets are carried attached to the board at the same time. When a map sheet is finished, it is placed under a clean one. Celluloid sheets may be used in regions where wet weather is continuous for many weeks, but otherwise the cloth-mounted paper is to be preferred. On rainy days office work can be done instead of mapping in the field.

346. Stadia and Leveling Rods.—In plane table mapping a stadia rod is used in connection with the telescopic alidade. This is a collapsible jointed wooden rod, 12 to 15 ft. long when open, and 3 or 4 in. wide, graduated in feet and tenths of feet. It should be painted in contrasting colors, preferably with white background and a black saw-tooth design to mark feet and fractions of a foot. Such a design can be read at great distances. The rod is carried by a "rodman." When set up for a reading, it should be vertical and the graduated side should

be held facing directly toward the instrument man who, at some distant point, is looking at it through the telescope of his alidade.

Sometimes mapping is done by means of a telescopic hand level and a level rod. This rod may be from 5 to 15 ft. long. It may be provided with a sliding disc or *target* which can be set at a chosen elevation above the ground.

347. The Open Sight Alidade.—An open sight alidade consists of a flat rectangular metal base with one edge bevelled and graduated, about 10 in. long, provided with an open folding sight at each end. It is used in conjunction with the plane table. In practice the sights are turned up at right angles to the base. They should be at least 4 or 5 in. long, for observations up or down slopes. The observer, having set up the plane table at a station (403), places the fiducial (bevelled) edge of the alidade against the point that represents this station on the map, and rotates the alidade about this point until he brings some distant object, which he has selected as the next station, into line with the cross-hair of one sight and the slit of the other sight. He then draws a line on the map along the fiducial edge from the point for his present location toward the distant object. The use of the alidade is further described in Chapter XVI.

348. The Telescopic Alidade.—The telescopic alidade most commonly used in geologic field work is of the Gale type. It has a flat metal base, 11 in. long and $2\frac{3}{4}$ in. wide, with one edge bevelled and graduated to fiftieths of an inch. Upon this base are two short vertical pillars on which a small telescope is so mounted that it may be rotated in a vertical plane parallel to the bevelled edge of the base. The line of sight of the telescope is always in this vertical plane when the instrument is properly adjusted. On the right side of the base is a tangent screw for raising and lowering the telescope. On the left side of the base is a magnetic needle. This should be kept locked when not in use. With the alidade resting flat on the plane table, the latter can be levelled by means of a round spirit level, or bullseye level, on the alidade base. A detachable striding level, which is employed in levelling the telescope, is supported by two wyres.

each resting on a metal collar, one on one side and the other on the other side of the sleeve in which the telescope is set. A graduated arc, firmly attached to the telescope, shows, by reference to a vernier the angle through which the telescope is rotated.

At the objective end of the telescope are a vertical and a horizontal diametric cross hair and two horizontal stadia hairs, these being carefully fastened in proper relative position on a reticle, or cross-hair ring. The two stadia hairs are at equal distances above and below the horizontal cross-hair. They are spaced, as in the telescopic hand level, so that they will exactly include a distance of 1 ft. on an object 100 ft. away, or 2 ft. on an object 200 ft. away, and so on, when this object is viewed through the telescope. The vertical distance thus covered between the stadia hairs is called an *interval* or a *step*, and half this distance, between either stadia hair and the horizontal cross hair, is a *half interval* or a *half step*. The reticle, as a whole, is movable by four capstan screws. For purposes of adjustment it is very necessary to understand how these screws control the movement of the cross-hair ring. Before tightening one screw, the opposite one should be loosened, for otherwise the ring cannot move and the screw threads may be damaged. By loosening the lower screw and tightening the upper screw the whole ring may be drawn upward, or by reversing the process, it may be turned downward. By working the side screws in a similar manner, the ring may be turned to one side or the other. All this can be done without turning the ring, while the vertical hair remains vertical, and the horizontal hair remains horizontal.¹

A telescopic alidade may be equipped with a Beaman stadia arc for simplifying the reading of differences of elevation, and with a gradienter screw and Stebinger drum for measuring distances and determining vertical angles. The Beaman arc is attached to the horizontal axis of the telescope. The drum, which is attached to the tangent screw, is so graduated that if

¹ After MATHER, following J. C. TRACY. Bibliog., MATHER, KIRTLEY F., 1919, p. 101. This is a very excellent treatment of the subject. With the kind permission of Professor Mather and also of the Scientific Laboratories of Denison University, we have quoted extensively from this article.

it is rotated through one complete revolution, the telescope will be raised (or lowered) through one interval, as above defined (see Art. 412, 4, 5).

349. Care of the Alidade.—Like all instruments of precision the alidade must be handled with extreme care. It should never be placed on the ground or on a rock pile. If for any reason it must be removed from the plane table, return it to its leather case and close the case tightly. Its base must be kept free from dirt. When in constant daily use, all screws and moving parts should be carefully wiped clean with a soft rag dampened in light oil. The springs which play against the bearing studs on the opposite sides from the vernier and tangent screws should be removed from their housings, wiped clean, stretched a little, and replaced. At all times the instrument should be protected against jars and shocks which might cause changes in adjustment of cross-hairs, level bubbles, or other delicate parts.

“If the Stebinger drum is used in determining the elevations, the tangent screw must be treated with special care. Experience indicates that very trivial and unobtrusive things may change the relation of the screw to the arc sufficiently to make a Stebinger table no longer applicable and necessitate the construction of a new one. If possible, the gradienter screw should be entirely withdrawn every week or two and wiped absolutely clean with the oily cloth. The bearing plate stud against which the point of the micrometer screw pushes must be kept securely tightened. Should it become loose very erratic readings will result. The surface of this plate will gradually wear at the point where the micrometer screw bears against it until a distinct socket is made. Ultimately this becomes so pronounced that not only does it throw out the relation of the straight line push of the screw to the circular movement of the arc, but the point of the screw will not hit exactly the same spot on successive readings, and as a result three or four readings from the same station to the same object will fail to check. When that happens, the bearing plate should be surfaced with a file and a new gradienter table constructed. (See Art. 412. 5.)

"The compass needle should always be raised from its pivot and clamped immediately after it has been used . . . Place the alidade as nearly as possible in the magnetic meridian before releasing the needle, and thus avoid the blow to the needle resulting from sudden contact with the compass box. The danger of destroying the polarity of the needle is another reason for guarding against reckless treatment of the alidade as a whole. When working in the rain, the compass box is the most vulnerable part of the instrument. Unless the glass cover is securely sealed all around, moisture will penetrate the box and put the needle out of commission by causing it to adhere to the inside of the glass. If this occurs, the box must be opened, the needle removed, and all parts thoroughly dried before proceeding with the work."¹

350. Adjustment of the Alidade.—"The most important adjustments of the miniature or explorer's alidade, which require attention in the field, are those for collimation and of the striding level. All other adjustments are reasonably permanent as made in the factory. It is, however, well for the instrument man to be able to detect, and if possible correct, faulty workmanship or damage from mistreatment or accident.

"The line of sight through the telescope is determined by the intersection of the cross-hairs, whatever their position in the tube, and the nodal point in the objective lens. This line is correctly collimated when it coincides with the optical axis of the objective. That is, the intersection of the cross-hairs should remain stationary in the field of vision when the telescope is rotated on its horizontal axis. The telescope is mounted between 180-degree stops in the axis-sleeve for this purpose.

"Sight some distant fixed object of small size and center the cross-hair exactly upon it. The telescope need not be horizontal. Rotate the tube carefully half way round and twist the prismatic eye-piece back into position. Note whether the cross-hairs are still centered upon the object. If not, correct half the discrepancy by means of the diaphragm adjusting studs, which may or may not be concealed beneath a ferrule which forms a guard

¹ Bibliog., MATHER. KIRTLEY F., 1919, pp. 141, 142.

against accident or tampering . . . Move the vertical hair to left or right by turning both lateral studs in the same direction, first slightly loosening the one, then tightening the other. If the alidade is of the erecting type with field reversed from right to left, as is commonly the case, loosen the screw *away from which* the *vertical* hair must apparently be moved, and tighten the opposite screw. Move the horizontal hair up or down by turning top and bottom studs in the same direction, first slightly loosening the one and then tightening the other. If the eye-piece is of the erecting type, loosen the screw *towards which* the *horizontal* cross-hairs must apparently be moved and tighten the opposite screw. Having corrected half the discrepancy in this way, shift the alidade until the cross-hairs are again centered upon the distant object, and rotate the telescope as before. - The line of sight should now remain fixed upon the distant point; if it does not do so, correct half the apparent error as before. Repeat until the hairs are properly centered.

"The test for collimation should be frequently made. No important triangulations should be begun until one is certain that the cross-hairs are properly located. Should the instrument be subjected to any unusual jar, it must be collimated before it is again used. In the normal routine of field work the position of the cross-hairs should be examined at least once each week."¹

Probably the most important adjustment of the alidade to be made in the field is that of the striding level. The bubble of the striding level is sensitive to changes in temperature, shocks, etc., and must be watched carefully in order to do accurate work. It should be checked at least three or four times daily, and especially before starting work in the morning and in the middle of the day. If the temperature change is great, or if many stations are visited, the bubble should be checked more frequently.

For making such adjustments a screw will be noted at one end of the bubble carriage. By means of a spring a slight turn of the screw raises or lowers one end of the carriage. To make correct adjustment, bring the bubble to level by means of the vertical

¹ *Bull. U. S. Geol. Surv.*, MATHER, KIRTLY F., 1919, pp. 137-139.

tangent screw. Reverse the bubble carriage and if the bubble does not return to the central position, adjust for one-half of the error by means of the adjustment screw. To be in perfect adjustment, the bubble should remain in the center when the bubble carriage is reversed. A number of trials may be necessary to obtain the correct adjustment. While a slight error of adjustment does not make an appreciable difference in short shots, it increases largely the percentage of error in long shots.

351. Stadia Reduction Tables.—If, in plane table work, the observer's station is higher or lower than the observed station, the solution of a right triangle is involved. The inclined distance along the line of sight is the hypotenuse, the horizontal projection of this inclined distance is one leg, and the vertical difference of elevation of the two stations is the other leg. The inclined distance (hypotenuse) and the vertical angle between the line of sight and its horizontal projection (horizontal leg) are read by the instrument man. By reference to a stadia reduction table, or conversion table (Appendix XVIII), he finds the length of the vertical leg of a right triangle similar to the one above described, but with its hypotenuse 100 ft. long. This factor he multiplies by the number of hundreds in the inclined distance between the two stations in order to determine their difference in altitude (409).

352. Stadia Slide Rule.—A stadia slide rule is a mechanical device which may be substituted for stadia reduction tables. The stationary part of the rule is graduated above for horizontal and below for vertical distances. The movable scale is marked in angular degrees. When the horizontal distance to a given station, *A*, is known, and the angle of inclination of the line of sight to this station is also known, the vertical difference in elevation between the observer's station and *A* can be found by setting "0" (marked on the side of the movable scale nearest to the fixed scale for horizontal distances) opposite the value of the given horizontal distance. The required vertical distance, on the other fixed scale, will be against the observed angle. It is important to remember that, if the horizontal distance is

greater than the vertical distance, one fixed scale is used for horizontal distances, and if the vertical distance is greater than the horizontal distance, the other fixed scale is used for horizontal distances.

353. Scale for Plotting.—A *plotting scale*, or a scale for plotting, is a straight-edge graduated in intervals representing feet, yards, meters, or paces, on whatever scale is adopted for the mapping. Such a scale is best graduated in inches and tenths of inches when plane table mapping is done on a scale of 1 in. = 1,000 ft., or 1 in. = 2,000 ft.

354. The Protractor.—A 4- or 5-in. protractor is often very useful for laying off angles in any kind of mapping. Probably it is employed most frequently in plotting compass traverses (374).

355. The Steel Tape.—The steel tape is of especial importance in measuring base lines for triangulation nets (411, ¶ 2). It is also serviceable in measuring stratigraphic sections, in determining pace lengths, and in measuring other short distances where considerable accuracy is required. For geologic mapping there is practically never any necessity for correcting taped distances for tension, temperature, sag, or standardization of the tape.

356. The Odometer.—When an automobile is used in geologic mapping, the car must have an odometer registering the distance travelled in miles and tenths of miles. This instrument constitutes part of the mechanism in a speedometer, as usually provided. By keeping watch of the trip gauge, the geologist can estimate distances to less than 0.05 mile, which is close enough for most reconnaissance work (366).

357. The Tally Register or Pace Counter.—A tally register is an instrument, about the size of an ordinary watch, used for keeping count of paces. In traversing on foot, the geologist holds it in his hand and presses the small knob at every second or every fourth step. With a little practice, this becomes so much a habit that it requires hardly any thought. If one is traversing moderately hilly country, perhaps with a fairly open

growth of vegetation, the average length of two steps will be very nearly 5 ft. that is, one can allow about 1,000 double paces to the mile, a convenient quantity for approximate measurements of distance. If the land is less rolling, or more open, the geologist will probably go a mile in less than 1,000 double paces.

358. The Camera.—A camera is almost an essential part of a geologist's field equipment. There is considerable divergence of opinion as to which is the most satisfactory kind to use. Some prefer one of vest-pocket size, whereas others choose a larger type. Much depends upon conditions of climate and travel in any particular field investigation, for sometimes the pack must be reduced to the lowest possible weight and dimensions. Ordinarily the writer prefers a Leica, or other miniature camera, because of its size and the large number of pictures that can be carried. In any case the lens should have good definition. In moist climates, and particularly in tropical regions, films should always be carried in water-tight tins, and they should be developed as soon as possible after exposure (328).

359. Base Maps.—For most kinds of geologic field work, some sort of a preliminary map of the region is of great advantage. This may be a simple property plat; a road or railroad map; a township plat (Appendix VII); a county or state map; a plotted triangulation net (411) or other control system; a sketch map of the drainage; or, better than any of these, a good topographic contour map, or an aerial photographic map (423, ¶ 2, p. 545). Such a map, which has been previously prepared and on which the geologist can plot his data in the field, is termed a *base map* or a *working map*. Sometimes the base map must be enlarged or reduced to bring it to the scale adopted for the field work.

360. Additional Equipment.—In addition to the instruments which may be used, the geologist will need various other articles. A few words will be said concerning notebooks in the next chapter which treats of the methods of field surveying. If the work necessitates the collection of rock specimens, the geologist should provide himself with a geologic hammer, a collecting bag, small paper bags or newspapers in which the specimens can be

separately wrapped, and paper labels (327). The style of hammer depends partly on the preference of the individual and partly on the nature of the work and the character of the rocks. Hard crystalline rocks require a heavier hammer than fissile shales. The fossil collector generally chooses a hammer with a peen shaped for splitting.

For plane table mapping, a 7-H or 8-H pencil is best. A 4-H to 6-H pencil is better for recording information in the notebook. Colored pencils are convenient for marking, on a working map, the distribution of the different formations encountered. The boundaries of the formations are first outlined and then the areas between are filled in with the colors.

A hand lens is always useful, and is almost indispensable for work in regions of igneous or metamorphic rocks.

For automobile work, in rough country, the geologist will do well to prepare himself for trouble. He will be wise if he carries two spare casings, three or four spare inner tubes, an extra tin of gasoline (3, 4 or 5 gal.), a tin of lubricating oil, a spade, mud chains, 30 or 40 ft. of stout rope, an axe, some bailing wire, extra spark plugs and valve caps, and so on, besides all the usual equipment that belongs with a car.

CHAPTER XVI

GEOLOGIC SURVEYING

PART III. INSTRUMENTAL METHODS IN FIELD MAPPING

GENERAL CONSIDERATIONS

361. Procedures in Geologic Mapping.—As stated in Art. 306, geologic mapping requires the following three procedures: (1) the examination of the rocks; (2) the determination of the location of outcrops or points where observations are made; and (3) the plotting of the field data on a map. All three of these procedures are important, but the extent to which each is carried and the manner in which each is executed depend on the nature of the country, the kind of rocks, the rate at which the mapping must be done, the character of the results desired, and many other factors. Geologists should be impressed with the necessity of carefully locating outcrops and stations, not only in reference to natural objects and to one another, but also—and particularly—in relation to established survey corners, land lines, and other such features. The significance of this remark is often brought out in those phases of geologic surveying which have an economic purpose.

362. Traverse Defined.—In studying an area a geologist proceeds along the route which he thinks will show him most in the time at his disposal. His course, known as a *traverse*, is a line, or a system of lines, connecting outcrops or stations where observations were taken. Obviously several traverses have to be made when an area is to be investigated. Traverses are often designated by the instrument which figures most largely in their making. Thus, there are compass traverses, plane-table traverses, transit traverses, barometer traverses, etc.

363. Quantities Measured.—The accurate location of points involves measurements of horizontal distance, vertical distance or difference of elevation, and horizontal direction. Distances are determined by direct measurement, as in pacing, taping, chaining, etc., by reference to the stadia interval (348), or by triangulation (411). Horizontal distances can seldom be measured in actual practice. They can be obtained by right angle calculations when inclined distances or slope distances have been determined, but, except in accurate mapping, the allowable limit of error in geologic work rarely demands the reduction of the measured inclined distances to their horizontal equivalents. Such reduction is necessary only when the ratio of the length of the inclined distance between two stations to the

difference of elevation of the two stations is relatively large. The limiting ratio, which will decide whether or not a given inclined distance should be corrected to its horizontal equivalent, varies according to the degree of refinement wanted in the results

FIG. 371—Section of a slope to illustrate slope distance, ab , horizontal or map distance, ac , and difference of elevation, bc

(366). Ordinarily no such correction is necessary for slopes of less than 5° . If, in Fig. 371, ab is a rather steeply inclined slope distance, bc the elevation of the point b above a , ac the horizontal or map equivalent of ab , and $\angle bac$ the slope angle, then ac may be obtained by the equation, $ac = ab \cdot \cos \angle bac$, or by the equation, $ac = \sqrt{ab^2 - bc^2}$, according to whether the slope angle, $\angle bac$, or the difference of elevations, bc , has been determined.

Differences of elevation are found by stepping (335, 412), by vertical angle computations (336, 412), and by barometric readings (362, *et seq.*).

Directions, always regarded as horizontal in mapping, are determined by compass or by triangulation (411).

In addition to these quantities, geologic work often requires the measurement of dips of strata, faults, veins, etc. Dips are found by clinometer (334) unless they are very low, in which

case they may be determined by obtaining elevations of points on a given key horizon (317).

364. Correction of Pace Lengths.—Pacing is a common method of measuring distances on the ground. If a certain distance is paced from one known point, by way of several unknown stations, to a second known point, and an error in the distance is found at the second known point, this error may be divided proportionally among the several parts of the traverse, from station to station. If long distances are to be paced, without control stations for checking, the geologist should measure his pace lengths in the different types of country traversed. His paces will be longer in smooth open country than in rough topography, or on land overgrown with tall weeds or grass, or thickly overgrown with shrubbery or trees. They will be longer on level ground than up or down a relatively steep slope. If desired the following table may be used for finding the value, in terms of horizontal paces, of any number of paces on a slope of 30° or less.¹ Multiply the

TABLE FOR REDUCING PACES ON SLOPES TO THEIR EQUIVALENTS IN
TERMS OF HORIZONTAL PACES

Angle of slope.....	0°	5°	10°	15°	20°	25°	30°
Gradient of slope... ..		1/11 4	1/5 7	1/3 7	1/2 7	1/2 1	1/1.7
Factor for paces going uphill...	1.000	0.907	0.799	0.717	0.625	0.542	0.413
Factor for paces going downhill.	1.000	0.959	0.929	0.905	0.860	0.753	0.591

number of paces recorded on the slope by the factor in the table for that slope, thus: if a distance on a slope of 20°, going uphill, is 300 paces, the actual distance on the slope is equal to 0.625×300

¹ Before using this table each individual should test it for his own paces measured on different slopes. He will do well to make a similar table for himself. As a matter of fact, however, many geologists standardize their paces by walking several miles uphill and downhill over the kind of country to be mapped and computing an average pace length for the whole distance. This average pace is then adopted for all measurements of distance without reference to slope.

= 187.5 horizontal paces. If the horizontal pace is equal to 2.5 ft., the distance *on the slope* is 2.5×187.5 ft. = 468.75 ft. After making this correction for the slope value of the paces, the slope distance obtained, here 468.75 ft., must be reduced to the horizontal by one of the equations given in the preceding paragraph. In using the table for slope factors, interpolate for slope angles not multiples of 5.

Where the traversing is done on horseback, the length of the horse's pace must be determined under different conditions, just as in the case of a man's pace, and these values may be used as units of measurement of distance.

365. Controls for Mapping.—Geologic mapping, like all kinds of mapping, is done by determining and plotting the locations of certain chosen points or stations and then sketching in the details with reference to these points. Gannett has well defined a map as "a sketch, corrected by locations." These selected points may be said to *control* the map. Their horizontal directions and distances from one another are termed the *horizontal control*, and their elevations the *vertical control*, of the map. Occasionally, in regions which have not yet been surveyed, the geologist has to establish the entire system of control points for his map; but generally he finds that a control of the district to be investigated has already been plotted, perhaps by the U. S. Geological Survey, or the Coast and Geodetic Survey, or by a survey conducted by state or township, by a railroad or mining company, or by some other interest.¹ Yet, even in this case, because the fixed control points are too far apart or because, as is usual, they have been chosen with little regard for geologic structure, he will have to locate a secondary group of stations whose horizontal and vertical positions will be determined in relation to the original or primary control points. The control system for any geologic work should be laid out more accurately, *i.e.*, with a smaller allowable limit of error, than is demanded for the geologic mapping itself.

¹ The control points may be triangulation stations, U. S. G. S. bench marks, township corner posts or quarter posts, claim corner posts, etc.

366. Detail and Reconnaissance Mapping.—The degree of accuracy with which field mapping may be done, is open to wide variation. In some kinds of work every outcrop and every geologic contact must be located with precision, whereas, in other cases, only a sketch is required of the position and size of the larger structures and rock formations. In general, the more precise methods are included under the term, *detail mapping*, and the less precise methods are *reconnaissance mapping*. In the former progress is slower and, therefore, more time is needed for covering a given area. The mapping is performed with as small an error as is consistent with the limits of error of the geologic structure (417). On the other hand, in reconnaissance work, speed is often of paramount importance, and a large limit of error may be permissible. For the field work for each problem, instruments are chosen and field methods are pursued, which will be best adapted to the needs of the particular case in hand.

Reconnaissance surveying, if properly done, is far more difficult than detail work. It requires wide experience, thorough training, quick judgment, constant observation of soils, vegetation, outcrops, and topography, and the ability to remember the impressions obtained during the part of the work already completed. The geologist must be able mentally to picture in three dimensions structures and formations which he can actually see, usually poorly exposed, in but two dimensions. In geologic training one should become proficient in detail mapping before attempting reconnaissance mapping. A good reconnaissance man is always on the alert. We know of one instance where such a man, accustomed to driving an automobile in his field work, noticed that his rear wheels became clogged with mud in a manner not characteristic of the wet mud of the locality. From this he was led to make a search which revealed a small area of exposure of an older formation uplifted by salt doming (161, 6). Hundreds of geologists would have passed by this incident without notice. Again, a good reconnaissance man, even if he must drive over the same route many times, will always be trying to account for the geology and physiography which he is traversing.

367. Note-taking in General.—Geologic notes should always be full and accurate. Do not rely on your memory. Write down all your observations and impressions. Be careful to distinguish between facts and theories. If you are not quite sure of a statement, punctuate it with a question mark in parentheses. Notes may be abbreviated to save time; but if scientific knowledge is to be increased by the investigation, abridgment of the field notes should not be of such a character as to impair their lucidity for any geologist who may subsequently read them. Symbols and unintelligible abbreviations should be listed with their meanings near the front of the notebook. Following are a few common abbreviations which may well be learned and put into practice. Others will suggest themselves as occasion demands.

ABBREVIATIONS OF GEOLOGIC TERMS FOR FIELD NOTES

about, ca.	metamorphosed, met.
basalt, b.	outcrop, etc.
bedding, stratification, bd.	rocks, rx.
conglomerate, cg.	sandstone, ss.
diorite, di.	shale, sh.
from, fr.	slate, sl.
granite, gr, γ.	specimen, sp.
joint or jointing, jt.	trap, tr.
limestone, ls.	

Strike and dip of bedding may be recorded in short form by always writing them in the same order: N30E40NW, meaning strike, N. 30° E., and dip, 40° NW.

It is good policy to write on only every other page so that plenty of space will be left blank for future additions and corrections. Illustrate all significant geologic structures and other features by sketches and diagrams. These are the briefest and most satisfactory means of recording information (Chapter XIX).

On the last pages of the field notebook the rock specimens and photographs should be separately catalogued (327, 328). For each specimen give its number, locality, field name, date of collection, and the page on which it is described, and leave spaces for additional remarks and for the numbers of thin sections if these are to be made. For each photograph give its number,

locality, name, the direction in which it was taken, and also remarks on time of day, light value, length of exposure, diaphragm, and focus (328, 358).

368. Four Principal Methods of Field Mapping.—Although the methods of geologic field mapping are innumerable and diverse, depending upon such factors as the nature of the country, the mode of travel, the degree of precision demanded in the work, and the individual preferences and notions of the geologist himself, yet most of these are simply variations of the following four principal methods: (1) the compass and clinometer method, (2) the hand level method, (3) the barometer method, and (4) the plane table method. These will be described below. To these might now be added (5) the methods of aerial mapping, discussed in Chapter XVII.

THE COMPASS AND CLINOMETER METHOD

369. Definition.—In the *compass and clinometer method*, frequently used in reconnaissance mapping, the clinometer is employed for taking dips and the compass for determining strikes and directions (331–333). Distances are often paced, on foot or on horseback, or are measured by odometer (356), and differences of elevation are commonly obtained by barometric readings, properly corrected (368). Where the topographic relief is comparatively low and the dips of strata are high, no attempt is made to ascertain the relative altitudes of stations or outcrops, for under such circumstances the resulting error is practically negligible. On the other hand, if dips average only 5° or 10° and the relief is considerable, the elevations of outcrops should not be disregarded (174).

370. Equipment.—For the compass and clinometer method of mapping, the Brunton compass with its clinometer attachment is most convenient. Besides this instrument one needs a tally register, a notebook, a working map if such is available, a protractor, pencils, hand lens, probably a hammer, a camera, and an aneroid barometer if elevations are to be determined. A Locke level may be of service. The compass should be set for magnetic declination (333).

Notebooks of various shapes and sizes are used according to the preference of the geologist. A convenient kind is 5 by $7\frac{1}{2}$ in., opening at the shorter edge, and having its pages ruled with coordinate lines $\frac{1}{5}$ in. apart. This easily fits in one's pocket.

371. Preparation of the Notebook.—Before you begin field work, the notebook should be made ready. Write your name and address on the inside of the front cover. On the first blank page, facing the front cover, record the name of the region where the investigation is to be made, and the year and date of beginning the work. The magnetic variation of the compass needle (332, 333) in the region is noted on the first ruled page. On page 3 you will start your notes unless you can secure a good topographic map of your area for a working map.

If you have a base map, its scale, contour interval, and name are to be recorded on the first ruled page, as well as the magnetic variation. Cut this map into rectangles of equal size and somewhat smaller than a page of the notebook, so that, if mounted, there will be at least $\frac{1}{4}$ -in. margin on the ruled page on all sides. Topographic sheets of the U. S. Geological Survey may be cut into nine rectangles, each bounded by parallels and meridians.¹ These rectangles may be mounted on a piece of linen or they may be pasted in the notebook. If mounted on linen, the sections should be separated a little to facilitate folding. When so mounted, all parts of the map are together and the whole can be folded and kept in a pocket in the notebook. If they are to be pasted separately in the book, number them as shown in Fig. 372. Glue rectangle 1 on page 3, making its upper and left edges flush with horizontal and vertical coordinates, respectively (looking at the open book with its length up and down). On page 5 mount rectangle 2 in a position exactly analogous to that of rectangle 1, but leave an inch or so near the upper margin of this map free. The lower edge of rectangle 1 can then be bent down to touch the upper edge of rectangle 2, if you wish to see the relations of contours, roads, etc., near this common

¹ These are called rectangles although actually the corner angles are not quite 90° on account of the northward convergence of the meridians.

margin. The other portions of the working map may be mounted like rectangle 2 in proper order on pages 7, 9, 11, 13, etc. Above each rectangle write its number. If you intend to adopt the *coördinate system* in taking your notes (373), letter the coordinate spaces (not the lines) above each rectangle, and number the spaces on the left of each rectangle, beginning at the top left corner (Fig. 373). In just the same manner letter and number the corresponding spaces on the even-numbered pages facing the maps. If the *point system* (373) is followed, the coördinate




FIG. 372.—Method of numbering the divisions of a working map.




FIG. 373.—Method of mounting a working map.

spaces need not be numbered or lettered. All the preliminary writing should be done in waterproof India ink, not in pencil nor in an ink that will wash off.

It is hardly necessary to say that the exact manner in which each geologist will keep his notes will depend on his own personal taste. The writer believes, however, that the student should be taught several accepted methods so that he may be able better to choose his own course in later work.

372. Compass Traverses.—When a good base map of a region to be surveyed cannot be procured, and the mapping is done by the compass and clinometer method, the geologist generally follows a course across country from point to point, finding the directions of the different parts of his route by compass. His

course is a *compass traverse*. Even if a base map is available, traversing by compass may be necessary because the scale of the map is too small or because it has some comparatively large areas so lacking in geographic features that stations can not be readily located by reference to it. Sometimes, also, short compass traverses are run from stations in a triangulation net or a stadia traverse (411).

Let us now briefly consider the manner of conducting a compass traverse. The first thing to do is to find, in the field, some point which has been definitely established by previous surveying. It may be a triangulation station, a land survey post, a geographic boundary monument, a claim post, etc. If a topographic map is provided, it may be the intersection of two roads, the confluence of two streams, etc., as shown on this map. Call this point Station 1.

Having located Station 1, find the bearing to any conspicuous object, preferably an outcrop, in the general direction in which the traverse is to be run, and pace to this object. Call it Station 2. If it is of geologic interest, record your observations. Proceed in the same way to Stations 3, 4, and so on. In this work it is always a good plan to check the course by sighting back to the last station, or by sighting from two or more of the stations to some recognizable point on one side or the other of the traverse (Resection, p. 509). For areal surveying traverses should be run as near one another as time will permit and near enough for the geologist to feel reasonably sure that he has seen most of the district. They should be connected at intervals by cross traverses.

Before setting out on a compass traverse, you should ascertain the approximate average length of your stride. This is best done by counting the number of paces in walking half a mile or some other known distance across country of the type you are to investigate, and then dividing this distance in feet by the number of paces. Two circumstances must be allowed for: (1) the length of a pace in going uphill or downhill is not the same as in travelling on level ground; and (2) the map value or horizontal projection of any interval on a slope is less than the actual distance (300, 364).

If elevations are to be determined, the aneroid barometer should be read at each station. For methods of correcting such readings, see Art. 390.

A compass traverse should be tied with a known point at its end as at its beginning. This point may be some new locality not yet visited on this particular route, or it may be Station 1. In the latter case the traverse is said to be *closed*. If the end does not tie up precisely, the gap distance should be measured and this error is subsequently to be divided up proportionally along the whole traverse when the final map is made (375). For closer checking the traverse may be tied in at other stations in the route or at previously established points.

373. Notes for a Compass Traverse.—With regard to recording the data of a compass traverse in the notebook, the student would do well to begin conforming to a prescribed system. Then, if he prefers, he is at liberty to change his method later. Following is an illustration of a convenient form for field notes:

July 17, 1914

Up a tributary of ——— River, starting at Sta. 46.

- From 46, N 10E-60 × N 60 E-35, banks low, evidently of drift × N75E-55 to Sta. 47, a 40' terraced bank of solid well stratified highly plastic blue clay, showing thin laminæ of fine brown sand $\frac{1}{2}$ "-1" apart. Strata nearly horizontal. If not well sorted Pleistocene, are Tertiary ×
- From 47, E-260 (at 160 are otc¹ of massive ss and sh in S. bank, N 40 E 40 SE (g). At 200 sh seems N 35 E 35 SE) × S70E-80, no rx. Bank slowly rising × N75E-100 to Sta. 48, large blocks of massive ss in stream, ca in place, seems N 10 W 20 NE (o) ×
- From 48, N80E-240 (at 60 are large otc¹ of fine and coarse sandy tuffs and agglomerates (Sp. 268) etc.

Observe that each compass bearing for the traverse is followed by a dash and the distance (in paces) of the line along which this bearing was taken; that a large cross (×) indicates a change in direction of the traverse; that notes for stops along a given part of the traverse, between changes in its direction, are put in parentheses; that the number for a hand specimen is given, also in parentheses, after the name of the rock from which it was

¹ See Art. 367.

collected; that strike and dip are recorded thus, N. 40 E. 40 SE.; and, that each such record for attitude is immediately followed by parentheses containing a letter to show how well the bedding was exposed and, therefore, how reliable the readings are for dip and strike. In the sample notes above, "g" means *good* or *bedding well exposed*, and "o" means *bedding obscure*.

Some geologists prefer to *plot* the traverse while *en route* (374), carrying it from page to page of the notebook, and recording all the notes in their proper places beside it. This plot, rough though it be, has the advantage of revealing errors which might be made in a *written* record of directions and distances.

Provided a base map can be secured for a working map, the geologist must first know: (1) how to locate, on the map, outcrops and other points of interest seen in the field; (2) how to record certain data on the map; and (3) the best methods of note-taking. He must be able to understand and interpret contour maps (Chapter XIII), since these, if well made, are most satisfactory for working maps.

Whether the working map is mounted in the notebook or separately, every outcrop or station at which observations are made is indicated on it by a dot or a small cross at the correct place. Where strata are exposed, the dip, strike, and rock type may be recorded by the symbols given in Art. 437. The different rocks seen, igneous, sedimentary, or metamorphic, may be colored in on the map as far on each side of the traverse as can safely be done without fear of serious error. In this case the distinction must be drawn between alluvium and the several varieties of bedrock. Where the alluvium is so thin and outcrops are so numerous that there can be little chance of misnaming the covered bedrock, the map is colored for rock rather than alluvium.

If the working map is on a large scale, all possible information is entered on it rather than in the notebook in order to simplify the task of recording. If the scale of the map is small, little more than the locations of the outcrops or stations can be indicated, and the other data must be written in the notebook.

are two commonly accepted methods of note-taking, the coordinate system and the point system. For the coordinate

system the working map is cut into rectangles which are pasted in the notebook, and the pages bearing the maps and those opposite the maps are lettered and numbered as explained in Art. 371. The dots or crosses, by which outcrops and stations are located on a given map, fall on the coördinate lines or in the intervening spaces. Suppose that the station is in the vertical space *B* and in the horizontal space, 5. It is then called *B: 5*. If it is on the vertical line between *A* and *B* and is still in 5, its position is denoted by *A-B:5*. Similarly, *B:5-6* indicates a station in *B* and on the line between spaces 5 and 6; and *A-B:5-6* refers to the intersection of the two lines. If two or three stations are in the same square, they may be called, *e.g.*, *B: 5 W*, *B: 5 SE*, etc., where the final letters signify compass directions.

The notes are started on the first odd-numbered page after the last map rectangle. In the middle of the page at the top write the date. Just below this, at the extreme left of the page, note the number of the map rectangle on which the traverse starts. On the next line, set in a little from the left margin, record the location of the first station or outcrop, *e.g.*, *B:5*. Then continue with the notes concerning *B:5*. Follow the same method for each outcrop. If the traverse runs on to a new rectangle, write the number of this new map in the same way as you did that of the first. Head each day's traverse with the date in the middle of the page. Below is an example:

SAMPLE OF GEOLOGIC NOTES

June 5, 1911

Map 4.

- G: 26.* Small exposure of sandstone. Bedding well shown: N20°W, 30°E.
K: 30. Conglomerate with rounded pebbles of quartzite and granite, quartzite predominating. Average, 3 in. in diam. Largest 5 or 6 in. No bedding seen.

Map 5.

- H: 2.* Sandstone like that seen at 4, *G: 26*. Bedding not seen.

The lettered and numbered page opposite each map is to serve as an index to the notes relating to the stations located on that map. For instance, if an outcrop in *C: 25* is described on page 41, 41 should be written in square *C: 25* on the page facing the map.

For the *point system*¹ the map, either with its original scale or photographically enlarged, may be mounted in any way, but preferably on linen. It can then be folded so that any rectangle is face out and can be held thus in the notebook with rubber bands. The stations at which observations are recorded are shown on this map by small crosses. The crosses in any rectangle (or other division of the map) are numbered consecutively from first to last.

The note-taking is essentially like that in the coördinate system except that the remarks on each locality are headed by its station number. When the book is filled a page index (*point index*) to the notes may be made in which each group of station numbers is listed in consecutive order, *e.g.*,

Rectangle III		
Stations		Pages
1		21-22
2-5		22-23
	etc.	

With regard to the advantages and disadvantages of the two systems . . . "locations can be fixed more quickly and more accurately on the map and can be referred to more quickly by this method than by the system of coördinates more commonly used. It is unlike the coördinate system in that the localities at which notes were made cannot be relocated if the map accompanying the notes is lost."²

It is a good habit, at night or on rainy days to copy in full the abbreviated notes recorded during the day. A separate book should be kept for this purpose. Here, too, lists of specimens and of photographs are to be rewritten. Indices arranged according to maps and station numbers, dates, and subjects, may be prepared, so that facts can easily be found when one starts in with the office work.

¹ A more detailed account is given by C. H. CLAPP on pp. 177-181 in "Economic Geology," Vol. VIII. This is one contribution in Bibliog., IRVING, J. D., *et al.*

² Bibliog., IRVING, J. D., *et al.*, Vol. VIII, p. 181 (CLAPP, C. H.).

374. Plotting Compass Traverses.—Compass traverses should be plotted as soon as possible, preferably in the field. This is done on a piece of paper, or on one or more pages of the notebook, a certain direction having been chosen as north and a certain distance having been selected as the unit of scale. A very convenient method is to rule the paper with coördinate lines spaced according to the adopted scale. Beginning at Station 1, the different parts of the traverse, from station to station, are drawn in with protractor and plotting scale.

In plotting directions on coördinate ruled paper, the course from any station to the next can be approximately laid out as the hypotenuse of a right triangle by measuring distances, equal to the two legs, along the E.-W. and N.-S. coördinates. Thus, suppose that Station *B* is N. 30° E. from Station *A*. Measure a unit distance of 1 *eastward* from *A* to *x*, and from *x* measure two units due *north* to *y*. Draw *Ay*, which will trend N. 30° E. On *Ay*, produced if necessary, mark off the distance *AB* on the adopted scale, thus obtaining the location of *B*. Paying due heed to compass directions, the following values¹ may be used for rough plotting in this manner:

TABLE OF RECTANGULAR VALUES FOR PLOTTING COMPASS TRAVERSES

Angle, in degrees measured from coördi- nate line	Distance, in number of squares, on short co- ördinate (leg)	Distance, in number of squares, on long co- ördinate (leg)
5	$\frac{1}{4}$	3.0
10	$\frac{1}{2}$	3.0
15	$\frac{3}{4}$	2.0
20	1	3.0
25	1	2.5
30	1	2.0
35	1	1.5
40	1	1.25
45	1	1.0

¹ After M. L. FULLER. Bibliog., FULLER, M. L., 1919, p. 414. This paper is an excellent description of practical methods in rapid surveying by compass, clinometer, and aneroid barometer.

375. Correction of Plotted Compass Traverses.—If the last station of a plotted compass traverse does not tie up accurately, that is to say, if it is a little out of place, the whole traverse must




FIG. 374.—First method of correcting a compass traverse. (Cf. Figs. 375, 376.)

be corrected. This may be accomplished as follows: let *abcde*, Fig. 374, represent a traverse of which the last station, *e*, should fall at *f*. Draw a line from *e* to *f* and, parallel to *ef*, rule lines from the other stations (*bx*, *cy* and *dz*). Divide *ef* into as many




FIG. 375.—Second method of correcting a compass traverse. (Cf. Figs. 374, 376.)

equal parts as there are stations in the entire traverse, less one. Here there are five stations. Therefore *ef* is divided into four equal parts. On *bx* mark a point, *m*, $\frac{1}{4}ef$ from *b*; on *cy* mark a

point, n , $\frac{3}{4}ef$ from c ; and on dz mark a point, o , $\frac{3}{4}ef$ from d . Draw $amnof$, which is the corrected traverse.

A more exact method is illustrated by Fig. 375. Here $abcde$, again, is the traverse as plotted from the notes, and f is the point at which e should fall. Determine what percentage of af is represented by ae . Here ae is 101 per cent of af , i.e., ae is 1 per cent too long. Therefore the length of each part of the traverse (ab , bc , etc.) must be reduced by 1 per cent of its present length. The angle between ae and af is 10° , and af is to the south of ae . Hence the direction of each part of the traverse (ab , bc , etc.) must be shifted southward 10° . The procedure is as follows: draw av making an angle of 10° with ab at a . From a




FIG. 376.—Corrected traverses of Figs. 374 and 375 shown together for comparison.

measure off $ap = 99$ per cent of ab . From b draw bw making an angle of 10° with bc . From p draw a line parallel to bw , and on this line measure off $ps = 99$ per cent of bc . Proceed in the same way with cd and de .

The first method is not accurate because it takes no account of angles, yet it is usually satisfactory for compass traverses. It requires less time than the second method. The difference in the results obtained by both operations is shown in Fig. 376.

THE HAND LEVEL METHOD

376. Definition.—The hand level method may be used in regions where stratified rocks have dips too low for satisfactory measurement by clinometer. The hand level is employed for taking differences of elevation on any given stratum. The dip of

this stratum can then be indicated as a fall of so many feet per mile between certain designated points. Distances may be obtained by pacing, odometer, etc., or by stadia if a telescopic stadia hand level is used. Directions are found by compass.

377. Equipment.—The equipment necessary for the hand level method includes a Locke level or a telescopic hand level, a Brunton compass, a tally register or other instrument for recording or measuring distances, a notebook, a base map if one can be obtained, pencils, etc.

378. Determination of Strike.—To find the approximate strike of an inclined bed, stand on the top¹ of the bed at some point from which the same bed is visible at a distance either across a dip slope or across a valley. Sight through the hand level at the distant outcrop of the bed where this is about at the same level as the observer. Holding the instrument horizontal, swing it back and forth until the top of the bed¹ in the distant outcrop is on a level with the middle cross hair. The direction in which the instrument is pointed will then be the approximate strike. Determine this direction by compass.

379. Determination of Dip.—To find the dip of an inclined bed, stand on the top of the bed¹ and select a distant outcrop of the same bed as the station to be observed. Choose some object, the height of which can be easily judged, near the distant outcrop. Taking this height as a unit of vertical measurement, a *step*, see how many times it will be included in the vertical distance between a horizontal line from the observer's eye toward the distant outcrop and a point which is the height of the observer's eye above the top of the bed in the distant outcrop. The approximate inclination of the bed between the two points will be the height of the *step* times the number of *steps* recorded. This is usually expressed in feet per mile.

Unless the strike of the inclined bed is known and the measurement of the dip is made at right angles to the strike, the observed

¹ The top of the bed is here mentioned, but any recognizable horizon within the bed, or its bottom surface, can be used, provided the same horizon is sighted at the distant exposure.

inclination, obtained as described above, will not be the true dip. It will be a component of the dip, measured in a certain direction not perpendicular to the strike. If the geologist finds several dip components in as many different directions, he can make an estimate of the approximate value of the true dip and its direction (488).

380. Hand Level Traverses.—For the most part the hand level is used only for short branch traverses, or for side shots from traverses mapped by other methods. Sometimes, however, extensive areal mapping can be done by this instrument. Directions and distances will then be run and corrected as in the compass and clinometer method. Elevations, obtained by stepping or levelling, may be checked by planning the traverses to meet or intersect at certain stations, and the errors in elevation, discovered by failure to tie in at these stations, can be divided proportionally, in each case, among the several stations of the traverse since the last similar station where correction was made.

381. Note-taking.—Since the hand level method is seldom applied in extensive mapping, there is no special system of note-taking devised for it. Notes may be kept much as in the compass and clinometer method. If a base map is supplied, all the written information and also arrows for dips or dip components can easily be recorded on this map.

THE BAROMETER METHOD

382. Definition.—The barometer method of field surveying¹ involves the measurement of relative elevations by an aneroid barometer or by a Paulin altimeter (341).² The method is employed principally in regions of stratified rocks where dips are so low that they are most satisfactorily determined by

¹ For earlier descriptions of the use of the aneroid barometer in this connection, see Bibliog., GILBERT, G. K., 1882; Bibliog., CAMPBELL, M. R., 1896. M. R. CAMPBELL described this method as he applied it in investigations for coal.

² A Paulin altimeter, being essentially a special form of aneroid barometer, may be used in the barometer method instead of the ordinary aneroid if the geologist prefers.

obtaining elevations on a chosen key bed (317), rather than by using a clinometer. Although, in the name of this method, emphasis is placed on the importance of the barometer and on the measurement of vertical distances, the geologist should realize that directions and horizontal, or essentially horizontal, distances between stations must also be measured. Directions may be found by compass or by triangulation, and distances by pacing, odometer, etc., or by triangulation. If a good base map is provided, the locations of stations may often be estimated by reference to recognizable landmarks, and plotted by eye.

383. Equipment.—In addition to the aneroid barometer, the geologist will need a compass, a watch, a coordinate-ruled notebook, a hand level, and a base map upon which to mark the positions and elevations of stations along his traverse. He will find a tally register serviceable for pacing and an odometer indispensable in automobile work. In some cases he may use a small plane table and open sight alidade (347). The compass should be corrected for the local declination (333). When two or more men work together in the same area, their watches should be set together. The notebook is most serviceable when ruled in fifths or tenths of inches. Any fairly accurate county, state, or property plat will generally do for a base map. An aerial photographic map may be particularly useful (Art. 423). There is no special need to have a base map that shows topographic features, although it is well to have streams indicated. If the geologist cannot procure a satisfactory map of some sort, he should make or have made a simple outline map showing a few prominent landmarks in their correct relative positions, so that he can tie his traverses to these. Where the land is sectionized, he can often sketch his own base map along with his geologic work. The degree of precision demanded in the work will determine the kind of base map necessary.

384. Horizontal Control for Mapping by Barometer.—Before considering in detail the use of the aneroid barometer, we may well give some attention to the subject of the horizontal control. By horizontal control is meant the system of measured horizontal distances and directions between the stations included in the

mapping. These stations may be classified under two heads: (1) certain relatively few points, known as control stations, which are located with considerable accuracy; and (2) those stations which are less precisely located and which have their positions established in reference to the stations of the first class. As a matter of fact, the *control stations* govern the positions of all the other stations not only in respect to their horizontal distances and directions, but also in respect to their relative elevations. The student should bear in mind the distinction between these terms *horizontal control* and *control stations*.

There are many variations in the methods adopted in establishing the horizontal control for barometric work. If a satisfactory base map is provided, the horizontal locations of stations are often simply estimated by reference to recognizable charted landmarks and are accordingly plotted by eye on the map. The degree of accuracy of this method depends on the number and distribution of such recognizable points, and also on the class of workmanship of the map. In any event the limit of error is likely to be large.

Ordinarily the geologist will find it necessary to prepare some kind of a horizontal control along with his barometric work. This he may do by running a system of compass traverses in which distances are measured by pacing, by horse paces, by the revolutions of a wheel, by odometer, etc. (372), or he may use a small plane table and an open sight alidade or a Gurley compass. In sectionized country where roads lie on nearly every section line, directions of road traverses are along north-south or east-west lines and are easily mapped. In such country travel is generally accomplished by automobile. Only occasional branch traverses, on foot or in the automobile, must be run by compass and measured by pacing or odometer, as the case may be. For the running of irregular compass traverses and their correction see Arts. 372-375.

The use of the small plane table and open sight alidade, rather than a compass, is chiefly a matter of individual preference. With the plane table, the features may be mapped as a route

traverse with branch sights where necessary or as a triangulation network (Art. 411).

385. System of Recording Stations.¹—The writer has found it most convenient, for note-taking, to designate days by letters and stations by numbers. Thus, in a given area, the first day will be *A*, the second *B*, and so on until the investigation is finished. The next area will be commenced *A*, again. If more than 26 days are spent in one district, the 27th day will be *AA* or *2A*, the 28th *BB* or *2B*, and so on. The stations on the first day will be *A1*, *A2*, *A3*, etc.; on the second day, *B1*, *B2*, etc. These symbols are plotted on the base map and are recorded in the notebook, as will be explained presently. Some geologists use consecutive numbers for an entire field season or for an entire district or problem, even when more than a single season is consumed in the work.

386. Graphic Method of Note-taking.—According to the method devised by M. R. Campbell, the notes may be recorded in the form of a profile section. Figure 377 illustrates one. To explain this let us assume that the geologist is at Station *A1*. He has a sufficiently clear idea of the area to know that Station *A1*, his starting point is rather low and that most of the stations which he will visit will be above the level of Station *A1*. The barometric elevation at this station he finds is 2,460 ft. Consequently, holding the notebook with its length right and left, he chooses a horizontal line rather low on the page, in order to leave room above for higher points, and he labels the left end of this line, "2,400." Letting 1 in. = 100 ft., the other horizontal lines are labelled accordingly, upward and downward from the first line (Fig. 377).

Suppose that he arrives at Station *A1* at 8 A.M. On the intersection of the 2,460 line and a vertical line at the left of the page, he marks a small cross or a dot to represent *A1*. Let the direction from *A1* to the next station be due north. Along this same vertical line he writes, "*A1*, 8.00 A.M., No.," and any other

¹ This article and much of the following description of the barometer method have been taken from *Economic Geology*, Vol. XV, pp. 150-169. Bibliog., LANE, F. H., 1920.

necessary information. If, as we may suppose, A1 is on the top of a bed of limestone, this is plotted by the usual symbol.

He now proceeds 110 double paces to Station A2, a point here assumed to be on a 10-ft. bed of sandstone, at an elevation which he reads as 2,500 ft. He arrives at A2 at 8.10 A.M. Letting the horizontal scale of the section be 1 in. = 100 double paces (equals approximately $\frac{1}{10}$ mile), he plots A2 according to the adopted scales. As before, he writes on the vertical line through the point for A2, "A2, 8.10 A.M., N10E.," the direction being from A2 to A3. To save time that might be lost later in measuring distances in the notebook, he records the number of




FIG. 377.—Profile section of features observed on a traverse.

paces from A1 to A2. He represents the sandstone bed by the convention for that rock (437).

In this manner he continues from station to station, recording whatever information seems to be of importance and sketching the topographic profile along his traverse.

Every effort should be made to settle the correlation of the strata during the course of the field work, and the correlations should be suggested in the section by dashed lines, as in Fig. 377. The profile section is carried from page to page, care being taken to keep the elevation coördinates as nearly as possible in the same

relative positions on the sheet. The section should terminate on each page at a station and should begin on the succeeding page at the same station at about the same level on the page, so that the pages may be matched for comparison.

387. Tabulation Method of Note-taking.—In many cases much time may be saved by keeping the notes in tabulated form. This may be done especially when speed is required, when travel is done by automobile, and when a structure contour map, and not a geologic section, is the principal graphic result to be attained. The following plan of tabulation has been found to be serviceable. The facts indicated in Fig. 377 are recorded in this table.

TABLE I.—TABULATED NOTES

Station	Time	Barometer	Corrected barometer	Direction from last station	Distance from last station (paces)	Remarks
A1	A. M. 8.00	2,460	No.	...	Top of 5 ft. bed yellowish ls. Abundant <i>Fusulina</i> . Call "L1."
A2	8.10	2,500	N10E	110	Top 10 ft. brown blocky ss. Call "S1."
A3	8.22	2,520	No.	140	S1.
A4	8.30	2,490	No.	55	L1.
A5	8.35	2,460	No.	60	Change of slope.
A6	8.45	2,440	No.	135	Stream channel.
A7	8.52	2,475	N30W	95	No outcrops. L1.

If an automobile is used, the trip distance is recorded in the sixth column. The fourth column is left blank to be filled in subsequently with the corrected barometric readings (388 *et seq.*).

As in the graphic method of taking notes, the positions of the stations are to be marked on the base map.

388. Necessity for the Correction of Barometric Readings.—

An aneroid barometer is in principle a sensitive air pressure gauge. If properly made, it is "compensated for temperature," *i.e.*, it will read correctly any pressure irrespective of the temperature of the instrument. In this it has an advantage over the mercurial barometer which requires correction due to the unequal expansion or contraction of the mercury and the containing glass under varying temperatures.

The aneroid barometer and the Paulin altimeter are used for registering differences of elevation. If the temperature of the air were constant, a scale for altitude could be made to correspond to a scale for pressure; but since air density varies with changes in temperature, these instruments can be made to read altitude correctly only at one temperature. This is known as the *temperature of calibration* of the instrument. Generally speaking, aneroids and Paulin altimeters are calibrated to register correct altitudes at 50°F. If the air is warmer than 50°, the elevation indicated on the barometer will be too high, because the air, being lighter, will have a pressure corresponding to a higher altitude at 50°. On the other hand if the air temperature is below 50°F., and, therefore, abnormally heavy, the aneroid will record an elevation too low. Obviously, therefore, barometric readings must be corrected for these errors due to the effect of temperatures above or below the temperature of calibration of the instrument.

Another very important source of error in the use of the barometer lies in the fact that atmospheric pressure is subject to almost continuous and often violent changes. Thus, if an aneroid is left undisturbed in the same place for 24 hours, the needle will gradually alter its position. Under ordinary conditions, it will swing slowly downward¹ from dawn until 9 or 10

¹ *Downward* and *upward* are here used in reference to the scale in feet, for elevations. When the needle points to successively lower elevations, it naturally indicates higher pressures in inches of mercury.

o'clock, after which it will remain nearly steady for an hour or two; then it will rise, at first slowly and later, by 1 or 2 P.M., more rapidly until between 4 and 6 P.M., when it will again change and begin to fall. These movements are illustrated in Fig. 378. There is some variation, both from day to day and




FIG. 378.—Type curve illustrating diurnal variations in atmospheric pressure from 6.30 A.M. until 9.30 P.M. on a day when conditions were exceptionally steady. (Cf. Fig. 380.)

from season to season, in the time of the changes from rise to fall, and from fall to rise.

The regular curve of diurnal barometric variation is more or less modified by local fluctuations in atmospheric pressure such as may be caused by gusty winds, "twisters" or "baby tornadoes," irregular air currents due to the effects of strong topographic relief, and especially by storms (Figs. 379, 380).




FIG. 379.—Curve of atmospheric pressure variation during a thunderstorm, plotted from observations made at frequent intervals at a single station.

Just as in the case of errors due to atmospheric temperature barometric readings must be adjusted for this second class of errors caused by atmospheric pressure changes, if such readings are to be correct. Although corrections for temperature should properly be made before those for pressure variation, we shall describe the latter first, partly because the temperature factor may often be omitted from consideration (397), whereas correc-

tion for pressure change must always be made; and partly in order to avoid confusing the reader in explaining this subject of correcting for pressure variations. The matter of temperature corrections is left for Art. 394.

389. Correction for Atmospheric Pressure Variations.—Since variations in atmospheric pressure are constantly in progress, the elevations indicated by an aneroid while traversing are




FIG. 380.—Examples of atmospheric pressure curves, as indicated by barometric readings, on different days. *A* to *D* are by the same barometer. *E* was plotted from the record of a poor barometer. *A* and *B* show abnormally large increases of pressure during the afternoon. *C* is abnormally flat. *D* is characterized by several rises and falls due to unsteady weather conditions. A thunderstorm occurred during the drop at *t*. The great diversity of these curves shows how great may be the errors due to correcting barometric readings by the use of a type or average curve.

incorrect. All through the day atmospheric changes are being superposed, as it were, upon relief variations, and before the recorded barometric readings can be regarded as truly representing differences in topographic relief, the atmospheric variations must be eliminated. To a certain extent this may be done by reference to a type atmospheric pressure curve, like that in Fig. 378, which the geologist can obtain by a barograph (342, 390 ¶ 8), or by observations on his aneroid or on another while not in use in the field; but correction by this means is very rough and large discrepancies may result from the effects of the local atmospheric variations (Fig. 380). This method should be avoided when possible and should never be employed unless the allowable error in elevations of stations is large.

The only safe way to eliminate the effects of fluctuating atmospheric pressure is by *checking the barometric readings* at frequent intervals during the field work. It is safe to say that the proficiency of the geologist in the barometer method of mapping and the accuracy of his results depend almost wholly upon his skill in checking and correcting the barometric readings. The more important methods of checking are described below.

390. Methods of Checking Barometric Readings.—1. *Checking on an Established Control.*—If there are points, such as U. S. Geological Survey bench marks, U. S. Geodetic Survey monuments, railroad stations, etc. of which the true elevations have already been established, in the region to be geologically surveyed, these points may serve as a control for correcting the barometric readings. The traverses should be planned so as to include such stations. In sectionized country bench marks are usually to be found at the section corners or the township corners.




FIG. 381.—Plot of a traverse. The correction curve for the barometric elevations on this traverse is shown in Fig. 384.

To illustrate this method, let us suppose that Fig. 381 is the plot of a traverse. The crosses are stations of which the true elevations have been determined. If the true elevations of 1 and 6 are 700 and 630 ft. above sea level, respectively, and the barometric elevations at these same stations were recorded as 775 and 750 ft., respectively, the barometer was reading 75 ft. too high at Station 1 and 120 ft. too high at Station 6; that is, while the geologist went from 1 to 6, the atmospheric pressure curve rose $120 - 75 \text{ ft.} = 45 \text{ ft.}$

Checking by reference to established control stations is the best method of ascertaining the variations of the barometer provided the elevations of these stations are reliable; but ordinarily such control points are too infrequent, and, accordingly, other methods of checking must be employed.

2. *Checking by Two or More Readings at a Station.*—When several minutes are spent at one station, perhaps in studying the fossils or rocks, or in automobile delays, the aneroid should be read shortly after arrival and just before leaving. It is better to wait two or three minutes after arriving to allow for lag of the instrument. Otherwise, the first reading might perhaps be made immediately after a considerable ascent or descent from the preceding station, whereas the second reading would be made after the aneroid had been kept at rest for some time. With some instruments the results obtained under these unlike conditions would not be exactly comparable.

A distinct rise or fall in the barometer during a stop of 30 minutes or more is probably atmospheric and should be recorded, as at Station 7 in Figs. 381 and 384. Usually changes observed during shorter stops should be given little weight.




FIG. 382.—Plot of a course to illustrate checking by branch traverses.

3. *Checking by Branch Traverses.*—Figure 382 shows a map of a traverse. The geologist's course, in the order of stations visited, was 1, 2, 3, 2, 4, 5, 4, 6. At 2 and 4, each, he obtained two readings which served to indicate whether the atmospheric pressure curve was steady, rising, or falling, while he visited 3 and 5, respectively. For example, if his instrument showed an elevation of 1,140 ft. at Station 2 when he first arrived there, and an elevation of 1,150 ft. at Station 2 after his return from Station 3, the atmospheric pressure increased 10 ft. while he made the branch traverse to 3. By this method, the effects of lag are largely eliminated by reading always upon arrival at the station:

but it has the disadvantage that serious discrepancies may appear at the end stations of adjoining branch traverses, as at 3 and 5. When such branch traverses are near, the geologist should connect them, going, for instance, from 5' to 3, before he returns to 4.

4. *Checking by Closed and Intersecting Traverses.*—A closed traverse is illustrated in Fig. 383, A, and an intersecting traverse in Fig. 383, B. The progress of the geologist was in the sequence of the station numbers. When he returned to 1 from 6, Fig. 383, A, his aneroid reading showed what the total change in atmospheric pressure had been since he departed from 1 toward 2. In




FIG. 383.—Plots to illustrate checking by closed and intersecting traverses.

the method of Fig. 383, B, a check was obtained on the atmospheric curve at 2 and at 1.

The reader should observe that there is nothing in these methods of checking to indicate just how the atmospheric pressure varied in the intervals between checks. Thus, it might have risen 10 ft., or it might have dropped 10 ft. and risen 20 ft., and the result, as far as could be detected by the checking, would have been the same in either case. The error would be in the elevations at the intermediate stations. The closed and intersecting traverses have the advantage of distributing such errors among all the stations in the closure, so that the error at any one station is relatively small. Obviously the shorter the time allowed to elapse between checking, the less opportunity will there be for large errors (416).

5. *Checking by Return Traverse.*—If the geologist returns on the same day along the same route, he may read his barometer a second time at several, not necessarily all, of the stations of his traverse. The double record at each of these check stations will indicate the amount of atmospheric pressure change between the visits to their particular station. This is like a combination of the second and third methods of checking. It is useful especially in automobile work in rough country where roads are few and are more or less parallel, perhaps following steep-sided divides or narrow canyons. It will suffice for a single day's work, or it may be repeated on successive days, but before the mapping in such a region is complete, these parallel or radiating traverses must somewhere be connected and tied in on one another by occasional cross-country traverses, even if these have to be made on foot.

6. *Checking by Hand Level.*—Both sight and telescopic hand levels may be used to considerable advantage in checking barometric readings at stations of approximately the same altitude. The geologist may level from one point to another visible point from which he has come or to which he is going, and if the two stations differ in elevation, he may estimate this difference. Assuming, for example, that the hand level shows Station 1 to be 10 ft. higher than Station 2 and the barometer indicates that Station 1 is 20 ft. higher than Station 2, then the atmospheric pressure has risen 10 ft. in the time elapsed while going from Station 1 to Station 2. Whenever a check is made by hand level, the fact should be recorded in the notebook. Care should be taken to see that the hand level is in perfect adjustment.

7. *Checking by Eye.*—The constant comparison, by eye, of the observed barometric readings with the true slopes and elevations of the ground traversed is fairly difficult, for it requires experience and judgment. It means that the geologist must have an idea not only of the topography, but also of the structure, which he is crossing, and it means that he must give constant attention to the barometric elevations which he records. This method is particularly valuable for catching sudden rises and

falls of the barometer entirely inconsistent with the true relative elevations. Such sharp changes do occur, especially in the vicinity of thunderstorms and they should be detected if possible, for otherwise a rise or a fall that actually happened within a few minutes and while the geologist moved only a short distance may be distributed over a much longer period of time and a larger part of the traverse, thus leading to an erroneous profile of the ground and most probably a distorted geologic structure.

8. *Checking by Reference to Another Record.*—Some geologists take a barograph into the field with them and place it somewhere near the center of the area to be surveyed during the day. Or an assistant at camp, or at some chosen spot in the field, may note and record the readings of a second stationary aneroid every 15 minutes or half hour during the day. The record made automatically by the barograph, or the curve plotted by the assistant from the record of his aneroid, can then be used to correct the readings of the field man's barometer. Besides the fact that a barograph or a second aneroid is an unnecessary burden, this method of checking and correcting is generally unsatisfactory because the stationary instruments may fail to record sharp local atmospheric pressure changes that may affect the field aneroid, and, on the other hand, they may register changes which escape the field aneroid. In other words, atmospheric pressure variations, even though pronounced, may sometimes affect areas of relatively small extent.

391. *Plotting the Correction Curve.*—The following is a brief explanation of the plotting of the atmospheric pressure curve, or, as we have called it here, the *correction curve*.¹ Let Fig. 381

¹ This curve, as it is derived from observations by the aneroid barometer, is to a large extent indicative of actual variations in the pressure of the atmosphere; but it no doubt includes, also, certain indeterminable irregular fluctuations consequent upon the individual peculiarities of the barometer. These fluctuations, as well as the atmospheric pressure variations, are for the most part eliminated by the application of the correction curve. The reader should remember that, in this explanation, we are still disregarding errors which may have been occasioned in the records as a result of atmospheric temperature (388, 394).

represent a traverse in which several methods of checking have been employed, yielding the results listed in the table below.

TABLE II.—BAROMETRIC READINGS RECORDED ON A TRAVERSE

<i>A</i> Station	<i>B</i> Time	<i>C</i> Barometer	<i>D</i> Corrected barometric readings	<i>E</i> Elevations previously established
	A.M.			
1	6.00	625	700	700
1	7.30	620	700	700
2	8.00	575	660	
3	8.20	580	665	
4	8.50	685	780	
3	9.15	565	665	
5	9.30	535	640	
6	9.40	525	630	630
7	10.00	540	650	
8	10.25	505	615	
9	10.45	520	630	
10	11.10	550	660	
11	11.45	595	700	
	P.M.			
7	12.15	550	650	
7	1.00	560	650	
8	1.15	535	625	
12	2.00	560	635	635
13	2.20	570	640	
14	2.35	590	655	
15	3.00	620	680	
2	3.30	605	660	
1	3.50	650	700	700
1	5.30	655	700	700
1	7.05	640	700	700

Camp is at Station 1 which happens to have its elevation already established as 700 ft. above sea level. It is therefore a control station. Stations 6 and 12 are also control stations (column E, Table II). At 6.00 A.M. the barometric reading was

625 ft. or 75 ft. too low, at Station 1. For plotting the curve, take a piece of coördinate-ruled paper and, holding it with its length right and left, label every other vertical line for the hours, beginning at 6 A.M. (Fig. 384). Every space, right and left, will correspond to 30 minutes, and smaller intervals of time can be interpolated. Label a horizontal line near the middle of the page "0"; label the next line, both above and below the "0" coördinate, "20," the next "40," and so on, as far as seems necessary. The horizontal coördinates below the zero coördinate represent quantities, in feet, to be added to the barometric




FIG. 384.—Correction curve (curve of atmospheric pressure variation) for barometric elevations recorded on the traverse plotted in Fig. 381. The diagram illustrates the lower part of a page in the notebook.

readings to obtain corrected elevations, and those above the zero coördinate represent quantities to be subtracted from the barometric readings to obtain corrected elevations. Since the first reading, at 6 A.M., was 75 ft. too low, 75 ft. must be added for correction. Mark a cross (for an established control station) at a point on the 6 A.M. vertical line one-fourth of a space up from the 80 ft. horizontal line. At 7.30 A.M. the barometer read 80 ft. too low. Mark the intersection of the 7.30 vertical line and the 80 ft. horizontal line.

Between the two visits to Station 3, at 8.20 and 9.15 A.M., the barometer fell 15 ft. Somewhere well below the probable position of the curve to be drawn through the points just plotted, mark a point (*m*, Fig. 384) on a horizontal line at 8.20 and another

point (*n*, Fig. 384) three-fourth space (= 15 ft.) below *m* on the 9.15 line. Draw a straight line between *m* and *n*. *mn* may be called a *guide line*. It is not necessarily parallel to the ultimate correction curve (Cf. *st* and *vw*, two other guide lines), but merely indicates to the eye that points in the curve corresponding to the ends of the guide line are related to one another exactly as they are in the guide line. This will become clearer presently.

At Station 6, at 9.40 A.M., the barometric reading was 105 ft. too low. Mark a cross (again for an established elevation) where the 105 coördinate intersects the 9.40 coördinate.

At Station 7 readings were made at 10.00 A.M., and at 12.15 and 1.00 P.M. 12.15 to 1.00 was the lunch period. Again, below the region of the curve, construct another guide line, *opr*, *o* being at the intersection of any horizontal line and the 10.00 A.M. vertical, *p* being 10 ft. above *o* and on the 12.15 coördinate, and *r* being 10 ft. above *p* and on the 1.00 P.M. coördinate. The 10-ft. intervals correspond to the rise of the barometer from 540 at 10.00 A.M. to 550 at 12.15 P.M., and from 550 at 12.15 P.M. to 560 at 1.00 P.M.

A guide line is plotted for Station 8, visited twice, and for Station 2, visited twice. Also crosses are plotted at 2.00 P.M. and 75 ft. for Station 12 (columns *C* and *E*, Table II), and at 3.50 P.M. and 50 ft., at 5.30 P.M. and 45 ft., and at 7.05 P.M. and 60 ft., these last three being readings at Station 1.

The correction curve is drawn through the plotted crosses, which indicate the actual corrections to be made, and in such a way that points in this curve are the same distances apart, vertically and horizontally, as the end points of the several guide lines, vertically below. For example, *v'* is in the curve at 8.00 A.M. and *w'* is in the curve at 3.30 P.M., 30 ft. higher than *v'*. These are exactly the relations of the end points of the guide line, *vw*, but, to repeat what was stated above, the curve between *v'* and *w'* is not by any means necessarily parallel to the guide line, *vw*.

The curve is drawn smoothly except for storm depressions (Fig. 379) and the effects of sudden jars. It is not drawn as a series of connected straight-lines.

Observe that two or more readings may be taken at the same station before starting in the morning and after returning in the afternoon. These additional observations are seldom made by geologists, but the writer has found them to be of considerable value in showing the slope and general tendency of the curve. Note also that the curve is drawn through the crosses, that is, through the points which indicate the corrections to be applied at stations whose elevations have been previously established. The guide lines are obtained by checking. In this traverse (Fig. 381) checking was accomplished by reference to control stations at 1, 6, and 12; by closure at 2, 7, and 8; by branch traverse at 3; and by two readings with intervening wait at 7.

392. Application of the Correction Curve.—By means of the correction curve, constructed after the manner above described, any barometric readings made during the day may be corrected. If notes were kept by the graphic profile method, the corrected elevations may be written against the proper points in the profile section. If the notes were tabulated, the corrected elevations are to be written in a column for the purpose (see the tables on pp. 466 and 475).

For illustration of the way in which corrections are made, let us take Station 14 (see the table on p. 466). The barometric elevation for 14 was observed to be 590 ft. at 2.35 P.M. A point at 2.35 P.M. in the curve, Fig. 384, is just below the horizontal line that would represent "add 65 ft." Approximately 65 ft., then, should be added to the recorded reading, 590, thus giving the true elevation of Station 14 as 655 ft.

Where stratigraphic intervals must be added to or subtracted from the elevations of certain strata in order to obtain elevations on a chosen key horizon (88, 89, 317), this may be done at the same time as the correction of the barometric readings, and the *corrected elevation of the key horizon* may then be entered in the notebook, in the manner suggested above, ready to be copied on to the map.

393. Comparison of Different Correction Curves for the Same Route on Different Days.—The beginner sometimes finds it

difficult to understand how dissimilar correction curves can give essentially the same results for the corrected elevations of the

TABLE III.—BAROMETRIC READINGS RECORDED ON A TRAVERSE

<i>A</i> Station	<i>B</i> Time	<i>C</i> Barometer	<i>D</i> Corrected barometric readings	<i>E</i> Elevations previously established
	A.M.			
1	7.00	580	700	700
1	7.18	570	700	700
2	8.00	520	660	
3	8.30	525	665	
4	9.00	645	780	
3	9.15	530	665	
5	9.40	500	640	
6	10.00	480	630	630
7	10.30	485	650	
8	10.50	435	615	
9	11.15	440	630	
10	11.50	460	660	
11	12.15	495	700	
11	12.45	490	700	
11	1.30	500	700	
7	1.55	460	650	
8	2.10	435	615	
12	3.00	475	635	635
13	3.30	485	640	
14	3.45	505	655	
15	4.10	530	680	
2	4.45	500	660	
1	5.05	535	700	700
1	5.30	545	700	700
1	7.00	570	700	700
1	9.00	555	700	700

same stations visited on different days. We have, therefore, added Table III in which are listed the data obtained in repeating the traverse shown in Fig. 381 on a second day. Figure 385 represents the correction curve based on these data.

All barometric readings, on this second traverse, were lower than on the preceding day (Fig. 384), so that quantities of over 100 ft. had to be added for correction. By careful study of this figure, and comparison with Fig. 385, the reader will observe that the elevations obtained from either curve are practically identical for each station. There is opportunity for a variation of perhaps 5 ft.—hardly 10 ft.—in elevations adjusted from the part of the curve (Fig. 385) between 3.15 and 4.15 P.M. Also, a 5-ft. drop or a 5-ft. rise of the curve at 10.30 A.M. (Station 7), either of which would be possible, might cause a




FIG. 385. —Correction curve based on data recorded in going over the traverse illustrated in Fig. 381 on a stormy day. (Cf. Fig. 384.)

difference of 5 or 10 ft. in the corrected elevations of Stations 8 and 11, visited between the two records at Station 7. Note, however, that variations of this degree would only very slightly alter the *relative* elevations of adjacent stations; and the errors which might affect stations rather far removed from one another would usually be less than the probable limit of error of the stratigraphy (417).

394. Correction for Atmospheric Temperature.—As stated in Art. 388, aneroid barometers are calibrated to record elevations correctly only at a specified temperature. The difference between the elevations (pressures) read at two consecutive stations will be too small if the temperatures at the stations are above the calibration temperature (here assumed to be 50°F.), and *vice versa*. "These differences . . . amount to approximately $\frac{3}{10}$ of 1 per cent" (of the difference of elevation at the

stations) "for each degree of temperature above or below 50°F. If air were a true gas its density at any temperature would be inversely proportional to the absolute temperature . . . and a 1° change would cause a pressure variation of 0.1961 per cent. Actually, the rate of change, due to the fact that air is not a true gas, is 0.2039 per cent for each degree above or below 50°F."¹

For example, if the temperature at Station A were 60°F. and at Station B were 70°F., the average temperature would be 65°, or 15° above the temperature for which the instrument is calibrated. Let us suppose that the recorded elevation at A is 200 ft. lower than at B. Using $\frac{2}{10}$ of 1 per cent for each degree (15°), the correction would be $0.2 \times 15 = +3$ per cent. The true difference of elevation would be, not 200 ft. as read, but 200 ft. + 3 per cent of 200 ft., *i.e.*, $200 + 6 = 206$ ft.

Generally it is simpler to use the sum of the temperatures at each two successive stations, and to multiply by $\frac{1}{10}$ of 1 per cent. If the sum is greater than 100°, the percentage factor is positive; if less than 100°, it is negative. Thus, in the example above cited, the temperatures, 60° and 70° are added, making 130°, from which is subtracted 100°, leaving 30°. Multiply this result by $\frac{1}{10}$ of 1 per cent and multiply the result by the difference of elevations, here 200 ft.

$$0.1 (30) = +3 \text{ per cent}$$

$$3 \text{ per cent of } 200 = +6$$

The corrected difference of elevation is $200 + 6 = 206$ ft.

If the temperatures had been 30° and 50°, and the recorded difference of elevations 160 ft., the procedure would be:

$$30^\circ + 50^\circ = 80^\circ$$

$$80^\circ - 100^\circ = 20^\circ$$

$$0.1 (-20) = -2 \text{ per cent}$$

$$-2 \text{ per cent of } 160 = -3.2$$

This means that the quantity 3.2 ft. is to be subtracted from 160 ft., making the difference of elevations actually 157.8 ft.

¹ Bibliog., HILL, RAYMOND A., 1929, p. 3.

In order to facilitate the correction of barometric (aneroid or Paulin altimeter) readings for the temperature factor, we have prepared the chart shown in Fig. 386). On the left are shown feet of difference of elevation between successive stations. For differences greater than 100 ft., use tens and multiply the final result by 10 or 100, as the case may be. Thus, if the difference in elevations is 320 ft., make the calculations for 32 ft. and multiply the final result by 10. Similarly, if the difference is 1,100 ft.,




FIG. 386.—Graph for making temperature corrections in barometric readings.

calculate for 11 and multiply the final correction by 100. The radiating lines in the diagram represent the number of degrees by which the sum of the temperatures at the two stations exceeds 100° or is less than 100°.¹ On the base line are marked feet to be added to, or subtracted from, the difference of elevations in order to obtain the corrected relative elevation for the last of the two stations visited. For example, let the difference of elevations at A and B equal 75 ft., A being the lower of the two, and suppose

¹ This explanation is for the case where the aneroid or altimeter is calibrated for 50°. If the instrument is calibrated for 60°, the radiating lines represent the number of degrees by which the sum of the temperatures at the two stations exceeds, or is less than, 120°.

that the temperatures at *A* and *B* when the readings were made, were 65° and 75° , respectively.

$$\begin{aligned} 65^{\circ} + 75^{\circ} &= 140^{\circ} \\ 140^{\circ} - 100^{\circ} &= +40^{\circ} \end{aligned}$$

Find the point of intersection (*a*, in the figure) of the radial line marked 40° and the horizontal line for 75 ft.; then, from this point of intersection, follow the vertical line down to the base line where the correction is indicated. In the present case this correction is +3.05 ft., or simply 3 ft. The true difference in elevations between *A* and *B* is therefore $75 + 3 = 78$ ft.

If the difference of elevations, as read on the aneroid, had been 750 ft., the calculations would have been made on the quantity 75, and the final result would have been $10 \times 78 = 780$ ft.

If the temperatures at *A* and *B* had been 35° and 50° , and the difference in recorded elevations 75 ft., as before, we should have:

$$\begin{aligned} 35^{\circ} + 50^{\circ} &= 85^{\circ} \\ 85^{\circ} - 100^{\circ} &= -15^{\circ} \end{aligned}$$

The vertical through the point of intersection of the horizontal for 75 ft. and the diagonal line for 15° indicate a correction of 1.15 which will be minus, *i.e.*, subtracted from the recorded elevation at *B*, since the sum of the temperatures at *A* and *B* was *less* than 100° .

Figure 387 represents another method of correcting aneroid readings for difference in temperature at the observing stations. The difference of observed elevations at the two stations, recorded in feet, is shown on scale *X*; the sum of the temperatures at the two stations is given on *Z*; and the correction (to be added if the sum of temperatures is over 100° and subtracted if the sum is less than 100° , as given on *Z*) is shown on scale *Y*. Take the example already mentioned, where two stations, *A* and *B*, differed in elevation by 75 ft. and the sum of the temperatures recorded at the two stations was 140° . Lay the straight-edge from 75, on scale *X*, to 140 on scale *Z* (Fig. 387, line *st*). This straight-edge will cut *Y* at just over 3, which is the correction, in feet, to

be added to 75 ft. to obtain the true difference in elevation of *A* and *B*.

If the instrument is calibrated for 60°, use a number, on scale *Z*, equal to the sum of the two temperatures -20° .




FIG. 387.—Alignment chart for temperature corrections in barometric readings.

395. Source of Temperature Data.—If barometric readings are to be corrected for temperature, evidently temperature data must be secured during the progress of the barometric surveying. Such data can be obtained by means of a thermometer carried by the geologist and read at each station, or by a thermograph

(self-recording thermometer) kept at camp or at the base station. Under normal conditions the temperature of the air rises and falls through each 24 hours. Its fluctuations may be plotted as a graph (Fig. 388), which, as will be noted, has its lowest point near dawn and its peak between 2 and 4 in the afternoon. Only in the event of abrupt weather changes is the normal form of this graph radically modified. Where the topography is not very rugged and the relief is not more than a few hundred feet, the method of obtaining temperature variations by a stationary thermograph is satisfactory.




FIG. 388.—Average diurnal temperature curve.

396. Method of Correcting for Both Temperature and Pressure Variations.—In Arts. 390–393, we described the methods of correction for pressure variations. These methods were discussed first in order not to confuse the student; but he is reminded that in practice he must correct for temperature *before* he corrects for pressure. To illustrate this procedure, we have used, in Table IV, the data of Table II (p. 475). In column *A* (Table IV) are the station numbers; in *B*, the time; in *C*, the elevations read on the aneroid; in *D*, the temperature readings; in *E*, the drop (–) or rise (+) in elevation from one station to the next (Cf. *C*); in *F*, the sum of the temperatures at each two stations; in *G*, the percentage adjustment in temperature (equals $\frac{1}{10}$ of the sum of the temperature – 100); in *H*, the actual correction (factor in *G* times factor in *E*); in *I*, the number of feet to be added

TABLE IV

A	B	C	D	E	F	G	H	I	J	K	L
1	A.M. 6.00	625	65	- 5	132	+3.2	- .16	0	625	700	0
1	7.30	620	67	- .	135	3.5	-1.58	0	620	700	0
2	8.00	575	68	+ 5	138	3.8	+1.9	-2	573	658	- 2
3	8.20	580	70	+105	142	4.2	+4.41	0	580	670	+ 5
4	8.50	685	72	+105	142	4.2	+4.41	+4	689	784	+ 4
3	9.15	565	73	-120	145	4.5	-5.40	-1	504	609	+ 4
5	9.30	535	75	- 30	148	4.8	-1.44	-2	533	643	+ 3
6	9.40	525	75	- 10	150	5.0	- .5	-3	522	630	0
7	10.00	540	77	+ 15	152	5.2	+ .78	-2	538	658	+ 8
8	10.25	505	79	- 35	155	5.5	-1.06	-4	501	626	+11
9	10.45	520	80	+ 15	150	5.0	+ .885	-3	517	642	+12
10	11.10	550	83	+ 30	163	6.3	+1.80	-1	549	669	+ 9
11	11.45 P.M.	595	85	+ 45	168	6.8	+3.00	+2	597	712	+12
7	12.15	550	88	- 45	173	7.3	-3.28	-1	551	661	+11
7	1.00	500	91	- 25	183	8.3	-2.075	0	500	655	+ 5
8	1.15	535	92	+ 25	186	8.6	+2.15	-2	533	623	+ 2
12	2.00	500	94	+ 10	189	8.9	+ .80	0	500	635	0
13	2.20	570	95	+ 20	190	9.0	+1.8	+1	571	641	+ 1
14	2.35	590	95	+ 30	190	9.0	+2.7	+3	593	658	+ 3
15	3.00	620	95	- 15	180	8.0	-1.335	+6	626	681	+ 1
2	3.30	605	94	+ 45	186	8.8	+3.96	+5	610	665	+ 5
1	3.50	650	94	+ 5	186	8.6	+ .43	+9	659	700	0
1	5.30	655	92	- 15	181	8.1	-1.215	+9	664	700	0
1	7.05	640	89	- 15	181	8.1	-1.215	+8	648	700	0

to, or subtracted from, the recorded elevation (*C*) to give the altitude reading *corrected for temperature*; and in *J*, this reading (*C*) corrected for temperature.

At this point a few words of explanation may be given. Take Stations 7 and 8 as an example. The aneroid readings at 10 and 10.25 A.M. were 540 and 505 ft., respectively; that is, a drop of 35 ft. from Station 7 to Station 8. The temperatures were 77° and 79°, which, when added together, equal 156°, or 56° more than 100°. The percentage adjustment is therefore 5.6 (column *G*). Multiply 35 by 5.6 to obtain the actual adjustment, 1.96, which




FIG. 380.—Correction curve based on same data as those used Fig. 384, but here first corrected for temperature.

is here negative because Station 8 was lower than Station 7. The last correction in column *I* was -2 , obtained from the data for Stations 6 and 7. The present correction, -1.96 , is essentially -2 , which is to be algebraically added to the -2 for Station 7, making -4 as the correction at Station 8. That is, 4 is to be subtracted from the elevation 505 ft. recorded at 8 (column *C*). In this manner each *actual correction* figure is to be added algebraically to the last total correction figure in column *I* to find the next total correction figure, which is then added to, or subtracted from, the recorded elevation (column *C*) to obtain the corrected reading (column *J*).

In column *J*, then, are the elevation values to be used in constructing the correction curve for *pressure* variations as explained

in Arts. 390-392, inclusive. Figure 345 is based on the data in column *J*, Table IV. In column *K* are listed the elevations as corrected by the use of this graph. By reference to column *E*, in Table II, the reader will note that the altitudes of Stations 1, 6, and 12, had already been established.

397. To What Extent Is Correction of Barometric Readings for Temperature Fluctuations Desirable?--In column *L*, Table IV, are the amounts in feet, by which the adjusted elevations of this traverse, as corrected for both temperature and pressure, differ from the adjusted elevations when correction has been made for pressure only (*D*, Table II). Observe that the greatest difference is 12 ft., at Stations 9 and 11; also that the greatest difference in relative values, *i.e.*, from station to station, is only 7 ft. (between Stations 2 and 3, at 8.00 and 8.20 A.M.). In view of the facts: (1) that, in plotting these correction curves and in applying them, there is easily room for an error of 5 ft. or even 7 or 8 ft.; and (2) that a contour map based on the corrected altitudes of Table IV would not materially differ from a contour map based on the corrected altitudes of Table II, one may conclude that temperature corrections are not always necessary. To lay down a rule as to when they should be made, and when not, is practically impossible. One must remember that the greater the difference is between 100°F. and the sum of the temperatures at two consecutive stations, the greater will be the resulting correction. If barometric surveying is being done in very cold weather or very warm weather, the aneroid or altimeter readings should be adjusted for temperature. In general, we would say that, if, in Fig. 364, the point of intersection of the diagonal and the horizontal lines falls to the left of the heavy vertical line, and the difference in elevations is 100 ft. or less, correction for temperature is unnecessary. If the difference in elevations of consecutive stations is more than 100 ft., the geologist will have to use his own judgment as to whether disregard of the temperature factor will introduce too large an error into his results, always bearing in mind the amount of permissible error as governed by the rate of travel (399), the area to be covered within a specified time, the

regularity of the geology, the contour interval to be adopted for the map, and so on.

398. Degree of Precision of the Barometer Method.—The feeling is widespread among geologists that the barometer method is at best inaccurate and uncertain in its results. As far as the writer has been able to observe, this is not quite the case. If the geologist and his aneroid are reliable—and a satisfactory aneroid *can* be found by careful testing of several instruments—the accuracy of the results will be directly proportional to the frequency of the checking. The fewer the checks and the greater the interval of time permitted to elapse between checks, the smaller will be the chance for catching changes in atmospheric pressure and, hence, for obtaining true relative elevations by reference to the correction curve. On the other hand, there is a practical limit to the number of checks which should be made. Too many checks merely add to the work of correction without yielding a corresponding or necessary increase in the accuracy of the results.

For detail mapping, check stations should not be over a mile or two apart, and not over an hour should elapse between checks. When, on the other hand, the object is to prepare a small scale map of an extensive area and to show only the larger structures, travel is usually much more rapid, minor details are omitted, check stations are selected at 5, 10, 15, or even 20 miles apart, depending on the rate of progress possible, and the barometric elevations are checked at intervals of from 1 to 3 hours.

The reader will perceive that the barometer method is highly elastic. It can be made slow and fairly precise, or rapid and less accurate. In other words, it may be adapted to both detail and reconnaissance geologic mapping. Under ordinary circumstances, whether progress is slow or rapid, the average relative error may be made less than 1 vertical in 1,000 horizontal, which is usually less than the variations in thickness of mappable groups of strata.

399. Rate of Mapping.—Detail mapping, involving sufficiently careful field work to enable the geologist to prepare a reasonably accurate contour map of the geologic structure on the scale of

$\frac{1}{2}$ to 2 miles to the inch with a contour interval of 10 to 20 ft., may be done by the barometer method at rates varying from 2 to 50 square miles per day. Two to four square miles should be mapped in a day where foot traversing is necessary. From 10 to 50 square miles may be mapped by automobile. More than 25 square miles as a day's work is exceptional.

In more rapid reconnaissance, for a map, let us say, on a scale of 2 to 10 miles to an inch and with a contour interval of 25 to 100 ft., as much as 100 square miles, or even more, can sometimes be surveyed by automobile in a day.

For both detail and reconnaissance work the size of the area examined in a day depends upon the number, condition, and distribution of roads, the abundance of outcrops and ease of correlation of strata, and whether or not the geologist has a helper to drive the car.

THE PLANE TABLE METHOD

400. Definition.—In the plane table method of geologic mapping, directions, horizontal distances, and vertical distances, are all determined by plane table and alidade, and the map is plotted in the field.

401. Equipment.—The equipment used in this method includes a plane table of convenient size, a telescopic alidade, usually of the Gale pattern, a stadia rod, plotting scale, several sheets of plane table paper, two notebooks, a stadia slide rule or stadia tables, pencils, eraser, thumb tacks, etc. An *instrument man* carries the plane table, alidade, one notebook, and other articles needed for making the map; and a *rod man*, who is usually the geologist, carries the rod, the other notebook, etc. He may also carry a Brunton compass and an aneroid barometer for occasional side traverses.

The instrument man's notebook is commonly ruled by vertical lines, the columns being labelled for the various data to be assembled. In these columns are recorded the station number; the level reading or reading of the vernier when the telescope is level; the vertical angle of the line of sight, and a notation

whether this angle is positive or negative;¹ the distance to the next station; the difference of elevation between the instrument station and the rod station; the height of the instrument, or "H. I.;"² the elevation of the distant station; and other data.

1	2	3	4	5	6	REMARKS
7	8	9	10	11	12	
13	14	15	16	17	18	
19	20	21	22	23	24	

FIG. 390.—Page from an instrument man's field notebook. (See Fig. 391.)

Sample pages from an instrument man's field notebook are shown in Figs. 390 and 391. In every such book there should be a table giving values for vertical heights up to at least 9° or 10°, and also horizontal corrections for distances (Appendix XVIII).

¹ A positive vertical angle is one between a horizontal line of sight and the inclined line of sight when the objective of the telescope is raised to observe a higher station; a negative vertical angle is included between the horizontal line of sight and the inclined line of sight when the objective is lowered to observe a lower station.

² The height of the instrument (H. I.) is the vertical distance from sea level to the horizontal axis of the telescope when the instrument is set up on the plane table for use. The instrument man sets up the plane table at approximately a constant elevation above the ground, making no record of this quantity unless, for some reason, the table must be set up exceptionally high or low.

402. Preparation of the Map Paper.—In preparation for the field work, several sheets of paper of the proper kind are generally fastened, one on top of another on the plane table board. This is the easiest way of carrying them. These sheets should be ruled in coördinate squares, parallel to the edges of the board, on the scale to be used in the mapping. One set of lines is assumed to run north and south, and the other set, east and

DATE _____ 193__ GEO _____ INSTR _____ PAGE _____												GEO COL	
PLANE TABLE SHEET NO _____												—MAP AREA NO _____	
NO ON PAGE	NO ON MAP	LEVEL	ANGLE			DIST	DIFF. ELEV	H. I	ELEV	DIFF. TO DATUM	DATUM		
			LEVEL	-1- OR -	DIFF								
1													
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													
14													
15													
16													
17													
18													
19													
20													
21													
22													
23													
24													

FIG. 391.—Page from an instrument man's field notebook. When the notebook is open this page is to the right of the page shown in Fig. 390.

west. Somewhere near the middle of the sheet, through the point of intersection of an east-west coördinate and a north-south coördinate, a line should be ruled in the direction of the magnetic north in the district to be surveyed. Methods of determining the magnetic declination are described below (404).

403. Centering and Levelling the Plane Table.—When the plane table is to be set up for use at a station, it must be centered, levelled, and oriented. Orienting is explained in Art. 405. To center the table, bring the point for a station on the map

over the corresponding point on the ground. In geologic work this may be done by eye without introducing serious errors.

For levelling, set up the plane table and roughly level it by eye. Place the alidade near the middle of the board. Then, by slightly tilting the board this way and that, center the bubble in the circular spirit level of the alidade. When this bubble is centered, clamp the angular motion of the board.

404. Determination of Declination.—Ordinarily the magnetic declination (332) in a given region can be found by reference to published records or to an isogonic chart (Plate I, facing p. 422); but sometimes the geologist must determine the declination for himself. Below are outlined three methods of doing this.

1. If there are any previously established control stations in the district, such as U. S. Geological Survey bench marks, etc., two of these, which are intervisible, may be chosen for the following operation. They should have been carefully plotted on the map sheet. Set up the plane table at one of these stations, levelling it as described in Art. 403. Clamp the angular motion. Move the alidade on the board until its bevelled edge coincides with the line between the plotted points for the two established stations. Rotate the board in a horizontal plane until the other station, in the distance, is in the line of sight of the alidade. Fasten the horizontal motion of the board and release the compass needle. Rotate the alidade about the point of intersection of an east-west coördinate and a north-south coördinate until the needle points to magnetic north. Draw a line along the fiducial (bevelled) edge of the alidade. This will be the declination line, making an angle with the north-south coördinates equal to the magnetic declination.

2. Where the country has been sectionized and roads are laid out accurately along the section lines, the declination may be found by reference to these roads. Select a point on the road from which you can see the road for 2 or 3 miles preferably across a valley. Set up the plane table at this point and level it. The alidade should be placed with its bevelled edge against a north-south coördinate. Center the vertical cross-hair on a

point in the road 2 or 3 miles away, endeavoring to choose this point in the same relative position across the road as the site of the plane table. After releasing the compass needle of the alidade, rotate the alidade about the intersection point of an east-west and a north-south coordinate near the middle of the board, until the needle swings freely and points to magnetic




FIG. 392.—Stars and constellations near the Pole Star

north. East of the zero isogonic line (Plate I, p. 422) the alidade will be turned counter-clock-wise in this procedure, and west of the zero isogonic line it will be turned clock-wise. Draw a line along the fiducial edge of the alidade. This line will lie in the direction of magnetic north and south, and will make an angle with the north-south coordinates approximately equal to the magnetic declination for the district.

3. With a suitable book on astronomy, or with the aid of a person who knows the stars, first learn to recognize the constellations, Cassiopeia, Ursa Minor (the "Little Bear"), and Ursa Major (the "Great Bear"), and the stars called Delta Cassiopeia, Mizar, Polaris (the "Pole Star"), and the "Pointers" in Ursa Major. Ascertain at what time of night an imaginary line connecting Delta Cassiopeia, Polaris, and Mizar (Fig. 392), will appear to be vertical. Either Delta or Mizar may be below Polaris. Fifteen minutes or so before this time go out and carefully level the plane table. Set the alidade with its bevelled edge exactly parallel to a north-south coördinate on the map sheet, but support the objective end on a rectangular block of wood of which the right-and-left edges are perpendicular to the length of the alidade. This is to enable the observer to raise the objective end of the telescope enough to see the higher star. Turn the board horizontally until, by raising and lowering the objective end of the telescope, Polaris is brought into the line of sight. Raise and lower the telescope alternately until the time when both Polaris and the "Guide Star" (Delta or Mizar) may be brought successively into the line of sight. When this is possible, the north-south coördinates on the map are lying due north and south. Now lock the table, releasing the compass needle of the alidade, and turn the alidade, resting flat on the board, about a coördinate intersection until the needle points to magnetic north. Draw the declination line along the fiducial edge of the alidade.

405. Orienting the Plane Table.—In most plane table mapping the board is set up, at any station, so that its edges bear exactly the same relations to compass directions as at all other stations.

The process of setting up in this way is called *orienting*.

Following are three methods of orienting the board:

1. Set up the plane table. Place the alidade on the board with its fiducial edge coinciding with the declination line (402), and with its objective end toward the north. Turn the board horizontally until the released compass needle points north. This is *orientation by compass*.

2. To *orient by backsight*, set up the table at a given station, *B*, and see that the north edge of the board is toward the north. Place the alidade so that its fiducial edge coincides with the line drawn from the station previously visited, *A*, to the station now occupied *B*. Rotate the board until Station *A* is brought into the line of sight of the alidade. The board is now oriented.

3. Still another method of orientation makes use of the Baldwin Solar Chart. The angle between the apparent position of the sun and true north is graphically determined by means of this chart which is so constructed that when turned until the proper pivot point on an arrow and the *sun-time point* on a latitude are on a line parallel to the shadow cast by a plumb-line upon a level table the arrow points true north. A copy of this chart and full directions for its use may be found in Topographic Instructions of the U. S. Geological Survey, pp. 219-225.¹

406. Lining in a Station.—"After the table has been properly oriented at a station, the location of which has been plotted on the map, the bearing of any visible object may be drawn directly. The alidade is moved until the straight-edge touches the side of the needle-hole or pencil dot representing the occupied station and the vertical cross-hair in the telescope bisects the distant object, the bearing of which is desired; a line drawn along the straight-edge will then represent the compass-bearing plotted to position on the map under construction.

"The best method to pursue in lining in a distant station is to grasp the ends of the alidade base with either hand; shift the instrument until the line of sight through the telescope falls upon the desired objective and the fiducial edge rests within an inch or two of the dot locating the occupied station; then move the alidade diagonally forward and to the right, keeping the vertical cross-hair on the distant object, until the ruler edge touches the proper point. If the alidade is equipped with a parallel-edge ruler, it is only necessary to place the instrument somewhere near and to the left of the plotted point in such a position that the

¹ Bibliog., BIRDSEYE, C. H., 1928. (Quoted from MATHER, p. 109. See Bibliog.)

vertical cross-hair cuts the distant station; then push the parallel straight-edge outward until it touches the proper point. Some surveyors make it a practice to stick a needle vertically into the plane table at the point representing the occupied station, and to pivot the alidade on the needle when lining in a station. This practice is not recommended. Although it is an easy way for the novice to increase his speed, it involves inaccuracies of considerable import. If the needle is inserted far enough to hold its upright position, it makes a hole several times as large as necessary; the point becomes a space which on the customary scales represents an area on the ground, 30 to 60 ft. in diameter.

"Lines representing bearings should be drawn with the chiseled edge of a 9-H pencil, being careful always to hold the pencil at the same angle, and to see that the contact of rule and paper is perfect. By placing the ruler-edge in a position tangential to the tiny circle formed by a needle-hole or dot, the line when drawn should exactly cut the center of the 'point.' If the distant station is subsequently to be occupied and orientation there is to be by backsight, the foresight line should be the full length of the alidade base; if not, the foresight line may be short, covering only the estimated position of the point. It is better not to draw lines through the dot or needle-hole representing the occupied station; break the line for a fraction of an inch."¹

407. Determination of Horizontal Distances.—Let *A* and *B* represent two intervisible stations at the same elevation above sea level. *A* is occupied by the instrument man, and *B*, by the rodman. The distance *AB* is to be determined. Set up the plane table at *A*. Line in *B* from *A* as explained in Art. 406. Looking through the telescope, set the lower stadia hair on a foot mark on the rod held at *B*, and count the number of feet on the rod intercepted between the two stadia hairs. Multiply this intercept by 100 to obtain the distance from *A* to *B* (348). If *B* is so far away that the rod does not extend across the space between the two stadia hairs, read the intercept on the rod between the lower stadia hair and the horizontal cross (diametric)

¹ Bibliog., MATHER, KIRTLEY, F., 1919, pp. 110, 111.

hair, and multiply this intercept by 100×2 to obtain the distance AB (Figs. 393, 394).

408. Long Sights.—"Occasionally, it is necessary to measure distances greater than 200 times the rod length with an alidade equipped only with three stadia hairs. Several different methods of procedure are available; the choice of the one to use depends upon the equipment of the instrument, the geographic environment, and the custom of the individual surveyors. Some of the methods are in effect schemes to provide a longer rod. Others




FIG. 393.—Stadia rod in field of view at a distance of 720 ft. (After Kirtley F. Mather; reproduced with permission of Scientific Laboratories of Denison University.)




FIG. 394.—Stadia rod in the field of view at a distance of 1,740 ft. (After Kirtley F. Mather; reproduced with permission of Scientific Laboratories of Denison University.)

depend upon trigonometric principles. The method numbered 5 is probably best suited to the more common conditions met in geologic mapping.

"1. Rotate the telescope 90° in its sleeve so that the stadia hairs are vertical instead of horizontal. Signal rodman to mark his station with a flag or to select a certain sapling or post for his station. Place one hair on the station and signal rodman to move at right angles to the line of sight until the rod, held vertically, is in line with the other stadia hair. The rodman will then measure the distance horizontally on the ground from his second position to his first, using the rod as a measuring stick, and report the result to the instrument man. Distances of 4,000 to 7,000

ft. may be determined with a fair degree of accuracy by this method. It may be used to advantage only when the two men are able to communicate freely by signals such as the two-arm semaphore code.

"2. Rotate the telescope as before. Signal rodman to hold rod horizontally and to be prepared to move laterally so that the base of the rod will occupy the point now occupied by its top. Intersect base of the rod with one stadia hair. Signal rodman to move over in the desired direction a sufficient number of rod-lengths so that the other stadia hair will finally intersect the rod. Read intersection; add the number of feet indicated by the length of the rod multiplied by the number of moves; multiply by 100 or 200 depending upon which hairs were used.

"3. If instrument is equipped with a Stebinger gradienter drum attached to the fine adjustment screw, proceed as follows: place bottom hair on lowest visible primary division of the rod; read and record Stebinger. Turn Stebinger drum until middle hair rests on the top of the rod; read and record Stebinger. Take the difference of the two Stebinger readings; turn an equal number of divisions in the direction which brings the middle hair down onto the rod; observe the number of feet between the top of the rod and the intersection of the middle hair. Add this to the length of the rod which was above the bottom hair at the first reading; the sum multiplied by 200 is the horizontal distance. For example:¹ 12 ft. of the rod are entirely visible and the middle hair is well above the rod when the bottom hair rests 12 ft. below its top. In that position the Stebinger drum reads 24. Turn down until middle hair touches the top of the rod; Stebinger reading is now 60. The difference between the two readings is 36. Turn down 36 divisions more, to 96. The middle hair now intersects the rod 3.4 ft. below its top. The horizontal distance is $200 \times (12 + 3.4)$ or 3,080 ft.

"4. If instrument is equipped as in 3 and there is at hand a table previously prepared for this particular instrument, showing

¹ This, and the following examples apply only to those instruments in which a clock-wise rotation of the Stebinger drum depresses the objective end of the telescope.

Stebinger factors,¹ *i.e.*, the differences in elevation at the unit distance of 100 ft. corresponding to the vertical swing of the telescope denoted in divisions of the Stebinger drum, proceed as follows: place one hair on the top of the rod; read and record Stebinger. Turn down until that hair cuts the lowest visible primary division of the rod; read and record Stebinger. Take the difference of the two readings. Repeat for each of the other two hairs. The three results should check. Select from the table the Stebinger factor corresponding to that number of divisions. Note the number of feet passed over on the rod; multiply it by 100 and divide by the factor. The result is the horizontal distance. For example: 13 ft. of the rod are visible. With the middle hair resting on the top of the rod, the Stebinger reading is 62. When the middle hair is turned down to the primary division 13 ft. lower, the reading is 106. Difference of the two readings is 44; corresponding factor is 0.4111; horizontal distance is $1,300 \div 0.4111 = 3,160$ ft.

"This method is frequently employed by ingenious surveyors to good advantage in determining distances without the use of the stadia rod. Any two points, one above the other, at known distances apart suffice; two flags at a measured interval, the crown plate and girths (commonly 8 ft. apart) of a standard derrick, the eaves and lower copings of a church tower, are listed merely as suggestions. If the location of such a target is plotted, the surveyor may *shoot himself in*, with a fair degree of accuracy, at any point from which it is visible.

"5. If alidade is equipped as in 3, an alternative method which may be used is as follows: place middle cross-hair on top of rod; read and record Stebinger, denoting the record as *A*. Turn down until middle hair intersects the lowest visible primary division; read and record Stebinger (record *B*). Turn down until top hair rests on top of rod; read and record Stebinger (record *C*). Compute distance by the formula

$$D = 200r \frac{C - A}{B - A},$$

¹ The preparation of such a table and the mathematical principles on which it is based are discussed on pp. 522-523.

in which D represents the distance, r the length of the rod above lowest visible primary division, and A , B , and C , respectively, the three readings of the Stebinger drum. For example: a 13-ft. rod is entirely visible. The middle hair on top of rod gives a Stebinger reading of 31; middle hair on bottom of rod gives a reading of 54; top hair on top of rod gives a reading of 78.

$$\text{Distance} = 200 \times 13 \times \frac{78 - 31}{54 - 31} = 5,300 \text{ ft.}$$

"The formula may be more easily recalled if one has grasped the principle upon which it is based. The Stebinger difference, $C - A$, is theoretically a constant, the measure of the angle between the rays converging from the top and middle cross-hairs to the focus of the telescope. If the rod at the distant point were of sufficient length, the intercept subtended by this angle could be read and, multiplied by 200, would give the distance to the rod. That is, if i be taken to mean the length in feet of that hypothetical intercept,

$$i = D \div 200$$

But

$$i:r::C - A:B - A,$$

for the Stebinger difference $C - A$ is the measure of the angle defined by the chord i and $B - A$ is the measure of the angle defined by the length of the rod at the same distance. Therefore,

$$(D \div 200):r::C - A:B - A$$

or

$$D = 200r \frac{C - A}{B - A}$$

409. Inclined Sights.—"This discussion of the measurement of distances with the stadia (407, 408) has been based on the assumption that the rod is always held perpendicular to the line of sight and that the desired distance is to be measured along that line. As a matter of fact, most of the sights in stadia work are taken not on a level, but on a slope or inclination, as sug-

¹ Bibliog., MATHER, KIRTLEY F., 1919, pp. 114-117.

gested in" Fig. 395 (351). "Consequently if the rod is held vertically, the stadia intercept is somewhat more than it would be when held perpendicular to the line of sight, and an element of error is introduced. This error amounts to 1 per cent of the distance for a gradient of 8° , 2 per cent for 11° , and 3 per cent for 14° . It may obviously be corrected by tilting the rod so that it is perpendicular to the central visual ray from the telescope. This may be accomplished by attaching a short pointer to the rod at right angles to its face and aiming this pointer at




FIG. 395.—Diagram illustrating the stadia principle applied to inclined sights. (After Kirtley F. Mather; reproduced with permission of Scientific Laboratories of Denison University.)

the instrument when the sight is taken. It is, however, difficult to hold the rod steadily in this position and this corrects only one of the two discrepancies. It is, therefore, customary to hold the rod vertical no matter what the angle of slope may be and make the correction in the tables for distance and elevation. The second discrepancy is due to the fact that the distance to be plotted is the horizontal distance from telescope to rod, not the inclined distance. So far as plotting is concerned, this discrepancy, and, therefore, the angle of inclination, must be fairly large before it need be taken into account; how large depends upon the scale of the map, but for most work it may be neglected

for all angles of less than 3° ." (See p. 444.) "With an angle of $5\frac{1}{2}^\circ$ this discrepancy amounts to about 1 per cent, which for a distance of 1,000 ft. is little more than the diameter of a needle hole on a scale of 1:31,250.

"The stadia tables ordinarily used include the correction for horizontal distance of inclined sights. In practice, such tables should be consulted before plotting distances determined by sights which depart more than 3° from the horizontal. Reference to the accompanying diagram (Fig. 395) will make clear the mathematical formula upon which the correction tables are based. In the diagram, AB represents the intercept on the rod held vertically, CD the intercept on the rod held perpendicular to the line of sight from G , GE , the distance from table to rod in the line of sight, and GF the horizontal distance from set-up to station. The angle of inclination of sight and the equal angle between the two positions of the rod are indicated by m . For all practical purposes, $\angle ACE$ and EDB may be assumed to be 90° . By trigonometry,

$$CD = AB \cos m$$

and

$$GF = GE \cos m.$$

But

$$GE = 100CD = 100AB \cos m;$$

therefore, by substitution,

$$GF = 100AB \cos^2 m,$$

by means of which the horizontal distance may be computed from the rod intercept and the angle of inclination."

For the vertical distance EF (Fig. 395), we have the following:

$$EF = GE \sin m$$

and

$$GE = 100AB \cos m,$$

as stated above. By substitution,

$$EF = 100AB \cos m \sin m.$$

From trigonometry,

$$\sin 2m = 2(\sin m \cos m).$$

Therefore, again by substitution,

$$EF = 100AB \cdot \frac{1}{2} \sin 2m.$$

"The correction to be applied to the observed distance on inclined sights may be determined without reference to tables or formulæ by means of the Beaman stadia arc, an attachment for the mechanical solution of the stadia problem . . . The arc carries two scales, a multiple scale and a reduction scale, having coincident zero points marked 50 and 0, respectively. The reduction scale is, of the two, the more distant from the adjustable index and gives percentages of correction that may be used to reduce observed stadia distances to horizontal. The adjustable index should be set opposite the zero of the reduction scale when the telescope is level. To get the necessary correction, simply read the same scale with the line of sight cutting the distant station. Reading to the nearest per cent is usually sufficient. For example: the reduction scale reads 3 with an observed rod intercept of 16.2; then 3 per cent of 1,620 = 48.6; 1,620 - 48.6 = 1,571.4 = corrected horizontal distance."¹ (See Art. 412.)

410. Correction for Curvature and Refraction.—No matter what method of determining vertical distances is used, a correction for curvature and refraction must be applied to all 'shots' of a mile or more in length. The level datum to which all elevations are referred is a surface having the curvature of the earth; the line of sight through the telescope in a level position is tangential to this curved surface; therefore, distant objects appear to be lower than they really are. In the greatly exaggerated Fig. 396, for example, point *B* appears to be at the same level as the instrument, whereas it is really at a height *CB* above the level line. The result of curvature can be determined with reasonable accuracy. It varies directly as the square of the distance and

¹ Bibliog., MATHER, KIRTLEY F., 1919, pp. 117-119.

may be computed by the formula: $\text{curvature} = 0.667 \times D^2$, where D is the distance in miles.¹

"Refraction, on the other hand, has the opposite effect. When light rays pass obliquely from one air stratum to another of different density they are bent or refracted from their original position. In Fig. 396, the light from the target at B , passing into air strata of increasing density as it travels to the alidade at




FIG. 396.—Diagram, greatly exaggerated, to illustrate influence of curvature and refraction upon observations for determining differences in elevation between two points. (After Kirtley F. Mather; reproduced with permission of Scientific Laboratories of Denison University.)

the left, is bent downward and enters the telescope as though it had come by a straight line from A . Thus, the effect of normal atmospheric refraction is to make distant objects appear higher than they really are. It, therefore, tends to decrease the curvature correction, as shown in the figure. The amount of refraction depends upon the density of the air and is, therefore, quite variable. It is much greater near the ground than 3 ft. above it, and generally greater at midday than early in the morning or late in the afternoon.² The empirical valuation ordinarily

¹ *Ibid.*, with some changes.

² Obviously, the refraction to which reference is here made is not that of the direct rays of light from sun or stars. The refraction for which correction must be made in determining sun azimuth is least between 9 A.M. and 3 P.M.

placed upon the effects of refraction gives the combined formula: curvature plus refraction = $0.57135 \times D^2$.

"A table showing corrections based on this formula may be found in the ordinary stadia tables. The correction amounts to only 0.1 ft. for distances of 2,200 ft., 0.2 ft. for 3,125 ft. and 0.5 ft. for 4,940 but increases rapidly to more than 5 ft. at 3 miles and 20 ft. at 6 miles. It may safely be disregarded for the great major-

ity of rod 'shots,' which will of course be less than 3,000 feet long."¹

The correction is always a positive quantity and should be added algebraically after the proper sign has been placed in front of the vertical distance as instrumentally determined, an angle of elevation giving a plus sign and an angle of depression giving a minus sign. Occasionally, for nearly level sights, the correction to be applied for




FIG. 397.—Mapping by the method of radiation. The square represents the plane table board.

curvature and refraction will be greater than the observed difference in elevation, but no confusion will arise if the rule stated in the first sentence of this paragraph be rigidly observed.²

411. Methods of Determining Location.—There are four methods of locating points for map construction by the plane table. They are radiation, intersection, resection, and progression or traversing. Intersection and resection are the two principal modes of triangulation.

1. The *method of radiation* is illustrated by Fig. 397. *a, b, c,* and *d* are stations to be located. Set up the plane table above

¹ Bibliog., MATHER, KIRTLEY F., 1919, pp. 135–137. The original text has been somewhat modified.

² This paragraph has been modified from Kirtley Mather's article.

any point, s , from which the stations are visible. If an open sight alidade is used these stations must also be accessible from s . Orient if necessary. Let s' be the position of this point on the map. s is vertically below s' . Place the fiducial edge of the alidade against s' , sight at the rod held at a , and draw a line from s' toward a . Measure sa (407). Lay off $s'a'$ on the scale adopted for the map. In like manner plot $s'b'$, $s'c'$, and $s'd'$. In each case find the elevation of the distant point and record it on the map (412).




FIG. 398.—Mapping by the method of intersection. The squares represent different positions of the plane table.

2. The *method of intersection* is illustrated in Fig. 398, where a , b , c , d , e , and f , are points to be plotted. Set up the plane table at a given station, a . Let a' on the map represent a on the ground. Sight with the alidade at b , c , d , e , and f , and draw lines from a' toward these points. From a measure the distance to one of the stations, c , and lay off $a'c'$ on the scale adopted for the map. Set up at c by backsight on a (405). From c sight at b , d , e , and f , and draw lines toward these points from c' . The intersection of the two lines of sight from a' and c' to each point will determine the position of this point on the map. The angle made by these two lines at each point (e.g., $a'e'c'$) should not be less than 30° or more than 150° . Whenever possible it should approximate 90° . Elevations of the distant stations may be determined as described in Art. 412.

To check the work, the observer should always sight from a third station at all points previously located by two-line intersections (Fig. 399). If the line from the third station does not pass through the intersection point for any other station, there has been an error in the plotting and the mapper may have to go back and repeat until his error has been discovered and corrected. The elevation of any station can be checked by reading the vertical angle to this station from a second and a third station and computing the elevation in each case.




FIG. 399.—Enlargement of the plot shown in Fig. 398. All points are fixed by the intersection of at least three lines. Full lines were sighted from *a*, dashed lines from *c*, and dotted lines from *d*; *a*, *c*, and *d*, being the stations represented by *a'*, *c'*, and *d'*.

By advancing from station to station, always locating points by intersection in the manner just described, any number of stations may be plotted. The lines joining stations will form a network of triangles, a *triangulation net*. The process of developing this net is called *expansion*. Expansion may be accomplished by building up a series of triangles, quadrilaterals, or polygons (Fig. 400).

The method of intersection requires the actual measurement of the length of but one line, termed the *base line* (*ac* in Fig. 398). In most cases, however, the system should be tied to a check base line at the other end of the net (Fig. 400, D). The accuracy of the whole net is proportional to the degree of precision with which the base line is measured. Errors in triangulation tend to

balance out, but not so with the base line, which should, therefore, be measured as accurately as practicable. The position of the base line should be chosen on as open and as level ground as




FIG. 400.—Triangulation nets consisting of a series of triangles (A), quadrilaterals (B), polygons (C), and intersecting polygons (D). In each figure *mo* is the base line. *st* is a check base line. A is the least accurate method. B and D are most satisfactory.

possible. It should be of such a length in the field that it will be at least 2 in. long when plotted to scale on a plane table map of any scale.¹

3. The *method of resection*, or “cutting in,” is virtually intersection backward. Let *a*, *b*, and *c*, in Fig. 401, be three stations previously determined, and let *a'*, *b'*, and *c'* represent these stations on the map. The observer is at *d* and wishes to ascertain his location with respect to *a*, *b*, and *c*, which are visible from *d*. Set up the plane table at *d* and orient it by compass. Lay the fiducial edge of the alidade at *a'* and turn it until *a* is in the line of sight. Draw a line from *a'* away from *a*. Place the alidade against *b'*, turn it until *b* is in the line of sight, and draw a line from *b'* away from *b*. This line intersects the line from *a'* at *d'*. Check by repeating this operation for a third station, *c*. If




FIG. 401.—Mapping by the method of resection. The square represents the plane table.

¹ This does not mean that the line on the map should not be drawn 6 or 8 in. long when its *direction* is plotted, in order to facilitate laying the alidade along it.

only two stations, a and b , are visible from c , no satisfactory check of this kind is possible.

If the line from c' intersects $a'd'$ and $b'd'$ at d' , d' is the correct location of the point (Fig. 401). If it does not, the three lines will form a *triangle of error*, which may lie inside or outside the triangle made by the three fixed points (a' , b' , and c') on the map,



FIG. 1




FIG. 3



FIG. 6




FIG. 5




FIG. 4




FIG. 2

FIG. 402.—Different aspects of the three-point problem. The "point sought," in each case, is the correct position, on the map, of the station occupied. The arrows are the lines drawn toward the three stations in the field. (Reproduced from I. C. Tracy's "Plane Surveying" by permission of John Wiley & Sons, Inc.)

and inside or outside a circle which passes through these three fixed points.¹ In this case the correct position of the observer can be found through a series of approximations by the application of the following rules: (1) The desired point will be on the same side of each of the three lines, when looking from the triangle of error, toward the respective stations; e.g., in Fig. 402,

¹ If the triangle of error falls about on this circle, it is well to substitute another station for one of the three fixed points.

the point is on the *right* of each line (arrow). (2) If the triangle of error is inside the triangle made by the three points (a' , b' , and c' in Fig. 401), the observer's position is inside the triangle of error, and *vice versa*. (3) The distance of the observer's position from the three lines is proportional to the lengths of these lines from the fixed points to the triangle of error. Having chosen a point, d' (Fig. 401), for the approximate position of the observer, draw a line from d' to b' , the most distant of the three fixed points, lay the alidade against $d'b'$, and turn the board until the sights are in line with b . Check by sighting along $d'a'$ at a and along $d'c'$ at c . If there is still a triangle of error, repeat the procedure.

The solution of this *three-point problem*, as it is called, may be performed graphically as follows: if a triangle of error is obtained by drawing lines from the three fixed points, as described above, rotate the table a little and, in just the same way, draw three more lines from the same three points, making another like triangle of error. If this second triangle of error is larger than the first, rotate the table in the opposite direction, and try again. It will be found that the triangle will reach a minimum size and then, with continued rotation of the table in the same direction, will become larger again and *inverted*. In seeking the correct position of the occupied station, refer to a triangle of error in normal position and another in inverted position. Draw straight lines connecting the corresponding apices of these two triangles. The corresponding apices in the two triangles are those from which sight lines were drawn from the same distant station. The three lines connecting these apices will intersect in a point which will be the observer's correct position on the map.¹ Lay the alidade against this point and the most distant fixed point, rotate the table until the station represented by this fixed point on the map is in the line of sight of the alidade, and then check by sighting at the other two stations.

¹ These lines do not meet mathematically in a point, but, on the scale of ordinary plane table work, they will so nearly meet at a point that for all practical purposes they may be considered to do so.

A third useful, but less accurate, solution is accomplished by means of tracing paper. Fasten the tracing paper to the board, orient the table by compass, let a point near the center of the paper be the observer's position, lay the alidade against this point, and sight successively at three distant stations already determined, each time drawing a line from the station of the set-up. Unfasten the tracing paper and shift it on the board until the three lines fall over the plotted points for the three distant stations. Prick through the observer's position. Test




FIG. 403.—Mapping by the method of progression or traversing. The dotted line is a check sight line made by the observer at c looking toward a . The squares represent different positions of the plane table.

the correctness of the location in the way described for the preceding methods.

From the vertical angles measured from d to a , b , and c , of which the elevations are already known, the elevation of d can be calculated (412).

4. The *method of progression*, commonly termed *stadia traversing* when a telescopic alidade and rod are used, is illustrated by Fig. 403. a , b , c , and d are points to be plotted. Let a' on the paper represent a on the ground. Set up the plane table at a and orient it by compass or, preferably, by backsight or resection from some fixed points. Place the fiducial edge of the alidade against a' and sight at b . Draw a line from a' toward b . Determine and lay off the distance, ab , on the scale adopted for the map, along the line just drawn. This will locate b' . Set up at b and orient by backsight on a . Place the fiducial edge of the

alidade at b' and sight toward c . Draw a line from b' toward c . Determine bc and lay off $b'c'$. Set up at c , orient by backsight on b , and continue as before. When possible sight back from a given station, such as c (Fig. 403), to an earlier station, such as a , and note whether the direction from c to a coincides with the line $c'a'$. This will serve as a check on the work. In passing, always tie the traverse to fixed points, previously located, and if there is an error of closure, correct that part of the traverse which has not yet been corrected, as explained in Art. 375. At its end, too, the traverse should be tied to a fixed point, and any error of closure should be corrected.




FIG. 404.—A plotted traverse, showing side points located by intersection, m , perpendicular offset, s , t , and radiation, w , x , y . hf and hd are check sight lines from h .

Features on one or the other side of the course are plotted in by eye estimate, by perpendicular offset with measured distance (s and t in Fig. 404), by radiation (w , x , y , in Fig. 404), or by intersection from two or more of the stations of the traverse (m in Fig. 404). Such intersection often helps as a check on the traverse.

In common practice, when mapping outcropping strata, the instrument man occupies one station, *A*, and reads the rod held by the rodman at *B*. This is a foresight reading. He then proceeds to Station *C*, after having been signalled to do so by the rodman, and again reads the rod held at *B*. This is a backsight reading. Then the rodman goes to *D* and the instrument man reads the rod held at *D*; and so on. Thus, instrument man and rodman alternate along the main traverse. The rod stations (*B*, *D*, etc.), on which foresight and backsight readings are made, are *turning-points* (Cf. p. 514).

The rodman, who is the geologist, selects his own route which is governed by the nature of the geologic evidence sought. In regions of moderately dipping strata, he endeavors to walk the beds (310, 317). He holds the rod at points which he chooses with a view to the subsequent mapping of the structure. Most of these points lie on one or the other side of the main traverse. They are called *intermediate stations*, and the sights (lines) made by the instrument man toward them are popularly termed *side shots*. The reader will understand that relatively few rod stations are turning-points. Only when the rodman signals the instrument man to proceed to a new station does he (the rodman) establish his location as a turning-point. Notice, further, that the choice of route therefore rests with the rodman (geologist).

412. Determination of Elevations.—When plane table mapping is undertaken with a small plane table and an open sight alidade, the differences in elevation of the various stations may be overlooked, or they may be determined by barometer (382, *et seq.*). On the other hand, if a telescopic (stadia) alidade is used, an effort is generally made to obtain the altitudes of the stations with some degree of accuracy. In the latter case, the difference in elevation between two stations may be found by direct level reading, stepping, vertical angle, Beaman stadia arc, and Stebbinger drum.

1. Suppose that *A* and *B* are two intervisible stations of nearly the same altitude. Set up and orient the table at *A* and place the alidade in proper position for sighting at the rod held at *B*. Level the telescope by the striding level. Sight at *B*. If the middle cross-hair falls on the rod, read the length of the rod between this cross-hair and the base of the rod. If the height of the instrument (H.I.) at *A* is known, subtract the rod reading at *B* from the H.I. at *A* to get the elevation of *B*. In levelling this is called a *foresight reading*. If the elevation at *B* is known, add the rod reading at *B* to the elevation of *B* to obtain the H.I. at *A*. This is a *backsight reading*. A station upon which a backsight is taken to establish the H.I. is a *turning-point* (Cf. p.

513). The student should remember that an error made at a turning-point will affect every succeeding reading.

2. In *stepping*, proceed as follows: level and orient the board at Station *A*, place the alidade in proper position, sight at the rod held at *B*, and draw the alignment, *ab*. Determine the distance, *AB* (407). Let us assume that *B* is higher than *A*. Level the telescope by the striding level. Looking through the telescope, choose some recognizable object, such as a rock, bush, etc., which is crossed by the horizontal cross-hair. Revolve the telescope on its horizontal axis until the lower stadia hair is on this object. This is a *half step*, or a *half interval*. Note a new object crossed by the upper stadia hair. Revolve the telescope till the lower stadia hair is on this object. Repeat, recording the number of *steps* until the upper stadia hair falls on the rod at *B*. Read the rod and wave the rodman to proceed. The elevation at *B* is the total number of *steps* times the vertical stadia interval for the distance, *AB*, minus the rod reading. If *E* is the elevation at Station *B*, H.I. is the height of the instrument above sea level at Station *A*; *N* is the number of steps, including the last one which brought the upper stadia hair on to the rod; *S* is the vertical stadia interval (348) for the distance *AB*; and *R* is the reading of the rod where crossed by the upper stadia hair; then

$$E = (\text{H.I.}) + (N \times S) - R.$$

If *B* is lower than *A*, the process consists of *stepping down*, and the formula becomes,

$$E = (\text{H.I.}) - (N \times S) + R.$$

“The *step* method when used by an experienced instrument man is very fast and fairly accurate. It is not, however, sufficiently accurate for important work, as there is wide margin of error involved in the placing of one hair in the position previously occupied by another. Moreover, there is no simple way of correcting the error resulting from the inclination of sight to the rod when the intercept is read. The *step* method should never

be used when more than six steps are necessary, nor to determine the elevation of a turning-point or set-up. It is well fitted to serve as a check upon the more accurate methods next described, when there is need for especial care to guard against error."¹

3. The elevation of Station *B* can be found by measurement of the vertical angle between the horizontal line of sight at Station *A* and the inclined direct line of sight from *A* to *B* (Fig. 405). After setting up the plane table and placing the alidade with its fiducial edge parallel to *AB*, raise or lower the telescope, with its clamp loosened, until the middle cross-hair rests near the foot mark of the rod. Tighten the clamp and by the tangent screw accurately place the middle hair on the foot mark. Record




FIG. 405.—Illustration of a method of determining vertical angles.

this foot mark in the notebook and wave the rodman off the station. On the vertical arc read the angle of inclination of the telescope to the nearest minute and record this under "Angle." Level the telescope, read the vernier again, and record the reading under "Level." Angles upward from the horizontal are positive, and those downward from the horizontal are negative. Algebraically subtract the plus or minus angle (as the case may be) from the level reading to obtain the included vertical angle (Fig. 405). The difference of elevation corresponding to the included angle for a horizontal distance of 100 ft. can be found by using a stadia conversion table or a stadia slide rule. Multiply this quantity by the number of hundreds of feet in the distance, *AB*, to get the difference in elevation between these stations. If the base of the rod was not used, the computed difference of elevation must be corrected accordingly. The corrected quantity

¹ Bibliog., MATHER, KIRTLEY F., 1919, pp. 123, 124.

is to be recorded under "Difference of Elevation," and is to be marked minus if *B* is lower than *A*, and plus if *B* is higher than *A*. Algebraically add this quantity (the difference of elevation) to the H.I. at *A* to obtain the elevation of *B*.

"A vertical angle of 1 minute subtends a chord of 0.3 ft. at a distance of 1,000 ft.; hence it is imperative that no mistake be made in selecting the vernier division which coincides most closely with a line of the main scale. Most surveyors make it a practice always to use a pocket magnifier in reading the vernier. It is also easier to detect offsets of the main scale and vernier division lines if one looks obliquely along the lines at an angle of 30° or 40° with the face of the scale than it is when observing the vernier face from a direction perpendicular to it . . .

"The procedure of the instrument man should be planned explicitly to minimize the length of time the rodman is kept at a station. Just as much of instrument work as possible should be done after the rodman has been 'waved on.' With this in mind, the instrument man signals the rodman as soon as the cross-hair is set on the selected mark on the rod; after the rodman has departed he reads and records the vernier, levels the telescope, reads and records the new position of the vernier, wherever it happens to be, and determines the vertical angle by subtraction. He is then under no pressure of haste in reading the vertical arc and in centering the level bubble. To increased speed of geologic work is added thereby greater accuracy in instrumental observations¹ . . . "

"4. *Beaman Stadia Arc*.—The reading of vertical angles may be avoided by the use of the Beaman stadia arc . . . This is a specially graduated vertical arc which may be attached to the vertical limb of a transit or telescopic alidade. It carries two scales, of which the one nearer the adjustable index is known as the multiple scale because it indicates multiples for obtaining difference in elevation. The zero point of this scale is marked 50 and its divisions are so spaced as to be proportional to one-half the sine of twice the angle through which the telescope moves.

¹ Bibliog., MATHER, KIRTLLEY F., 1919, pp. 127-128.

"To determine differences in elevation read the distance subtended on rod and express in feet (for example, 8.7 = 870 ft.). Clamp telescope and level. Set index exactly at 50, by means of the tangent screw back of arc, and do not touch this tangent screw again.

"Then, by means of the customary clamp and tangent movement, raise or lower telescope until there is brought exactly opposite the index such a graduation on the multiple scale as will throw the middle stadia wire somewhere on the rod, it does not matter where. The arc reading, minus 50, multiplied by the observed stadia distance gives the difference in elevation between the instrument and a known point on the rod— that is, the height on rod indicated by middle wire. Settings of both index and arc should be made carefully under reading glass.

"Example: suppose observed stadia distance is 6.3 (630) ft. and that telescope is so inclined that multiple scale reads 58, at which exact setting the middle wire on rod reads 7.2 (7.2 ft. above base of rod) then multiple is $58 - 50 = +8$, and computation for a fore sight would be

$$\begin{array}{r}
 6.3 \\
 \quad 8 \\
 \hline
 +50.4 \\
 \quad -7.2 \\
 \hline
 +43.2 \text{ ft. base of rod above H.I.}
 \end{array}$$

"If middle wire were set on H.I. or top or other fixed point on rod and the arc were read by estimation (for example, 54.2) to obtain a multiple, the result would be approximate only; therefore, this method is not to be used with this attachment.

"If the half-wire interval is read and this reading is then doubled to get the stadia distance, it occasionally happens that no even multiple arc setting which will throw middle wire on rod can be found. In this case make arc setting that will throw the lower wire anywhere on rod; the middle wire will then be somewhere above the top of the rod. Then take multiple as read on

arc, but compute position of middle wire above base of rod by adding one-half the expressed stadia distance (in feet subtended) to the reading of the lower wire.

"Example: if the half wires subtend 7.2 on rod, the distance would be $7.2 \times 2 = 14.4$ (1,440 ft.). If the lower wire cuts the rod 8.7 ft. above its base, the computed middle wire reading would be $8.7 + 7.2 = 15.9$ ft. above base rod. Then compute as before.¹

"The advantages of the stadia arc are readily apparent. The use of stadia tables, slide rules, or diagrams is entirely obviated, nor is there any vernier to be read. The accuracy of the result is identical with that obtained from formula or table computations; in fact, differences in elevation may be read more closely than is possible where vertical angles are determined only to the nearest minute. Moreover, the simplicity of the process eliminates many of the chances of error which are incidental to the use of other methods and gives final results in minimum time. The use of the arc is, however, limited to sights which involve the reading of the stadia rod, and for most 'shots' it holds the rodman on the station longer than is necessary with certain other methods.

"5. *Stebinger Gradiometer Drum*.—The accuracy of a sensitive bubble vial in the striding level is greater than that implied by the reading of the vertical angle only to even minutes. The fine adjustment tangent screw is so threaded² that a complete revolution deflects the telescope about 34 minutes, so that if the unit of measurement be 1/500 a revolution of that screw, the accuracy of reading vertical angles is greatly increased. This is especially important in determining the difference in elevation of a station 2 to 8 miles distant as is frequently done in triangulation work.

¹ "Topographic Instructions of the U. S. Geol. Survey," Washington, Government Printing Office, 1918, pp. 131, 132.

² "The intention of the makers commonly is to calculate the pitch of the screw and the length of the clamp arm so that one complete revolution of the screw head moves the line of sight 1 ft. vertically at a horizontal distance of 100 ft., but this ratio may not be safely depended upon except as a broad approximation."

ANGULAR VALUES OF BEAMAN INTERVALS¹

Number of interval	Angle		Difference in minutes	Number of interval	Angle		Difference in minutes
	°	'			°	'	
0	0	00.00					
			34.38				36.16
1	0	34.38		16	9	19.89	
			34.39				36.42
2	1	08.77		17	9	56.31	
			34.42				36.70
3	1	43.19		18	10	33.01	
			34.47				37.00
4	2	17.66		19	11	10.01	
			34.52				37.32
5	2	52.18		20	11	47.33	
			34.59				37.71
6	3	26.76		21	12	25.04	
			34.68				38.08
7	4	01.44		22	13	03.12	
			34.77				38.49
8	4	36.21		23	13	41.61	
			34.88				38.95
9	5	11.09		24	14	20.56	
			35.02				39.44
10	5	46.11		25	15	00.00	
			35.16				39.97
11	6	21.27		26	15	39.97	
			35.33				40.54
12	6	56.60		27	16	20.51	
			35.50				41.16
13	7	32.10		28	17	01.67	
			35.71				41.85
14	8	07.81		29	17	43.52	
			35.92				42.58
15	8	43.73		30	18	26.10	

¹Reproduced by permission from "Metro Manual," Bausch and Lomb Optical Co., Rochester, N. Y., 1913, p. 114.

The Stebinger gradienter drum surrounding the tangent screw is graduated into 100 divisions, so broadly spaced that the drum may be read accurately by estimation to 0.2 division, and so quickly legible that there is marked saving of time and increased safeguard against error in observation when it is used in preference to the vertical arc. It is in reality simply another method of reading the vertical angle, denoting the angle by an arbitrary unit instead of by degrees and minutes. The value of that unit in length of chord at known distances may be expressed in tables similar to those provided for computation from vertical arc readings.

"In most instruments a clock-wise rotation of the Stebinger drum depresses the objective end of the telescope by pressing against a little stud fixed to the inside surface of the right-hand standard. A counter-clock-wise rotation permits a spiral spring to expand against the opposite side of the stud and thus to raise the objective end of the telescope. Experience indicates that it is unsafe to trust the spring to act with uniform regularity and smoothness. It is, therefore, necessary in using the Stebinger method always to read vertical distances in one direction—usually downward¹—the direction in which the telescope is moved by clock-wise rotation of the drum. If the station is higher than the telescope, the first reading is taken with the horizontal cross-hair cutting the target; the telescope is then turned down to the level position for the second reading. If the station is lower than the instrument, the telescope is leveled for the first reading of the Stebinger drum and then turned down till the cross-hair cuts the target for the second reading.

"The fine adjustment screw to which the Stebinger drum is attached is a tangent screw; *i.e.*, its motion is tangential to the arc described by the arm of the clamp of the telescopic axis. Therefore, a revolution of the screw, when it is near one of its limits of

¹ In some instruments the screw is fixed to the telescope standard and the stud is attached to the arm of the clamp of the telescope axis; when so attached the direction of movement to be used in reading the gradienter is upward.

motion will elevate or depress the telescope through an arc slightly different from that resulting from an equal turn of the screw when it is midway between its limits. Therefore, it is necessary always to begin an angle reading with the tangent screw in approximately the same position as that from which the determination of the Stebinger factors was made. This position, generally about a quarter turn of the screw after it first 'takes hold,' should be indicated by a mark on the celluloid or steel index. After each reading the tangent screw should be withdrawn to that position, ready for the next reading.

"In practice, then, the first reading is made with the Stebinger drum somewhere near the predetermined starting point and with the cross-hair on the distant object, if it is higher than the instrument or with the telescope level if the sight is a *down shot*. The reading, a figure between 0 and 100, is recorded in the proper column of the notebook. The telescope is then turned down by means of the tangent screw to position for the second reading. As the Stebinger drum revolves the total number of revolutions should be counted. The count may be verified by the graduations on the index bar if present and is set down on the left of the two digits which indicate the Stebinger division beneath the index. For instance, after completing eight revolutions, the Stebinger drum is brought to rest at 67; the second reading is therefore recorded in the appropriate column as 867. With an alidade which *reads down*, as is the more common arrangement, the smaller of the two Stebinger readings will be in the 'Sight' column if the target is higher than the instrument, and in the 'Level' column if lower than the instrument. The difference of the two readings expresses the size of the vertical angle in terms of Stebinger divisions. From the Stebinger tables prepared for the individual instrument the corresponding 'Stebinger factor' is selected. This factor multiplied by the apparent distance gives the difference of elevation of target and plane table.

"The preparation of the Stebinger tables is essentially the determination of the value of Stebinger units in terms of circular measure. Withdraw the micrometer screw to the position from

which determinations of vertical angles will be started. Set the drum on an even division and read the vertical arc; turn the drum through 100 divisions and read the arc again. Turn through 200, 300, etc., divisions, reading the arc at each hundred until the screw has reached the farther limit of its play. Usually 9 or 10 hundred divisions will suffice. Repeat the operation at least five times and take the average value in minutes for each hundred divisions. Determine the corresponding difference in elevation for each of these angles by interpolation of regular stadia tables or from a table of natural sines by the formula:

$$\text{Difference of elevation} = \frac{1}{2} \text{ sine of twice the angle.}$$

The first value thus determined divided by 100 is the difference in elevation corresponding to each Stebinger division between 0 and 100. The second value minus the first and divided by 100 is the difference in elevation corresponding to each Stebinger division between 100 and 200. The third minus the second and divided by 100 is the value for Stebinger divisions between 200 and 300, etc. Carry the quotients in each case to the fifth decimal. With an adding machine set at the difference in elevation for one division between 0 and 100, print 100 additions for the factors corresponding to the second 100 Stebinger divisions. Then with the machine set at the difference in elevation per division between 100 and 200, print 100 additions for the factors corresponding to the second 100 Stebinger divisions. Complete the table in this manner, changing the addition figure after each 100 additions. Number the divisions, strike out the extra decimals beyond the third for the first 50 divisions and beyond the second, thereafter, and typewrite into tabular form in parallel columns; the number of divisions in one column, the corresponding factors in another. Brief tables for correction because of curvature and refraction as well as for conversion of observed to horizontal distances should be added at the margin. The whole, if properly planned, will occupy a sheet about 5×7 in. in size when photographed to one-half reduction for field use.

"A slight modification¹ of the above method will give a still more accurate series of factors. Read the vertical arc at each 50th division of the Stebinger drum instead of each 100th; determine the corresponding difference in elevation for each Stebinger unit as before; with the factors thus obtained plot a curve using the numbers of divisions as the abscissas and the values as the ordinates. From this curve the point will be readily apparent at which the micrometer screw begins to work with reasonable uniformity; begin constructing the table to be used at that point. From the curve determine the points where the factors for two successive divisions differ by 0.00005 and compute the factors for the number of divisions represented by each of these points; interpolate between the values thus obtained to complete the table.

"The table of Stebinger factors should be checked every few weeks by comparing a half dozen Stebinger readings, made at haphazard intervals well distributed throughout the range of the micrometer screw, with the corresponding readings of the vertical arc. The Stebinger factor should be identical, on the average, with the vertical distance corresponding to the arc reading.

"In reading the Stebinger drum the observation should be made from directly above the celluloid or steel index so as to project the index line vertically downward to the drum. Ordinarily, a reading to the nearest Stebinger division is sufficiently close, but for low angles and long 'shots' it is better to estimate half divisions, and for the nearly horizontal 2-5 mile 'shots' of triangulation it is frequently worth while to estimate to tenths of a division. For these long sights, the distance of which is determined by scaling off the space on the map, there is a theoretical error in using tables based on the formula involving one-half the sine of twice the angle, but there is practically no discrepancy here for the difference between the sine of a small angle and one-half the sine of twice the angle is negligible."²

413. Application of the Methods of Location.—The method of radiation is practicable for small areas, quarries, etc., and for

¹ Suggested by K. C. Heald.

² Bibliog., MATHER, KIRTLEY F., 1919, pp. 128-135.

side shots from the main traverse or triangulation net. It has the disadvantage of giving no check upon the accuracy of the work.

The method of intersection is the only one by which inaccessible points may be located and their positions checked. For general mapping it is usually too slow, since several readings have to be made on every station in the triangulation net. Consequently it is seldom used by the geologist except for the location of single stations. In some kinds of open country, and particularly in unsurveyed regions, a triangulation net may be prepared by engineers in advance of the geologic work.

Resection is of great value to the geologist who is provided with a base map and wants to locate himself by reference to visible stations previously established. In some kinds of open country and in unsurveyed regions, an engineering party may go out and prepare a triangulation net. The engineers build monuments or set flags at conspicuous triangulation points, and make an accurate map of the system of stations established by them. Provided with this map, the geologist can then go into the field and, whenever he wishes to locate an outcrop or other point of interest, he can do so by resection from three or four of the triangulation stations. They constitute his control system. A disadvantage of this method is that, unless he is accompanied by an assistant, the geologist is encumbered with plane table and alidade. With an assistant to carry the instruments, he can use an ordinary plane table and telescopic alidade, but, if alone, he will do well to reduce this equipment to a small plane table, a Gurley compass or other open sight alidade (331, 347), and an aneroid for elevations.

Stadia traversing is especially useful for route maps along roads, streams, or across country, and for general mapping of exposed stratified rocks. In comparison with triangulation it has the advantage: (1) that ordinarily each station has to be visited only once; and (2) that the course, being open to more modification than in triangulation, is more adaptable to the tracing of exposures.

414. Variations in Plane Table Parties.—We have stated that plane table mapping with telescopic alidade is performed by a rodman, who is commonly the geologist, and an instrument man. These two individuals constitute a plane table party. To each such party a specific area may be assigned for mapping. Under certain circumstances larger parties may be used to advantage. There may be an instrument man, a geologist, and one or two rodmen. The geologist will then be the chief of party, and it will be his duty so to direct the work that all members of his party are kept busy while he, himself, has time, not only to supervise their work, but also to reconnoitre ahead of the mapping and lay plans for their advance. He may have to spend a day or two looking over the field before his party begins work.

CONCLUSION

415. Comparison of the Methods of Field Mapping.—The four methods of field surveying, described in the foregoing pages, differ in respect to the accuracy of the results which may be obtained by using them. Named in the order of increasing possible precision, they are, the hand level method, the compass and clinometer method, the barometer method, and the plane table method.

The hand level method is of value chiefly in certain kinds of rough reconnaissance work, and more often for ascertaining local strikes and dips of gently inclined stratified rocks. It is very seldom employed in areal mapping.

The compass and clinometer method is satisfactory in the mapping of areas underlain by igneous and metamorphic rocks and sedimentary rocks which have dips of about 5° or more. It should not be chosen for work in regions of low-dipping strata. The degree of accuracy of the results depends primarily on the number and precision of location of the control stations to which the compass traverses are tied.

Both the barometer method and the plane table method may be used in many types of mapping, but they probably have their greatest value in the mapping of moderately dipping stratified

rocks. There can be no question that the plane table method, when performed by competent men, is more precise than the barometer method. On the other hand, the latter has several advantages which make its practice more desirable under certain conditions. Among the advantages of the barometer method, we may mention the following:

1. It requires only one man, whereas the plane table method requires at least two, namely, the instrument man and one or more rodmen.

2. It is very elastic in its possibilities of speed and degree of precision attainable, and these factors are to a considerable extent within the geologist's control. The plane table method is more limited in this respect.

3. The equipment for the barometer method is much lighter and more easily portable than that for the plane table method.

4. The barometer method is more satisfactory than the plane table method in forested areas and regions of low relief, where the intervisibility of points is poor.

Some of the disadvantages of the barometer method are:

1. Satisfactory aneroid barometers are difficult to secure.

2. In general this method requires a more experienced, and therefore a more highly salaried, man than does the plane table method.

3. Since, in the barometer method, it is customary to follow north-south or east-west lines, or roads, or property boundaries, or other definite directions, the traverses usually cross outcropping strata, making correlation very difficult where the beds are not easily recognized. Under these circumstances the plane table method is more satisfactory since the rodman may walk or trace the outcropping beds and so facilitate their correlation.

4. The barometer method necessitates the correction of the barometric readings before the map can be made, whereas, by the plane table method, the mapping may be practically completed in the field and errors may thus be more readily detected.

416. Sources of Error.—Errors, which may affect the results in geologic mapping, may be classified as: (1) instrumental

errors; (2) errors in procedure; (3) errors caused by geologic conditions; and (4) personal errors.

1. Instrumental errors are occasioned by imperfect adjustment or defective manufacture. To determine the efficiency and accuracy of his instruments, the geologist should at least know how to test them. He will often find it of advantage to be able to make minor adjustments. For complex adjustments he should send the instrument back to the maker.

2. Errors in technical procedure are due to carelessness, insufficient training, or lack of practical experience. These errors may come through misuse of the instruments and equipment or through misinterpretation of such geologic features as cross-bedding, settling, etc. (319, 321).

3. Errors caused by geologic conditions include certain variable quantities which are dependent on the number and size of outcrops, the amount and kind of weathering of exposures, changing stratigraphic intervals between beds, ease of correlation, etc. These errors are sometimes large and sometimes small. They are never entirely eliminated. The geologist, however, should always endeavor to estimate about how great such errors may be in his work.

4. Personal errors are those which are attributable to the habits and state of mind of the geologist himself. They come under the head of the *personal equation*. Each man should try to discover his own personal equation and reduce it as far as possible.

417. Limits of Error.—Every instrument, if carefully used, can yield results which are accurate within certain limits; but beyond these limits greater precision is practically impossible. In the same way, each method of field surveying has its limitations. Instruments and methods are usually chosen for field investigations with a view to: (1) the precision required; and (2) the precision attainable. If the work must be done rapidly and great accuracy is not demanded, field procedure and equipment are selected with rather large limits of error; in other words, with a rather large permissible error; and *vice versa*. In every case, however, the geologist should know the limits of error of his instruments and of the field method which he adopts.

Distances obtained by pacing may be correct to 3 per cent or less. The error may be reduced to 1 per cent if the paces are frequently standardized. In very rough country with heavy underbrush, the error will probably amount to more than 3 per cent. Taping, with ordinary precautions, is much more accurate, being correct to at least 1 in 3,000. On automobile traverses measured by odometer, readings may be in error as much as $\frac{1}{10}$ mile for any distance, if the odometer is perfectly regulated. Usually such an instrument registers a little more or a little less than a mile for every map mile (horizontal mile) traversed, on account of imperfect adjustment, rough roads, strong topographic relief, use of over-size casings, etc. Errors of this kind the geologist must ascertain for his particular machine.

Triangulation performed with sight alidade and oriented plane table should be correct to 1 in 500, and with telescopic alidade and oriented plane table, to 1 in 1,000 or 1,200. In stadia traversing, with oriented plane table, telescopic alidade, and stadia rod, reasonable care will yield results correct within 1 in 200 for horizontal closure or better, and within 3 to 5 ft. of closure in elevation, no matter how long the traverse may be, since these errors are largely compensating. For smaller scales under like conditions, the limits of error are larger.

In barometric work, the permissible error in relative elevations ought not to be more than half a contour interval, as the map is finally constructed.

Something has already been said in reference to errors in determining dips (318).

It should be noted that the error in location of a point is equal to the error of the least precise method of measurement employed for the three quantities of direction, horizontal distance, and vertical distance. For instance, a compass traverse or a traverse with plane table and sight alidade is correct to only about 1 per cent if the distances are measured by careful pacing. In any mapping the error permissible for elevations should be similar to that allowed for the horizontal control. For this reason, on the basis of the limits of error cited above, reduction of slope distances to their horizontal equivalents is unnecessary.

on slopes of 1 in 7 (about 8°), or less, for work in which distances are paced; on slopes of 1 in 12 (a little under 5°), or less, for compass traverses in which distances are measured by tape; on slopes of 1 in 15 (about $3^{\circ} 30'$), or less, for triangulation with sight alidade; and on slopes of 1 in 25 (a little under 2°), or less, for ordinary triangulation with telescopic alidade.

For further remarks on the subject of degree of accuracy, and sources and limits of error, see Arts. 305, 318, 324, 363, 365, 366, 397, 398, 399, 409, 415, 416.

418. Factors Affecting Choice of Method.—In view of the great variety of the problems which may require field mapping, we can do no more here than mention some of the factors which may influence the geologist in his selection of the field method. Such factors are:

1. The kind of rocks prevailing in the region.
2. The type of geologic structure.
3. The type and extent of vegetation.
4. The topographic relief, steepness of slopes, and altitude of the region.
5. The purpose of the investigation, *i.e.*, whether purely scientific or economic.
6. The scope of the result desired, *i.e.*, whether information is wanted on all related phases of a general geologic problem or information is sought only in reference to some one particular question.
7. The accuracy of the results required.
8. The number of men available.
9. The number and condition of the roads, and the methods of travel.
10. The source of food and other supplies.
11. The time available for the work.
12. The funds available for the work.
13. Whether or not the work is to be done in a foreign country.
14. The general climatic conditions.

419. Topographic Contour Sketching.—Occasions not infrequently arise when the geologist finds it of advantage to sketch the topography by contours. To do this, a contour interval

adapted to the relief of the land and to the scale of the map must first be selected. In general a smaller interval will be used for low relief and for large scale. Mean sea level is commonly taken as the datum plane. The position of the first contour drawn on the map will depend upon the altitude of Station 1 above sea level and upon the slope of the ground between Stations 1 and 2. As the mapping proceeds, the points where successive contours intersect the lines of sight are interpolated according to the differences of elevation between stations. The spacing of these points will naturally be close on steep slopes and wide on gentle slopes. Observations for relief should always be made at changes of slope. The contours themselves are sketched in by eye, the observer having due regard for the changes of slope, and for valleys, hills, and other topographic forms. Contour sketching is often done in connection with traversing. If the traverse runs across a slope, the geologist stops at any favorable locality, notes the distance from the last station, sights uphill or downhill perpendicular to the contours, and reads the slope angle in this direction. He plots the sight line on the map and marks off the points where the contours intersect this line at intervals which are determined by the slope angle. If the traverse runs up or down the slope, he can sight parallel to the contours and plot their directions adjacent to his course. When a few such lines with the contour intersections have been plotted, the contours themselves can be sketched.

420. Schedules for Mapping.—To summarize the procedure in certain types of geologic mapping, the following schedules have been prepared. In using them the reader must bear in mind that, since it is impossible to make such schedules applicable to the great variety of conditions which may arise, they may require modification and enlargement.

SCHEDULE I. A COMPASS TRAVERSE

Method.—Directions by Brunton compass; distances paced; elevations by barometer; plotting with notebook or unoriented plane table.

Conditions.—A control system established; a base map with a few control stations plotted; camp (or headquarters) near one of the control stations.

Procedure. Preliminary.—(a) Rule base map with N.-S. and E.-W. coördinates. (b) Set the compass for true bearings. (c) Find the elevation of camp with reference to the adjacent control station, which may be called Station 1. (d) Record the reading of the barometer an hour or so before leaving camp. (e) Record the reading of the barometer just before leaving camp.

At Station 1.—(a) Check barometer. (b) Mark a point on the map for Station 1, and record the elevation of Station 1. (c) Select a suitable point in the field for Station 2, or decide in which direction to walk from Station 1. (d) Find the bearing from 1 toward 2 and plot this bearing on the map. (e) Observe and plot the bearings of any other objects to be located from Station 1.

Between Stations 1 and 2.—(a) Pace toward Station 2. (b) If necessary stop to make and plot offsets, or to record useful geologic information. (c) Always note and scale off the distance from Station 1 to the point of stopping. (d) Continue pacing toward 2.

At Station 2.—(a) Make a note of the distance, 1-2. (b) Check bearing by backsight on 1. (c) Scale off distance, 1-2, on map. (d) Read barometer and record this reading. (e) Select a suitable point in the field for Station 3. (f) Find the bearing from 2-3; etc. (Continue as before. See (a) under Station 1.)

Whenever possible tie the traverse to another control station and make any necessary corrections for distance and direction. Keep a record of the barometric readings and correct them by a plotted correction curve after returning to camp (388-392).

SCHEDULE II. TRAVERSE WITH ORIENTED PLANE TABLE

Method.—Directions by sight alidade; horizontal distances by pacing; vertical distances indirectly by clinometer; contours by reference to differences of elevation; plotting with oriented plane table.

Conditions.—A control system established; a base map with a few control points plotted; one of these control points is

taken as Station 1; another control point, *X*, is visible from Station 1.

Procedure. *Preliminary.*—(a) Rule base map with N.-S. and E.-W. coördinates. (b) Select a contour interval to be used in contouring the topography.

At Station 1.—(a) Set up the plane table at Station 1 and orient it by the method of backsight on *X*. (b) Select a suitable point in the field for Station 2. (c) Sight at 3 and draw 1-2. (d) Determine the slope angle from 1-2 and record it. (e) Observe and plot the bearings of any other objects to be located from 1, or of slopes for contouring (419). (f) Fix the position of contours and sketch them in (419).

Between Stations 1 and 2.—(a) Pace toward Station 2. (b) If necessary stop to make and plot offsets, or to record useful geologic information, or to take slope directions and slope angles for contouring. (c) Always note and scale off the distance from 1 to the point of stopping, correcting for pacing and slope. (d) Continue toward Station 2.

At Station 2.—(a) Set up the plane table at 2. (b) Make a note of the distance, 1-2. (c) Correct this distance for paces on slope and reduce to horizontal equivalent (364). (d) Scale off the corrected distance, 1-2, on the map. (e) Orient the plane table by backsight on 1. (f) Select a suitable point in the field for Station 3. (Continue as before. See (c) under Station 1.)

SCHEDULE III. A STADIA TRAVERSE

Method.—Directions, distances, and differences of elevation by telescopic alidade and stadia rod; plotting with oriented plane table.

Conditions.—Control system of widely spaced stations established; base map available; elevation of Station 1 may be known or assumed; magnetic declination known.

Procedure. *Preliminary.*—Rule the map sheet in coördinate squares on the scale adopted for the work. Rule the magnetic north-south line on the map. Select an established station on the ground and locate it on the map as the starting point. Call it Rod Station 1.

At Instrument Station 1.—The instrument man goes to a point, designated Instr. Station 1, from which he can see Rod Station 1 and a wide stretch of surrounding country. Here he sets up, levels, and orients his board, and sights back at the rod held at Rod Station 1. He reads the distance and difference of elevation, determining his position and the height of the instrument (H.I.). When ready he waves down the rodman (geologist), who proceeds to Rod Station 2. The instrument man locates this point and determines its elevation, and then waves the rodman to Rod Station 3; and so on, until the rodman, having been to as many points as he wants located in the vicinity of Instr. Station 1, signals the instrument man to plot and record the last Rod Station as a turning-point, and then to proceed to Instr. Station 2.

At Rod Station 1.—The geologist, as rodman, first goes to Rod Station 1, the elevation of which is known or assumed, and examines the rocks while the instrument man is on his way to Instr. Station 1. He then holds the rod for the instrument man to make the observations noted above.

At Rod Station 2.—After the instrument man has waved the rodman down from Rod Station 1, the latter follows the outcrops, and holds the rod at any points—Rod Station 2, 3, 4, etc.—which he will need for making the map. If he is surveying an area in which stratified rocks outcrop, he takes elevations above or below his key horizon whenever practicable, thus determining and checking the exposed geologic section. When he has examined all the exposures surrounding Instr. Station 1, he signals the instrument man a *turn* (T), and holds his station until the instrument man has set up at Instr. Station 2 and has located this station (Instr. Station 2) by backsight on the turning-point. After this is done, the process is repeated as before.

SCHEDULE IV. TRIANGULATION

Method.—Directions by telescopic alidade; base line measured by tape; other horizontal distances plotted by triangulation; vertical distances computed by stadia method; plotting with oriented plane table.

Conditions.—The elevation of Station 1 is either known or assumed; no plotted control; no base map; magnetic declination not known.

Procedure. Preliminary.—(a) Rule the paper for the map with N.-S. and E.-W. coördinates. (b) Choose a suitable position for the base line. (c) Call one end of the base line Station 1 and the other end Station 2.

At Station 1.—(a) Mark a point on the map sheet for Station 1 and record its elevation. (b) Determine the magnetic declination. (c) Set the compass (to be used for any necessary radiation, traversing, strike-reading, etc.) for true bearings. (d) With the table oriented, sight at the rod held at Station 2 and draw 1-2. (e) Note angle of declination from 1-2, and compute elevation of 2. (f) Sight at other stations to be located from 1 and draw lines from 1 toward them. (g) Compute elevations of these stations.

Between Stations 1 and 2.—Measure base line by tape.¹

At Station 2.—(a) Scale off 1-2. (b) Carefully orient the table by backsight on 1 and check for inclination and elevation. (c) Sight at all stations located from 1, and at any additional stations; draw lines on the map from 2 toward these stations; note angles of inclination from 2 to each of them; and recalculate their elevations and check with their elevations as determined from Station 1. Call one of these stations 3.

Between Stations 2 and 3.—Proceed to Station 3.

At Station 3.—(a) Orient by backsight on 2 and check for elevation. (b) Check also by sighting at other stations located from 1 and 2. (c) Sight at any additional stations, draw lines toward them, note angles of inclination from 3 toward them, and compute their elevations.

Continue thus from station to station, each time using one of the plotted sides of a triangle as a base for the further expansions of the system.

The reader should understand that all sights are made from instrument stations at the rod held at the distant stations.

¹ It is often better to measure the basic line twice, once in each direction, before locating stations from 1 and 2.

CHAPTER XVII

GEOLOGIC SURVEYING

PART IV. AIRPLANE MAPPING

421. Methods.—Before the airplane became an accepted and reliable means of transportation, maps were made by methods such as those described in Chapter XVI. For detailed mapping, a great deal of time and labor were expended. With flying in its present state of development, however, surveying and mapping from the air can often be accomplished over many square miles in a remarkably short time and in more detail than was formerly possible.

Aerial mapping is rapidly gaining in practical application. It is used for charting routes for railroad and pipe-line construction; sites for reservoirs, dams, and irrigation projects; shore lines for submerged rocks and bars which endanger shipping; and geologic features of various kinds.

In general three methods of airplane geologic surveying are in vogue. In each, the plane is controlled by an experienced pilot, and the surveying is done by another person. In one method this other person is a geologist who is provided with a base map on which he sketches such features as he wishes to record. He makes his observations by eye. The base map has on it the main roads, railroads, towns, ponds, and stream courses in the country to be examined. Sometimes two, or even three, geologists fly together in the same plane and endeavor to sketch the same geologic features, each on his own base map, thus facilitating comparison and correction of the results at the end of the flight. Since the progress of the plane is rapid, this kind of sketching requires constant attention and uninterrupted observation of details. It is very exacting work, and cannot well be done for

more than a few hours at a time. This method may be called *aerial* or *airplane reconnaissance sketching*. It is of value only where the features to be sketched stand out conspicuously.




FIG. 406.—A. Oblique airplane view of an area in West Virginia. B. Sketch cross section to show geological structure. The Oriskany sandstone and Tuscarora quartzite are hard, resistant formations. Note that the hill (B in the section) is anticlinal. (Figure 406, A, reproduced from Rich, with permission of the American Geographical Society of New York. See Bibliog., Rich, John L., 1939, Fig. 25.)

In the second method of airplane surveying, the geologist or physiographer, who accompanies the pilot, takes photographs of the country in which he is interested. These photographs are usually *oblique*, that is, they are not taken vertically downward. They have a general scientific value in displaying physiographic,

geographic, and geologic features in perspective (Figs. 406 and 407). They are excellent for purposes of illustration. When paired and examined by stereoscope, they facilitate studies of small differences of slope and elevation.




FIG. 407.—A. Oblique airplane view of an area on the Virginia-West Virginia line. B. Sketch cross section to show geological structure. (A and B reproduced from Rich, with permission of the American Geographical Society of New York. See Bibliog., Rich, John L., 1939, Figs. 16 and 17.)

The third method of airplane surveying is *aerial photographic mapping*, in which the photographs are made with the camera pointing vertically downward. This is the most precise of the three methods, and it is the one to which the rest of this chapter refers, unless otherwise stated.

In aerial photographic mapping, the pilot is accompanied by an expert photographer and the "ship" is provided with a camera devised for the purpose and mounted so that it will take photographs through an opening in the floor of the plane. Most of the cameras for this work take pictures $7\frac{1}{4}$ by $9\frac{1}{2}$ in. in size, on roll films in lengths of 75 ft., enough for at least 100 exposures. To emphasize color differences and to reduce the effects of haze, color filters are used on the lens, and the films are panchromatic.

Ordinarily the plane is flown in straight lines as nearly as possible at a fixed average height above the ground. For most geologic work, the best practical heights are between 10,000 and 16,000 ft. The photographs are taken sufficiently often, and parallel belts of the country are photographed sufficiently close to one another, to permit each picture to overlap the adjoining pictures by a margin of 50 per cent.

In aerial photography absolutely clear weather, without clouds and with a minimum of haze, is necessary. Haze greatly reduces the definition of distant objects, and cloud shadows very seriously obscure the features of the ground. If the nature of the work requires topographic details, the photographing is done in the middle of the morning and the middle of the afternoon, but not too near noon. On the other hand, if shadows due to relief are not desired, the photography is undertaken in the two or three hours of day when the sun is highest. To assist in locating boundaries, etc., on the finished map, strips of unbleached muslin may be spread on the ground before the photographs are made. Two strips, each 100 ft. long, may be laid at right angles to one another in the form of an L, one east and west, and the other north and south; and these signals, which should be carefully surveyed in position, should be so disposed as: (1) to bear fixed relations to the property or land lines; and (2) to be recognizable on the photographs. These marks are the *ground control* for the aerial map.

The films exposed in airplane photographic mapping are developed and printed and the prints are carefully matched and glued together. The resulting mosaic may be photographed to larger

or smaller scales. Where a map of this kind is wanted to serve as a base for geologic field work on the ground, it may be enlarged and printed in sections mounted on linen for folding. A semi-gloss or dull paper is used so that the field man can draw on it with pen or pencil.

The scale of an airplane photograph should always be known and indicated on the film; also the angle of the camera lens, the altitude from which the picture was taken, the time of day, and the tilt of the camera if off the vertical. The scale of the photograph is equal to the focal length of the lens (f) divided by the height (H) of the plane. Thus, if the focal length is 6 in., and the picture was taken at 5,000 ft., the scale will be

$$\frac{f}{H} = \frac{0.5}{5,000} = \frac{1}{10,000}^*$$

422. Errors and Distortion in Aerial Photographs.—Aerial mapping, even when conducted under the most favorable conditions, is subject to certain inaccuracies. These are due (1) to the difficulty of flying a straight course, both horizontally and vertically; (2) to the difficulty of preventing tilting of the plane, and therefore tilting of the camera axis, in flight; and (3) to the fact that all photographs, even when taken looking vertically downward, are perspective views.

If provided with a good aeronautical map as a guide, and if flying between 10,000 and 15,000 ft. above the ground, an experienced pilot can usually maintain a course within less than 1° of the intended direction, and changes of altitude will not greatly exceed 100 ft. over flat or moderately rolling country.¹ At lower levels air conditions become much more variable, and consequently steady flying becomes difficult or impossible. For this reason aerial photographic mapping is seldom attempted at altitudes of less than 7,500 ft.

Tilting of the plane, caused by variable winds and air currents, is almost impossible to avoid. This means that there may be

* See Art. 290. Bibliog., LEE, WILLIS T., 1922, p. 74.

See Bibliog., DAVIS, FOOTE, and RAYNER, pp. 784-785.

some distortion of the photographs. However, the statement is made¹ that in photographs taken between 10,000 and 15,000 ft. above the ground, from 50 to 80 per cent of the pictures will be tilted less than 1° , and rarely will any be tilted over 3° .

A photograph taken looking vertically downward includes only a single point that is *directly* beneath. This point, on the picture, is called the *nadir point*, since the nadir is always vertically below, just as the zenith is vertically above, the observer's position. All objects with vertical dimensions, not at the nadir point, are distorted, since they are actually viewed in perspective. In other words, an aerial photograph is a radial projection and not, like all drafted maps, an orthographic projection. We may explain this as follows: Imagine two points, one vertically above the other. Call the higher *A* and the lower *B*. If the camera is vertically above *A*, it is vertically above *B* also. In other words, a photograph would show no distortion here on account of differences of elevation of the ground. But suppose that the plane is off to one side of *A*, so that the rays of light from *A* (or *B*) will enter the lens along an inclined path. Then the rays from *A* will reach the film in the camera farther from the center of the picture than the rays from *B*. Obviously, there will be distortion in photographing the ground on the vertical line from *A* to *B* according to the height of this point relative to the surrounding country. Where the land surface is not horizontal, all points not directly below the lens will be more or less displaced in the photograph, and the amount of this *topographic distortion* will depend on the ruggedness of the country, the focal length of the camera lens, and the height at which the picture was taken.

"The most commonly used type of mosaic is made by matching the various prints along lines of common points. Where there is much variation in elevation, such mosaics become less and less accurately matched, as the area included in a single sheet is increased. In order that the unavoidable errors of matching may be equally distributed, rather than allowed to accumulate from one print to the next, some form of map control is desirable.

¹ *Ibid.*, p. 785.

Inasmuch as radial lines from the center of a photograph to various points subtend true angles at the center point, the pictures may be used as a basis of a triangulation system by which the true position of control points is determined. This is commonly known as the radial-line method of control. The U. S. Geological Survey has used this method in compiling line maps of considerable accuracy, and has issued a booklet describing compilation of maps by this method. A map of this type may be used as a base on which a picture mosaic is laid. To make the individual pictures fit the control points on such a map, it is necessary to alter the size and shape of the prints used from the size and shape of the original negative. Such prints are known as *rectified prints* and are made in a projection printing machine, instead of on a contact printer. Some pictures may be rectified only by changing the scale of the print from that of the original negative. Such prints are *scale corrected*. In other cases it may be necessary, however, to change the shape also, and for this purpose the negative and the paper carrier in the projection machine must each be tilted relative to the principal axis of the projection lens. Such prints are *tilt corrected*. If sufficient care is used in laying a controlled mosaic with scale- and tilt-corrected prints, the resulting accuracy is greatly improved as compared with that of an uncontrolled mosaic. This accuracy, however, is not comparable with that of points located by the use of transit and chain, as in ordinary ground surveys."¹

423. Application to Geology.—Aerial maps have proved to be of inestimable value in many kinds of geologic, topographic, and physiographic work.² They present a bird's-eye view of the land surface—the shape and distribution of land forms, the distribution of rocks and soils, and the relations of roads, railroads, and other man-made elements, to these natural features—a wealth of detail that could not be matched by the older methods of mapping; and these aerial maps, with all their detail, can be made and studied in less time than was required for the older

¹ Bibliog., ENGLISH, WALTER A., 1930, pp. 1057, 1058.

² Bibliog., WILLCOX, H. CASE, 1925.

maps. In many instances they have revealed geologic features that were entirely overlooked in earlier, even intensive, field exploration.

By the geologist an aerial map may be used (1) as a guide for field work; (2) as a base for field mapping; and (3) for direct interpretation of the geology.

1. If the geologist is provided with a good airplane map of an area in which he is to undertake field work, not only can he gain a fair idea of the nature of the country that he must traverse, but also he can intelligently plan his program in relation to roads, topography, and geologic features. He can see whether roads are numerous or few and to what extent he may have to resort to horseback or to walking, rather than to automobile in examining the land. If pack train or foot traversing is necessary, he can route these to avoid such difficulties as marshes or precipices.

For an understanding of airplane maps for this purpose, the geologist must learn to recognize roads, railroads, houses, water, various kinds of vegetation, stream courses, slopes, etc., as these appear on the maps. Most roads are either very irregular, or they may be in rectangular patterns. Except along well-graded highways, they usually have sharp, angular turns. On the other hand, railroad turns are always curved. Houses and other buildings are most conspicuous by their shadows. Lake waters, if calm, may look black, or dark gray, but, if ruffled by a breeze, they may look white, or light gray. Stream courses commonly branch headward, thus indicating the direction of the general slopes controlling them. Vegetation—woods, grass, brush, cultivated fields, etc.—has various appearances, which must first be checked on the ground. Often it is a good plan for the geologist to make a hasty reconnaissance of the region to compare the features on the ground with their representation on the aerial photographic map before he goes far in outlining his field procedure on the basis of this map. Provided with such a map, he can easily locate himself on the ground and thus facilitate his progress in reconnaissance work.




FIG. 408.—California, coast west of Santa Barbara. Monocline of Tertiary beds dipping toward ocean at angle of 45 degrees. Scale: width of picture = 8,250 ft. (Published through the courtesy of the Continental Air Map Company of Los Angeles.)

2. On the aerial photographic map, geologic features observed in the field can be sketched. The positions of outcrops, traces of scarps, and symbols for rocks may be plotted in their proper relations to topography and culture. For this object, it is best to have two copies of the map, one for the actual sketching in the field, and the other to be used in camp or in the field office. By following this plan, the office copy is kept clean and is available if the field map happens to be lost or damaged. Sometimes, instead of having two photographic maps, a blueprint from the original film or a photostatic copy of the photographic print or an accurate line drawing of the more important features of the photograph, serves for field use, and the photographic map is then kept for the office. To illustrate the value of a photographic base map, consider a region where outcropping strata are nearly horizontal and are dissected by a drainage system that has produced a dendritic and intricate pattern of scarps on the hard layers. If either barometer or plane table mapping is to be done, a great deal of time may be saved if the field men are furnished with an aerial photographic base map or with a copy of the essential features from such a map. They can then very easily trace and correlate the exposed beds shown in the photograph, and they can record elevations on a selected key horizon at properly distributed stations in the field without the need of "walking" this bed through all its ramifications of outcrop.

3. Aerial photographic maps may be used for direct interpretation of the geology, as illustrated in Figs. 408 to 414. If well exposed strata are inclined more than 10° or 15° , the direction of their dip may be evident from the bowing of contacts and beds in the valleys (Figs. 408, 519). Both anticlinal and synclinal folds may be clearly shown by the trend of the strata and their downdip bowing in the valleys (Figs. 409, 410).

Faults, which perhaps are inconspicuous on the ground, may be brought into prominence (Figs. 411, 412).

In countries where rock exposures are few and difficult of access and therefore hard to find, but where there is not too much forest cover to hide them, aerial photographic maps may save

a large amount of time by indicating the positions of these rare outcrops which may then be quickly visited and investigated in the field.

In areas where the rocks are relatively soft and exposures are too small to be seen on an airplane map, the soils derived from



FIG. 409.—An anticline in the Imperial Valley, California. Note small fold developed on NE. flank of large fold. Relief is due to hard and soft Tertiary strata. Desert conditions exist, with the ground almost bare of vegetation. Scale: width of picture equals 3,000 ft. (Published through the courtesy of the Continental Air Map Company of Los Angeles.)

the various formations may be sufficiently distinct, either in color or in respect to the vegetation supported by them or in the details of their topographic form, to reveal, on such a map, how the underlying strata are distributed (Fig. 413). In making the pictures, the photographer uses a color screen to bring out the color effects. In this way, under suitable conditions, formation belts can be charted; contacts can be followed, sometimes with the discovery of broad swings which are significant of anticlinal




FIG. 410.—A synclinal basin seen from the air. Note how some outcrop belts can be seen bending toward center of structure where they cross the valleys. View taken in northern Mexico. Conditions arid, with little soil. Scale such that area shown covers 22 square miles. (Published through the courtesy of Fairchild Aerial Surveys, Inc.)




FIG. 411.—Aerial view of a series of outcropping strata broken by two faults (which trend about N. 80° E.). Scale: width of picture about 8,000 ft. (Published through the courtesy of Edgar Tobin Aerial Surveys of San Antonio, Texas.)

or synclinal structure (314); and obscure faults can be found and traced.

This type of aerial map work requires care and experience on the part of the geologist studying the photographs. He should first examine them in the office; then take them into the field





FIG. 412.—Nearly horizontal strata, cut by a group of parallel vertical faults of small displacement (striking NW.-SE.), and then eroded. These faults are scarcely visible to an observer on the ground. Note how closely erosion is controlled by the faults. The river is the Pecos River, the picture having been taken in northern Pecos County, Texas. The width of the area shown is just over 2 miles. (Published through the courtesy of Fairchild Aerial Surveys, Inc.)

and check the pictured features in a series of traverses planned to cross the formation belts or faults, as the case may be; and then in the office complete the draughting of a geologic map from the combined data of airplane base map and field observations.

It is remarkable how distinctly some soil effects, due to geology, are shown on these airplane maps made by camera and color screen, in spite of the fact that they would pass quite unnoticed



A




FIG. 413.—A, aerial map and B, outline map of same area, showing two gently dipping formations, one *a*, characterized by rather smooth topography and a growth of scattered liveoak trees, and the other, *b*, characterized by dendritic topography and a growth of mesquite trees. The contact can be very easily traced on the air map, whereas in the field it would require a great deal of time. The contacts are shown on the outline map, B. The scale is such that the width of the picture is about 3.9 miles. (Published through the courtesy

on the ground. An instance of this was noted in California. A soil contact, invisible on the ground, was readily traceable on the airplane photograph even where it crossed a field of full-grown



FIG. 414.—Aerial map of the Barbers Hill salt dome, in Chambers County, Texas. No bed rock is exposed. The effect of the uparched formations is brought out by slight differences in the soil. A lighter central area, nearly circular in outline, may be discerned surrounded by soil of darker shade. The edge between these two areas is most distinct on the north and northeast. The picture shows cultivated fields, wooded areas, roads, drainage features, etc. Scale: width of mapped area about 3.4 miles. (Published through the courtesy of Edgar Tobin Aerial Surveys.)

wheat. Figure 414 represents a circular area within which the soil contrasts and drainage pattern are largely a result of the uparching of strata by a salt plug.

424. The Stereoscope in Geologic Mapping.—The principle of the stereoscope is essentially the same as in vision by two eyes

(binocular vision) that see a given object from slightly different angles. This kind of vision enables us to perceive variations in distance, within certain limits, and so to recognize the relief, or three-dimensional character, of objects. For stereoscopic study, two photographs are simultaneously taken of the same view, but through two separate lenses, correctly mounted with reference to one another, and these photographs are then finished on glossy nonshrinkable paper. For the purposes described below, vertical aerial photographs are used. The most satisfactory instrument is the Zeiss pocket stereoscope, which magnifies two and one-half times. The pair of photographs, properly adjusted in this instrument, may serve for areal geologic mapping, for topographic mapping, or for geologic structure contouring.

1. Geologic mapping by stereoscope is like field mapping in miniature. It has an advantage in that the relations of outcropping ledges and formation belts, often difficult to see and follow on the ground, may be easily traced and may be observed at a glance, even on opposite sides of a hill.¹

The most valuable criterion for tracing an exposed stratum under the stereoscope is the break in slope that it produces, if it is relatively resistant to erosion. This may or may not be an actual outcrop. If the bed continues, its scarp also continues, modified according to changes in lithology, structure, relation to the drainage system, cultivation, etc. Scarps that in the field are vague may be traced with ease under the stereoscope, since the observer in this case can instantly get the effect of walking them out simply by moving his eye over the photograph.

A second important criterion and one that is used simultaneously with that of the break in slope is the vertical interval

¹ Much of the following discussion, including direct quotations, is taken with permission from a brochure by Louis Desjardins and S. Grace Hower, entitled "A Technique for Geologic, Topographic and Structural Mapping," published in 1938 by the Aero Exploration Company of Tulsa, Okla. The same paper, somewhat modified, was printed on pp. 44 *et seq.* of the *Oil and Gas Journal* for May 11, 1939.

between beds. In general, this remains fairly uniform over a considerable area.

"Consequently, when work is begun in a region, a rapid examination is made of all the photographs and the place providing the most distinct section is chosen as a starting point. . . . At this type section . . . the breaks in slope are marked, *i.e.*, the working columnar section is drawn up. It has been found convenient to use a different color of ink for each scarp. These scarps are now traced around the country. In cases of thick soil cover or slight lithologic variation giving rise to decreased resistance to erosion, a given scarp may become obscure. It is in such cases that the vertical intervals are of especial use, since if they remain fixed immediately on either side of the obscure locality, it is a fair assumption that they are the same throughout. . . .

"Careful attention to this stratigraphic interval is, in stereoscopic mapping as in the field, one of the best means of recognizing the wedging out or thickening of formations. . . .

"The two criteria mentioned thus far, break in slope and vertical intervals between breaks in slope, have proved by far the most valuable in areal mapping. . . . There are, however, other criteria, which may in certain cases assume . . . importance." Such are soil and vegetational coloring seen on the photographs as variations in tone of gray; also type of topographic form.

In starting to work in unfamiliar regions the aerial geologist can be greatly assisted by advance acquaintance with any peculiar or abnormal geological conditions, either from the study of existing geological maps or reports, or from reconnaissance field work. Such conditions might include glacial deposits, caliche, major unconformities, igneous features, wind deposits, alluviation, faulting, etc. It is not necessary to know the details of these; they will probably be supplied from his stereoscopic study; but fair warning that such abnormal features may occur often saves time and labor.

. . . In "mapping under the stereoscope, one is freed from the task of determining locations with reference to a conventional map, with the attendant difficulties and errors, since the features are drawn exactly in place upon the visual model of the earth's surface. . . . Anyone who has worked in a rugged structurally complex country realizes the clarifying effect of a broad view from some high point within it. Then a ridge can actually be seen bending around in an anticlinal nose or ending abruptly against a fault. Down below, such features have to be walked out before they become apparent. With aerial photographs under the stereoscope, there is always this broad view. The actual dip of a fault plane may often be observed. Again, immediately below the eyes of the observer, there may be a dome with beds dipping off on all sides. The whole structure can be seen at once. It does not have to be pictured in the imagination from data taken at various points."

2. In topographic mapping, all available ground elevation control is used, both to give an essentially correct vertical scale, or contour interval, as applied to the particular area under consideration and also to give the true elevations above sea level. The latter is not necessary if only relative elevations are required, in which case the base level datum may be assumed. The picture seen with the stereoscope is virtually a three-dimensional model of the ground. On this levels are run by eye to agree with the ground control.

"Like field topographic mapping, the stereoscopic technique requires considerable practice before the attainment of proficiency. It is essentially the same training of the eye and the hand. The topographer in the field sketches his contours on white paper, whereas the stereo-topographer has the advantage of drawing his contours on the relief model itself. He is thus enabled to see that they exactly fit and, in addition, preserve equal vertical spacing. Again the topographer in the field is required constantly to allow for the perspective effect of hills and valleys seen from a point on the ground, whereas under the

stereoscope the whole scene is in equal perspective viewed from above. For these reasons such contour sketching in the field requires measured control points very close together, whereas similar accuracy with the same method under the stereoscope can be had from control points half a mile or more apart.

"Though the stereo-topographer has a model of the earth on which to work, that model is always to some extent distorted by slight tilting in the photographs. This tilt may make a stream appear to run up hill during part of its course; may make level ground appear rolling; may steepen or flatten hills. It has been found possible to draw accurate contours in spite of tilt simply by applying ordinary principles of physiography and the results of experience gained in areas with plentiful control."

3. We have described, under 1 and 2, methods of mapping areal geology and topography from aerial photographs by simple stereoscopic means. By combining the results of these two processes, geologic structure contours can be drawn.

"In practice it has been found most successful in the study of any given area to have two sets of prints of the photographs covering it. On alternate pictures of one set the areal geology is drawn. On opposite pictures of the other set are drawn the topographic contours. The two processes are carried on separately, as they may be mutually confusing if done simultaneously. The picture bearing the geology is then combined, under the stereoscope, with one bearing the topography, and a single image showing geology and contours is the result" (Fig. 415, A, B, and C).

"Where only one set of prints is available, the topographic contours can be drawn on traceolene placed over the alternate prints not used for geology. Traceolene is at this point placed over the print bearing the geology and section lines or other location marks are traced through. Elevations are then noted at many points on all the beds mapped, using different colors for the figures for each bed. Tentative structure contours are drawn for each bed from these elevations. When this has been done,

GEOLOGIC SURVEYING



FIG. 415, A.—Airplane photographic map of an area in Oklahoma, showing geologic contacts (top of Fort Scott limestone and top of Prue sandstone) which have been sketched in on the picture. (Figures 415, A to C, are reproduced through the courtesy of the Aero Exploration Company of Tulsa, Okla.)



FIG. 415, B.—Same view as in Fig. 415, A, but with topographic contours sketched in. Contour interval, 20 ft.




FIG. 415, C.—Same view as Fig. 415, A and B. By superposing the contours of Fig. 415, B on the formation boundaries of Fig. 415, A, as described in the text, structure contours may be drawn on a selected key horizon. This has been done in Fig. 415, C, where the top of the Fort Scott limestone has been contoured, using a 10-ft. contour interval.

cross sections are run on the basis of the structural contours at half-mile or other intervals across the strike. This is done on cross-section paper on the same scale as the photograph. At this point many previously unnoted discrepancies in vertical intervals show up and may be corrected or taken into account. On the cross sections, a key bed is selected and extended where necessary, at its proper interval with reference to other beds above or below. On a fresh sheet of traceolene, placed over the other, the elevations of the key bed are laid out along the lines of each of the cross sections. Then a single system of structural contours with these elevations is finally drawn to agree with the average directions of the contours of all the individual beds.

"A convenient final form for the mapping of a region has been found to be a photo-mosaic on the same scale as that of the contact prints. On to this, under the stereoscope, is transferred, with all the accuracy of tracing, the areal geology. The final structural contours are then drafted directly on to the mosaic or on to a tracing vellum plat made from it. The result then is a photograph of the region with superimposed geology and structural contours."

Although the stereoscopic method, as outlined above, applies to regions of exposed *sedimentary* beds, there are many ways in which it is valuable for mapping in areas of igneous and metamorphic rocks. In comparison with field mapping, it requires much less time and provides much more detail. If the photographs have been secured, their stereoscopic examination can go on regardless of weather conditions, degree of accessibility of the region, and the attitude of the inhabitants.

CHAPTER XVIII

SUBSURFACE GEOLOGIC SURVEYING

425. Scope.—Underground or subsurface geologic surveying has long been practiced in the mining industry, by observations in shafts and tunnels and also by means of cores obtained by the diamond drill. Between 1920 and 1930 great advances were made in interpreting subsurface conditions through the study of samples of the formations penetrated in drilling for oil, gas, or water. Since then further advances have been made, especially through the application of electrical logging (430). In petroleum geology, subsurface research in many parts of the country has become more important than surface mapping, and there is every reason to believe that subsurface geology will gain in value as time goes on. In the present chapter we shall refer only to subsurface geology as this is related to bore-holes. The subject of mine surveying and examination can be found discussed in textbooks and treatises devoted to mining and mining geology. In this chapter attention will be given mainly to methods of securing and studying data and samples. In Chapter XIX, Arts. 457 to 464 describe the uses of these data in subsurface correlation and mapping. Many parts of Chapter XIX relate directly to subsurface geology.

426. Methods of Drilling.—There are three principal methods of deep drilling. These are cable drilling, rotary drilling, and diamond drilling. For the better understanding of logs, these three methods are described below, but only in the briefest way.

1. *Cable drilling* is also known as *cable-tool drilling*, the *percussion method*, or the *standard method* of drilling. The outfit consists essentially of a "string of tools," at the lower end of which is a heavy steel bit, suspended on a manila or wire cable

which can be lowered or raised by controlling machinery near the mouth of the hole. In drilling, the tools are alternately lifted and dropped, the rock being cut by the repeated blows of the bit. Some water is always kept in the hole. Enough may drain in from the rocks penetrated, but if they are dry, water must be added from above. If a water-bearing stratum yields too copious a flow, it must be "cased off" by sinking a "string" of pipe, or "casing," to a point below it. In the same way, relatively soft materials may have to be cased off to prevent their "caving."

The rock cuttings are removed in a bailer which is lowered at intervals sufficiently frequent to keep the bottom of the hole fairly clean of *débris*. These cuttings are dumped into a "slush pit," at the mouth of the well. They serve as specimens of the rocks drilled. Other indications of the rocks penetrated are found: (1) in mud or clay stuck to the bit; (2) in exceptional wear on the edge of the bit, caused by the drilling of sand, sandstone, or other hard, abrasive materials; (3) in the "kick," or vibration, of the cable, noticeable while drilling in hard rocks; and (4) in the observed rate at which the drilling proceeds, since hard rock is more slowly cut than soft rock.

2. *Rotary drilling*, as generally understood, is accomplished by the rotation of a perforated fishtail bit (or, in harder formations, a "rock bit") which is screwed firmly to the lower end of a string of pipe, known as a "drill stem." The drill stem itself is rotated by a turn-table at the mouth of the hole. It is lengthened by the addition of new "joints" of pipe whenever the increasing depth of the hole demands. When the bit requires sharpening, it is raised to the surface by unscrewing the joints of the drill stem, usually in threes ("thribbles") or fours ("fourbles"), and these thribbles (or fourbles) must be screwed together again when the bit is lowered to resume drilling. During the drilling, a thin mud is kept constantly flowing downward inside the drill stem, out through the perforations in the bit, upward between the drill stem and the walls of the hole or the innermost casing, if casing has been set, and out at the mouth of the hole. This mud serves the double purpose of keeping the bit cool and

supporting the walls of the uncased part of the hole by virtue of the hydrostatic pressure exerted by it (the mud fluid). By this means, in many cases, loose materials may be prevented from caving and water may be kept from entering the hole when water-bearing sands are penetrated. Where the driller expects to encounter natural gas under high pressure, he thickens the mud in order to hold the gas back in the sand, for otherwise the whole column of mud may be blown out, an event which may entail serious consequences. In deep holes part of the weight of the drill stem is held off the bit to prevent the hole from "going crooked," i.e., deviating from a vertical course (Art. 434). The amount of weight applied on the bit is shown by a recording weight indicator on the derrick floor.

The mud returned from the bottom of the hole brings up with it cuttings of the materials drilled. They are not always easy to recognize, and furthermore, they do not appear at the surface until some minutes after they were cut. The determination of their source is assisted by the driller's observations on the behavior of the bit, indicating whether it is cutting soft or hard rock. When better samples of the rock are required, the driller uses a bit constructed to cut and retain a core of the formation penetrated. The *conventional* core bit, like the ordinary fishtail bit, is screwed to the lower end of the drill stem. Centrally, inside it, is a barrel into which the core passes as the bit cuts deeper. The drilling mud, meanwhile, passes down between this barrel and the outer metal shell of the bit; thence out at the lower end of the bit; and from there up outside the bit and drill stem. When the desired length of core has been cut (usually from 10 to 20 ft.), the core is raised to the surface for examination by the slow process of "breaking down the drill stem" in thribles or fourbles.

For quicker results, it has become common practice to use what is termed a *wire-line core barrel*. In this tool the bit is so made that the core barrel is removable at will. During drilling, the barrel is held in place within the bit. After the core has been cut, a wire line is lowered, and the barrel is caught and raised by

this line *through* the drill stem, which remains in the hole. This is a great saving of time, since it does away with the necessity of "breaking down" and "making up" the drill stem for each core, as in the case of the conventional type.

3. *Diamond drilling* is another process in which the cutting tool is rotated. The bit used in this method is a hollow cylinder of soft steel in the lower edge of which black diamonds are set so that they project a little way beyond the outer and inner edges of the cylinder.¹ The bit is screwed to a "core shell" which is screwed to the lower end of a "core barrel," and the core barrel, in turn, is screwed on to a string of hollow steel rods which reach to the top of the hole. In drilling, the string of rods and the tools attached thereto are rotated. The rods are clamped to a hydraulic feed which enables the driller to control the pressure applied to the bit. A stream of clear water or of thin mud is kept flowing down inside the rods and core barrel and up between the rods and the walls of the hole or the casing. This keeps the tools cool. The diamonds on the bit cut a way for the metal of the cylinder, and a core of rock is left inside the hollow bit, shell, and core barrel. As soon as the core extends to the top of the barrel, the rods must be pulled and the core removed. The pieces of the core, preserved in the order in which they were obtained, furnish an excellent record of the rocks penetrated by the hole. To check the positions at which the rock materials change in character, the rock cuttings washed up by the circulating water are examined and the action of the tools is watched.

Diamond drilling is the method commonly employed for mining and engineering problems. It is especially useful where there are so few rock outcrops that examination of the surface geology reveals nothing or too little in reference to the true underground structure. Under these conditions, several core holes may be drilled solely for the purpose of correlating and mapping the

¹ For drilling in formations that are medium hard, a bit may be used in which, instead of diamonds, irregular pieces of specially hardened steel, such as *haystellite* and *borium*, have been set.

shallow subsurface strata. Such holes are drilled in positions selected by a geologist. For the sake of economy they are distributed in the manner or in the order which he thinks will yield the data sought with the drilling of the smallest possible number of holes. Thus, where a dome is suspected, one test hole might be located on the supposed crest, and three or four others might be placed surrounding the first. Or, if faint indications of a fault are to be checked by coring, one or two rows of three or four holes in each should be laid out to cross the possible fault at right angles to its trend.

This core drilling for information on stratigraphy or structure is one method of *exploratory drilling*. Since it is rather slow and expensive, another method has now come into common use. Holes of small diameter are rapidly drilled by fishtail bit deep enough to find reliable key beds for correlation, and then the hole is electrically logged (Art. 430).

427. Reliability of Samples.—As far as the geologist is concerned, the type of record obtained in drilling is of great importance. The reader will perceive, from the foregoing article, that the samples secured in different methods of drilling are likely to vary considerably in their reliability. The rock core that is cut in diamond drilling, or by any improved type of core bit in ordinary rotary drilling, is by far the best index of the formations penetrated, although even this may not always be entirely accurate, since, in drilling through some kinds of rock, unless adequate provision is made, particles may be washed out of the core by the circulating water. Complete recovery of the entire length of the core that has been cut is rare.

The record obtained in cable drilling is fairly reliable if kept by a competent driller and properly interpreted by a geologist. It is subject to errors caused by: (1) too infrequent bailing; (2) loss or confusion of rock particles bailed up; (3) occasional caving of materials from points above the bottom of the hole; and (4) incorrect measurements of depths.

The least satisfactory record is that secured from the cuttings in rotary drilling, for the rocks are thoroughly ground up, the

particles are mixed with mud, and considerable time may elapse between the drilling of a given rock and the appearance of its particles at the mouth of the well. Rock variations having a thickness of only a few feet are likely to escape notice. The driller pays more attention to the reaction of the bit than to the cuttings. He may call a hard sandstone layer a *lime shell*, simply because, in his experience, this sandstone has the same effect on the drilling as a limestone. The geologist must familiarize himself with the significance of the driller's terms.




FIG. 416.

FIG. 416.—Core showing bedding perpendicular to axis of hole, therefore horizontal, if hole was vertical. Figures 416 to 420, and Figs. 431–434, inclusive, are reprinted from Bull., Amer. Assoc. Petrol. Geol. (Bibliog., LAHEE, F. H., 1929, b).




FIG. 417.

FIG. 417.—Core with moderate dip.

Because of the many difficulties experienced in securing adequate subsurface information in cable-tool and rotary drilling, a great deal of time and thought has been devoted to inventing and perfecting the various types of core barrel. There are now in use coring devices for both cable-tool drilling and rotary drilling. Coring in cable-tool holes is done only when there is a very special reason for securing a sample of rock, since ordinarily the cuttings brought up by the bailer are sufficient. In drilling *wildcat wells* (that is wells far from known oil or gas production) by the rotary method, the hole is sometimes cored all the way down from a few feet below the surface, in order to avoid missing any possible

oil or gas sands, and also in order to secure a complete record of the formations penetrated. When this is done, the hole may be cored by a relatively small bit, and then reamed to full diameter by a large bit, or the hole may be cored and simultaneously drilled to its full diameter. In the former case, coring and reaming are alternated, usually 50 to 100 ft. of depth at a time.

Most varieties of core barrel can cut the core from the bottom of the hole only, so that once the drilling has progressed beyond a given point or formation, there is no possibility of going back and taking a sample. To overcome this deficiency, several kinds of *side-hole sampler* have been devised for punching or cutting small *side-hole cores* from the wall of an uncased hole.¹

428. Oriented Cores.—Usually, in securing cores from a bore-hole, no attempt is made to ascertain how the core was oriented before it was cut out of the rock formation. If the bedding is horizontal (Fig. 416), there is no particular reason for wanting an *oriented core*; but if the strata are inclined as in Figs. 417 and 418, the determination of the *direction* of their dip may be very important. In Fig. 419 are shown an incorrect (A) and a correct (B) interpretation of an observed dip of 30° in each of four cores taken from different depths in a hole. To understand these dips correctly, their direction must be known. Actually, as indicated in B, a pronounced angular unconformity was crossed in this well.



FIG. 418.—Core with steep dip. This was taken in a fault zone. The dip is drag. The isolated crystals are of pyrite.

¹ On the subject of sampling and coring, see Bibliog., KRAUS, EDGAR, 1924; CLARK, STUART K. and JAS. I. DANIELS, 1928; and OFFICER, H. G., GLENN C. CLARK, and F. L. AURIN, 1926. In some respects these papers are out of date, but they are excellent presentations, each of the particular phase of the subject treated.

Figure 420 is a diagram of the record of a hole which, after passing through 3,500 ft. of nearly horizontal beds, unexpectedly entered a series of steeply dipping strata, which were penetrated for 400 ft. before the hole was abandoned. If an oriented core of this lower series could have been secured, the geologist would have known




FIG. 119.—Two interpretations based on four cores taken from a drilled well, as seen in vertical section.

in what direction he must go to approach the axis of the deeply buried structure.

Several varieties of instrument have been devised with the object of cutting oriented cores, but none has been very successful as yet. One reason for this is the fact that the core is likely to break and turn in the core barrel while in operation. However, an ingenious method has been discovered for overcoming such difficulties, a method dependent on certain magnetic properties within the core.

As will be explained in Art. 514, the earth may be regarded as a large magnet. The system of its magnetic forces is known as its magnetic field. These forces vary in direction and intensity




FIG. 420.—Vertical section through strata penetrated by a hole which encountered steeply dipping beds at 3,500 ft. Without knowing orientation of cores from below 3,500 ft., the geologist could not tell in what direction to go to reach the axis of the anticline.

in different parts of the earth. Because some of the mineral constituents of common rocks have the property of acquiring and retaining a certain amount of polarity from the earth's

magnetic field, cores of these rocks, having been examined by a special instrument of high sensitivity, are found to reveal polarity that they had while *in situ*. In this instrument a core under investigation is slowly rotated in a position such, with reference to two suspended magnets, that its magnetic north and south sides can be determined. For reliable results a core that is to be examined for its magnetic polarity must be carefully labeled at the well as to its top and bottom. Since the main object is to find out the direction and amount of true dip at the depth from which the core was secured, only cores with good lamination should be used, preferably shales or sandy shales. Shales with no observable bedding and sandstones with cross-bedding are of no value. The rough core, as received from the well, is accurately ground to the form of a perfect cylinder, and on it the strike and direction of dip of the lamination are marked—also its top—before it is tested for its polarity. Thus, after the examination has been completed, the original position of the core before it was cut in the hole can be correctly determined.¹

Two significant facts must be impressed upon the geologist, in considering the subject of taking oriented cores: (1) Assuming that perfect cores can be secured, there will always be present the danger of misinterpreting cross-bedding for true bedding. This has been mentioned above. The only safeguard is to take plenty of cores for comparison and to place more reliance on laminated shales than on sandstones. (2) If a bore-hole is not drilled vertical, the original orientation of the core in the inclined hole can be learned, but, before the true dip of the strata from which this core was cut can be determined, the angle and direction of inclination of the hole must be ascertained, and corrections must be made accordingly (434).²

429. Correlation of Samples from Bore-holes.—In order that the records of bore-holes may be used for constructing subsurface maps and determining subsurface geologic structure, the strata

¹ See Bibliog., LYNTON, EDWARD, 1937, 1938.

² For an interesting paper relating to this subject, see Bibliog., MEAD, WARREN J., 1921.

penetrated by the drill must be correlated; *i.e.*, the formations must be recognized and traced from hole to hole. For this purpose, lithologic characters are sometimes sufficient; but if the beds are very similar and hard to discriminate by eye, recourse may be had to a microscopic examination of the specimens. By far the most important branch of this work is micropaleontology, or the study of microfossils. Other lines of microscopic investigations which may assist the geologist in correlation are the study of the forms, surface features, and proportions of clastic grains, the relative proportions and classification of heavy mineral grains, and the kind and relative amounts of insoluble residues.

Micropaleontology is very largely concerned with the study and classification of foraminifera,¹ microscopic one-celled organisms which have left their minute tests buried in the rocks as a record of their former existence. Their little shells are most likely to be found in muds, clays, and shales, that is, in the finer sediments which were deposited in water not too violently agitated nor too swiftly flowing. Like all fossils, some species are found ranging through several or many geologic formations, whereas others are more narrowly limited. Formations may sometimes be recognized and distinguished by a characteristic species, or more often by a particular assemblage of species, different from the species in other associated formations.

For the study of these foraminifera and other microscopic fossils, the rock samples (cores or cuttings) are first crumbled, but not crushed, and are boiled in water containing a little ordinary baking soda. This is to break down the colloidal matter. Next, after the partly disintegrated sample has cooled, it is carefully washed under the faucet in a weak stream of running water. The lighter constituents are decanted, little by little, until only a heavy residue remains. The rest of the water is then poured off and the residue is dried on the stove. In this residue will be found the shells of foraminifera, if any were present in the specimens. They can now be put on a slide and examined under the

¹ Other microscopic fossils of value in this connection are diatoms, ostracods, conodonts, etc.

microscope.¹ The micropaleontologist must be warned always to be on his guard lest the samples be contaminated by material from higher up in the hole.

Where foraminifera are absent, correlation of the formations or strata may perhaps be possible through a careful study of their content of "heavy minerals," for in many localities investigation has proved that the proportions in which these mineral grains occur may differ markedly in different beds, yet hold fairly constant in one bed or formation over an area of considerable extent. These "heavy minerals" are elastic, sometimes altered in shape by secondary crystallization. Following is a list of the more common varieties, with their specific gravities. Quartz, muscovite, and biotite are noted for comparison.

Andalusite	3.16-3.20
Apatite	3.17-3.23
Biotite	2.7-3.1
Calcite	2.713
Cyanite	3.56-3.67
Epidote	3.3-3.51
Garnet	3.15-4.3
Ilmenite	4.5-5
Magnetite	5.17-5.18
Muscovite	2.76-3
Pyrite	4.5-5.1
Quartz	2.65
Rutile	4.18-4.25
Staurolite	3.65-3.75
Topaz	3.4-3.65
Zircon	4.68-4.7

In preparing samples for heavy mineral determinations, crush the rock in a mortar. If calcareous, treat with hydrochloric acid, decant, wash with distilled water, and dry. If the material is impure sand or sandy shale, boil with soda, decant, thus removing colloids, wash with distilled water and dry. If

¹ For references on this subject see Bibliog., CUSHMAN, JOSEPH A., 1924; SCHUCHERT, CHARLES, 1924; APPLIN, ESTHER RICHARDS, *et al.*, 1925; GALLOWAY, J. J. 1926; CUSHMAN, JOSEPH A., 1928; MILNER, HENRY B., 1929.

the sample contains oil, wash with benzol, chloroform, or alcohol, and dry. The dried cleaned material is then poured into bromoform having a specific gravity of 2.69 (test with a hydrometer), and contained in a funnel. The mineral grains of higher specific gravity will sink. They may be drawn off through the stem of the funnel into an evaporating dish. After the small quantity of bromoform which escapes has been decanted, the heavy residue is then washed with alcohol. To clean grains of iron coatings, heat residue with nitric acid or aqua regia, which will remove pyrite, marcasite, limonite, and other iron compounds. After drying, the grains may be mounted in balsam on a slide ready for study.

The comparison of sands by their heavy mineral content is tedious unless very striking differences are discovered. In general practice a rough count is made of the relative proportions of each such mineral in a type sample of the rock, and this assemblage is taken as the criterion for comparison.¹

A great deal can sometimes be learned, in the way of correlation, by studying the shapes of the clastic sand grains, their surface features, such as pitting, gloss, etc., and other such features, which are largely dependent upon their mode of origin, for after all, sediments must have characteristics imposed upon them by virtue of the particular climatic and physiographic conditions under which they were transported and accumulated. To a considerable degree, a like statement applies also to microscopic fossils and "heavy minerals."

Another avenue of approach to the problem of subsurface correlation is by water analyses.² Within reasonable distances, the water from a given stratum may have roughly similar chemical properties, which may differ strikingly from those of the waters from overlying or underlying strata. Care must be exercised,

¹ For further information on this subject and on the study of insoluble residues, see Bibliog., REED, R. D., 1924; TICKELL, F. G., 1924; ROSS, CLARENCE S., 1926; REED, R. D., and J. P. BAILEY, 1927; MILNER, HENRY B., 1929; McQUEEN, H. S., 1931...

² Bibliog., ROSS, J. S. and E. A. SWEDENBORG, 1929.

however, in using this means of correlation, for: (1) water from the same sand may reveal very different mineral contents adjacent to faults, or other passages for fluid circulation *across* formations; and (2) from point to point the water in any given stratum is likely to show a progressive change in mineral content. Not infrequently, for example, water in a "sheet sand"¹ will contain a higher proportion of chlorides in the upper part of a closed structure (anticlinal closure) than lower on the flanks, for the reason that any circulation within the sand has probably been more active, and consequently the original connate nature of the water has been more modified by dilution, low on the flanks, nearer to the synclinal troughs or basins. Similarly, in a given sand which has a regional dip for many miles from its surface exposure, the water is apt to be freshened and modified updip toward the outcrop, where meteoric waters have ingress.

If samples of water cannot be obtained from bore-holes, cores of the water-bearing sands may be tested instead, and thereby a fair approximation to the composition of the water may be made. The rock specimen for analysis must be solid and as free as possible from contamination by drilling fluid, etc. It should be broken from inside the core. First, its porosity is roughly determined, thus:

(a) Weigh sample, cool to 40°F. in a closed vessel to prevent condensation, dip in melted paraffin, cool to room temperature, and weigh again. The difference in weight times the specific volume of paraffin equals the volume of the paraffin.

(b) Using a wide-mouthed specific gravity flask, weigh flask plus sample, then flask plus sample plus distilled water. Subtract the difference of these weights from the calibrated volume of the flask (indicated by a mark on the neck of the flask). Result is volume of sample plus paraffin plus pore space. Subtract volume of paraffin to obtain volume of sample plus pore space.²

¹ A sand entirely blanketing over a structure.

² Temperatures of water used in (b) and (c) should be observed so that corrections for volume may be made.

(c) Peel off paraffin, crush sample, dry in oven at $212^{\circ}\text{F}.$, cool in a desiccator, and weigh sample plus specific gravity flask. Add enough distilled water to cover sample, stir out all air bubbles, place top on flask, fill to mark on neck (for calibrated volume) and weigh again. Calculate volume of sample as in (b).¹

(d) Volume of sample plus pore space minus volume of sample equals volume of pore space.

(e) Percentage porosity equals volume of pore space divided by volume of sample plus pore space.

(f) Specific porosity (cubic centimeters of pore space per grain of sample) equals pore space divided by weight of original sample.

Having thus determined the approximate porosity, add to a large portion of the crushed and dried residue of the sample 250 cc. of distilled water. Run the analysis on the leachings and calculate the results in parts per million based on the volume of the pore space in the core specimen.

While this method is open to some criticism, it has met with considerable success. It has often been checked by comparing the analysis of the sample with the analysis of the water subsequently obtained from the same sand, and the results have been very satisfactory.

430. Electrical Surveying of Bore-holes.—The exact position from which samples come, in a drilled hole, is always more or less open to question. Cores can be more accurately located than cuttings, but often there is considerable loss of material, so that the precise depth to the top or bottom of any stratum represented by the well samples is difficult to ascertain. Furthermore, the fluid content of cuttings and cores received at the surface is not likely to be the same as the original fluid content of the rock from which these samples came. To determine, even qualitatively, what this original fluid may have been, is frequently very desirable. For the purpose of learning more about the lithology and

¹ Temperatures of water used in (b) and (c) should be observed so that corrections for volume may be made.

fluid content of rocks in the walls of a bore-hole, and in conjunction with this, for more accurately fixing the top and bottom contacts of rocks of varying character, a procedure known as *electrical surveying*,¹ or *electrical logging*, has been developed and improved to such an extent that it has become common practice in nearly all holes drilled for oil or for geologic information. In the following paragraphs electrical surveying and electrical logs are briefly described, and the uses of these logs, for the purposes just mentioned, are outlined. Their application in subsurface correlation is discussed in Art. 459.

There are several methods of electrical surveying now in common use, but in most of them two classes of electrical potential are measured. In the first, only currents come into play that are generated as a result of chemical and physical reactions set up between natural conditions in the rocks and certain conditions in the drilling mud in the bore-hole; whereas, in the second, an electrical field is artificially imposed. Observed effects are plotted as lines or "curves," respectively called a *natural*, or *potential*, or *self-potential curve*, in the first case, and a *resistivity curve*, in the second case (Fig. 421). The natural "curve" is also known as a *porosity curve*, or, better, a *permeability curve*. Measurements are made by lowering certain apparatus into the hole while the hole is full of drilling mud (426) and before it is cased, *i.e.*, while its rock walls are still exposed to the drilling fluid.

The *permeability (natural) curve* represents the algebraic sum of three kinds of electrical potential resulting from pressure differences and chemical differences between the drilling fluid and the fluids in the rock formations.


1. A flow of electric energy may be caused by filtration of water out of the drilling mud (426) and into a porous medium (such as a sandstone penetrated by the hole) or from the porous medium into the hole. The former direction of filtration (and electrical current flow), regarded as of negative sign, is much more

¹ See Bibliog., SCHLUMBERGER, C. and M., and E. G. LEONARDON. 1934; also, Bibliog., Houston Geological Society Study Group, 1939.

common, because ordinarily the mud column at any depth in the hole is heavier (exerts more pressure) than the hydrostatic pressure at that depth. Water from the mud may be squeezed into the pores of the rock for a distance of several inches or even several feet back from the face of the hole. Occasionally the flow is in the opposite direction (positive) if strong artesian pressure or strong gas pressure forces fluid from the porous rock into the hole in spite of the resisting pressure of the mud column. These effects (negative and positive) are referred to as *electro-filtration*.

2. A second kind of electrical effect, called *half-cell electro-chemical potential*, is produced as a result of chemical conditions at the surface of a metal electrode. In a very thin layer small currents can rapidly change the chemical conditions and "polarize" the electrode. Since this action may obscure and perhaps conceal the effects of electro-filtration, precautions are taken to reduce the half-cell potential to a minimum, so that, as nearly as possible, variations in the electro-filtration potential alone will be recorded.

FIG. 421.—Example of an electrical log, showing two curves, one on each side of the central vertical column, the divisions of which mark hundreds of feet of depth in the hole surveyed. The curve on the left is called the "first curve," or "permeability curve"; and that on the right is the "second curve," or "resistivity curve." A scale of millivolts (MV) is given for the first curve, and a scale of ohms, for the second curve, both at the top of the log. Note (1) that permeability of sands is not well shown in the upper part of the log (say down to 1,000 ft.) where there is little difference in the composition of the drilling mud water and water in the formations; (2) that in this upper zone, where the formation waters are fresh or brackish, rather high resistivity is indicated (second curve); (3) that, with increasing depth, the positions of sands are clearly marked by indications of high permeability; and (4) that salt water present in these deeper sands shows little or no evidence of resistivity. However, near the bottom of the log is a sand that contains oil or gas, as evidenced by high resistivity. (Cf. Fig. 422.)



3. A third, but less important, electrical effect, called *boundary electro-chemical potential*, is produced by an exchange of ions between the water in the mud and the water in the porous formation, at their boundary or interface. An electric current flows from the water of lower salinity into the water of higher salinity. As pointed out in the footnote on p. 65, underground waters (also called "formation" waters) become progressively more saline with depth. Since drilling mud is usually made with fresh water, there may be little or no electro-chemical action in upper sands, but, as greater depths are reached, the increasing salinity of the formation waters produces stronger electro-chemical effects. If the current flows from the mud into the formation the phenomenon is called negative. The reverse, which is comparatively rare, is positive. It may occur when a hole is drilled into a stratum of salt, and the mud, in its circulation, becomes highly saline through gradual solution of this salt.

These three effects—electro-filtration, half-cell electro-chemical action, and boundary electro-chemical action—are recorded as an algebraic sum in the self-potential or permeability curve. Their measurement is accomplished by lowering an electrode at the end of an insulated conductor into the hole. The upper end of the conductor is connected to one terminal of a potentiometer, the other terminal of which is connected with a grounded reference electrode near the mouth of the hole. The difference between the electrical potential of the ground (reference) electrode and the potential at any point in the hole (at the suspended electrode) is indicated by the potentiometer and is recorded as a point in the permeability curve, which is built up by reading and recording this quantity in a continuous series of observations as the suspended electrode is moved through the length of the hole.

In general, the three components of the self-potential curve are proportional to the permeability of the rock, although their absolute values may vary with the weight, viscosity, and salinity of the mud and with some other minor factors. Their order of

magnitude may be roughly expressed as follows: (a) electro-filtration potential, up to hundreds of millivolts; (b) half-cell




FIG. 422.—Electrical log of the lower part of a hole drilled for oil. Here the beds showing very high resistance are of anhydrite, which, as indicated opposite in the first curve, is highly impermeable. Contrast this with the oil sand near the bottom of the log in Fig. 421.

Because of the inconvenient width of a log, where high resistivity is shown, as in this case, it is common practice to reduce the scale of ohms to one-fifth of the usual scale (see top of log) for the outer parts of the peaks in the curve, which are then shown shaded or, as in this diagram, solid black.

electro-chemical potential, up to hundreds of millivolts; (c) boundary electro-chemical potential, up to tens of millivolts. Provided variations in the half-cell electro-chemical effect are

successfully reduced to a minimum, electro-filtration thus becomes the major component in the permeability curve.

Rock materials in the lithosphere differ in respect to their electrical conductivity or, conversely, their resistivity. Dense rocks, like granite, quartzite, gneiss, marble, gypsum, rock salt, anhydrite, and coal, have high electrical resistivity (Figs. 422, 423). In porous rocks the resistivity is determined by the nature and composition of the contained fluids. Fresh water has high resistivity; salt water has low resistivity; and, again, oil and gas




FIG. 423.—Electrical log of a small part of a deep hole in south Texas. Lignite with low permeability (a) and relatively high resistivity (b), and oil sand with good permeability (c), and high resistivity (d) were penetrated in drilling this section.

have very high resistivity (Fig. 421). In shales and fine sediments the water held in the pores is usually relatively saline, even at shallow depths where interbedded sands may carry fresh or only brackish water. The sands that contain oil have more or less adsorbed saline water on the surfaces of the mineral grains (*i.e.*, on the walls of the pores), and the effect of this water may sometimes mask or reduce the opposite effects of the oil, especially in fine sands. In view of these facts, wide variation may be expected in the resistivity characteristics of rock materials at different depths, in different stratigraphic and structural associations, and in different localities.

The electrical resistivity of rocks penetrated by the hole is usually determined by sending an electric current through the ground, by battery or otherwise, and by measuring the variation in intensity of current, where only one electrode is used; or by measuring the difference in potential between two exploring

electrodes where a system of four is used, one being on the surface of the ground and the other three being lowered into the hole; or by measuring certain electrical quantities by various other methods, all of which yield results that, from a practical view-point, are comparable. The electrical characteristics of the formations are automatically recorded in the form of the so-called *resistivity curve* (Fig. 421).

If the three suspended electrodes (in a system of four) are relatively close together, electrical effects that are measured will be the result of conditions in the immediate vicinity of the electrodes. The radius of investigation may reach only a few inches into the wall of the hole, a distance that may be less than the distance of infiltration of water from the drilling mud into a porous formation. In this case the measured electrical resistivity will not be that characteristic of the particular rock and due to its true fluid content. To obviate this difficulty, additional resistivity




FIG. 424.—Electrical log showing first, second, and fourth curves. (Third curve omitted for sake of clarity.) At shallow depths the second and fourth curves are similar (fresh water). With increasing depth, peaks in the second curve are not always duplicated in the fourth curve. Fresh water from the drilling mud may have penetrated a few inches into the wall, but not far enough to affect the fourth curve. A definite peak in both second and fourth curves may indicate an oil sand or a gas sand if the first curve shows a fair degree of permeability.

curves are sometimes run, with wider spacing of the suspended electrodes so that the radius of investigation of the electrical effect will be greater than the distance of infiltration of the drilling fluid. Such additional curves are commonly referred to as third and fourth curves (Fig. 424). The student should note that, because of the wider spacing of the electrodes for third and fourth curves, the measured resistivity is an average for a thicker zone of rock materials and is therefore less detailed than the second curve run with more closely spaced electrodes. In other words, the third and fourth curves may more surely indicate the nature of the fluids originally present in a porous stratum, but they may not so accurately determine the top and bottom and thickness of this stratum. These, however, can often be ascertained from the permeability curve.

In practice, the readings for the self-potential (permeability) curve and for a resistivity curve are made in the same run of the electrodes in the hole.

Summarizing, then, we may say that electrical surveying of bore-holes provides us with a double record of certain characteristics of the formations drilled. On the one side we have the first, or self-potential, curve reflecting permeability variations in the rocks; on the other side we have one or more (second, third, fourth, etc.) resistivity curves that, by high figures may indicate dense, nonporous rocks or fresh water, sulphur water, oil, or gas in porous rocks, and, by low figures, may indicate salt water in porous formations, whether permeable (sand, etc.) or not (mud, shale). These curves are drawn on the same paper, thus providing an *electrical log* of the hole. They must be studied together, in their mutual relations, to arrive at the most satisfactory interpretation; but the student must always remember that they do not represent absolute values. These curves picture a resultant of many factors, so that rules cannot be too rigid as to the significance of individual peaks and depressions in the lines, nor as to the quantitative measure of these peaks and depressions on the horizontal scales employed (milli-volts for self-potential curve; ohms for resistivity curves).

These remarks bear chiefly on the intrinsic value of an electrical log for study of the formations intersected by a given hole. As already indicated, there is another very important use for these logs when they are compared one with another, namely, for purposes of geologic correlation. This phase of the subject is reserved for the next chapter (Art. 459).

431. Drilling-rate Charts.

Of assistance in correctly correlating samples of strata penetrated in drilling is the driller's time chart or drilling-rate chart. Figure 425 illustrates such a chart. It records the rate at which drilling progressed through formations between the depths of 2,720 and 2,920 ft. From 2,720 to 2,883 ft., drilling was relatively slow, because the formations were hard, but at 2,883 ft. there was an abrupt increase




FIG. 425.—Drilling speed record. In this record, made of a well in west Texas, the rate of drilling, in feet of depth per hour, is recorded for every foot of hole drilled between certain limits (here between 2,720 and 2,920 ft.). The greatly increased rate beginning at 2,882 ft. indicates penetration of a highly porous, or soft, zone, which, in this case, carried oil. The base of this zone was between 2,904 and 2,907 ft.

in the rate of drilling where a soft rock (here sandstone) was encountered. After passing through this zone, hard limestone was drilled at a very slow rate down to the total depth, 2,920 ft. It should be evident that this chart, when checked against the drill cuttings, may help the geologist to place the top and bottom contacts of strata that differ in their hardness. Similar records in adjoining wells facilitate subsurface correlations (Art. 458).

432. Geothermal Data in Relation to Geology.—That the temperature of the lithosphere increases with depth is a well-known fact. The rate of increase with depth is called the *temperature gradient*. In different localities it has a wide range in values, but, in general, the average may be regarded as 1°F. increase for every 50 to 60 ft. of depth. Estimates are usually made from mean annual temperature at the earth's surface, this value being added to depth in feet times the rate of temperature increase per foot. Tables giving data on temperature gradients in many parts of the United States have been prepared by Van Orstrand.¹

Measurement of subsurface temperature is usually made by a resistance thermometer in preference to the old type of fluid thermometer. The effectiveness of the resistance thermometer is based on the fact that the electrical resistance of a conductor varies as a function of its temperature. As the thermometer is lowered into a well, the temperature changes are continuously recorded at the surface. These observations may be made along with electrical logging of the hole (430).

The causes of temperature increase with depth and the causes of variation in the gradient are problems still under investigation. Some causes for abnormally high (steep) gradient are (1) proximity to igneous intrusive bodies; (2) proximity to a granitic (or other crystalline) basement; and (3) ascending hot water or hot gases. Causes for an abnormally low gradient are (1) freely circulating cool waters and (2) expanding gas.

Subsurface temperatures are of interest to geologists in two ways: (1) They may be indicative of certain lithological and

¹ Bibliog., VAN ORSTRAND, C. E., 1934, pp. 1009-1021.

fluid conditions in the rocks penetrated by drilling; and (2) they may suggest certain structural conditions, especially when they have been recorded and correlated in numerous wells in a given district.

1. The release of some gas from a sand, in which it has been under considerable pressure, results in its expansion, and, since expansion is a cooling process, this may cause a distinct lowering of temperature, as measured in a drilled hole, opposite the gas-bearing stratum (Fig. 426). Similarly, an oil-bearing sand may be indicated by a drop in temperature opposite the sand, because of expansion of the gas released from the oil. Strata containing cool subsurface water—usually only at shallow depths—produce local cooling effects. On the other hand, strata carrying hot water may be shown on the graph by an abrupt temperature rise. Changes of temperature of this kind are most evident when there is opportunity for the fluid (gas, oil, or water) to pass into the hole, provided circulation of the drilling mud is properly controlled; but, even where a hole has been cased, the temperature effects may sometimes be detected through the casing, especially if extraction of these fluids from adjacent wells has brought about their movement, or has facilitated expansion of gas, through the body of the containing porous strata.

2. Of much more significance for geologists are the particular relations of subsurface temperatures to geologic structure. Investigations made in Wyoming and California by Thom¹ and




FIG. 426.—Part of a temperature curve run in a hole drilled for oil. The average increase of temperature with depth is indicated by line *ab*. The sharp lowering of temperature at *c*, about 3,400 ft. below the ground surface, suggests a gas sand at this depth.

¹ Bibliog., THOM, W. T., JR., 1925.




FIG. 427.—Salt Creek Dome, Wyoming. Dashed contours show elevation of top of Second Wall Creek sand above sea level; solid lines are of equal temperature gradient; dots and heavy figures show locations of wells, and temperature gradients (showing ratio of increase in feet per 1°F.). (After W. T. Thom, Jr., reprinted with permission of Economic Geology.)

Van Orstrand¹ indicated that temperatures measured in a well on the crest of an anticline increase more rapidly with depth than the temperatures in wells drilled lower on the flanks of the structure; in other words, that in any given horizontal plane




FIG. 428.—Cross section showing depth to isothermal surfaces as determined in wells along a general line from Tulsa to Oklahoma City. (After John A. McCutchin; reproduced with permission of the Am. Assoc. Petrol. Geol.) The profile on top of the Oswego line was added by the present writer to show the general relations between the geothermal surfaces and the regional dip. The letters refer to locations of wells in the section.

across the structure, the temperature is higher at the crest of the fold than on the flanks (Fig. 427).

In Oklahoma, Kansas, Texas, and California, careful research under the auspices of the American Petroleum Institute revealed the interesting relations described below.² In all cases measurements were made in drilled wells.

In Oklahoma, a most striking condition brought out by these studies is the general westward dip of the isothermal (equal temperature) surfaces, in the direction of the regional dip of the

¹ Bibliog., VAN ORSTRAND, C. E., 1924; *ibid.*, 1926.

² Bibliog., HEALD, K. C., 1930; McCUTCHIN, JOHN A., 1930.

strata, and the convergence of these surfaces eastward. "The 100° isothermal surface is only approximately 1,500 ft. deep near Tulsa, although this surface is more than 4,000 ft. deep near Oklahoma City,"¹ some 70 miles down the regional dip from Tulsa. In other words, the steeper gradient (more rapid rate of increase) and the higher temperatures at any given depth are




FIG. 429.—This diagram shows the same data as those in Fig. 428, but we have referred both the geothermal measurements and the position of the Oswego line to sea level. The letters merely designate the location of wells in the section. (Prepared by F. H. L.)

found where the basement rock complex, on which the sediments rest, is at shallowest depth. In Fig. 428, copied from McCutchin, we have drawn a line roughly corresponding to the top of the Oswego lime, encountered in wells approximately along the course of McCutchin's profile. In Fig. 429 the same facts are shown more nearly in their correct relations, for here account is taken of the westward rise of the land surface, from which McCutchin plotted his data referred to depth, and not to sea level. Although

¹ Bibliog., McCUTCHIN, JOHN A., 1930, p. 541.

the dip of the strata and the dip of the isothermal surfaces are similar northeast of *i*, there is a distinct rise in the latter in the region of the Oklahoma City anticline (not shown in Fig. 429).

In Oklahoma and Kansas a definite relation between local structure and geothermal gradients was observed, though not in all instances. "The variations within individual fields (oil pools on structure) are ordinarily small but measurable and fairly uniform. The variations from area to area are large and seem to bear a relation to the regional dip of the formations."¹

In Texas, the symmetrical, dome-like structure of the Big Lake field in Reagan County was "clearly reflected by the temperature measurements,"² but only by the temperatures below a depth of 2,000 ft. On four salt domes examined, temperatures were highest on top of the dome, and less on the flanks.

In California "the results of this work . . . show conclusively that in fields of the Los Angeles Basin type the temperatures . . . reflect structure. Higher temperatures are found over the centers of domes or anticlines than near the edges of the folds."³

In general, a large proportion of the structures investigated showed "a well-defined variation with the highest temperature always at or near the crest of the anticline."⁴ Although these relations are subject to considerable variation and may not always be evident, their study and correlation offer a useful method of seeking concealed geologic structures, through measurement of temperatures in comparatively shallow holes.

433. Use of Radioactivity in Logging Bore-holes. Rocks of various kinds are radioactive in different degrees. Their radioactivity may be due to minerals that were formed in their origin, as in igneous rocks, or to minerals transported and redeposited, as in sedimentary rocks. In the present connection the impor-


¹ Bibliog., McCUTCHIN, JOHN A., p. 554; also, VAN ORSTRAND, C. E., 1934, p. 998.

² Bibliog., HEALD, K. C., 1930, p. 107; also, VAN ORSTRAND, C. E., 1934, p. 993.

³ Bibliog., HEALD, K. C., 1930, p. 109.

⁴ Bibliog., VAN ORSTRAND, C. E., 1934, p. 1004.

tant fact is that apparently the radioactivity of a given stratum,



LEGEND

Sandstone	Shaly Sandstone
Limestone	Sandy Limestone
Shale	Shaly Limestone

FIG. 430.—Gamma-ray log of part of a hole in Oklahoma. To the left of the gamma-ray curve is a lithologic log for comparison. Note the high peak indicated in the gamma-ray curve for the Chattanooga shale. (Reproduced with permission of Well Surveys, Inc., of Tulsa, Okla.)

or of a given rock type, as evidenced by certain electromagnetic radiations called *gamma rays*, may be remarkably constant, and therefore characteristic, over wide areas. The correspondence between rock type and gamma-wave radioactivity is illustrated in Fig. 430. Note that, among sedimentary rocks, shales are commonly most highly radioactive, particularly black or dark-colored shales; whereas sandstones and pure limestones are less radioactive.

The great value of radioactivity as a means of correlation (460) rests on the fact that it can be measured in cased holes. Gamma rays penetrate considerable thicknesses of iron, so that, with proper equipment for measuring this radioactivity, it is possible to determine the top and bottom contacts and correct thicknesses of strata that were not satisfactorily logged when the hole was drilled. Other methods of log determination and correlation must be applied only in open (un-cased) holes.

434. The Problem of Crooked Holes.—Except under special conditions, when a hole is drilled into the ground for water, or oil,

or gas, or simply for information as to subsurface geology, the intention is to drill it vertical. One can easily realize, however, that if too great pressure is put upon the bit by forcing it, or by not lifting some of the weight off the drill-stem in deep holes, the drill-stem is likely to bend or lean in the hole and crowd over to one side, with the result that the hole wanders off a plumb line. To illustrate, holes have been found to go off the vertical as much as 30° or more with no indication of this condition in the drilling. Several very curious instances are known where two wells, started on the surface several hundred feet apart, ran into one another at depth.¹ This, of course, would apply to diamond drilling and rotary drilling, but not to the cable-tool method, though even here *crooked holes*² have been drilled.

There are several important causes for this tendency of holes to deviate, but we cannot discuss them now.³ The main points to remember are, that while a great deal of careful study was given to this problem in 1927 to 1929 with the result that better drilling methods have very greatly reduced the amount of deviation of holes and the number of holes which are still drilled off plumb, nevertheless: (1) in some regions and on some types of structure the drilling of vertical holes is difficult; (2) the increasing depths of drilling for petroleum⁴ mean that holes that have only a small angular deviation may be far to one side of their intended position at the bottom; and (3) if a hole is not vertical, then obviously certain geologic inferences, based on the data

¹ Bibliog., LAHEE, F. H., 1929 (b).

² By *crooked hole*, a drilling term, we mean simply any hole which deviates from its predetermined course—generally a hole that deviates from the vertical.

³ Bibliog., DODGE, JOHN FRANKLIN, 1930; also LAHEE, F. H., *op. cit.*

⁴ The deepest well in the world in July, 1930, was the Mascot No. 1, drilled, but not yet completed, by the Standard Oil Co. of California, in the Midway field of California. It was 9,629 ft. deep on July 1. On Jan. 1, 1940, 427 holes had been drilled, in different parts of the world, to over 10,000 ft. The deepest hole drilled up to that time was completed in 1938 in California to a total depth of 15,004 ft. This was the Continental Oil Company's KCL A-2 in Kern County (see the *Oil Weekly*, vol. 96, Pt. 8, pp. 68-74, Jan. 29, 1940).

recorded in the well, may be in error, and perhaps seriously so. Resulting misinterpretations of geologic structure are illustrated and described in Art. 464.




FIG. 431.—Illustration of dip in a core supposed to have been taken from a vertical hole. The glass tube represents the hole, the surface of the dark liquid marks the horizontal plane, and the strip of tape represents the bedding in the core.

A phase of this problem in which the geologist is vitally interested is the correct orientation of cores. On the assumption that cores can be secured in such a manner that their original orientation before they were cut, can be ascertained (Art. 428), then it becomes necessary, in a hole which deviates from the vertical, to find out in what direction and how much the hole is off plumb; for otherwise estimates of the position of the cores from this hole are incorrect.

"The study of cores for their orientation and the determination of the direction of true dip is not easy. For instance: (1) in a vertical hole penetrating horizontal strata, the lamination is at right angles to the axis of the core. If (2) the beds are horizontal and the hole is inclined, the angle between the axis of the core and the lamination is equal to the inclination of the hole (Fig. 432). If (3) the beds dip, let us say, 30° due south, and the hole is vertical, the lamination in the core makes an angle of 30° with the axis of the core. But, unless the angle of deviation of the hole is known in case (2) and unless the orientation of the core is known in case (3), we cannot interpret the dip in the core.

"Now if we suppose that (4) the beds dip 30° due south, as in case (3), and the hole is inclined 30° off the vertical in a due north direction, the core will show lamination perpendicular to its axis, as in case (1); or, (5) the hole may be inclined more than 30° from the vertical in a due north direction; or (6) less than 30° due north; or (7) at an angle of less than 30° from the vertical due south.




FIG. 432.—Similar to Fig. 431, but here the hole (and core) is inclined in such a way that the bedding, actually about horizontal, would be said to dip the amount of inclination of the hole, if this latter figure were not known.



FIG. 433.—Similar to Fig. 431, but dip is about 65° to left and hole is inclined about 30° off vertical toward right, giving impression of bedding dip of about 35° .

"These are all comparatively simple cases, for the hole is inclined in the plane of the dip of the strata. They are illustrated in Figs. 431-433. The real difficulty lies in the fact that extremely few crooked holes are inclined in the plane of the dip of the bedding, even in the short length of hole from which the core came. Thus, in Fig. 434, the core, represented by the graduated glass tube, slopes toward the left in the plane of the




FIG. 434.—Similar to Fig. 431, but here hole is inclined to left and bedding is inclined from front to back, in figure.

picture. The surface of the black liquid marks the horizontal line. The bedding (white line) dips toward the background, almost at right angles to the plane of the picture. It is evident from this picture that if the relations of the bedding (white line) to the horizontal plane and to compass directions were not known, nothing could be determined from the relations of the bedding to the core alone, and this is true even if the correct attitude of the hole were known.

"This topic is stressed to make it thoroughly evident that oriented cores ought to be secured from drilling wells, but in

order to secure them the hole must be surveyed as to both its angle and its direction of deviation from the vertical."¹

We cannot enter into a discussion of methods of measuring the deviation of bore-holes. Many types of instrument have been made for determining the vertical angle of deviation only, and several devices have been used for measuring both the vertical angle and the direction of deviation.

435. Directional Drilling.—In this place we may briefly mention what is called *directional drilling*, or *inclined drilling*, which means purposely drilling a hole off the vertical. This is not uncommon practice, where, for example, an inclined hole can be drilled onshore to reach a desired point offshore or where, by drilling several inclined holes from one derrick location, a great deal of money can be saved as contrasted with drilling these holes at locations on the surface directly above the points that they must reach at depth. If these inclined, or directional, holes bend off their intended course, they are brought back approximately into line again. The important thing is that a hole of this kind must be carefully surveyed at frequent steps during its drilling, and, when completed, not only must it reach its predetermined destination, but its exact course must be charted. Obviously the proper correlation of formation tops and other geologic phenomena encountered in such a hole must involve corrections for the inclined course just as in the case of "crooked" holes drilled inadvertently off the vertical (434).

¹ Bibliog., LAHEE, F. H., 1929 (b), pp. 1135-1141.

² For various methods of surveying holes for verticality, see the different oil-trade journals; also, Bibliog., LAHEE, F. H., 1929 (b), and DODGE, JOHN FRANKLIN, 1930.

CHAPTER XIX

MODES OF GEOLOGIC ILLUSTRATION

GEOLOGIC MAPS

436. Definitions.—Any map that shows the distribution of rocks and the form or distribution of geologic structures is a *geologic map*. An areal geologic map or formation map shows the distribution of formations. A structure contour map represents the form of geologic structures by contour lines (456). A special type of geologic map is an *outcrop map* which represents only the actual outcrops. In the preparation of a geologic map the geologic features are plotted on a land map, showing survey or ownership divisions, or on a topographic map, or on an airplane photographic map (423). In either case this map is referred to as a *base map*. The distribution of rocks is indicated on a geologic map by various patterns or colors, and linear features, such as fault lines, igneous contact lines, boundaries, etc., are shown by lines of different kinds and weights. If there are many formations to be represented, a literal abbreviation may be printed at intervals in each color area (see folios published by the U. S. Geological Survey). In the margin of a geologic map is a legend, that is, a key to the meaning of the colors, patterns and lines used on that particular map (288, 442).

437. Conventional Patterns, Lines, and Symbols.—The color or pattern to be employed on a geologic formation map depends largely upon the inclination of the investigator unless he is working for some organization which has already adopted a scheme. On the maps of the U. S. Geological Survey certain colors and patterns have a definite significance. "Patterns composed of parallel straight lines are used to represent sedimentary formations deposited in the sea, in lakes, or in other bodies of standing

water. Patterns of dots and circles represent alluvial, glacial, and eolian formations. Patterns of triangles and rhombs are used for igneous formations. Metamorphic rocks of unknown origin are represented by short dashes irregularly placed; if the rock is schist the dashes may be arranged in wavy lines parallel to the structure planes. Suitable combination patterns are




FIG. 435.—Symbols used on maps of igneous rocks. *a*, flow layers, strike as plotted (N. 18° E.), dip 25° eastward; *b*, flow layers, strike N. 45° W., dip 60° NE. (dips below 30° shown as open triangles); *c*, flow lines, trend plotted, pitch 30° nearly north; *d*, horizontal flow lines, trend as plotted; *e*, vertical flow lines; *f*, combination of flow layers and flow lines. (After U. S. Geological Survey, with some additions by Balk. See Bibliog., Balk, Robert, 1937, p. 154.)




FIG. 436.—Symbols for strata. *a*, strike plotted (N. 10° E.), dip 30°; *b*, strike plotted (N. 10° E.), dip overturned, 80°. These symbols may be used with or without the arrowhead. In *b*, the strata have been turned through an angle of 100°, i.e., up to 90° and then 10° beyond the vertical. *c*, strike east-west, dip vertical; *d*, beds horizontal. (After U. S. Geological Survey.)

used for metamorphic formations known to be of sedimentary or of igneous origin. The patterns of each class are printed in various colors. With the patterns of parallel lines, colors are used to indicate age, a particular color being assigned to each system.”¹

In Figs. 435 to 444 are sketched many of the symbols used on maps and sections by the U. S. Geological Survey.² Some of those in Fig. 435 are from Balk’s “Structural Behavior of Igneous Rocks.”³

¹ Geologic folios published by the U. S. Geological Survey.

² Copied here with permission of the Director of the Survey.

³ See Bibliog., BALK, ROBERT, 1937, pp. 154, 155.

Note that symbols that indicate directions of geologic features are to be carefully oriented in their correct positions on the map. Strike and dip of bedding are represented by a symbol like a




FIG. 437.—Symbols used for a folded strata. a, general strike and dip of minutely folded beds; b, direction of pitch of minor anticline; c, same for minor syncline; d, axis of anticline; e, axis of syncline; f, pitch of axis of major anticline; g, same for major syncline; h, axis of overturned or recumbent anticline, showing direction of inclination of axial surface; i, same for overturned or recumbent syncline. (After U. S. Geological Survey.)

broad, low T, which is so placed that the intersection of the two lines is at the point for the outcrop on the map. The upper line of the T (a, Fig. 436) marks the strike, and the stem of the T is drawn at right angles to the strike, pointing *down* the dip. Sometimes an arrowhead is drawn on this dip line to emphasize the direction of dip. The *angle* of dip is recorded beside the symbol. In Fig. 437 are symbols for folds. Figure 438 indicates anticlinal

structure on the west and synclinal structure on the east. Figure 439 is more complicated. The folds are overturned, as shown in the section.

The type of rock, also, may be shown with the symbols for strike and dip (Fig. 440). A second line drawn parallel to the strike line, close to it and just the other side of it from the dip line, stands for shale or slate; a similar line with short cross lines between it and the

strike line means limestone; a row of dots parallel to the strike line, in the same place as the shale line, is for sandstone; and a row of small circles signifies conglomerate.




FIG. 438.—Outline map of sedimentary rocks, showing dip and strike symbols.

Figures 441 to 444 represent symbols used for joints, cleavage, schistosity, and faults. On both colored and black-and-white




FIG. 439.—Map and cross section of overturned anticline and syncline. *ab*, in map, is crestal line of anticline; *ce* is cross section of crestal surface of anticline; *de* is section of axial surface of anticline; and *gh* is section of axial surface of syncline. The hook on the axis of the anticline and of the syncline, on the map, denotes overturning of the axial surfaces of these two folds, respectively.

maps faults may be indicated by heavy black lines (*a*, Fig. 443) and boundaries between adjacent areas of different color or pattern by fine black lines. These fine boundary lines may stand




FIG. 440.—Symbols for rock type combined with symbol for dip and strike. *a*, shale or slate; *b*, limestone; *c*, sandstone; *d*, conglomerate.




FIG. 441.—Symbols used for cleavage and schistosity on maps. *a*, strike (long line) and dip (45° in direction of short lines) of cleavage of slate; *b*, strike of vertical cleavage of slate; *c*, horizontal cleavage of slate; *d*, horizontal schistosity or foliation; *e*, strike and dip of schistosity or foliation; *f*, strike of vertical schistosity or foliation. (After U. S. Geological Survey.)

for conformable contacts between adjacent strata, lines of unconformity, and igneous contacts. A fault line may be drawn full where its position is reasonably certain, dotted where it is partly

buried or where its location, likewise, is reasonably certain, and dashed where its location is less sure (*a* to *d*, Fig. 443).

438. Position of Boundaries between Rock Bodies.—Areal mapping consists largely of plotting boundaries. When these have been correctly placed, filling in the spaces with arbitrary colors or patterns is a simple matter. Before a line can be properly




FIG. 442.—Symbols used for joints, on maps. *a*, strike and dip of joint; *b*, strike of vertical joint; *c*, horizontal joint; *d*, direction of linear elements (striations, grooves, or slickensides) on joint surfaces and amount of pitch of these linear elements on a vertical joint surface. Linear elements here shown in horizontal projection. (After U. S. Geological Survey.)

located on a map, its position must be determined in the field (**313, 315, 316**). Some maps represent only mantle rock with or without the actual outcrops of bedrock; others give the distribution of bedrock only, as if the overlying *débris* had been entirely removed; and still others, the most common variety, show both bedrock and mantle rock, but the latter is indicated merely where it is comparatively thick.

In field work a good deal of trouble may be experienced in locating boundaries for the second and third types of map. When bedrock only is to be shown (second type), the division

lines between rock bodies are often concealed. In this case their position may be suggested by the topography. To take examples from sedimentary rocks, a weak stratum may form a valley between two resistant beds; or a valley may be situated along the junction of two strata which are of nearly equal resistance to erosion (**270, B, D**). Frequently further investigations along the general trend of the line may reveal some substantial key to the relations. Provided the boundary between two outcrops with parallel strikes is neither visible nor can be closely located by the topography, it is usually drawn halfway between these outcrops and parallel to the strikes (Fig. 445). This is on the assumption that the beds in the two outcrops are mutually conformable. Care must always be taken to avoid errors that may be occasioned by unconformity or faulting. For rocks

of two kinds, having no definite structure like bedding, the contact line may be put halfway between the nearest outcrops, but its trend must be determined by correlation with exposures over an extensive area (Fig. 446).

When the geologist prepares a map of the third type, he tries to mark out areas where outcrops are numerous and mantle rock is relatively thin and discontinuous from areas in which exposures are rare or absent and the surficial deposits are comparatively thick. Such a boundary is purely arbitrary and is seldom drawn in exactly the same way by different geologists.

439. Relations of Topography to Geologic Mapping.—A map is a projection of lines and areas upon a horizontal plane, lines and areas which, in reality, are usually distributed over an uneven land surface. A line which trends without deviation across hills and valleys is therefore straight on a map; its sinuosities in the vertical plane do not appear. On the other hand, an irregular line which is entirely within a horizontal plane has all its bends and angles represented with their true shape on a map. When a crooked line lies in any plane other than one which is vertical or horizontal, its projection on a map has the same number of bends in the same relative positions, but the arcs of curves are broader and angles are more




FIG. 443.—Symbols for faults on maps. a, known fault; b, known fault not accurately located; c, hypothetical or doubtful fault; d, concealed fault (known or hypothetical) covered by later deposits; e, dip and strike of fault surface; f, strike of vertical fault; g, direction of linear elements (striation, grooves, slickensides, shown by longer arrow) caused by fault movement, and amount of pitch of striations on vertical surface; h, shear zone; i, strike and dip of shear zone; j, high-angle fault, normal or reverse, with upthrust (U) and downthrust (D) shown; k, normal fault; l, reverse fault; m, relative direction of horizontal movement in shear or tear fault, or flaw; n, overthrust low-angle fault, T being the overthrust (overhanging) side; o, klippe, or outlier remnant of low-angle fault plate (T, overthrust side); p, window, fenster, or hole in overthrust plate (T, overthrust side. (After U. S. Geological Survey.)




FIG. 444.—Symbols for faults in sections. *a* to *d*, high-angle faults; *e* to *j*, low-angle faults. *a*, vertical fault, with principal component of movement vertical; *b*, vertical fault with horizontal movement, block A moving away from the observer and block T moving toward the observer; *c*, normal fault; *d*, reverse fault; *e*, overthrust; *f*, underthrust; *g* and *h*, klippen, or fault outliers; *i* and *j*, fenster, windows, or fault inliers. (After U. S. Geological Survey.)




FIG. 445.—Maps illustrating the method of locating a concealed bedding contact between outcrops of different strata. The boundary is drawn through *a*, half way between the outcrops.




FIG. 446.—Maps illustrating the method of locating a concealed irregular boundary. In A the dots and crosses represent outcrops of two kinds of rock. On the left no boundary is shown; on the right its approximate position is indicated. In B the boundary has been completed and the map filled in with symbols for both rocks.

obtuse. It follows from this that the rules laid down in Arts. **153, 174, and 205**, with reference to the effects of topography on the distribution of outcrops must be applied in map construction. These rules are repeated below, although in modified form. For




FIG. 447.—Relations of horizontal bedding to contours shown in a block diagram (A) and in a map of the surface of the block (B). Stippled and blank portions represent two rock strata. Figures 448–451 are drawn in the same way.

the sake of simplicity the relations of a surface only are considered. The surface may be any kind of geologic contact, *i.e.*, the top or bottom of a stratum, the walls of a vein, an igneous contact, a surface of unconformity, or a fault. It is assumed to be flat or nearly so.




FIG. 448.—Relations of vertical strata to contours. (See Fig. 447.)

1. If the given surface is horizontal its outcropping edge on a hill-and-valley topography will have all the characters of a contour; in its directions and curves it will closely correspond to the nearest contour lines on the map (Fig. 447). (2) If the surface is vertical its outcropping edge will be a straight line on a map no matter how rugged the topography is (Fig. 448). (3)

If the surface is inclined, its outcrop will be an irregular line with elbow-like bends. In valleys these bends will point upstream if the dip is opposed to the slope of the valley bottom (Fig.




FIG. 449.—Relations of inclined strata to contours. (See Fig. 447.)




FIG. 450.—Relations of inclined strata to contours. (See Fig. 447.)




FIG. 451.—Relations of inclined strata to contours. (See Fig. 447.)

449), and they will point downstream if the dip is in the same direction as the slope of the valley bottom (Fig. 450), unless the dip is less than the slope. In this case, which is rare, the bends point upstream (Fig. 451). Note that the apex of the bend in valleys falls at the stream channel. The more uneven a surface

is, the more irregular will be its line of outcrop. Dikes, sills, veins, and strata, when of approximately uniform thickness, may be treated as surfaces if they are thin. Otherwise the top and bottom, or each of the two walls, must be plotted separately, and the distance between the boundary surfaces will then vary according to the slope (173).

440. Filling in an Outcrop Map of Stratified Rocks.—

The method of filling in an outcrop map of stratified rocks may be described with reference to two cases, according as the land surface is level or is uneven. In Art. 440 the ground is assumed to be level. Article 441 deals with the problem of geologic map construction where the topography is uneven.

Let us suppose that the geology is to be plotted on the outcrop map represented in Fig. 452, A. Presumably the exposed strata are continuous along their strikes beneath the soil mantle. Being along the same line of strike, *d* and *e* are probably outcrops of the same bed of conglomerate. Each of the other outcrops is the visible part of a strip of rock that trends parallel to the *e-d* bed, for all the strikes are here parallel (Fig. 452, B). Now, there





FIG. 452.—Stages in the construction of a geologic map of folded strata which outcrop on a level land surface. The crosses in B and C are in the positions of the outcrops in A.

is nothing to show that conglomerate does not exist between the *c* strip and the *e-d* strip, and, accordingly, this area may be marked for conglomerate. Similarly, shale probably occupies the space between *g* and *h* along the strike. It will be observed that there are indications of six different belts of rock, as follows: shale on the west, including outcrop *a*; sandstone next east, including outcrop *b*; then conglomerate, including outcrops *c*, *d*, and *e*; then sandstone, *f*, followed eastward by shale, *g* and *h*, and finally sandstone, *i*, at the extreme east. By locating the boundaries between these belts, as directed in Art. 438, the map is completed (Fig. 452, C).

441. Use of Profile Sections in Geologic Map Construction.—

Few regions are flat as in the hypothetical case just described. If the topography is varied, the construction of the geologic map is more complicated. An example is chosen here in which strikes are regarded as trending across valleys, for the relations are better brought out in this way. Let *n* (Fig. 453, A) be an outcrop exposing a contact between two strata and imagine that this contact is essentially flat near the surface of the ground. Choose a vertical scale and construct a profile section through *n* perpendicular to the strike (Fig. 453, B) (295). The base line, *X-Y*, of this section may be drawn on the same sheet of paper as the map, but it must be drawn actually perpendicular to the strike. Project *n* upon the profile line of the section *n'*. From *n'* draw a line, *n'-e*, westward and downward at an angle of 25° to the horizontal. *n'-e* is the intersection of the plane of the section with the bedding contact plane through *n*. It cuts the 160-ft. contour level in the section at *a*, the 140-ft. contour level at *b*, the 120-ft. contour level at *c*, and the 100-ft. contour level at *d*. From these four points draw lines perpendicular to *X-Y* upward and across the map. Wherever the line from *a* crosses the 160-ft. contour on the map, the bedding contact plane comes to the surface at this point; wherever the line from *b* crosses the 140-ft. contour line on the map, the contact plane meets the surface at the level of 140 ft.; and so on. Between these points of intersection on the map a curved line, *UVW*, is drawn, this line

being the position of the continuous outcrop of the contact plane on the surface of the ground. The line from *d* does not meet the 100-ft. contour because the valley in the middle of the map is not deep enough to reach this contact.




FIG. 453.—Construction of a geologic map of folded strata which outcrop on an uneven land surface. Contour interval, 20 ft.

Now let *fg*, Fig. 453, A, be a traverse across the strike of a series of strata. Suppose that, at outcrops *o*, *p*, and *s*, contacts between strata have been recorded and that *n* and *p* are at the same horizon. The structure, inferred to be synclinal, may be shown on a profile section along the traverse, as directed in Art. 450. If one desires to make a geologic map of the rocks and structure

represented in this section, each outcrop is to be separately treated as has been explained for *n*. Figure 453, A, shows the distribution of the contacts exposed in the five outcrops. Between them the different strata are indicated by cross-hatching and stippling. The boundary that runs through *o* is not continuous across the valley, for the stream has cut below this horizon, entirely removing a large part of the overlying bed (diagonally lined in Fig. 453, A).

In ordinary geologic mapping it is not customary to locate contacts with such mathematical precision unless great accuracy is particularly desirable. After one has gained some familiarity with the general effects of topography on the distribution of outcrops, one can sketch the boundaries between strata on a contour map with sufficient precision without the assistance of geometry, provided dips are known and the relief is observed, and provided, also, the different beds in the series have been located along several traverses.

442. Nature of the Legend.—The nature of the legend of a geologic map is illustrated in Fig. 454. The conventional signs and colors should be tabulated in a column of small rectangles of equal size. On the U. S. Geological Survey maps, the signs for rocks are above those for such features as faults, glacial striæ, lines of section, etc. Igneous and sedimentary rocks, metamorphosed or not, are grouped separately, the sediments being above. For metamorphic rocks whose origin cannot be determined, the signs may be placed under the head "Unclassified" below those for igneous rocks. In each group the formations are placed in the order of their relative age, youngest being at the top. Unconformities, when present, are often noted between the symbols for the unconformable formations. The geologic ages are printed beside the column. The legend is put in the right margin of the map and, if too long, it is continued in the left margin (Fig. 454). In this case the left portion really belongs below the part in the right margin.

443. Requisite Data for a Completed Geologic Map.—A geologic map is incomplete unless it has a legend, a scale, compass

bearings, both magnetic and true, and lines of section (445) if any geologic sections have been drawn to accompany this map. It must have a name, and the year in which it was made must appear somewhere upon it. If it was constructed on a contour




FIG. 454.—Arrangement of the legend for a geologic map. The rectangles would be filled in with the colors or symbols employed on the map.

base map, the contour interval and datum plane must also be recorded. If possible, it should have at least one parallel of latitude and one meridian correctly indicated on it. With regard to scale, compass bearings, and contours, what was said in Arts. 289-291 is applicable here.

JOINT DIAGRAMS AND MAPS

444. Methods of Representing the Attitude of Joints.—The field geologist should not neglect to study the joints in his area of investigation. Not until their attitudes and relations to one another are known can deductions be made as to their origin. They are an important aid toward the elucidation of structural and genetic problems in many kinds of rock formations (213




FIG. 455.—Diagram showing the strikes of joints observed on an outcrop.

to 219; see Fig. 442 for symbols for joints). For the larger fracture systems it is well to prepare special maps or diagrams to show the dips and strikes of the joint sets observed. For each station on a traverse the strikes may be plotted on a map as a radiating group of lines which intersect at the station (Fig. 455). Along each line the strike and also, if it is desired, the amount and direction of dip may be noted. If one wishes graphically to represent in a single diagram all the

joint trends in a region, this may be done by plotting all the strikes about a single center; or the following method may be employed.¹ Tabulate all the joint strikes in groups of 3° each, beginning at the west and passing through north to east. In the first group will be all strikes between N. 90° W. (= E.-W.) and N. 88° W., inclusive; in the next group of three, readings from N. 87° W. to N. 85° W., inclusive; and so on. Having tabulated the strikes in this way, construct a diagram like that in Fig. 456, in which: (1) the radii are drawn at intervals of 3°, beginning at the west, and thus intercepting segments corresponding to the joint groups; (2) the radial distance between the middle and inner circles is measured in any convenient unit and is made proportional to the greatest number of joints falling in any one of the groups; (3) the number of joints in each group is recorded between the middle and outer circles; (4) the number of joints in each

¹ Bibliog., SHALER, N. S., 1889, pp. 563-588; and SHELDON, P.

group is graphically shown by blackening the corresponding segment inward from the middle circle a distance proportional to this number and measured in the chosen unit; and, (5) the compass directions are indicated just outside the outer curve.

Dips may be plotted in like manner; but for this the reader is referred to the reports above cited. Needless to say, the attitudes of veins and dikes may be illustrated by diagrams similar to that above described, if the veins and dikes are comparatively uniform in trend and thickness.




FIG. 456.—Method of plotting the strikes of the joints observed in a given region. (After P. Sheldon.)

GEOLOGIC SECTIONS

445. Definitions and General Nature.—If it were possible to make a deep vertical cut in the ground and then remove all the soil and rocks on one side of the cut, the other side might stand up as a flat vertical wall upon which rock structures and rock relationships could be seen in cross section. While incisions of this kind are impossible, except for very slight depths, the geologist can draw vertical sections of the underground structure as he thinks it exists from data obtained from outcrops, artificial excavations and bore-hole data (457). Such sections, whether actually seen or merely inferred, are called *geologic sections*. They depict geologic structure by means of certain conventional

lines and patterns or colors, and, therefore, like geologic maps, they must have a legend.

The line of intersection of the land surface with the plane of a geologic section, as shown on a map, is called a *line of section*, exactly as in the case of profile sections (294).




FIG. 457.—Symbols used in geologic sections for different types of rock.

For every geologic section one must first make a *base section* upon which the geologic features may be drawn. This may be a profile section, prepared as described in Art. 295, or a simple rectangle. The simple rectangular base consists of two horizontal lines connected by two vertical end lines. The lower horizontal line corresponds in every way to the base line of a




FIG. 458.—Illustration of the nature of a geologic section.

profile section (294). The upper horizontal line is intended to represent the intersection of the plane of the section and a horizontal plane which may be taken at any convenient elevation. The advantage of the rectangular base section is that it eliminates the necessity of plotting the topography; but since it does not depict the actual nature of the land surface, it should not be


used except where the scale is so small that the relief variations would be negligible in a profile section of the same district on the same scale (451).

446. Methods of Indicating Geologic Structure.—Within the closed space of a geologic section all lines for faults, contacts, unconformities, etc., are drawn full, and between these lines, as on a geologic map, the rocks or formations are filled in by conventional colors or patterns (Fig. 457). It is a common practice further to indicate the geologic structure by extending the *lines*, now *dotted*, beyond the confines of the base section (Fig. 458); but observe that the colors (or patterns) for the rocks should be restricted to the area of the base section. Above the top line of the base section these dotted lines stand for the inferred structure of the rocks which have been removed by erosion. Below the bottom line such dotted lines represent the structure where it is uncertain on account of its great depth. Note that the general characters indicated by the full line for a particular contact should be simply represented by the dotted prolongation of the same line (Cf. *ab* and *cd*, Fig. 458).


447. Position of Sections across Folded Strata.—The location of a geologic section depends upon the exact features which the geologist wishes to emphasize. Ordinarily it is drawn perpendicular to the strike of stratified rocks, so that it will show their true dip. When pitch is to be figured, the section must be drawn parallel to the axis, and it is then called an *axial section*. In districts where the bedrock is abundantly exposed, locating a section is easy; but if outcrops are few and scattered, the rocks and structures which they reveal must be projected along the strike (Fig. 459, B, C). Frequently strikes vary 10° to 15° to one side or the other of their average direction. For a large-scale section, covering a short distance, it may be important to make allowance for these variations; but for a small-scale section they are insignificant if the outcrops are situated relatively near the line of section. Experience will soon teach the student how to deal with these cases. He must not confuse this indiscriminate and slight variation of strikes with a gradual or

sudden, pronounced and regular change in direction. The latter phenomenon may be due to a fault, an unconformity, or some other important cause.


To illustrate the relations between the trend of a geologic section and the position of outcrops and structures, several examples are given below. In all the land surface is assumed to be horizontal.




A




B



C



D



E

FIG. 450.—Location of a geologic section across stratified rocks.

1. The bedrock is broadly exposed, or the outcrops are situated in a row trending perpendicular to the strike (Fig. 459, A). Draw the section along a line from *a* to *b*.

2. Outcrops are scattered. Strikes are all identical or very nearly so (Fig. 459, B). Project the rocks and dips of the several outcrops along their strikes to points on the line *ab*, which is perpendicular to the strike. Thus, the rock exposed at *c* and the dip of the beds at *c* would be represented in the section at *d*.

3. For some reason, not here stated, the section must be drawn at an acute angle to the strikes, along such a line as *ab* in Fig. 459, C. Project rocks and dips along the strikes of the outcrops to points on the line, *ab*, just as in example 2. Since a section perpendicular to the strike shows beds with their maximum inclination or dip, and since, in a section parallel to the strike, the beds would appear to be horizontal, obviously a section located between the dip and strike directions must show the beds inclined at an angle more than 0° and less than their true

dip. In other words, in cases like the present one, a correction must be made for the inclination of the beds as this would be seen in the section, and this correction will depend upon the

actual dip and upon the angle between the strike and the line of section (Appendix XIII).

4. When strikes vary regularly, as in D and E, Fig. 459, the line of section may be straight, *ab*, or it may be drawn with one or more changes in its direction, *cde*, the object in this case being to keep it as nearly as possible perpendicular to the strikes. In Fig. 459, D, the curve in the strikes indicates a pitching fold. Let us assume that the axis of this fold lies along *fg*. The outward dip of the beds shows that the pitch is toward *g*, and, as far as the map reveals, there is every reason to believe that the strata pitch in this same direction at all points along the axis. Hence, in geologic sections on *ab* and *cde* the beds would appear to be horizontal where *ab* and *cde* cross the axis. (Why?) The sharp change in strikes in Fig. 459, E, suggests a fault or an unconformity, *fg*, between the two sets. In either D or E, Fig. 459, a section along *ab* would need correction for dips as explained for case 3.

448. Operations Necessary in the Construction of Geologic Sections.—The method of constructing geologic sections may be treated under four heads: (1) the transfer of data from a map to a base section; (2) the correlation, in the section, of rocks already correlated in the field; (3) the location of boundaries between adjacent strata or formations; and (4) filling in the section. The construction of a rectangular geologic section will be discussed first, and then that of a profile geologic section. In both cases we shall consider a region in which all the rocks are folded strata. Geologic sections may be enlarged as described in Art. 296.

449. Construction of a Rectangular Geologic Section across Folded Strata. A. Transfer of Data Recorded on a Map.—Let Fig. 460 be a map of an area in which the relief is relatively low as compared with the length of the section to be drawn. *xy* is the line along which the section is to be made. Upon *xy* project the rocks and dips of the outcrops as directed in Ex. 2, Art. 447, and transfer the points of intersection, *a-g*, to *xy* in Fig. 461, A. At point *a*, Fig. 461, A, lay off a row of dots inclined

downward and westward and making an angle of 20° with the horizontal line xy . This denotes sandstone (437) dipping 20° W.,




FIG. 460.—Outcrop map of folded strata. A geologic section is to be made along xy , the "line of section." (See Fig. 461.)




FIG. 461.—Stages in the construction of a rectangular geologic section along line xy in Fig. 460.

and it stands for outcrop a in Fig. 460. Follow the same method for each of the other points, always observing the proper rock and

dip to be used. Conglomerate is to be represented by a row of small circles parallel to the dip, and shale by a straight line parallel to the dip. Figure 461, A, is the result of this work. It is well not to make the symbols, *i.e.*, the rows of dots or circles, or the lines for shale, extend more than a very short distance down from the top of the figure, merely far enough to show the dip.

—**B. Correlation of Rocks.**—In Fig. 461, A, *d* and *g* may be connected in a syncline (Fig. 461, B), since they are parts of the same bed, a fact which we shall assume has been ascertained by one or more of the methods of field correlation mentioned in Arts. 177 and 322. For the same reason, the outcrops of conglomerate at *b* and *c* may be drawn as if they had formerly been joined in an antiline. The structure, then, indicates a stratigraphic sequence from conglomerate below, through sandstone, to shale above.

—**C. Location of Boundaries.**—The location of boundaries between strata has been described for maps in Art. 438. In general the map of a region should be completed before the sections are made; but if a geologic section is to be plotted directly from field notes, location of bedding contacts is determined in the same way as in the case of maps. Stratigraphically, *i.e.*, at right angles to the bedding, outcrops *a* and *b* (Fig. 461), of sandstone and conglomerate, are nearer than *c* and *d*, also of sandstone and conglomerate. Hence, the boundary between these rocks is placed halfway between *a* and *b* (Fig. 461, C). Similarly, the shale-sandstone boundary is located halfway between *d* and *e*. Between *c* and *d* the sandstone-conglomerate contact is placed east of *c* at such a distance that there shall be the same thickness of conglomerate represented between this spot and *c* as there is between *b* and the sandstone-conglomerate contact west of *b*. This is because *b* and *c* have been proved to be at the same stratigraphic horizon (same bed). In like manner the position of the shale-sandstone contact is determined between *f* and *g*.

When locating boundaries between strata, always use the most accurate information available. If a contact is exposed, this

contact should be the starting point. From its position other boundaries may be fixed, provided the thickness of each bed is known. If no contact is exposed, determine the position of the boundary between the nearest outcrops of two adjacent strata, and then locate other contacts.

—**D. Filling in the Section.**—It is now possible to complete the section by extending the rock contacts and filling in the




FIG. 462.—Construction of a profile geologic section.

inclosed rectangular space with the proper symbols for conglomerate, sandstone, and shale. The boundaries are drawn, as full lines in the section and as dotted lines beyond the confines of the base section, parallel to the structure shown in the anticline between *b* and *c* and in the syncline between *d* and *g* (Fig. 461, D). The last step is the filling in of the section proper (Fig. 461, E).

450. Construction of a Profile Geologic Section across Folded Strata.—Let Fig. 462, A, be an outcrop contour map of an area and suppose that a section is to be made through the line *xy* which marks a cross-strike traverse. A profile base section must

be constructed (295). This is illustrated in Fig. 462, B, where *vw* is the base line which corresponds to *xy* on the map. Here the points of intersection of the line of section (*xy*) with the contours may be transferred to *vw* most conveniently by dropping perpendiculars from these points of *vw*, it being understood that *vw* has been drawn equal in length to *xy* and, like *xy*, perpendicular to the strikes. Just as the intersections of the contours with *xy* are plotted on *vw*, so also the positions of the outcrops,




FIG. 463.—Errors resulting from exaggeration of the vertical scale of a geologic section. The lower section is drawn to natural scale; the upper section has a vertical scale exaggerated three times. The effects of this exaggeration are: (1) to cause the beds at *b'* to dip out of the hillside instead of into it, as at *b*, (2) to cause the sandstone at *c'* to run into the slate at *b'* (Cf. *b* and *e*); and (3) to alter the thickness of beds. (Cf., especially, the sandstone between *d'* and *e'* with that between *d* and *e*.)

a-e, projected along their strikes, are located on *vw*. The perpendiculars from the outcrops meet the profile line, *st*, at the proper sites of the outcrops *a'-e'*. At these points on *st* the dip and rock type are to be correctly indicated (449, A) and then the section is to be completed in the manner outlined in Art. 449, B-D.

The vertical and horizontal scales of a geologic section should be the same.¹ Exaggeration of the vertical scale necessitates adjustment of all the dips, and this not only involves a great deal of labor but also gives a false notion of the structure. On the other hand, if the dips are plotted with their correct values in a section with its vertical scale exaggerated, several absurdities may result, as illustrated in Fig. 463. How to make a scale for

¹ Five thousand feet to an inch, for the vertical scale, is satisfactory when the horizontal scale is 1 mile = 1 in.; and the same may be said of multiples of these scales.

use in sections with an exaggerated vertical scale has been described by Wentworth.¹

451. Comparison of Rectangular and Profile Sections.—The student should observe that rectangular geologic sections are more or less incorrect except when the land surface is flat and horizontal. The profile section, drawn to natural scale, is the most accurate mode of showing geologic structure. Figure 464 contrasts the results obtained by projecting the same data upon both rectangular and profile sections. Upon a map (not shown)




FIG. 464.—Errors introduced by the use of a rectangular section. A, profile section, and B, rectangular section, of a bed whose breadth of outcrop is ab , as projected from the map along the lines su and tv .

A), longer than ab in Fig. 464, B. cd , however, is the correct horizontal distance between the beds at the level, cd . Obviously, then, profile sections are always to be preferred to rectangular sections when actual geologic structure is to be depicted. Rectangular sections are useful for diagrams of general application, such as many used in this book.

452. Interpretation of Dips in the Construction of Geologic Sections.—In many cases after the dips and rock types of folded strata have been plotted, the final interpretation of the structure requires a good deal of thought. Several variations may be

¹ Bibliog., WENTWORTH, CHESTER K., 1930.

suggested by the data. In order to assist the student in completing his sections, a number of relations for dipping strata are noted below, together with their possible interpretations. In these examples it is assumed that field observations on rock type, strike, amount and direction of dip, etc., have been recorded. Simple symmetrical folds, asymmetrical and overturned folds, isoclinal folds, and parallel and similar folds, are considered. Strikes are regarded as parallel in all outcrops unless otherwise stated.



FIG. 465.—Section of beds with homoclinal dip.



FIG. 466.—Structures inferred from observations on homoclinal dip. The small closely ruled rectangle in each diagram corresponds to Fig. 465.

—A. Observations on Homoclinal Dips.—1. *On a single outcrop or on several adjacent exposures the dip is found to be of nearly constant value and in the same direction. There is no duplication of beds.* Let Fig. 465 be a section of the structure




FIG. 467.—Structures inferred from observations on beds which have homoclinal dip and which outcrop alternately in normal and reversed order.

beneath the area examined. Beds with this dip may belong in a monocline (Fig. 466, A), or in the limb of an upright anticline or syncline (Fig. 466, B) or in the limb of an overturned fold (Fig. 466, C). To determine which interpretation is correct, the country must be more extensively investigated across the strike

and beyond the limits of the original area. In Fig. 466, C, the strata are overturned, a fact which may perhaps be ascertained by such criteria as have been cited in Art. 166.

2. *The conditions are similar to those of case 1, but beds are repeated in inverse order as seen in a cross-strike traverse. The strata have been duplicated once or several times by isoclinal folding (Fig. 467). Obviously, correct interpretation of this kind of structure requires search for the top and bottom of individual strata (166) and for stratigraphic sequence (108).*

—**B. Observations on Dips of Varying Amount and Direction.**—1. *A bed, which is surely identifiable, is exposed in two localities where the strikes are alike and the dips, though equal, are*



FIG. 468.—Structures inferred from observations on dip. The short black lines indicate the dips as plotted at two outcrops.

in opposite directions. There are two possibilities: if the dips converge downward, the outcropping stratum is probably continuous underground as a syncline (Fig. 468, A), and if the dips diverge downward, the bed once extended above the ground as an anticline from which erosion has removed the crest (Fig. 468, B). Both folds are symmetrical and the axis is midway between the outcrops. This rule for converging and diverging equal dips is applicable to all folds except fanfolds. Observe that it is customary to draw the crests and troughs of folds *rounded* unless there is evidence to the contrary.

2. *In two localities two different strata are exposed, one, a, being older than the other, b. Dips are about equal in value and are in opposite directions.* As far as any observations reveal, the folding is symmetrical. The dips suggest a syncline on the left and an anticline on the right, in both A and B, Fig. 469. The axis is nearer the younger exposed bed, b, in synclines and nearer the older bed, a, in anticlines. In order most accurately to

determine the position of the axis, the thickness, t , of the concealed beds stratigraphically between a and b should be computed (486).

3. As in case 1, under B, above, the same stratum outcrops in two localities, but here the dips are unequal and opposite and one




FIG. 469.—Structures inferred from observations on dips recorded at outcrops labelled a and b .

of them is vertical. The fold is asymmetrical, the axial surface being inclined, and the axis is nearer the steeper limb (Fig. 470). The axis should be placed so that the perpendicular distances, t , from it to the given bed in each of the two limbs are approximately equal, unless there is good evidence for actual inequality.




FIG. 470.—Structure inferred from observations on dip. The short black lines indicate the dips as plotted at two outcrops.

As will be explained presently, not all instances of unequal dips are to be attributed to asymmetrical folding (see C, below).

4. The same bed outcrops in two localities, and the dips are unequal and in the same direction. Great care should be exercised in searching for criteria for overturning in the more steeply dipping rocks (166). If proof of overturning is forthcoming, the folds are overturned or recumbent according to the attitude of the axial surface, and the axis is nearer the steeper limb (Fig. 471); but if the steeper beds have not been turned beyond 90° , the structure must be that described in C, 1.

5. If available exposures are not of the same bed, but otherwise the conditions are such as were stated in 3 and 4 above, the folding may be asymmetrical (see, however, C). As in B, 2, the thick-




FIG. 471.—Structures inferred from observations on dip. The short black lines indicate the dips as plotted at two outcrops.

ness, t , of the concealed beds stratigraphically between a and b should be ascertained if possible (486). Study the diagrams carefully (Fig. 472).




FIG. 472.—Structures inferred from observations on dips recorded at the outcrops labelled a and b .

6. A succession of strata is exposed, all inclined in the same direction, but with some variation in the angle of dip. This is a phenomenon of frequent occurrence, chiefly because beds are not likely to undergo exactly the same amount of tilting when sub-




FIG. 473.—Correct (A) and incorrect (B) interpretations of structures based upon observations on varying dips.

jected to the complex forces of deformation. In this case, unless there is conclusive evidence to the contrary, the beds should be drawn as in Fig. 473, A. A mistake too commonly made by beginners is illustrated in Fig. 473, B, where a curious anomalous structure is given for the interpretation of the dip relations.

7. *The same bed is exposed in two localities. Dips are opposite and equal or unequal. The strata are found to be overturned in both localities. The structure is that of a fanfold (Fig. 474).*

C. Studies across Axial Regions.—The student will notice that all the diagrams used for this article are of parallel folding.




FIG. 474.—Structures inferred from observations on dip. The short black lines indicate the dips as plotted at two outcrops.

This is because the major folds in a set of deformed strata are apt to be more nearly parallel than similar, for similar folding is produced only under extreme compression (157). Figures 467 and 472 would perhaps be more natural if the folds in them were made on the similar pattern. Let us assume, now, that we are dealing only with folds of the parallel type. If the




FIG. 475.—Relations of erosion levels, *aa*, *bb*, *cc*, to folded strata where deformation has been moderate.




FIG. 476.—Relations of erosion levels, *aa*, *bb*, *cc*, to folded strata where deformation has been greater than that shown in Fig. 475.

dips on the limbs are moderate, the structure may be like that sketched in Fig. 475, and, on an erosion surface cut down to any level, *aa*, *bb*, *cc*, outcrops in the axial region will show low dips or no dip in vertical sections perpendicular to the axis. On the other hand, if the compression has been more intense and the dips on the limbs are relatively steep, synclines will be pinched, or *carinate*, in the upper part of the folded series and

anticlines will be carinate in the lower part of the series, whether the axial surfaces are upright or inclined (Fig. 476). If agents of erosion cut down to a level, *aa*, outcrops will expose the lowest dips in anticlinal axial regions and the steepest dips in synclinal axial regions. If the land surface has reached a level, *bb*, the



FIG. 477.--Variations in dip (short black lines) due to position of outcrops in a fold.

steepest dips will be on the limbs, and the lowest dips will be in both synclinal and anticlinal axial regions. And, if erosion has cut down to level *cc*, the steepest dips will be in the anticlinal axial regions and the lowest dips in the synclinal axial regions. In any of these cases the dips recorded on a cross-strike traverse may look like Fig. 477 when they are plotted, but as brought out by the dotted lines, this divergence of dip does not signify actual upward fanning of the strata. The stratification surfaces may still be parallel.

When the folds are even closer, the carinate crests of the anticlines may overlap the carinate troughs of the synclines (Fig. 478). Then, although erosion surfaces at *aa* and *cc* will be the same as in Fig. 476, at any erosion level in the middle belt, *bb*, both anticlines and synclines will be pinched. With the extremely close compression of isoclinal folding there may be no overlap of the carinate axial parts of the folds (Fig. 467).

453. Sections across Igneous Bodies.

If a dike is to be the principal feature in a section, the latter is drawn perpendicular to the strike of the dike. More commonly, dikes are incidental phenomena in a section of a sedimentary formation or of a larger igneous body, and in this event they may lie in various positions with respect to the trend of the section. Corrections for their inclinations, as represented in the sections, may then be necessary (Appendix XIII). Sills are treated like strata. A section through a laccolith or a chonolith is made preferably in




FIG. 478.—Relations of erosion levels, *aa*, *bb*, *cc*, to folded strata where deformation has been more intense than that shown in Fig. 476.

the plane of the dip of the basal contact. A section across a rock complex, such as is seen in the case of many of the larger intrusive bodies (batholiths, etc.) and their associated country rocks, may be oriented so that it will cut certain rocks, but generally without fixed relations to their boundaries.

As a rule one may safely infer that the nature of an igneous contact, as indeed, of any other geologic contacts, is similar in all directions, *i.e.*, that the features to be shown in its section are probably like those exposed in its horizontal, or nearly horizontal, outcrop. Hence, the details observed on rock exposures of contacts may often be drawn in the same general manner, whether




FIG. 479.—Method of representing faults and faulted structures in a geologic section.

on a map or in a vertical section (Cf. the different sections shown in Figs. 80 and 83).

454. Vertical Sections of Faults.—A section across a fault should be made as nearly as possible at right angles to the strike of the fault. For a dip-slip fault such a section gives the actual displacement; for all others, any displacement in the diagram is a rectangular component of the net slip. If the section is not perpendicular to the fault strike, the inclination of the fault must be corrected (Appendix XIII).

In a geologic section a fault is represented by a heavy line, full within the base section and dotted (or dashed) above and below the base section (Fig. 479). On each side of the line, preferably just outside of the base section, a small arrow should be drawn to show the *relative* direction of displacement of the blocks. The structures (bedding, igneous contacts, etc.) in the fault blocks, if indicated above the base section, should be drawn in dotted lines to the positions which they are imagined to have

had against the dotted (or dashed) part of the fault line, *after faulting, but before erosion cut them down to the present level of the land surface* (Fig. 479) (Cf. Arts. 179 and 470).

The construction of difficult fault problems may be simplified by sketching on scrap paper a section of the rocks before the displacement, cutting the paper along the line of the fault, and shifting the pieces along this cut until the rocks and structures are in their present relations.

455. Requisite Data for a Completed Geologic Section.—No geologic section of existing structures is complete which is not accompanied by a legend, vertical and horizontal scales, and some indication of its direction. With reference to scales, see Art. 294. The direction of a section may be shown by labelling its ends with the proper points of the compass, or by stating that it is drawn looking in such and such a direction¹ or by labelling its ends by letters or by numbers which are also placed at the corresponding ends of its line of section on the map. A common error of beginners is to mark the top and bottom of a section by points of the compass, an impossible condition since all sections are vertical and all compass directions are horizontal.

STRUCTURE CONTOUR MAPS²

456. Nature of Structure Contour Maps.—Most geologic sections of stratified rocks are far from being accurate in the information which they convey of the thickness and depth of the individual layers. They are usually diagrammatic inferences based on such scattered facts as can be assembled from the observation of outcrops and from bore-hole and mine records. When such sources of information are especially abundant and reliable, the folds may be indicated by structure contour maps better than by geologic sections. A *structure contour map* (Fig. 480), like a topographic contour map, depicts the configuration of a

¹ Common practice is to draw east-west sections looking north (east end on right) and north-south sections looking west (north end on right).

² See also Art. 461 on Subsurface Maps.




FIG. 480.—Structure contour map of the Amity, Brownsville, Waynesburg, and Mason-town quadrangles, Penn. Axes of folds are indicated by dashed lines. The contours are lines of equal elevation of the base of the Pittsburgh coal bed above mean sea level. Contour interval, 50 ft. (After F. G. Clapp.)

surface by lines of equal elevation, generally referred to mean sea level as the datum plane. These lines are the intersections of the surface with a series of equally spaced horizontal planes, the vertical distance between any two adjacent planes being known as the contour interval. For a shallow structure contour map the surface chosen is that of the top or bottom of some bed which is easily recognized, is persistent over large areas, has not suffered much erosion, and is not too far below the land surface. The elevation of this *key horizon*, as it is called, above mean sea level is obtained in the field at as many points as possible, both at actual outcrops and from the records of drill holes, and the data are plotted at the several stations on a base map. Sometimes it is necessary to secure these elevations by adding to or subtracting from the elevations of outcrops of other known beds, but this method is liable to error on account of the possible variations in thickness of the intervening strata (88, 89). For a deep structure contour map, the key horizon is again the top or bottom of some recognizable bed, but the data used come from subsurface geology (461 to 464).

To illustrate the method of drawing a structure contour map, let Fig. 481 represent a chart of the stations examined and plotted in the field. At stations to the left of the dashed line, *ST*, elevations were determined on the chosen key horizon. At stations to the right of this line, *ST*, elevations were found on a bed 30 ft. above the key horizon, so that 30 ft. must be subtracted from each of these quantities to obtain elevations on the key horizon. In Fig. 482 this subtraction has been done. On the assumption that a 10-ft. contour interval will be satisfactory, we may start by drawing a line through *a*, midway between *b* and *c*, through *d*, $\frac{1}{3}$ way from *e* to *f*, $\frac{1}{5}$ way from *g* to *h*, just south of *i*, and so on. This will be the 520-ft. contour line. In the same way the other contours may be drawn, either through stations having these elevations, or interpolated between stations of higher and lower elevations.

In Fig. 482 the 560- and 570-ft. contours are closed, representing a dome, *A'*; and the 470-ft. contour is closed to indicate

a structural basin, *B'*. Note the closed basin contours are hachured.

As regards the accuracy of these maps, the steeper the dip of the strata and the less reliable and less numerous the available data, the greater is the chance for mistake in placing the structure contours. There are often places where generalization is a neces-




FIG. 481.—Map of elevations determined at scattered stations on two outcropping beds. (See text.)

sity, simply because the facts are too few. The more doubtful contours on a map should be dashed (Fig. 493). The contour interval is selected with a value such that it is not less than the *limit of error* for the district. "For example, if over a given area the elevation of" the key horizon "was determined to an accuracy of within 50 ft., it would be useless to attempt to draw contours with a 25-ft. interval. Moreover, such a representation would be misleading to the reader, who would be led to believe

that the elevation at any given point was accurate within 25 ft., which would not be the case."¹

The intersection of a structure contour with a topographic contour of the same elevation marks a point on the outcrop of the key horizon. Where the land surface is higher than the key




FIG. 482.—Contour map drawn on the basis of the data shown in Fig. 481. The contours represent an anticlinal closure or dome at A'; a synclinal closure or structural basin at B'; an anticlinal nose with its axis along E'F'; a synclinal bowing or "chute" with its axis along G'H'; a monoclinial flexure at C'D'; and a structural terrace at I'J'.

horizon, the approximate depth of the latter below the ground surface may be found by subtracting the elevation of the structure contour from that of the topographic contour at that place. When the land is lower than the key horizon, the latter has been eroded away and the structure contours indicate its probable former position. In this case they would better be dotted.

If one wants to ascertain the depth of some horizon other than

¹ Bibliog., CLAPP, F. G., pp. 37, 38.

² JOHNSON, R. H., and L. G. HUNTLEY, "Principles of Oil and Gas Production," p. 65.

that chosen for the *key*, one must first know the thickness of the beds between the two horizons. Thus, in Fig. 483, *dc* is the key horizon, parallel to the bedding, *c* is a point of which the depth, *fc*, below the surface of the ground, *gfh*, may be determined on the structure contour map, and *b* is a point vertically below *c* in a horizon, *eb*, with a thickness of intervening beds equal to *ab*. The required quantity, *cb*, can be obtained by solution of the right triangle *abc* in which *ab* and the angle *acb* are known.




FIG. 483.—Vertical section to illustrate the method of computing the depth of a horizon below the key horizon of a structure contour map.

WELL LOGS

457. Definition.—When a deep hole is drilled into the ground, a record of the rocks penetrated is usually kept by the driller or by the field geologist. Such a record is called a *log*. It may be made up in written or type-written form, as shown below, or it may be plotted graphically to scale (Figs. 484, 485). In the laboratory a more detailed log is made of the same well, showing any data, discovered in the samples, pertaining to paleontology, lithology, etc.

Observe that every well log should have recorded on it the name of the locality or property where the well was drilled, the

EXAMPLE OF A WELL LOG

State—Texas. County—Stephens. File number—6,836
 Owner—XXXX Company. Farm—T. S. Hatch. Well number—2.
 Location of Farm— Lot number XX,—Survey.
 Location of well—500 ft. from east line; 500 ft. from south line.
 Casing record: set 18 in. . . . ; 15½ in., 615 ft.; 12½ in., 1,310 ft.; 10 in., 2,020 ft.; 8¼ in., 2,425 ft.; 6½ in., 3,075 ft.; 5¾ in.,
 Pulled 18 in. . . . ; 15½ in., 615 ft.; 12½ in., 1,310 ft.; 10 in., 2,020 ft.; 8¼ in.; 6½ in., ; 5¾ in.,
 Production: initial, 154 bbl.; settled, ; after shot, 750 bbl.; shot from 3,200–3,260 ft.; shot with 200 qts.
 Total depth, 3,260 ft. Elevation, 1,245 ft.
 Remarks: 2,425 ft. of 8¼ in. and 3,075 ft. of 6½ in. casing left in hole.
 Drilling began 8/27/20. Drilling completed 11/22/20.

DRILLER'S LOG (Cont. from p. 631)

Formation	Top	Bottom	Remarks
Clay.....	00	15	
Clay.....	15	30	
Blue mud.....	30	115	
Blue shale.....	115	210	
Brown lime.....	210	225	
Brown shale.....	225	345	
White lime.....	345	390	
Dark sand.....	390	410	Water
White lime.....	410	425	
Blue shale.....	425	460	
Broken lime.....	460	478	
Brown shale.....	478	595	
Lime.....	595	605	
Shale.....	605	630	
White lime.....	630	740	
Brown shale.....	740	765	
White lime.....	760	805	
Brown shale.....	805	1,005	
Lime.....	1,005	1,045	
Shale.....	1,045	1,060	
White lime.....	1,060	1,115	
Brown shale.....	1,115	1,125	
Gray lime.....	1,125	1,170	
White lime.....	1,170	1,195	
Black shale.....	1,195	1,223	
Gray sand.....	1,223	1,275	Water
Blue shale.....	1,275	1,310	
White lime.....	1,310	1,325	
Brown shale.....	1,325	1,500	
White lime.....	1,500	1,525	
Brown shale.....	1,525	1,700	
Gray lime.....	1,700	1,750	
White sand.....	1,750	1,785	Water
White lime.....	1,785	1,785	
Soft gray lime.....	1,785	1,790	
Brown shale.....	1,790	1,980	
Gray sand.....	1,980	1,990	Hole full of water
Dark shale.....	1,990	1,995	
Lime.....	1,995	2,000	
Gray sand.....	2,000	2,020	
Lime.....	2,020	2,035	
White shale.....	2,035	2,105	
Gray and white shale.....	2,105	2,315	
Gray lime.....	2,315	2,325	
White sand.....	2,325	2,330	Water. Gas show
Gray sand.....	2,330	2,425	
Blue shale.....	2,425	2,530	
Brown shale.....	2,530	2,600	
Blue shale.....	2,600	2,630	
Gray sand.....	2,630	2,645	Water
Brown shale.....	2,645	2,735	
Blue mud.....	2,735	2,752	
White sand.....	2,752	2,785	Water
Brown shale.....	2,785	2,900	
Blue shale.....	2,900	2,950	
White sand.....	2,950	2,960	Dry
Sandy shale.....	2,960	3,055	
Blue shale.....	3,055	3,075	
Hard lime.....	3,075	3,080	
Black slate.....	3,080	3,200	
Black lime.....	3,200	3,210	Steel line measure, 3,220 top black lime
Brown lime.....	3,210	3,245	
Gray lime.....	3,245	3,260	
		3,260	Total depth

name of the organization which drilled the well, the elevation of the mouth of the well above sea level, the method of drilling,

Form A (Left):

S	T	R
County		
Farm	No.	
Company		
Elev.	Prod.	
Method		

Form B (Right):

Serial No.	
County	
Farm	No.
Company	
Location	
Elev.	Prod.
Method	

Vertical Scale:

100
200
300

B

FIG. 484.—Illustration of two types of log form used for plotting well records. That on the left (A) is used for sectionized country and that on the right (B) for regions which are not sectionized (Appendix VII). In these forms, "S" stands for "section;" "T" for township;" "R" for "range;" "No." for "well number;" "Elev." for "elevation" of the mouth of the well above sea level; and "Prod." for "initial production." The vertical scale is 1 in. = 100 ft. in the original form.

depths of casing seats, positions where the formation caved, positions of water sands, oil or gas sands, etc.

In plotting a graphic log, various symbols or colors are used for the different rocks. Colors are better, since they stand out




FIG. 485.—Lower portion of a plotted well record showing method of recording data on the log form.

in greater contrast. For sedimentary rocks, the writer has found the following color scheme satisfactory: conglomerate, gravel, sandstone, or sand, yellow; shale, slate, clay, gumbo, and similar materials, blank; red shale, clay, or slate, red; limestone, chalk, and dolomite, blue; coal or peat, black. The sea level line should be drawn in its proper position across the log (Fig. 488).

Many varieties of printed log form are in use. In our experience the most convenient form is prepared as shown in Fig. 484. Here A is for sectionized country and B is for unsectionized country (Appendix VII). This outline is printed on heavy paper of good quality. The scale is 100 ft. = 1 in. The paper is about 2 in. wide. It should be long enough to plot a log of an average deep well. For an exceptionally deep hole, an extra strip may be glued at the bottom of a blank log form.

458. Correlation of Logs.—The correlation of logs involves the matching of plotted graphic records of two or more drilled holes, with a view to establishing the identity of the formations penetrated in these holes. The following two methods of correlation are frequently practiced.

1. Let A to K, Fig. 486, represent the locations of several wells of which the ground elevations are known. Plot the logs graphically and then place them, side by side, as close together as possible, in such a way that their sea-level lines (457)

are opposite (Fig. 487). Their order should not be selected at random, but should be chosen, according to the distribution of the wells in the field, with the object of placing together the logs of adjacent wells and of wells probably along the same line of strike. The sequence may often be one that a person might follow in going from well to well, provided no obstacles were in his way. Thus, here the order is *A, B, C*, etc. to *K*. Any scattered arrangement, such as *A, J, C, G, K*, etc., would be highly inadvisable.




FIG. 486.—Chart showing location of wells used in plotting structure illustrated in Fig. 493.

Having placed the logs in this order, they may be shifted a little up or down until they match. If they do not exactly match—and they probably will not—they may be lined up either on the top or bottom of a definite bed (Fig. 488), or on the best average position for some bed or group of beds (Fig. 489). In the former case, the horizon on which the logs are correlated (matched) (*ST*, Fig. 488) may be adopted as a key horizon for making a *subsurface map* (461). In the latter case, an arbitrary line may be drawn horizontally across the logs and used as the key horizon (*SS'*, Fig. 489). In matching the geologist will do well to remember that sharp and distinct changes in the hardness of rocks, either from hard to soft or *vice versa*, are more likely to be detected, and therefore correctly reported, by the driller than any other variations in materials.




FIG. 487.—Logs of the wells shown in Fig. 486 grouped in their proper vertical positions relative to sea level. Depths below the ground surface are shown for every 200 ft. *w.* means "water-bearing."




FIG. 488.—Same logs as those shown in Fig. 487, here arranged so that they line up on the top, *ST*, of the oil sand at the bottom of each hole.




FIG. 489.—Same logs as those shown in Fig. 487, here arranged so that they match most closely. Observe that this correlation was made before any of the holes, except D, had been drilled deep enough to reach the oil sand on which the correlation in Fig. 488 is based.

2. In the second method of correlation the logs are arranged with their sea-level lines all along a horizontal line, and they are spaced according to a chosen horizontal scale. They may be thumb-tacked on to a sheet of beaver board or on to a draughting table. The horizontal scale may be considerably smaller than the vertical scale of the logs, since too great a horizontal scale would require too much room. This method of arranging the logs on a horizontal scale facilitates their correlation in that strata may be projected from log to log along the inferred or known dips. Thus, in Fig. 490, *E*, *F*, and *G* are sufficiently close to one another for the geologist to be reasonably certain that bed *a* is the same in each. That *a* in log *I* is this same bed is indicated by the general flattening of the dip toward *I*, as shown by the line drawn on the base of *a* through *E*, *F*, and *G*. Observe that logs are used only of wells that lie along straight lines, or nearly straight lines, in the field.

This method is of value chiefly where the wells are fairly close to one another. It cannot safely be applied to widely scattered wells. In producing oil fields, it is often used in constructing geologic sections. For a subsurface structure contour map, the top or bottom of some easily recognized bed—frequently the pay sand in oil and gas wells—may be taken as the key horizon (462).

In difficult problems of correlation, both of the methods above described may have to be used, first one and then the other.

All correlation work with logs is subject to errors which should be understood and eliminated as far as possible. Certain important sources of error are these:

1. The elevations determined for the mouths of the wells may be more or less in error on account of inaccurate or careless instrumental work, or because they were found by individuals representing different companies and using different instrumental methods or different reference points.

2. Misunderstanding of driller's terms for rocks, and failure to appreciate the difference between cable-tool records and rotary records, may lead to misinterpretation of the logs.




FIG. 490 —Logs of E, F, G, and I, arranged on a chosen horizontal scale in their correct positions relative to sea level. Correlation is here made on the base of bed a. (Cf. with contour map, Fig. 493, B)

3. Errors may be made in measuring, and therefore in recording, the depths of points in the hole. These may be caused by failure to make steel-line measurements, or by actual mistakes in measuring, or by the use of different steel lines for successive measurements. Great care is always necessary in these measurements of depth. The length of cable or drill stem extending down to any important point in the hole should be compared with the record obtained by the steel line to this point. Measurement of depth is often made as part of the operation of electrical logging (430, 459).

4. Mistakes often creep into the written logs in copying and recopying them.

The methods of correlating logs, as discussed above, apply more especially to drillers' logs or to logs in which there is some latitude for interpretation, because of the scarcity or uncertainty of scientific data. If accurate determination of one or more horizons is possible, there is no necessity for shifting the logs up and down to select an average position for correlation. If the stratigraphic interval between any two definite beds changes across the area, a subsurface map on each may be advisable (463).

459. Electrical Logs for Correlation.—As we have explained in Art. 430, electrical surveying of bore-holes has a decided advantage over former methods of logging, since it permits more accurate determination of the points where changes in lithology occur. Electrical logs more surely indicate the positions of the tops and bottoms of strata—points, in other words, that may be used in correlation. However, we want to make clear the fact that, even where these logs are employed as the main basis for correlation, this cannot be done to the complete exclusion of lithological and paleontological data from each hole; for we must have knowledge of what the rocks are and what fossils they contain before we can have a satisfactory understanding of the subsurface geology.

Figure 491 illustrates the use of electrical logs in correlation. These logs are arranged in the actual field relations of the wells that they represent and on a horizontal scale here equal to one-




Fig. 491.—Correlation of electrical logs. These are logs of wells in south Texas. (See text.)

fifth the vertical scale. Only the lower part of each log is shown, beginning at a subsea depth of 3,500 ft. Depths from the surface of the ground, in each well, are indicated in the middle part of each log—40 meaning 4,000, 50 meaning 5,000, etc. The dashed lines (*a*, *b*, etc.) are correlation lines connecting, as nearly as possible, horizons that seem to be the same, from well to well. In making these correlations, the geologist first laid his electrical logs close together so that corresponding peaks and depressions in the self-potential and resistivity curves (430) could be more easily measured. (This is like the method of correlating lithologic logs, described under 1, Art. 458.) The capital letters *D* and *H* mark the highest points at which certain fossils, usually regarded as determinative, were recorded from examination of samples. Matching of key horizons across the logs, when properly arranged to scale (as in Fig. 491) reveals the presence of a fault that cuts well 2 between *c* and *f*. This fault has its downthrow on the west. Its angle of dip is such that it does not cut holes 1 and 3 within the depths represented in the diagram.

Careful study of this section (Fig. 491) reveals these facts:

1. There are several distinct porous zones, here sand (strong negative anomaly in self-potential curve), and these, for the most part, contain salt water (low resistivity).

2. One sand contains oil (high resistivity), and the oil in this sand is banked up against the fault (cutting hole 2) that has its downthrow on the updip side of the regional eastward dip of the strata.

3. Between the sands are shales (low porosity) that, no doubt, contain saline water (low resistivity) in their fine pore spaces.

4. The heavy sand, indicated by the high porosity curve in hole 6 between depths of 3,900 and 4,250 ft., thins westward (holes 4, 3, 2, 1), and becomes less porous and more broken by shales eastward (holes 6 and 7).

5. The two sand zones *ac* and *de*, conspicuous in holes 3, 4, and 5, seem to merge into a less porous but thicker sandy zone eastward to hole 7; the shale break *cd* thins eastward.

6. There is a notable thinning of sand *de* from hole 6 westward to hole 1.

7. Sand *de* is cut out by the fault in hole 2.

8. The stratigraphic section as a whole, from the upper dashed line in hole 4 (at about 3,760 ft. depth) to line *f*, thickens eastward from 1,850 ft. to 2,200 ft.; in other words, it thickens 350 ft. in a distance of a little less than 5 miles.




FIG. 492.—Correlation of gamma-ray (radioactivity) logs from four wells in Oklahoma. Wells 1 and 2 were less than $\frac{1}{2}$ mile apart; 3 is $3\frac{1}{2}$ miles from 2; and 4 is $\frac{3}{4}$ mile from 3. *ab*, base of Glenn sandstone; *cd*, base of lower Booch sandstone; *e*, unnamed shale layer; *gh*, top of Chattanooga shale (Cf. Fig. 430). Note that shale gives a relatively high reading (to right) and sandstone a relatively low reading (to left). (Published with permission of Well Surveys, Inc., of Tulsa, Okla.)

9. The first appearance of diagnostic fossils (*D*, *H*) is rather theoretical, due to poor sampling, lag in returns, etc., so that, certainly in this region, correlation of fossils, even if assisted by study of lithology, would probably give an incorrect picture of stratigraphic and structural conditions. The electrical logs greatly assist in checking the geologic data.

460. Radioactivity in Correlation.—As pointed out in Art. 433, a new (in 1940) method of correlating formations penetrated in drilling, by measurement of their radioactivity, gives promise of valuable application, especially in holes already cased and therefore not available for the usual methods of sampling and electrical logging. We merely call attention to this method here, presenting Fig. 492 as an illustration of the correlation of formations by radioactivity in four cased holes.

SUBSURFACE MAPS

461. Definition.—The kind of structure contour map described in Art. 456 is constructed largely from data secured at or near the earth's surface. Outcropping strata furnish most of the evidence. A structure map contoured on some deep-lying key horizon, elevations on which have been obtained from well logs or mine records, is known as a *subsurface map*.

462. Construction.—In Art. 458 we have briefly described methods of correlating well logs and selecting a key horizon for a subsurface map. Having chosen the key horizon, its elevation, in reference to sea level as datum, is to be found for each well by algebraically subtracting its depth from the elevation of the mouth of the well. Thus, if the key bed is at a depth of 800 ft. in a well which has a ground elevation of 1,000 ft., the elevation of the key horizon is $1,000 \text{ ft.} - 800 \text{ ft.} = 200 \text{ ft.}$ If the key bed is found at a depth of 1,300 ft. in a well with a ground elevation of 1,000 ft., the elevation of the key horizon is $1,000 \text{ ft.} - 1,300 \text{ ft.} = -300 \text{ ft.}$, or 300 ft. *below* sea level. The elevation of the key horizon is determined in this manner for all the wells in the area to be mapped, and these elevations are recorded on the map sheet in their proper places. A contour interval is chosen large enough to be somewhat greater than the probable error involved in the correlation of the logs, and the contours are drawn as explained in Art. 456. The completed map should have a title, legend, scale, etc., just as in the case of an ordinary surface structure contour map.

In oil fields, where wells are being drilled in fairly close proximity to one another, it is often desirable to make one or more preliminary subsurface maps from data obtainable from the wells during the progress of the drilling. Naturally such maps are likely to be somewhat in error on account of the incompleteness of the well logs. To illustrate the difference between a preliminary map and a final map of a given area, we have prepared Fig. 493, in which A has been plotted on elevations determined




FIG. 493.—Structure contour maps of the area shown in Fig. 486. A, preliminary interpretation based on correlation of Fig. 489. (Contours are above sea level. Key horizon is SS' of Fig. 489.) B, final interpretation based on correlation of Fig. 488. (Contours are below sea level. Key horizon is ST in Fig. 488.)

by the correlation of Fig. 489 and B on the elevations derived from the correlation of Fig. 488. Note that the structure is essentially the same in both maps, although the form of the contours varies a little. Map A would certainly be of value for choosing locations for new wells before all the wells shown on this map had reached the oil pay.

When the contours of a subsurface map are above sea level they are *positive*, and when they are below sea level they are *negative*. A map with positive contours has the greater contour numbers on the higher parts of the structure, whereas a map consisting of negative contours has the greater contour numbers on the lower parts of the structure (Fig. 493). Since the latter type of map is a little difficult for some people to read and understand, and since it may give a false impression of the structure

shown unless care is taken to ascertain whether the contours are positive or negative, some geologists prefer to raise the datum plane of a map to such a height above sea level that all the contours will be positive. Thus, if the lowest contour on the map is 850 ft. below sea level, the datum plane might be placed at 1,000 ft. below sea level, and then the negative 850-ft. contour would become a positive 150-ft. contour, and all the other contours would be raised accordingly. That an arbitrary datum has been taken in this manner must, of course, be clearly stated on the map.

In the writer's opinion this practice should be discouraged, for, although it simplifies the mere reading of the map, it greatly increases the time and labor incurred in making the calculations of depth, etc., based on the map. In the long run, the most practicable map is the one constructed on sea level as datum whether the contours are positive or negative.

In constructing Fig. 493, the contours were spaced essentially in mathematical relations to the elevation points recorded on the map. This is called *mechanical contouring*.¹ When there are numerous well-scattered elevation points, this method is fairly satisfactory, but if such points are few, the resulting contouring may be unreasonable, and even absurd, perhaps entirely out of accord with the known structural trends and forms of the region. Under these circumstances, the geologist must use his imagination, guided by his knowledge of the prevailing conditions. To illustrate these relations, Fig. 494, A to D have been drawn. Figure 494, A, represents a mechanical contouring of the data plotted at 12 stations. Figure 453, B, shows another contour map, based on the same data, but with the contours drawn more nearly parallel, and in a form suggestive of the known type and alignment of other structures in the district. This is termed *parallel contouring*. Figure 494, C, and D, again, are based on the same data as Fig. 494, A and B, and also, as in Fig. 494, B, the trend of the structures is made to conform with known trends of the region; but here the contours are spaced equally, the dis-

¹ Bibliog., RETTGER, R. E., 1929.

tance between contours being determined by the spacing where most data are available. This is called *equispaced contouring*.¹ A significant effect of equispaced contouring is the building of




FIG. A




FIG. B




FIG. C




FIG. D

Fig. 494.—Four interpretations of subsurface structure, all based on the same data obtained from the same wells. On each map the elevation of the key bed is given at the location of all wells. In A, the spacing is mathematically determined; in B, although proportionate spacing between wells controls the contouring for the most part, some latitude of interpretation has been employed in order to make the form of the structure look a little more reasonable. In C and D, equal spacing of contours has governed, the assumption being made that dips are everywhere essentially equal, which of course is unwarranted. Note that in both C and D, certain anticlines (a, b, c) and synclines (d) appear, whereas they are entirely absent in A and B. Contouring such as that done in C and D is not justified, and should be discouraged.

structures—sometimes very prominent structures—for which there is no real justification. Indeed the method is founded on the unsound premise that all the dips in the area mapped are

¹ Bibliog., RETTGER, R. E., 1929.

equal, which, of course, is almost certainly not the case. We believe that, although this type of contouring may occasionally represent conditions which are nearly true, as may subsequently be discovered by further accumulation of data, nevertheless it is not proper, especially in commercial mapping, since it has a distinct tendency to yield false impressions of structure and induce unwarranted expenditures of money. If such maps are made and utilized, they should by all means be accompanied by a statement clarifying their meaning and pointing out those features which may be exaggerated or untrue.

On the other hand, parallel contouring is justified, for it is founded directly and indirectly on facts. It is recognized as representing the best that a geologist can do when attempting to contour on relatively few data. In any event, a contour map must be read and interpreted with an open mind, for new data may necessitate altering the minor details of the contour lines. Usually the major features will persist through various modifications, provided correlations have been correct.

463. Comparison of Surface and Subsurface Maps; Convergence Maps.—On account of variations in the thickness of beds and unconformity between formations, surface structure may often differ considerably from the structure in deeper beds below. These differences are well brought out on structure contour maps. Figure 495 illustrates two maps, one of surface beds and the other of the strata a few hundred feet below. The discordance here is due to thinning of the beds westward within a conformable series. In Fig. 496, the difference between the two maps is due to unconformable relations between two series of strata.

Certain rules may be formulated in reference to the effects of convergence on local structures. Anticlinal axes transverse to the direction of general convergence are shifted *toward* the direction of this convergence in successively lower beds. Thus, if the convergence between two beds, *A* and *B*, several hundred feet apart, is westward, the axis of a transverse anticline in *B*, the lower bed, will be west of the axis of the same anticline in *A*. Synclinal axes under similar conditions are shifted *away* from




FIG. 495.—Structure contour maps of an area in which there is westward convergence between the beds in a conformable series. Figure A shows the surface structure. Figure B shows the subsurface structure as mapped on a key bed directly below the area of Fig. A. The interval between the key beds of the two maps increases about 40 ft from east to west across the area.




FIG. 496.—Structure contour maps of an area in which there is convergence between two unconformable series of strata. Figure A illustrates the structure of the exposed beds and Fig. B shows the subsurface structure of the older formation which lies unconformably below the series mapped in Fig. A.

the direction of convergence. In anticlines, synclines, monoclines, and structural terraces, dips *toward* the direction of convergence are lessened in the lower beds, and dips *away* from the




FIG. 497.—A. Contour map of surface structure in a region where oil (black dot) and gas (star) are produced. (The circles with four points represent "dry holes," or holes which yielded neither oil nor gas.)

B. Convergence map of same area as shown in A. The contours are lines of equal interval between two given horizons.




FIG. 498.—This figure shows Fig. 497, B, superposed on Fig. 497, A. At every point where the contours of the two maps intersect, the difference between the elevations of the intersecting contours is calculated and recorded.

FIG. 499.—Contour map of the deep horizon in the area mapped in Figs. 497 and 498. The contours here are drawn through the intersection points of the contours as established in Fig. 498.

convergence are steepened in the lower beds. In either case, low dips in the upper strata may be reversed in the lower strata (Fig. 501).

Where there is thinning between two horizons in a stratified series of rocks, and the approximate amount of this thinning is

known, structures in the upper series of beds may be projected down into the lower series by means of a *convergence map* (or *isopachous map*). Figures 497 to 499 illustrate the use of a convergence map. Figure 497, A, is a contour map of the surface




FIG. 500.—A. Surface contour map of an anticlinal nose. From data obtained in several wells in the district, it is known that the upper series which has an average southeastward dip of 15 ft. per mile, lies unconformably on a lower series which dips nearly due westward 30 ft. per mile. From these dips, the convergence of these formations is estimated to be about 45 ft. per mile S. 70° E. Lines of equal average interval, showing this convergence, are drawn straight across maps A and B. At each intersection point of these lines with the contours in A the interval is calculated. The quantities obtained are transferred to B, in the same relative positions, and they are then contoured with the result shown in B. In other words, B represents a contour map of the deep-lying formation, unconformably below the beds contoured in A. Observe that nothing is left, in B, of the structure in A, except a slight terrace effect.

structure in a certain region. Figure 497, B, is a convergence map of the same region, showing the rate and direction of thinning (convergence) between two given horizons as determined by the records of wells or by measurement of exposed strata. By superposing the convergence map (drawn on tracing paper) upon the surface structure map (Fig. 498) elevations on the deep horizon may be marked at every point where a convergence con-

tour (*isochore* meaning "equal interval," or *isopach*, meaning "equal thickness") crosses a surface structure contour. For instance, if the convergence line showing an interval of 600 ft. between the two given horizons crosses the surface structure contour of 1,040 ft., the elevation of the deep horizon at the point of intersection of these two lines (a, Fig. 498) is 1,040




FIG. 501.—Effect of convergence of beds on structure. The section (B) is drawn along ST as shown on the map (A). The key horizon contoured on the map is shown by the upper curved line in the section. This horizon has nearly 200 ft. of closure, but, due to westward convergence in the underlying strata, this closure becomes less with depth until it disappears, and, instead, there is a terrace (lower curved line in the section). Length of section about $3\frac{1}{2}$ miles.

ft. - 600 ft. = 440 ft. After the elevations have been established in this manner on the deep horizon, contours are drawn in reference to these points (Fig. 499).¹

The deep horizon maps in Figs. 495, B, 496, B, and 499 are decidedly similar to the shallow horizon maps of the same areas (495, A, 496, A, and 455, A, respectively); but it is important to note that such close similarity does not always occur. For

¹ Two excellent papers referring to convergence have been published by Corbett and Levorsen. Bibliog., CORBETT, C. S., 1919, and A. I. LEVORSEN, 1927.

example, compare Fig. 500, A and B, and Fig. 501, A and B. Also observe that, unless strata have low dips—let us say of 5° or less—errors may result from the fact that the distance between the top and bottom of a bed, as measured in a bore-hole, may not represent true thickness (Fig. 502).

464. Effects of Crookedness of Bore-holes on Subsurface Mapping. The subject of crooked holes has been touched upon in Art. 434. We wish now to point out some of the errors in interpretation of subsurface conditions which may be occasioned by the false assumption that holes, actually inclined, are vertical.




FIG. 502 — Sections to illustrate errors in measuring thickness of formations in holes (*s* and *t*) where dips are relatively steep. *ab* and *ce* are true thicknesses. *ed* is an incorrect thickness measured down from *t* to *d* in hole *s*. In A, *ce* actually equals *ab* but *ed* is much greater than *ab*, giving the impression that the formation thickens from hole *t* to hole *s*. In B, there is actual thinning of the formation from *t* to *s* but *ed* being equal to *ab* gives no clue to this thinning.

Figure 503 illustrates a possible spacing of the points at which six holes, located 660 ft. apart on the surface of the ground, encountered the top of a certain stratum, *S*. The arrows show the direction of drift of these holes, the horizontal migration being indicated in each case beside the arrow. If the facts of deviation of these holes were not known, and the holes were assumed to be vertical, the data (elevations, etc.) on *S* would be incorrectly recorded on a map at the points *A* to *F*, instead of at *A'* to *F'* where they really belong. It is not difficult to imagine how misinterpretations of this kind may lead to errors in contouring subsurface geologic structure, in estimating per-acre yields of oil from a given property, in trying to solve problems of porosity and rate of flow of fluids between wells, and so on. Further-




FIG. 503.—Map of six well locations (A to F) on the surface of the ground (double circles). On the assumption that these holes were drilled off the vertical in the directions indicated by the arrows and a horizontal distance shown beside the arrows, the bottoms of the holes would be at points A' to F', respectively. Figures 503 to 507, inclusive, are reprinted from the Bulletin of the American Association of Petroleum Geologists. (Bibliog., Lahee, F. H., 1929, b.)

more, in regard to contour maps, there is a vertical error as well as a horizontal error in the plotting of any data from a crooked hole. No doubt in a majority of wells, taking into consideration all regions where holes are drilled for oil, gas, or water, this vertical discrepancy is small; but it may be large without any suggestion in the drilling that the hole is going off plumb.




FIG. 504.—Vertical section to illustrate misinterpretation of subsurface geologic data from crooked holes.

Figures 504–507 represent other anomalies and misinterpretations which may result from deviation of holes from the vertical.

In Fig. 504, “five holes are shown in vertical section. From measurements in these holes, from the surface down to the key horizon, *RST*, the structure represented by line *VW* was inferred. Actually, however, the structure was that indicated by the full line, *RST*. The misinterpretation was due principally to the abnormal depth at which holes *B* and *C* reached the key horizon . . . ”

Figure 505 "is another example of false interpretation. Here the excessive depth of hole *B*, at the key horizon, *RMW*, led to the conclusion that a fault of approximately 400 ft. displacement lay between *B* and *C*, the strata on both sides of the fault having a dip toward *W*. Yet actually *RMW* is an unbroken anticline."




FIG. 505.—Hypothetical vertical section showing how incorrect geological structure may be inferred from data from wells not drilled vertical.

In Fig. 506, "C, between two wells, *B* and *D*, should have produced oil; and *G* should have been dry. As shown, however, *C* would have been a puzzle since it was dry and apparently missed the 'pay' altogether. *G* was a surprise in that it was a much better well than *F* . . . "

Figure 507 "illustrates one side of a salt dome in cross section. If the four wells had been vertical, *A* would have been a deep edge

well; *B* and *C* would have been good producers; and *D* would have gone into salt several hundred feet above the 'pay.' Due to the deviation of these holes, *C* was an edge well, *A* and *D* were big producers, and *B*, between two oil wells, went into salt."¹




FIG. 506.—Vertical section of an anticline carrying oil (black) on its crest. A to G represent wells drilled for the oil, but not all drilled vertical. (See text.)

These examples are sufficient. They emphasize the need for making daily checks on the verticality of holes that are in process of drilling, and the importance of surveying completed holes for their true position underground, when they are known to be more than a few degrees off the vertical. If their courses in three dimensions are determined, the geologic data which they reveal can be plotted in correct relations.

¹ Bibliog., LAHRE, F. H., 1929 (b), pp. 1129, 1133.

CONTOUR MAPS OTHER THAN STRUCTURE CONTOUR MAPS

465. Examples Mentioned.—Without entering into detail, we may say that the method of drawing lines or contours through mapped points of equal value is applied to many other features besides structure. For instance, contour maps have been made showing lines of equal magnetic anomaly (332), lines of equal chlorine content in water, lines of equal Baumé gravity of oil, lines of equal gasoline content in natural gas, lines of equal thickness of a particular bed within a stratified series, and so on. With the explanation of ordinary structure maps clearly in mind, the student should be able to prepare any kind of contour map to solve his own problems.

BLOCK DIAGRAMS

466. Definitions.—One of the most successful methods of geologic illustration, both for popular and for scientific demonstration, is the so-called *block diagram*. In brief this is a view of an imaginary rectangular block of the earth's crust. It is as if upon a rectangular block of wood, let us say, two geologic sections had been drawn on two adjoining sides and a map on the top face, and then the block itself had been sketched in a position such that these three faces were visible to the eye (Fig. 83). Frequently the top surface is drawn as if it were a model of the topography, with all the hills and valleys (Figs. 146, 179 280, 328, etc.). There are, then, two varieties of block diagram.




FIG. 507.—Relations of crooked bore-holes to the salt plug of a salt dome.

For easy reference the term, *map block*, will be used for the kind with a flat top, and the term, *relief block*, for the kind that shows the topography. The first brings out the relations of geologic structures in normal planes, and the second, the relations between geologic structure and topography. Relief blocks are best constructed in perspective, but map blocks may be made in isometric or cabinet projection or in perspective (467). Like geologic sections and maps, a block diagram represents the




FIG. 508.—A rectangular block drawn in isometric projection (A), cabinet projection (B), angular perspective (C), and parallel perspective (D).

geology by different lines and patterns, less often by colors, and consequently it must have a legend.

467. Construction of Block Diagrams.—Before the geology can be depicted on a block diagram, the outlines of the block itself must be drawn. This may be done in isometric projection, in cabinet projection, or in perspective. Figure 508, A, illustrates the isometric projection, and Fig. 508, B, the cabinet projection, of the same rectangular parallelepiped. In each case lines parallel in the block are drawn parallel, vertical lines are drawn vertical, and equal lines (those with the same letter in Fig. 508) are equal in the diagram. In Fig. 508, A, the angles marked *x*

are each of them 120° , and measurements along any of the lines of the diagram are on the same scale. In Fig. 508, B, angle $x = 45^\circ$ and angle $y = 90^\circ$; measurements parallel to a and c are equal, but parallel to b the scale is one-half its value parallel to a and c ; that is, if an inch or a foot or a mile is measured off as an inch along a and c , the same distance is represented by $\frac{1}{2}$ in.




FIG. 509.—Block drawn in angular perspective, showing its relation to the horizon line, ab .

parallel to b . A very useful variety of cabinet projection is one in which angle x (Fig. 508, B) is 30° , angle y is 90° , parallel edges of the block are drawn parallel, and measurements in directions parallel to all the edges are on the same scale. In both isometric and cabinet projections, then, measurements of length can easily be made in directions parallel to the edges of the block.¹




FIG. 510.—Block drawn in parallel perspective, showing its relation to the horizon line, ab .

On the other hand, in a perspective sketch of a rectangular parallelopiped, equal parallel lines are seldom equal or parallel in the figure. Vertical lines are drawn vertical, but horizontal parallel lines generally converge toward the background in such a way that, when produced, they will all meet in a single point, and the several points in which different sets of horizontal lines meet are all on the same straight line, the *horizon line* (ab in Figs. 509, 510). If all sets of horizontal lines in the object meet

¹ Measurement of angles and distance in nonperspective blocks is explained by Ives (see Bibliog., IVES, RONALD L.).

in the horizon line, the perspective is angular (Figs. 508, C, and 509), but if one set of horizontal lines in the object is drawn in the plane of the picture, the perspective is parallel (Figs. 508, D, and 510). Parallel perspective differs from cabinet projection




FIG. 511.—Construction used for measurements on a block drawn in parallel perspective.

in that the edges marked *b* in D and B, Fig. 508, are parallel in the latter, but converge to a point on the horizon line in the former. Parallel perspective involves a certain amount of distortion, as may be seen in Fig. 508, D, for if a rectangular block

were looked at perpendicular to one of its faces its other sides would not be visible.

Measurements can be made on block diagrams in both parallel and angular perspective,¹ but with very much less facility than in cabinet and isometric projections. Let us consider an example of parallel perspective. Suppose that in Fig. 511, *ljkmnop* represents a rectangular block which is 3 ft. thick and 5 ft. square on its top. The construction of this part of the figure may be stated briefly as follows: *abcd* is the square top (or bottom) of the block as viewed from above, drawn to the scale of $\frac{1}{6}$ in. = 1 ft. Choose a point, *g*, for the *view point*. Produce *dc* a certain distance to the right to *c'*. Draw *ag* and *bg*. *ag* intersects *dc'* at *e*, and *bg* intersects *dc'* at *f*. Next draw *hi* parallel to *dc'* and at a convenient distance below *dc'*. Drop perpendiculars to *hi* from *d* and *c*, meeting *hi* in *j* and *k*, respectively. Mark off *lj* and *mk*, each $\frac{3}{6}$ in. long. Draw *lm*. Then *lmkj* represents the front face of the block constructed on the chosen scale. Through *g* draw a line, *c'v*, perpendicular to *dc'* and *hi*. On this line select a point, *s*, at a convenient distance above *hi*. From *l*, *m*, and *k*, draw lines to *s*. From *e* and *f* draw lines perpendicular to *hi*, intersecting *ls*, *ms*, and *ks*, in *n*, *o*, and *p*, respectively. Draw *no* and *op*. Then *noml* is the top, and *mopk* is the side, of the block, both seen in perspective.

Now, the reader will notice that although, in the block, *jk* = *lm* = *no*, and *lm* = *mo* = *kp*, and *lj* = *mk* = *op*, this is not true in the diagram. Evidently the same scale cannot be used for all edges. The front face is here made with both horizontal and vertical scales the same, i.e., $\frac{1}{6}$ in. = 1 ft. Because of foreshortening, 1 ft. must be represented by less than $\frac{1}{6}$ in. on edges *no* and *op*. To obtain the scale for these two edges, divide *no* into five equal parts and *op* into three equal parts. The divisions of *no* and *op* are equal.

As for edges *ln*, *mo*, and *kp*, each consists of five parts, and each part represents 1 ft. in the block, but in the figure these parts are necessarily smaller toward the background. They

¹ See Bibliog., SECRIST, MARK H.

are obtained thus: referring to Fig. 511 again, draw through *s* a line, *su*, parallel to *hi*, and through *l* and *o* draw a line intersecting *su* at *t*. From *v*, on *hi*, mark off a distance, *vw*, equal to $\frac{1}{6}$ in. (the unit of the scale) toward *k*, and draw *ws* and *wt*. *wt* intersects *sv* at *x*. From *x* draw a line parallel to *hi* and meeting *kp* in *z*. *kz* represents 1 ft. *xz* intersects *ws* at *y*. Draw *yt*. From the point of intersection of *yt* and *sv* draw a line parallel to *hi* until it meets *kp*. Proceed in this manner until *kp* has been divided into five unequal spaces, each representing a length of 1 ft. in the original block. The divisions of *mo* may be obtained by erecting perpendiculars to *hi* through the points fixed on *kp*, and the divisions of *ln* may be obtained by lines drawn parallel to *hi* from the points on *mo*.

For further discussion of scale in perspective blocks, both parallel and angular, the student may consult the article by Secrist, already cited.¹

With regard to the advantages and disadvantages of these methods of illustration, perspective drawing looks more natural than either kind of projection, but it greatly increases the difficulty of measuring distances. Therefore, cabinet or isometric projection should be employed when the block diagram is intended to facilitate computations (see figures in Chapter XXI). Of the two, cabinet is preferable to isometric projection. For geologic illustration parallel perspective has a distinct advantage over angular perspective since it shows the structures in their true relations on at least one face, the front one.

Having completed the outline of the block, the next thing to do is to decide upon its orientation, or, rather, the orientation of the geology to be indicated upon it. A good rule to follow is, let the front of the block be perpendicular or parallel to some important structure. Thus, it is well to make the front face normal to the axis of a fold or normal to the strike of a fault, bed, or dike, on any of which measurements are to be computed.

When you have determined the orientation of the block, you are ready for the third stage. This consists of sketching in the

¹See bibliog.

geology and, on a relief block, the topography. The sides or vertical faces of the block are filled in first, and then the top surface. For any block in cabinet projection or in parallel perspective, complete the front face, which is parallel to the plane of the paper, exactly as you would a geologic section. If the finished diagram is to be a map block, this front face is treated as a rectangular base (449); if a relief block, it is treated as a profile base (450).

In any block diagram, for sides not parallel to the plane of the paper begin by making a preliminary true geologic section on a rectangular base or on a profile base according as the figure is to be a map block or a relief block, respectively. Do not complete this preliminary section; merely carry it far enough to get the locations of important points, and then transfer these points to their correct places on the side of the block diagram. In transferring, remember the rules for measurement in cabinet and isometric projection and in perspective. When the geologist has become proficient in making block diagrams, he seldom needs to construct these preliminary sections unless great accuracy is requisite. He is able to draw the geologic structure directly on the sides of the block in spite of the distortion of projection or perspective.

After the sides of the diagram are finished, the positions of structures and boundaries on its top surface may be obtained from points in the upper edges of the side faces. If it is a map block, this is fairly easy; but if it is a relief block, the topography is difficult to sketch properly. Indeed, good execution requires a true sense of proportions.

468. Requisite Data for a Completed Block Diagram.—A block diagram should have a legend arranged in the same way as for geologic maps and sections. The directions of the block's upper edges must be indicated. This may be done either by lettering the front corners with the appropriate compass points, or, if an edge lies in a north-south position, by drawing an arrow, pointing north, parallel to this edge (Fig. 132). Isometric and cabinet projections should be accompanied by the adopted

scales. For blocks in parallel perspective the scale for the front face should be indicated. A general idea of the horizontal scale in perspective may be given by labelling various known localities, such as lakes, towns, hills, etc., on the upper surface.




FIG. 512.—Construction of a skeleton diagram. (See text.)

SKELETON DIAGRAMS

469. Definition and Description.—Skeleton diagrams are made to show the probable relations of geologic structures inside the space of a block. They are essentially sketches of section models and peg models.¹ They are drawn to scale in their true field

¹ Section models are constructed of parallel or intersecting sections, usually on glass, but sometimes made of wire. These sections are prepared and spaced to scale. Peg models are groups of wooden sticks made to

relations, on the principle of block diagram construction (466-468). In Fig. 512 each side of the block is supposed to represent a distance of 1 mile. The plane, *bcd*, is taken for sea




FIG. 513.—Skeleton diagram showing structure on the oil pay sand in a certain region. The upright columns represent holes drilled for oil. The short cross line near the upper part of each hole marks the point where the sea-level plane, *bcd*, intersects the hole. A network of lines is drawn from well to well, connecting the top of the pay sand near the bottom of each well. These lines are made heavy where they connect rows of wells parallel to the front face of the diagram. These heavy lines, *hi*, *jk*, *lm*, *no* may be regarded as vertical sections of the pay sand. Essentially, therefore, the diagram illustrates an anticline, trending about N. 10° or 20° E., with a steep east dip and a gentle west dip.

level. The site of each well is plotted by reference to the three coördinates which correspond to the three edges of the block, thus: well *a* is 2,310 ft. east of edge *bc*, 990 ft. north of *cd*, represent well logs, and placed, according to scale, in an upright position on a horizontal wooden base.

and its elevation is 750 ft. above sea level. To find the site of this well, scale off $cf = 2,310$ ft. from c on cd ; then scale off $fg = 990$ ft. northward (parallel to edge bc) from f ; and then $ga = 750$ ft. vertically up from g . From a plot the log of this well downward and on the scale of the block. All other wells are similarly located and their logs plotted graphically. After this has been done, lines may be drawn connecting points at any given horizon as shown in the different logs.

Such blocks may be used for various purposes. For example, in oil fields, if the pay sands and water sands are plotted (Fig. 513), the depths at which these horizons are likely to be encountered in drilling other wells can be calculated, provided the locations and elevations of such new wells are known.

SERIAL DIAGRAMS

470. Use and Character.—Geologic sections, maps, or block diagrams are sometimes prepared in series to show the successive stages in the development of a structure or in the geologic history of a region (Figs. 113, 214, 215). Serial diagrams of this sort are especially useful for illustrating faulting. For example, a rock mass is represented in the first figure before faulting; in the second, after the displacement, but before erosion has reduced the upthrust block; and in the third, after erosion has brought the region to its present aspect. In each of Figs. 184–194, the second and third stages are drawn, but the first is omitted. This method is, of course, quite unnatural since, under ordinary circumstances, denudation more nearly keeps pace with faulting (179).

COLUMNAR SECTIONS

471. Definition.—A *columnar section*, or *geologic column* (Fig. 514), is made to show the sequence and original stratigraphic relations of the formations in a region. The height of each formation in the column represents the approximate relative thickness of this formation. The column cannot be drawn absolutely to scale since the formations vary in thickness




FIG. 514.—Example of a columnar section. (Van Horn Folio, No. 194, U.S.G.S., 1914.)
The rocks listed in the column are found in the region mapped for the folio.

from place to place. If the strata are inclined or folded, the thickness of each member must be computed (**486**). In this respect a columnar section differs from a well log, unless the well penetrates horizontal strata.

PLANS, SKETCHES, AND PHOTOGRAPHS

472. Requisite Data for Plans, Sketches, and Photographs.

Every plan, sketch, and photograph, which illustrates geologic phenomena should be accompanied by a scale and compass directions. The latter are most readily noted by stating the direction in which the observer was looking in making the picture. Scale, in photographs, is often given by including within the view a ruler, hammer, or some other article of known dimensions. Plans and sketches may be treated like maps and sections. Locality should also be mentioned, and if any conventional signs are employed these are to be tabulated in a legend.

CHAPTER XX

INTERPRETATION OF GEOLOGIC MAPS

473. Significant Features on Geologic Maps.—From an examination of a geologic map a great deal may often be learned of the geologic structure, provided the topography is shown by contours. In general three things must be considered, namely, the contours, the outcrop areas marked with different colors or patterns to represent different rocks, and the boundary lines between these areas. Contours have been discussed in Chapter XIII. Outcrop areas and boundary lines will be treated in the following paragraphs.

474. Outcrop Areas.—For the interpretation of a geologic map one should begin by ascertaining the meaning of the colors or patterns of the different outcrop areas. From the legend one should find out which colors or patterns are for igneous rocks, which for sedimentary rocks, and which for metamorphic rocks, and wherever the map shows that two rock bodies are in contact, their relative ages should be determined, also from the legend. For this purpose the geologic time scale must be known (Appendix I). The forms of the outcrop areas, being consequent upon the trends of the inclosing lines, may be described under the head of boundaries.

475. Boundaries of Outcrop Areas.—Geologic boundary lines on maps represent the exposed edges of contacts, such as surfaces between conformable strata, surfaces of unconformity, igneous contacts, and faults. Rules pertaining to the nature of these lines, as controlled by topography, have been stated in Arts. 174 and 439. In the present connection the rules may be reversed: (1) if the outcrop of a surface does not cross contours, the surface is horizontal (Fig. 447); (2) if this outcrop line is

straight and has no fixed relation to the contours, the surface is vertical or dips steeply (Fig. 448); (3) if the outcrop line has a sinuous course and intersects the contours, the surface is moderately inclined. In the latter case the line has elbow-like bends which point down the dip in the valleys (Figs. 449, 450), unless the inclination of the given surface is in the same direction as, but is less than, the slope of the valley floor (Fig. 451). The





FIG. 515.—Method of computing the strike and dip of an inclined layer by reference to its outcrop on a contour map.

longer and more acute the bends are, the lower is the dip of the inclined surface. These statements are based on the assumption that the given surface is essentially flat. If it is undulating or otherwise irregular its outcrop is likewise irregular, but with a little experience one can distinguish the disorderly bends and angles of a line of this sort from the more uniform curves due to the topographic intersection of a flat surface.

The strike of an inclined flat surface may be obtained by drawing a straight line between two points of intersection of a given contour with the outcrop of the surface (ab in Fig. 515). The approximate dip of such a surface may be found thus: from the intersection, c (Fig. 515, A), of the outcrop of the surface with any contour except that containing points a and b , draw a line, cd , perpendicular to ab . In Fig. 515, A, the second contour below a is used. Lay off a horizontal line, xy (Fig. 515, B) equal to $2cd^1$ and at the end for the higher contour (y , corresponding to d in Fig. 515, A) erect yz perpendicular to xy , making the length of yz four times¹ the contour interval. These lines, xy

¹ For convenience, here, Fig. 515, B, is enlarged twice.

and yz , must be drawn to natural scale. Complete the right triangle xyz . Angle zry will then be the dip of the inclined surface, and this angle may be calculated since xy can be measured on the map and zy is known. It is hardly necessary to remark that accuracy in the result depends not only upon the flatness of the surface, but also upon the care with which the map was made.

476. Strike Symbols.—On outcrop maps of folded strata the general trend of the strikes may give one an idea of the structure. Three varieties of strike arrangement are noted below. If




FIG. 516.—Strike and dip symbols on outcrop maps, indicating pitching folds in A and a dome fold in B.

several possible interpretations are mentioned, the correct one can be determined by a knowledge of the dip directions at the several outcrops.

1. Strikes are straight and parallel. The folding may be homoclinal, monoclinal, synclinal, or anticlinal. If anticlinal or synclinal, the fold axes are horizontal (Fig. 459, A, B, C).

2. Strikes converge alternately, first in one direction and then in the opposite direction, and at the angles of convergence they swing round sharply or broadly (Fig. 516, A). The structure consists of pitching anticlines and synclines.

3. Strikes run round in a complete curve which may be rudely circular or oval. The structure is a dome fold (Fig. 516, B) or a basin fold.

477. Conformable Strata.¹—Unless the dip of a stratified series exactly coincides with the slope of the ground—an exceed-

¹ See also pages 630 to 631.

ingly rare condition—the beds are exposed in belts. The two edges of any belt on the map are the outcrops of the upper and lower surfaces of a stratum, and for each belt these lines, in their relations to the contours conform with the rules given in Art. 475. When the top and bottom surfaces of a given bed are approximately parallel, as they often are, the trend of the outcrop belt as a whole is naturally governed by these same rules. The breadth of the belt varies according to the dip of the stratum and the slope of the land (173). To facilitate the interpretation of geologic maps of conformable strata, the following key is given.

KEY FOR THE INTERPRETATION OF MAPS OF CONFORMABLE STRATA

1. The color or pattern used on the map indicates—that only one stratum outcrops over a broad area.

- a. The topographic relief is low and the land surface is essentially horizontal.

The beds are probably horizontal.

- b. The relief is low and the land surface as a whole has a definite slope.

The beds dip with the surface of the ground.

- c. There is considerable relief.

The exposed stratum is essentially horizontal and is at least as thick as the measure of the relief (Fig. 517).



FIG. 517.—Profile section showing the relation between the thickness of a stratum (lined) and the topographic relief.

2. Different strata outcrop in relatively straight, parallel belts.

- A. The beds are exposed in regular sequence across the strike.

- a. The land surface is a nearly flat, horizontal plain.

The beds are inclined or vertical.

- b. The land surface is a nearly even plain which has a definite inclination.

The beds are horizontal, inclined, or vertical. If they are inclined, their dip is not parallel to the slope of the ground.

The relief is marked and may be rugged (Fig. 518). In case the topography consists of parallel ridges and valleys, the outcrop belts show no deviation in transverse valleys that may interrupt the continuity of the ridges.

The strata are vertical.




FIG. 518.—Geologic map of vertical strata, *a, b, d, e*. Contour interval, 20 ft.




FIG. 519.—Geologic map of folded strata, *a, b, c, d*. *a* outcrops in an anticline, and *d* in synclines. Which is the oldest bed shown? the youngest bed? Note how the contacts between strata bend in the direction of the dip in the valleys (see streams). Contours not shown.

- d. The relief is marked and the topography consists of parallel ridges and valleys. In transverse valleys the outcrop belts make sharp elbow-like bends.

The beds are inclined (Cf. Art. 475).

- B. Across the strike the stratigraphic succession is alternately normal and then reversed. Thus, if the digits, 1, 2, 3, and 4, stand for the beds in the sequence of their deposition, the order of exposure may be, 1, 2, 3, 4, 4, 3, 2, 1, or it may be, 4, 3, 2, 1, 1, 2, 3, 4.
- a. The relief may be low, or the topography may consist of parallel ridges and valleys which coincide pretty closely with the outcrop belts (Fig. 519).

The structure is anticlinal if older beds are flanked on both sides by younger beds, and it is synclinal if younger beds lie between older ones. Variations in the width of these belts may point: (1) to symmetrical folds in which opposite limbs are exposed on a uniform slope or on slopes of different inclinations; or (2) to asymmetrical folds outcropping on a surface of low relief and of no or uniform inclination (173).

3. Different strata appear in sinuous or zigzag belts.

- a. The relief is considerable. The boundaries between strata are roughly parallel to the contours, following these up valleys and thus giving a treelike, branching, or *dendritic* pattern to the rock distribution on the map (Fig. 520). When traced up the valleys, the belts are seen to make elbow-like turns which point upstream. Followed down the valleys, the same belts bend round projecting spurs of the uplands, here pointing down the slope.

The beds are horizontal or very nearly so.

- b. The topography is strongly rolling or rugged. The boundaries between adjacent strata cross the contours. The turns of the belts are situated on the valley floors and on the upland spurs. In the valleys the bends are convex toward younger beds, and on the spurs, toward older beds, but whether on spurs or in valleys, the convexity may point up the slope or down the slope.

The beds are inclined. The turns in the belts are convex down the dip in the valleys and up the dip on the spurs, provided always that the dip is greater than the inclination of the ground (Cf. Fig. 519).

- c. The relief may be low or considerable. In the latter case the hills are generally long ridges which trend parallel to the outcrop belts. The boundaries between adjacent strata are roughly parallel to the contours in the valleys which are parallel to the ridges (longitudinal valleys), but they cross the contours in the valleys that are transverse to the ridges (transverse valleys).

The strata are folded in pitching anticlines and synclines. Older beds outcrop between younger beds in anticlines; *vice versa* in synclines. In anticlines the beds

are convex down the pitch; in synclines, up the pitch. At the sharp bends the ridges usually have a gentle slope in the direction of the pitch and a steep slope on the opposite side of the crest.

4. Different strata appear in roughly concentric closed belts.

- a. The relief is considerable. The boundaries between strata are parallel to the contours. The closed belts appear only in isolated hills. Elsewhere on the map, in valleys and on spurs, the dendritic pattern prevails (Fig. 520).




FIG. 520.—Geologic map of horizontal strata, *a, b, c, d, e, f*. Which is the oldest bed shown? which the youngest? In the northwest corner of the map is a mesa. Contour interval, 100 ft.

The strata are nearly or quite horizontal (Cf. 3, a).

- b. The relief is low or considerable. If the latter, the uplands are concentric ridges parallel to the outcrop belts. The boundaries between adjacent strata are about parallel to the contours in longitudinal valleys, but they cross the contours in transverse valleys.

The structure is that of a basin fold if the strata are successively older outward in all directions from the center of the curving belts and if the boundary lines bend inward in the transverse valleys; and the structure is that of a dome fold if the strata are successively younger outward and if the boundary lines bend outward in the transverse valleys.

5. An outcrop belt, whether continuous or interrupted, becomes gradually narrower and finally disappears.

This signifies that the bed represented by this belt has thinned out to an edge. Do not confuse this phenomenon with the narrowing of a belt which passes on to the face of a steep slope or a cliff, nor with the abrupt termination of an outcrop belt at a fault, an igneous contact, or a line of unconformity.

478. Igneous Rocks.—Since sills and flows are like strata in their field relations, they also look like strata on geologic maps. They may be distinguished by their colors or patterns by referring to the legend. Most of the cases cited for stratified rocks in the preceding article are applicable to eruptive sheets. Dikes, too, have their outcrop belts controlled by the topography in




FIG. 521.--Geologic map of a batholithic rock (blank) and its country rock (lined). *p*, roof pendant or large inclusion; *c*, cupola.

the same manner as sills, flows, and strata. They usually dip pretty steeply. They are readily distinguished by their cross-cutting relations to the adjacent rock bodies, and by reference to the legend.

Necks are comparatively small oval or circular areas, as indicated on maps, and it is not uncommon to see dikes radiating from them and also to find the remnants of flows

somewhere in the neighborhood. Volcanic cones are recognized by the fact that they consist of pyroclastic débris or of lava (see legend) and, when fresh, they often have craters. Laccoliths appear as larger closed areas surrounded by sediments which have an outward dip if the intrusive body is essentially horizontal. If the laccolith is inclined, its outcrop may be lenticular. Exposures of batholiths are usually of still greater extent and of very irregular form. The edges of the map area of a batholith commonly truncate the outcrop belts of adjacent older sedimentary rocks. Isolated patches of these older rocks within the confines of the batholithic area are roof pendants or large inclusions (141), and isolated areas of the batholithic rock in the older sediments outside the main boundary are cupolas or pipes (Fig. 521) (151).

479. Unconformities.—Unconformities are noted in their proper places in the legend. Of the types described in Arts. 75 and 76, disconformity is the hardest to detect on geologic maps. Its presence is indicated in the legend by the fact that formations which should come between the disconformable strata are wanting. Angular unconformity between two groups of stratified rocks appears on a geologic map as a line, regular or irregular, against which about the beds of one or both formations. Lines of unconformity of this sort may separate older bedrock from younger overlying surface deposits or lava sheets. Unconformity between an *intrusive* igneous rock and a body of any kind of igneous, sedimentary, or metamorphic rocks, may be mistaken for an intrusive contact. If the intrusive (A, Fig. 522) is older than the rocks on the other side of the doubtful line, this line (*no*, Fig. 522) is one of unconformity; but if the intrusive is younger, the line is an igneous contact. The relative ages can be obtained from the legend.

Unconformities and faults cannot be confused on a map because they are represented by lines of different weight (437).

480. Faults.—Before one can interpret the relations of a fault which is shown on a geologic map, one must secure all possible information on the characters, structures, and relative ages of the rocks in the two contiguous fault blocks. These facts are to be sought by aid of the statements made in Arts. 475 and 477–479. The next step is to ascertain the attitude of the fault. For this see Art. 475. Ordinarily a fault with a low dip, and therefore a highly sinuous exposure where the relief is marked, is an overthrust (Fig. 523). In this case there may be associated isolated areas, each entirely inclosed within a fault line. Such an area is a *fault inlier* if the rocks within the closed fault line are younger




FIG. 522.—Geologic map of a regular contact, *no*, between an intrusive rock, A, and a body of sedimentary rocks, B. If A is younger than B, A is intrusive into B and *no* is an igneous contact; but if A is older than B, B was laid down unconformably on A and *no* is a line of unconformity.

than the rocks outside, and it is a *fault outlier* if the opposite condition holds (206) (Fig. 523).

Having determined the general attitude of a fault and the relations of the rocks on either side of it, we may proceed to classify it. If the fault is vertical, younger rocks are exposed at a given elevation near the fault line in the downthrown block. If the fault is inclined, younger rocks are exposed in the block




FIG. 523.—Geologic map of a region where an overthrust fault is exposed. Older rocks, stippled; younger rocks, blank. All the boundaries between these two formations are fault lines. *a*, fault outlier; *b*, fault inlier. The main NE.-SW. fault line dips southeastward. How may this fact be ascertained from the map?

toward which the fault dips in the case of a normal fault, and in the block away from which the fault dips in the case of a reverse fault. These statements refer to dip-slip and oblique-slip faults. Strike faults, dip faults, and diagonal faults which dislocate stratified rocks can be recognized at a glance.

With regard to offset, repetition and omission, the reader is referred to Arts. 184, 192, 194, and 195, where many of the rules laid down for the field interpretation of faults will be found to be applicable to the interpretation of mapped faults.

A word may be said of the appearance of faulted synclines and anticlines which have been truncated by erosion. The effect of dip faults and diagonal faults upon such folds is to increase the perpendicular distance between the outcropping edges of a stratum on opposite limbs of an open syncline (*s*, Fig. 524), and to decrease this distance in an open anticline (*a*, Fig. 524), always on the side of the downthrown block. From the map it is possible to tell which is the downthrown block if the nature of the folding is known. or, on the other hand, to ascertain the nature of the folding if the relative displacement is known.

481. Geologic History.—In the interpretation of geologic maps, one should be able not only to decipher the structural conditions, but also to read the geologic history represented on

them. Every geologic map shows certain features which, if properly understood, can be described in the chronological order in which they originated. The same may be said of geologic sections and block diagrams. Take Fig. 525 for example. Here the strata *f* and *g* dip gently southwestward, as shown by the bends of their contact lines at the streams. This series, *f* and *g*, is overlain unconformably by *h*, for this stratum occurs only on the uplands, whereas *f* and *g* outcrop as low as the stream channels, and *h* apparently conceals *f* and *g* (see near *x*, Fig. 525).




FIG. 524.—Geologic map of folded beds dislocated by a transverse dip fault. *s*, syncline; *a*, anticline.

Furthermore, the legend indicates that *h* is younger than *f* and *g*. In the northern part of the map a folded series of strata is seen to be overlain unconformably by the series *f* and *g* (see north contact line of *f* and refer to legend). This old series, *a* to *e*, is folded in a syncline, a fact which is demonstrated by the sequence of the outcropping belts of rock (younger between older) and by the bends of the contacts at the streams. The two stratified formations, *f* plus *g* and *a* to *e*, were faulted.

The geologic history of this area is therefore as follows: *a*, *b*, *c*, *d*, and *e*, were deposited in the order named. Subsequently these strata were folded and then laid bare by erosion, these processes probably consuming a long period of time. Upon their truncated edges, beds *f* and *g* were laid down in a transgressing sea. These two formations, *f* plus *g* and *a* to *e*, were broken by a vertical, or nearly vertical, fault. Erosion succeeded the faulting, thus finally exposing *f* and *g* and at least part of series

a to *e*. The next event was another invasion of the sea and the deposition of *h*. Later this was followed by uplift and erosion to the present conditions of exposure. Some conclusions might also be drawn as regards the physiographic history.

In the study of most published geologic maps, the history indicated will generally be much more complicated than the




FIG. 525.—Geologic map illustrating geologic history. (See text.) (In the legend, the formations are successively younger from below upward.)

outline just given. The student will do well to examine carefully the geologic maps accompanying folios published by the U. S. Geological Survey. One may approach the problem by listing all the events suggested and then considering the probable chronological order of each such event in reference to each of the others.

CHAPTER XXI

GEOLOGIC COMPUTATIONS

COMPUTATIONS IN GENERAL

482. Measurements and Computations Previously Discussed.

Certain problems of measurement and construction have been discussed in the preceding chapters. The more important of these may be listed here for reference, as follows: distance, on the surface of the ground, between two points on a contour map (300); inclination of a slope (302); correction of a compass traverse (374); depth of a horizon below the "key horizon" on a structure contour map (456); dip and strike of an inclined surface as determined from the outcrop line of the surface on a contour map (475).

483. Application of Computations Explained in the Present Chapter.—In geologic computations it is sometimes necessary to ascertain the direction and angle of inclination of the intersection of two planes which are not parallel, or the position of the point of intersection of a line and a plane. The intersecting planes may be two faults, a fault and the contact between two conformable beds, a bedding surface and the wall of a dike, etc. Accuracy in the results requires that such surfaces be as nearly plane as possible and that the lines be essentially straight. The methods of solving these two problems are outlined in Arts. **484** and **485**. Computations for thickness (486) are applicable to any inclined layers of uniform, or nearly uniform, thickness, such as strata, dikes, sills, veins, etc. Variations in thickness introduce errors into the results. Computations for the depth of a point in an inclined surface (487) may refer to the top or bottom surface of a bed, dike, sill, or vein, or to a fault or any

comparatively flat surface. Measurements of slip and shift (488) pertain only to faults.

SOLUTION OF PARTICULAR PROBLEMS

484. Line of Intersection of Two Planes, Not Parallel.—

Given: The dips and strikes of two intersecting planes.

Required: The angle of inclination and the direction of inclination of the intersection of these planes.

*Solution:*¹ Since strikes and compass directions are horizontal, the construction for this problem is assumed to be in a horizontal




FIG. 526.—Method of computing the angle and direction of inclination of the intersection of two planes. (After H. F. Reid.)

plane. Draw MN and OP (Fig. 526), the intersections (strike directions) of the given planes with any horizontal plane. MN and OP will be called *lines* when reference is made to the intersections, and *planes* when reference is made to the inclined planes passing through these intersections. From any point, a , on line MN erect a perpendicular, ab , in the direction of the dip of the plane MN . From a , also, draw a line, ac , making with ab an angle δ , equal to the dip of the plane MN . Through

¹ This problem and the next are modifications of those presented by Dr. Reid. Bibliog., Reid, H. F., 1909, pp. 173-176.

e, on *ab* at a convenient distance from line *MN* draw *df* through *ac* parallel to the line *MN*. The triangle *ead* may be regarded as a vertical triangle rotated about *ae* into a horizontal position. In its vertical position, *ad* would be in the plane *MN* and *de* would be vertical. *df* is the intersection of the plane *MN* and a horizontal plane which is at a depth, *de*, below the horizontal plane in which lines *MN* and *OP* are situated.

Use the same method of construction for *OP*, but draw the line *gh*, corresponding to *df*, parallel to line *OP*, and at such a distance from line *OP* that *gi* shall be equal to *de*. Then *df* and *gh* are, respectively, the intersections of planes *MN* and *OP* with a horizontal plane at a depth equal to *de* ($= gi$) below the plane of the figure; and *h*, the point of intersection of these lines, is also a point in the intersection of the given inclined planes. Therefore, a straight line through *h* and *k* will be the projection of the line of intersection of the inclined planes upon any horizontal plane. The direction of inclination of this line of intersection will be downward in the semicircle that contains the dip directions of the given planes. The amount of this inclination may be found thus: from *h* erect a line, *hl*, perpendicular to *hk* and equal to *de*. Draw *lk*. In right triangle *hlk*, $\angle lkh$ is the dip of the intersection of the inclined planes. $\angle lkh$ may be obtained from the equation, $\tan \angle lkh = lh/hk$, in which *lh* and *hk* are known.

Another method of solving this problem follows:¹

"1. Construct the angle *ACB* (Fig. 527), the sides of which have the directions of the strikes of the given planes, and produce one of the sides, as *AC*, so as to obtain the angle *BCD*, supplementary to the angle *ACB*.

"2. On *CD* lay off *CE*, the graphic tangent of the angle of dip of the plane whose strike is *AC* (either using a tangent scale for this purpose or else obtaining the value of the tangent from trigonometric tables and setting off this value according to any scale suited to the problem and the degree of accuracy required. The latter method is, in general, preferable, especially with very high

¹ After W. S. Tangier Smith, in personal communication.

angles of dip which are beyond the limit of the fixed tangent scale).

"3. On CB lay off (by the same scale) CF , the graphic tangent of the angle of dip of the plane whose strike is CB .

"4. Draw EF and, through C , the parallel line CH . CH is the required direction of inclination of the line of intersection of the two given planes.




FIG. 527.—Diagram for finding angle and direction of inclination of intersection of two planes not parallel.

"5. Draw CG perpendicular to EF . The length of this line when determined in degrees by means of the tangent scale used for plotting CE and CF , will give the required angle of inclination of the line of intersection of the given planes. This angle, it may be noted, is an apparent dip angle common to the two planes.

"By a slight modification of the method just given, the cotangents of the angles of dip may be used instead of the tangents in

solving this problem, although the solution is a little less simple when the cotangents are used. The cotangents are especially useful when the dip angles are large and a fixed tangent-cotangent scale is used.

"If the dips of the given planes do not exceed 10° , the numerical values of these angles may be used instead of the tangent values in solving this problem. This is of small importance, however, since intersecting planes, both with low angles of dip, rarely occur. On the other hand, if the dips of the given planes and the angle of inclination of their line of intersection are between 80° and 90° , the numerical values of the complements of the angles of dip may be used in place of the cotangent values in the cotangent method of solving the problem. The error involved in using numerical values instead of tangent or cotangent values is small, not to exceed a few minutes."

485. Point of Intersection between a Line and a Plane.

Given: The dip and strike of a plane and the angle and direction of inclination of a line not parallel to the plane.

Required: The point of intersection of the line and the plane.

Solution: Two cases are figured (Figs. 528, 529). The letters apply to both diagrams. MN is the trace of the given plane on a horizontal reference plane. MN will be used likewise to designate this plane. ST is the projection of the given line upon the reference plane. Through a , that point on ST in which the given line intersects the plane of reference, draw OP parallel to line MN . Let OP represent the trace of a plane containing the given line of which ST is the horizontal projection. From a draw ac making an angle with ST equal to the inclination of the given line. From any point, b , on ST draw bc perpendicular to ST ; bc is the depth of the given line below its horizontal projection, ST , at b . Draw af perpendicular to OP and MN , through a . Through b draw bd parallel to OP , intersecting af at d . From d lay off $de = bc$. Draw ae . Then $\angle dae$ is the inclination of the plane OP .

From f draw fg , making an angle with af (produced in Fig. 529) equal to the dip of the plane MN . fg must be drawn on




FIG. 528.—Method of computing the point of intersection of a line and a plane when the line and the plane are inclined in the same direction, the plane more steeply than the line.




FIG. 529.—Method of computing the point of intersection of a line and a plane when the plane and the line are inclined toward one another.

the side of line MN toward the dip of plane MN . In Fig. 528 the dip is on the right, and in Fig. 529 on the left, of MN . Produce ac until it meets fg at j . Through j draw kl parallel to line MN . Then kl is the projection, upon the horizontal reference plane,




FIG. 530.—Thickness of a dipping layer, the land surface being level.




FIG. 531.—Thickness of a dipping layer, the land surface sloping in a direction opposite to the dip of the layer.

of the line of intersection of planes OP and MN at the depth, kj , below k . The intersection of ST and kl , at w , is the projection, on the reference plane, of the intersection of the given line and the given plane.

486. Thickness of a Layer.—When an estimate is made of the thickness of a stratum, dike, vein, etc., the calculation is usually based upon a distance measured along a traverse perpendicular to the strike of the layer; that is to say, the breadth of outcrop must first be known. For folded beds, if the deformation is complex, the breadth of outcrop should be measured if possible along the axis of the fold rather than across the axis, for in this direction of least compression there is less likelihood of contortion and of other disturbing factors, and the results are less liable to error.




FIG. 532.—Thickness of a dipping layer, the land surface sloping in the same direction as the dip.

Thickness can be measured directly only when the surface of the ground or of an artificial excavation is perpendicular to the beds. In all other cases right angle computations must be made. Thus, in Fig. 530, ab is the breadth of outcrop and bc is the required thickness. Let the dip (here angle bac) be represented by δ . In triangle, abc , $\sin \delta = bc/ab$, and, therefore, $bc = ab \cdot \sin \delta$.

Two other cases are illustrated in Figs. 531 and 532. In Fig. 531 the strata dip 20° E. (δ) and the surface of the ground slopes 10° W. Call the latter, i . We want to find the thickness, bc .




FIG. 533.—Sketch map of traverse a, b, c, d , oblique to strike of beds exposed at these four points. For a section perpendicular to the strike (a'), the dips at a, c , and d are projected along the strike to a' at points a', c' , and d' , respectively.

For the solution of right triangle abc we must determine the angle bac . $\angle dac = 20^\circ = \delta$. $\angle bad = 10^\circ = i$. Therefore, $\delta + i = 20^\circ + 10^\circ = 30^\circ$. Then, as in the first example, $bc = ab \cdot \sin(\delta + i)$. In Fig. 532 the beds dip 40° E. and the ground slopes 10° in the same direction. The thickness, bc , is required. $\angle dab = i = 10^\circ$, the inclination of the ground, and $\angle dac = \delta = 40^\circ$, the dip. $\angle bac$ in right triangle $abc = \delta - i = 40^\circ - 10^\circ = 30^\circ$. Therefore, $bc = ab \cdot \sin(\delta - i)$.

If the traverse along which local measurements of dip and strike have been recorded is oblique to the general strike, the dip data should be projected along strike to a line perpendicular to strike, as in Fig. 533. Across wide areas with variations in strike and in direction of traverse, several such adjustments by projection may be desirable, each for a strip of the terrain examined, and then the results can be added together for the total thickness of strata traversed.

487. Depth of a Point in an Inclined Surface.

Another problem that must be solved by right triangles concerns the depth, below the surface of the ground, of a point in an inclined surface.

Again, the calculation is based upon the breadth of outcrop. The problem may be illustrated by three cases. In Fig. 534 the beds dip east at an angle of 25° ($\angle bac$). We wish to know the depth, bc , of the bedding surface outcropping at a below some point, b , on the ground surface. In right




FIG. 534.—Depth of an inclined surface, the land surface being level.

triangle abc , ab is known and $\tan \delta = \tan 25^\circ = bc/ab$. Therefore, $bc = ab \tan 25^\circ$.

In Fig. 535 the strata dip 25° E. and the ground slopes 15° W. ab is known. In triangle abd , $ad = ab \cdot \cos 15^\circ$. Also, $bd = ab \cdot \sin 15^\circ$. In triangle adc , $dc = ad \cdot \tan 25^\circ$. Therefore, $bc = (ab \cdot \sin i) + (ad \cdot \tan \delta)$, where i is the inclination of the ground and δ is the dip.

In Fig. 536 the ground slopes 10° W. and the beds dip 30° W. The depth of the bedding surface, ac , below a point, b , is required. ab is known. In triangle adb , $db = ab \cdot \sin 10^\circ = ab \cdot \sin i$ and $da = ab \cdot \cos 10^\circ$. In triangle adc , $dc = ad \cdot \tan 30^\circ = ad \cdot \tan \delta$. Therefore, $bc = dc - db = (ad \cdot \tan \delta) - (ab \cdot \sin i)$.




FIG. 535.—Depth of an inclined surface where the ground slopes in the opposite direction.




FIG. 536.—Depth of an inclined surface where the land slopes in the same direction.

In Appendix XVI will be found a table for computing depth and thickness.

Observe again (as in Art. 486) that if measurements in the field are made along a traverse oblique to the strike the dip data should be projected along strike to a line (or vertical section) perpendicular to strike for the solutions as given in Figs. 534 to 536.

488. Determination of Strike and Dip When the Elevations of Three Points in an Inclined Surface Are Given.—Let a , b , and c , Fig. 537, be three points at which the elevation of the flat upper surface of an inclined stratum is known. If the elevation at any two of these points is the same, the line between these two points is the strike and the direction of dip is along a line drawn from the third point normal to the strike line. The dip will be down toward the strike line if the third point is higher than the other two points, and it will be toward the third point if this point is lower than the other two points.

If all three points have different elevations, the strike and dip may be obtained graphically as follows: let *a* (Fig. 537) be the lowest point (200 ft.), *b* be the highest point (260 ft.), and *c* be of intermediate elevation (240 ft.). The directions are, from *a* to *b*, S. 30° E.; *b* to *c*, N. 75° E.; and *a* to *c*, S. 80° E. The distances between the stations are known. Having selected a convenient horizontal scale, plot these stations in their correct relative positions. Draw *ab*, the line connecting the lowest and highest points. At *b* erect a perpendicular to *ab*, and on it lay off *bd* = the difference in altitude between *a* and *b*, here 260 ft. — 200 ft. = 60 ft. This should be done on the same scale as the adopted horizontal scale. Lay off *de* = the difference of eleva-




FIG. 537.—Determination of dip and strike from three points in an inclined surface.

tion between *a* and *c*, here 240 ft. — 200 ft. = 40 ft., on the adopted scale. Draw *da* and, parallel to it, draw *ef*. Draw *fc*, which will be the line of strike of the stratum. From *b* draw a line perpendicular to *fc*, meeting *fc* at *g*. *bg* is the direction of dip. From *g* lay off *gh*, equal to the difference in altitude of *b* and *c*, here 260 ft. — 240 ft. = 20 ft. Draw *bh*. Angle *gbh* is the angle of dip. The direction of strike and dip and the angle of dip can be determined by measurement, since the diagram is drawn to scale in reference to north-south and east-west coordinates. *db* need not be perpendicular to *ab* for the solution of this problem.

Dr. W. S. Tangier Smith¹ has outlined a simple method for determining the strike in this problem, as follows:

¹ Personal communication.

"1. Having platted, on a map or a separate sheet, the three given points, *A*, *B*, and *C* (Fig. 538), *A* being the highest and *C* the lowest, measure, as accurately as possible, the distance between *A* and *C* on the plat. Let us suppose the measured distance to be 1.242 in.

"2. Determine the difference in elevation between *A* and *B*; also that between *A* and *C*. Express these two differences as a ratio, in fractional form, and reduce this ratio to its simplest terms. If, for example, the difference in elevation between *A* and *B* is 70 ft., and that between *A* and *C* is 230 ft., the ratio of these differences, expressed fractionally $\frac{70}{230}$ and reduced to simplest terms, is $\frac{7}{23}$.

"3. Multiply the measured distance between *A* and *C* by the fractional ratio obtained from the differences in elevation. The resulting distance, when laid off from *A*, along the line *AC* of the plat, will give the point *D*. Using the figures given above, the distance $AD = 1.242 \text{ in.} \times \frac{7}{23} = 0.378 \text{ in.}$

"4. *D* is the plat of a point lying in the given plane and having the same elevation as the point whose plat is *B*. The line *BD* will, therefore, be the required strike of the plane."

The following graphic method of obtaining the attitude of an inclined bed from three given points on the bed has been suggested by W. S. Tangier Smith as a modification of Moon's method.¹ For illustration of this problem, assume that the three points, *a*, *b*, and *c*, (as in Fig. 537), are on the top surface of a certain stratum where this stratum is intersected by three drill holes. Let the elevations of *a*, *b*, and *c*, be 830, 860, and 900 ft., respectively, above sea level. Each of these elevations was obtained by subtracting the depth of the stratum below the mouth of the well from the elevation of the mouth of the well.




FIG. 538.—Diagram for determining strike of a plane in which three points, not in same straight line, are known.

¹ Bibliog., Moon, F. W., 1913.

The sites of the wells are plotted to scale. Take the differences of elevation between the intermediate point, b , and the highest and lowest points, respectively. These differences are here 30 ft., $b - a$, and 40 ft., $c - b$. With compasses describe circles round the location points for a and c , using any convenient scale for the radii, and making the radius in each case proportional to the differences of elevation, reduced to lowest terms (*i.e.*, 3 and 4 in this example). Draw one (or both) of the *interior* tangents common to the two circles. Then, the intersection of the tangent (or tangents) with line ac will give point d . Line bd will be the required line of strike. How may the dip be found in feet per mile?

489. Determination of Strike and Dip from Two Components.

The geologist sometimes finds it necessary to determine true dip and strike from observations made on components of these quantities; in other words, true dip and strike, for one reason or another, may not be subject to direct measurement. Following are examples of graphic solutions of this problem:

1. Let us assume that the amount of inclination from the horizontal (*i.e.*, dip component) and the direction of this inclination are recorded, respectively, as 6° and N. 20° W., as measured on a certain horizon exposed on one side of an outcrop, and that the similar quantities are 8° and N. 60° E. on the same horizon on another face of the same outcrop. The same conditions might apply to a given stratum exposed at two widely separated outcrops, say on opposite sides of a valley, or of a ridge. To find the true dip and strike of the horizon (top or bottom of a bed, etc., etc.), proceed thus:¹

Lay off a long north-south line on a sheet of paper (Fig. 539, NS). At any convenient point, a , on this line, lay off with a protractor the lines am and ap with the bearings N. 20° W. and N. 60° E., respectively. At a draw perpendiculars to am and ap with the protractor, and on each lay off equal distances, ad and ae , any convenient length being used. From d lay off a line at an angle of 6° to am and intersecting am at b . From e lay off a line at an angle of 8° to ap , intersecting ap at c .

¹ Somewhat modified, after Kitson. See Bibliog., KITSON, H. W.

Draw bc , which is the line of strike of the inclined horizon. The strike of this horizon is the acute angle, Nob or coS , which may be measured with the protractor. Here it is $S. 28^\circ E.$

Draw af perpendicular to bc from a . At a draw a line ag , perpendicular to af , and lay off ag equal to ad . Draw fg . Then angle afg is the true angle of dip of the inclined horizon. As measured by protractor, this angle is here $9^\circ SW.$

Where the vertical angles of the components are small, a more accurate method is to lay off the natural cotangents of the vertical angles along lines am and ap , respectively, to a convenient scale, thus locating points b and c without drawing the perpendiculars ad , ae , and ag or platting the vertical angles. Then bc is drawn, and af is drawn perpendicular to bc . Thus, the natural cotangent of 6° is 9.5144; that of 8° is 7.1154. Therefore, scale off $ab = 9.5$ and $ac = 7.1$. With the same scale measure af , which is here 6.1, which is the natural cotangent of the true angle of dip, namely, just under 9° .¹

If dips are so low that they are recorded, not in degrees, but in feet per mile or as 1 ft. in so many feet, a method described by Rich² may be used. Let us suppose that field observations indicate a dip component of 1 ft. in 50 ft. in the direction $N. 30^\circ W.$ and another dip component, on the same horizon, of 1 ft. in 125 ft. in the direction, $N. 50^\circ E.$ (if the vertical difference in elevation is recorded as inches in so many feet, the ratio should be raised or lowered to the form 1 ft. in x ft.). The observations




FIG. 539.—Determination of strike and dip from two components where dips are measured in degrees.

¹ This method is described by Kitson. See Bibliog., *op. cit.*

² Bibliog., RICH, JOHN L., 1932. In a later note Rich credited this method to Prof. G. D. Harris (Am. Assoc. Petrol. Geols., *Bull.*, vol. 20, p. 1496, 1936).

are then plotted. From a convenient point, *a* (Fig. 540), on a north-south line (NS), draw a line, *am*, bearing N. 30° W. and, using any convenient scale, lay off on it a distance *ab* equal to 50 units. Draw a line *ap* and on this measure *ac*, equal to 125 units on the scale adopted. Draw *bc*, which is the true strike. Draw *ad* perpendicular to *bc* from *a*; *ad* is the direction of the true dip, the amount (angle) of which can be ascertained by scaling off the distance *ad*. This is 48. In other words, the true dip is 1 ft. in 48 ft. in a direction N. 17° W.

490. Slip and Shift of Faults.—A visible displacement between corresponding points in the broken sides of a faulted dike, vein, or other recognizable structure, is almost never the true displacement (net slip) of the fault, for there is small chance that a surface of erosion or an artificial section will coincide with the direction of the net slip which, as we have seen, may lie in any position in the fault surface. Consequently, direct measurement of net slip is seldom possible. Likewise, estimates of shift,




FIG. 540. — Determination of strike and dip from two components where dips are measured in feet per mile.

when based merely upon superficial evidence of dislocation, are apt to be incorrect. Yet in nearly all cases where fault measurements are to be made—and they must often be made—the net slip or the net shift is the quantity which must be obtained. This is done by the solution of right triangles, as will be explained below.

All fault computations depend upon facts observed and recorded in the field. When, for one reason or another, a geologist suspects the presence of a fault, he should search for the following: (1) the attitude of the faulted dike, bed, vein, igneous contact, etc.; (2) the measure of the visible displacement along an exposed portion of the fault; (3) the amount of gap, overlap,

repetition of strata, or omission of strata, if such relations exist (192, 194, 195); (4) the strike and dip of the fault; (5) the attitude of the fault with respect to the dislocated structures; (6) the direction of slipping of the blocks as indicated on the fault surface (188); (7) the direction of relative displacement of the blocks, *i.e.*, which seems to have moved in a certain direction with respect to the other.

With reference to the first two factors, dislocated structures may change their attitude in the immediate vicinity of the fault (191), and consequently, if displacement is visible *at the fault* it may be related to slip and not to shift; but shift is the quantity most desired and the one which will probably be obtained when the displacement is not visible along an exposed fault. This last remark applies especially to gap, overlap, repetition, and omission.

Since a majority of large important faults are more or less concealed, their attitudes with respect both to a horizontal plane and to the structures which they intersect must often be found in the field by indirect observations. If a fault can be approximately located at several points in a hill-and-valley topography, its line of outcrop can be plotted on a contour map and its attitude can be determined from its trace (475).

The sixth factor, the direction of slipping, is best ascertained by slickensides and other features on the fault surface (188), but these cannot always be seen. The same information can be secured in another way if two intersecting structures are cut by the fault. For example, let the structures be a dike and a bed. The attitudes of dike, bed, and fault, must have been recorded in the field. Construct a diagram as described in Art. 484, and so determine the position of the line of intersection of any chosen surfaces in the dike and the bed. Then find the two points at which the separated portions of this line—one in each block—meet the plane of the fault (485). These points, formerly in contact, will show by their mutual relation the direction and amount of the slip (or shift).

This method is not practicable when the fault is parallel to the line of intersection of the dislocated structures. Furthermore,

while it may give essentially correct results for slip or shift, as these have been defined, it is subject to misinterpretation as regards the true direction of slipping, just as are slickensides, if there was any change in this direction before the faulting ceased (188). It indicates merely the resultant of the combined movements.

We shall now suppose that enough data have been secured in the field to make possible the necessary computations. If the required quantities can be obtained by reference to but one right triangle, the figure should be drawn to scale; but if, as is usually the case, the problem demands the solution of two or more right triangles in different planes, these are best constructed in block diagrams made in cabinet or isometric projection (467). This is the most satisfactory method of visualizing the complex relations of faulted structures. This warning, however, must be heeded: in block diagrams *you cannot construct all angles and lines to scale on account of the unavoidable distortion due to projection.*

Below are outlined a few examples to illustrate the use of right triangles in solving fault problems. Although the first one might just as well be represented in a plane figure, it is shown in a block diagram so that it may be compared with the more involved cases that follow. In all these examples the surface of the ground (upper surface of the block) is regarded as horizontal and the fault surface is assumed to be flat.

1. *Given:* A vertical strike fault intersecting a series of beds which dip 40° due east. The displacement was vertical. A knowledge of the stratigraphic sequence in the region proves that a certain thickness of beds is missing.

Required: The net slip (or net shift).

Solution: Construct a block diagram in cabinet projection, having its front face in the plane of the dip of the beds (Fig. 541). Draw lines for the stratification and the fault. Field observations prove that the east block dropped with respect to the west block, for beds are missing on the east side of the fault trace. Draw a right triangle, *abc*, in which one leg, *bc*, meets the point

c , which was formerly in contact with a , in the west block. bc is the thickness of the missing beds and the hypotenuse, ac , is the required displacement. Since bc is known, and $\angle bac = \angle dac - \angle dab = 90^\circ - 40^\circ = 50^\circ$, ac may be found by the equation, $\sin \angle bac - \sin 50^\circ = bc/ac$.

2. *Given:* The same conditions as those stated for Problem 1, with the exception that the direction of slipping is inclined southward (forward in the block) at an angle of 30° to the horizon.




FIG. 541.—Diagram for finding the slip of a vertical dip-slip strike fault.




FIG. 542.—Diagram for finding the slip of a vertical oblique-slip strike fault.

Required: The net slip (or net shift).

Solution: Construct triangle abc (Fig. 542) as in Problem 1, and determine the length of ac . ae is the outcrop of the fault. Let f , in the west block, be the point which was once in contact with c in the east block. Draw cf . Then cf represents the amount of actual displacement. Triangle afc is a right triangle seen in projection, and $\angle afc = 30^\circ$. fc may be obtained from the equation, $\sin \angle afc = \sin 30^\circ = ac/fc$, for ac has been found already.

3. *Given:* A strike fault dipping 70° E. and intersecting a series of beds dipping 35° E. Field observations demonstrate repetition of beds in a strip having a breadth, B . Movement along the fault was in a direction inclined 20° S.

Required: The net slip (or net shift).

Solution: Having constructed, in cabinet projection, a block diagram showing the relations given (Fig. 543), first determine ac , the dip component of the net slip (or net shift), as follows: a ,

in the west block, and d , in the east block, are two points at the same horizon in the bedding. The distance between them, ad , is the breadth of outcrop, B , of the repeated strata. db , the thickness of the repeated beds, may be found from the equation, $\sin \angle dab = \sin 35^\circ = bd/ad$. Draw ac from a perpendicular to




FIG. 543.—Diagram for finding the slip of an inclined oblique-slip strike fault.

gc , the stratigraphic horizon in the west block that corresponds to ab in the east block. In triangles gae and abd , $ae = bd$. Therefore, in triangle aec , ae is known and $\angle ace = \angle bac = \angle dac - \angle dab = 70^\circ - 35^\circ = 35^\circ$. ac may be found from the equation, $\sin \angle ace = \sin 35^\circ = ae/ac$.




FIG. 544.—Diagram for finding the slip of an inclined dip-slip dip fault.

Now let f be a point in the west block that was formerly in contact with c in the east block. Then cf lies in the fault and is equal to the net slip (or net shift). Erect the line ch from c perpendicular to ad and draw hf . Triangle hfc is a right triangle seen in projection and $\angle hfc = 20^\circ$, the inclination of the direction of movement of the faulting. Likewise, triangle ahc is a right triangle in the plane of the front face of the block diagram.

In triangle ahc , $\angle hac = 70^\circ$ and ac has been determined. hc may be found from the equation, $\sin \angle hac = \sin 70^\circ = hc/ac$. In triangle hfc , fc may be obtained from the equation, $\sin \angle hfc = \sin 20^\circ = hc/fc$.

4. *Given:* A dip fault dipping 37° E. and intersecting a series of strata which dip 23° S. The fault is a dip-slip fault.

Required: The net slip (or net shift).

Solution: Construct a block diagram (Fig. 544) in cabinet projection as in the previous cases. Let ab be the net slip (or net shift), and let ac be the measurable offset. Draw bc , the trace of the bedding plane, bcd , on the fault plane, abc . Draw ce parallel to ab and draw be parallel to ac . From e draw ef perpendicular to cd , and from b draw bg perpendicular to ah . Draw gf and bf . In triangle bef , $be = ac$, which is known, and $\angle ebf = \angle bfg = 23^\circ$, the dip of the beds. $ef = be \cdot \tan \angle ebf$. In triangle cef , $\angle cef = 37^\circ$, the dip of the fault. Therefore, ce , the net slip (or net shift) $= ef / \sin \angle cef$.

CHAPTER XXII

PREPARATION OF GEOLOGIC REPORTS

THE REPORT AS A WHOLE

491. General Instructions.—Not only must the professional geologist be conversant with methods of research, but also he must be able to set forth the results of his work in good, concise English. The practice obtained in writing geologic reports in college courses is seldom long enough to be thorough. The student should therefore make the most of his opportunities while they last. He should plan his theses as if they were intended for publication, even though he may not actually contemplate publishing. The unavoidable differences between course theses and manuscripts for publication are very few indeed. They will be pointed out in the later pages of this chapter where detailed instructions are given for the preparation of reports.

Certain directions of general application may be noted in this place. Endeavor to use clear, idiomatic English. Avoid colloquial and slang phrases. Be heedful of punctuation and spelling. Remember that the words "data," "strata," and "phenomena" are plural forms of which the singular forms are "datum," "stratum," and "phenomenon" respectively. We say "data are," "strata are," "phenomena are"; and a "datum is," "a stratum is," or "a phenomenon is." Avoid repetition of words or phrases, but never at the expense of perspicuity. There are many students who seem to have an idea that these are matters of small moment, and who object to criticism which they think should be confined, in a geologic thesis, to geologic matters. They should realize that slovenly writing is as detrimental to

their profession as is careless field or laboratory work.¹ In writing a professional report for a client not too well versed in geology, do not be too booky. Aim to make your report simple and easily intelligible to him. It will do you no harm if you substitute common words and expressions for more technical terms with which you yourself may have become familiar.

The question is frequently asked, "How long shall I make my report?" This cannot be answered in terms of pages. Treat the theme from all points of view; omit nothing which will serve to elucidate the subject; but be concise. Aim to be brief and thorough. Let there be no mistake in your reader's mind between what is fact and what is theory. Also, be conscientious in acknowledging outside sources of important information, whether these were conversations or published works.

After you have completed your paper, number the pages and see that all page citations in the text are correctly filled in. Never submit the final copy of a thesis or of an article for publication until you have examined it critically for mistakes.

As for the paper, use sheets about 8½ by 11 in. Write on one side only. Leave a margin at least 1 in. wide on all sides. Double space the lines if you typewrite, and use a typewriter whenever possible.

492. Parts of a Manuscript Report.—A finished geologic report, in manuscript form, has a title page, a table of contents, a list of illustrations, the text, the illustrations themselves, and, if the paper is very long, an index, and a bibliography. These may be called the "parts" of the report. First, the text is written; then the illustrations, which have already been roughly drawn to assist in composing the text, are completed in final form; and the remaining parts are prepared last.

THE TEXT OF A GEOLOGIC REPORT

493. Order of Topics.—Before beginning to write a paper, one should consider the order of presentation of the subject matter.

¹ Geologists are strongly recommended to peruse pp. 6-22 in Wood's "Suggestions to Authors." Bibliog., Wood, G. M.

The topics should be arranged in the sequence of their dependence, that is to say, in a sequence such that each chapter is as little as possible contingent, for intelligibility, upon the chapters that succeed it. This is difficult to carry out for there is always more or less interdependence of subjects.

Different reports, of course, must be drawn up in different ways. Papers of a specific character, usually those with a purely economic motive, may need individual planning. Papers of a general scientific nature, both course theses and articles for publication, may often be arranged in accordance with a set outline like that given below:

GENERAL OUTLINE FOR A GEOLOGIC REPORT

Abstract (for an article for publication).

Introduction.

Location of area.

Size of area.

Purpose of investigation.

Method of investigation.

Acknowledgments.

Summary and conclusions.

Recommendations (in a paper with a practical object).

Geography.

Relief and elevations.

Topography.

Drainage.

Vegetation.

Rock exposures.

Stratigraphy and petrography.

Regional, or general.

Local, or detailed.

Geologic structure.

Regional.

Local.

Structural development.

Geologic history.

Economic considerations.

These headings will now be discussed in order.

494. Abstract.—An abstract—that is, a very much condensed presentation of the essential facts and conclusions—should appear

immediately following the title of a paper intended for publication. This enables the reader to find out in a very short time just what the paper treats and whether or not, from his standpoint, it warrants his careful study of the main body of the report.

495. Introduction.¹—In the introduction of a geologic essay briefly outline the location of the region to be described and the best ways of reaching it from the nearest cities. State its shape and area, and mention in what manner and to what extent, if at all, the district has been put under culture by man. Add a short explanation of the method in which the field work was conducted. Especially in economic papers, tell the reason for making the investigation and writing the report. Conclude this section with a paragraph acknowledging important sources of information and giving credit to those persons who have furnished assistance in compiling or preparing the report.

496. Summary and Conclusions.—The usual place for a summary is at the end of a paper, but in scientific literature clearness is gained and time is saved for the reader by putting this section immediately after the introduction. Notwithstanding its position, however, the summary should not be *written* until after the main text is finished. It is in no sense introductory. It should be a very concise review, in outline form, of the principal facts and inferences of the report. The reader should be able to acquire a true perspective of the scope and conclusions of a paper by looking over merely the introduction and the summary.

In economic papers the summary and conclusions should be followed by the recommendations.

497. Geography.—Under this head are discussed the relief and drainage of the field area, the nature of the topography, the abundance, shape, and size of outcrops, the relations of outcrops to topography, and the general distribution of surface deposits. Unless these subjects have an important bearing upon the geology proper, they should be briefly treated. In some reports

¹ Bibliog., Wood, G. M., p. 30.

the topography may be taken up with advantage in the introduction.

498. Stratigraphy and Petrography.—*Stratigraphy* refers particularly to various rock formations (called *map units* if they are shown on a map) in their individual characteristics and in their relations to one another. The description of the rocks themselves belongs under the head *Petrography*.

A brief discussion should first be given of the regional or general stratigraphy and petrography. Then, in chronologic order, each map unit (formation, rock body) should be described in detail and with reference to its local aspects.

In giving the detailed outline of the rock formations, or map units, the following items should receive attention:

- A. For sedimentary (and metamorphosed sedimentary) rocks:
 1. Name of rock or formation or map unit.
 2. A real distribution (may include nature of outcrops and topographic expression).
 3. Lithology (list visible mineral and rock constituents; give such characteristics as texture, color, fresh or weathered; also, describe lithologic structures such as ripple-mark, foliation, etc.).
 4. Thickness (state method of measuring thickness and probable accuracy of this measurement) (see also Art. 499).
 5. Origin (source of sediment and conditions of deposition).
 6. Relations to underlying and overlying rocks (conformable or unconformable; here should be described nature and extent of unconformities).
 7. Age and correlation (give method of determining age, and tell how certain the correlation is).
- B. For igneous (and metamorphosed igneous) rocks:
 1. Name of rock or formation or map unit.
 2. Areal distribution (may include nature of outcrops and topographic expression).
 3. Lithology (give mineral composition and approximate percentages of different minerals; also texture, internal structure, etc.).
 4. Thickness (of flows, dikes, etc.).
 5. Origin (intrusive or extrusive; depth at which intruded, or conditions of extrusion; other pertinent data).
 6. Relations to underlying and overlying rocks, or to wall rocks.
 7. Age and correlation (give method of determining age, and tell how certain the correlation is).

499. Geologic Structure.—This is the section in which the geologic structure and the mutual field relations of the different rocks are to be described and explained. Consider here the mode of occurrence of the rocks; the contact phenomena of igneous rocks; the spacial relations of magmatic differentiates in an intrusive body; the attitude of dikes, veins, beds, etc.; the nature of folding; joints; faults; cleavage; schistosity; and other like features. In this section, too, measurements of breadth of outcrop and thickness of beds may be taken up in detail, since these are related to folding, etc. Computations for the heave, throw, strike-slip, dip-slip, and other items of fault displacement should be made. Discuss the several topics which relate to your particular problem in some rational order. Whenever appropriate, refer to the geologic maps and sections to illustrate your statements.

In comprehensive reports, discuss the structural development of the area. Explain how the structures originated, giving attention to directions and points of application of forces, role played by competent and incompetent beds, etc. Serial or consecutive maps, sections, and block diagrams are of value in this discussion.

500. Geologic History.—For some reason students seem to find it hard to understand just what they should write under the caption, geologic history. There is really no great difficulty in the matter, provided the facts are at hand, if this one important rule is heeded: *describe the events in the natural sequence of their occurrence.* Here is an example: suppose that a certain region is underlain by a folded sedimentary series which is unconformably related to an older body of schists and injected granitic rocks; and suppose, further, that most of the bedrock in the district is covered by glacial deposits, and that the outcrops show evidence of glacial abrasion succeeded by more or less weathering. In the section, geologic history, of a report dealing with this particular area, one should describe the events in the following order: (1) origin of the schists; (2) intrusion of the granitic rocks; (3) erosion of these schists and igneous rocks (the lower unconformity); (4) accumulation of the stratified series; (5) folding of

the strata (and probably of the older rocks and structures); (6) erosion culminating in glacial abrasion, (7) deposition of glacial materials; (8) postglacial weathering. No doubt other phenomena, such as jointing and veins, would be found in a region of this kind, and these should be mentioned in their proper places in the account.

In the geologic history, then, the mode and conditions of origin of the various rock masses and important structures should receive consideration. Likewise the topographic forms should be described with respect to their origin and in relation to physiographic cycles (Chapter XII). Some authors include this last subject under *geomorphology* as a separate heading.

Try to determine the geologic age of each event. For this part of your report you will find that the field notes on the relative ages of the different observed phenomena are indispensable.

501. Economic Considerations.—Geologic facts that have a practical bearing and facts pertaining to economic operations already in progress are reserved for this chapter. Here should be described the pits, quarries, mines, or wells of the district, the products extracted, the values and uses of these products, and the available means for their conveyance to the nearest transportation depot. The subject of the resources not yet touched should also be treated, their nature, distribution, and extent, and the approximate cost of handling them. Recommendations based on these facts are usually presented early in a practical report in order to save the time of the reader, who is likely to be a busy executive.

PARTS OTHER THAN THE TEXT

502. Quotations and Footnotes.—Direct quotations from the works of other authors must be identical with the original, except that typographic errors may be corrected.

"Before making a footnote an author should carefully consider whether the matter does not belong in the text. Proper footnotes consist chiefly of references to the literature of the subject discussed. For reference marks superior figures (^{1,2,3})

should be used."¹ . . . In the manuscript each footnote should be written immediately below the line in which the reference mark appears and should be separated from the text above and below it by dotted, dashed, or full lines. Footnotes should be arranged according to a standard pattern, as in the following examples:

GEIKIE, ARCHIBALD, *Text-book of geology*, 4th ed., vol. 1, 1903, p. 49.

DANA, J. D., Volcanic eruptions of Hawaii, *Am. Jour. Sci.*, 2d ser., vol. 10, 1850, p. 235.

ARCHIBALD GEIKIE, *Text-book of Geology*, 4th ed. (1903), I, 49.

J. D. DANA, "Volcanic Eruptions of Hawaii," *Am. Jour. Sci.*, (2), X (1850), 235.

Observe the details of capitalization, abbreviation, punctuation, and order in these examples. Notice, also, the differences between the first two and the last two. Either way is correct and either way may be adopted; but consistency demands that only one be used for all citations in a given manuscript. If you are preparing an article for some particular journal, adapt your footnotes to the method practiced by this journal.

503. Illustrations.²—Figures are illustrations which are printed with the text and which are usually smaller than a printed page. Full-page illustrations in the published article are usually printed apart from the text and are then known as plates. All illustrations larger than a printed page are plates in the sense that they are made separately.

With regard to manuscripts, the illustrations should be numbered in the sequence in which they are referred to in the text. The number, name, and description of each *figure* should be given at the place where it is to appear in the text when published. The number, name, and description of each *plate* should be written on a separate sheet of paper, and the place where it is to be found in the publication should be clearly indicated. The original figures and plates themselves are not kept with the

¹ Bibliog., Wood, G. M., p. 16.

² *Ibid.*, p. 26.

text; they are put together in an envelope, and each is properly numbered.

Ordinarily maps and sections should be made in black and white, for the reproduction of colors is expensive. All black line work is to be done with India ink. Put shading in, not by a back-and-forth scratching motion, but by repeated strokes in one direction. The outlines of the illustration may be lightly sketched in pencil before finishing in ink.

If possible, when drawing for publication, make the illustrations larger than they are to appear in print, for their details are often brought into sharper contrast by reduction than by copying in the original size. Lettering must be large enough for the reducing process to make it of proper size. It should never be so small that, when printed, the lower case figures and numbers are less than $\frac{1}{50}$ of an inch in height. For easy legibility, they should be a little larger than this minimum size. Illustrations on paper over $8\frac{1}{2}$ by 11 in. may be folded for course theses, but never so for reports to be published. In the latter case they should be sent rolled or flat. *Always be neat.* Do not submit untidy drawings either for publication or for course theses.

Directions for the construction of geologic maps and sections have been given in Chapter XIX. A few more suggestions of practical import may be added here. In preparing a geologic map in black and white, only enough of the details of relief, drainage, and culture, need be shown to enable the reader to ascertain from this map the locations of geologic features in the field. Prominent hill crests, rivers, lakes, railroads, town lines, and a few of the more important roads, may be traced from a topographic map and used as a base for plotting the geology. In more accurate work, a finished topographic base map must be employed. It is often a good plan to make two maps on the same scale, one to represent the bedrock and the other, the superficial deposits and outcrops. You should also furnish a small-scale index map of the surrounding country with a small rectangle marked on it to indicate the exact location of the mapped area of investigation (Fig. 545).

Both maps and sections may be drawn on ordinary tracing cloth, from which, if desired, blue print copies can be made. Geologic sections should first be sketched on profile paper so that the measurements can be made accurately and quickly for




FIG. 545.—An index map. (Van Horn Folio, No. 194, U.S.G.S., 1914.) The heavily shaded area is the location of the Van Horn quadrangle of which the geology is discussed in the Van Horn Folio.

horizontal and vertical scales. Then they may be traced on the cloth. Line drawings for illustrations, if not traced, should be prepared on the thinnest grade of Bristol board. For photographs, which should always be in sharp focus for scientific purposes, glossy prints should be submitted. Do not fail to assure yourself that each of your illustrations has on it all the

data necessary to make it serviceable and comprehensible (443, 455, 468, 472).

504. Table of Contents, Index, Etc.—There remain for consideration the table of contents, list of illustrations, bibliography, index, title page, and the cover. The *table of contents* is a list of headings and subheadings used in the text. Each division, with the page on which it is to be found, is noted on a separate line. The wording is to be literally identical with that employed in the text. Differences of rank are indicated by indentation, the subordinate sections being set in somewhat to the right of those of next higher degree. The *list of illustrations* has only the names of figures and plates, not the accompanying legends. The pages on which figures appear and the pages facing plates are recorded on the right opposite the appropriate illustrations. The *bibliography*, which is best placed at the end or just before the index, is a catalogue of all books and articles referred to in preparing the report. It may be arranged alphabetically by authors, or chronologically. The utility of a lengthy bibliography may be enhanced by grouping the references according to subject.

An *index* is not necessary except for long articles and books. If one is undertaken, it should be comprehensive and thorough, for a deficient index is far worse than none at all.

After the report is complete it should be securely bound in a cover of some kind either by stitching or by metal fasteners. On the front of the cover are the title of the report and the author's name. In college reports the date on which the paper is due is also on the cover. The title page bears exactly the same information as the cover. Always strive to make the title brief and to the point.

CHAPTER XXIII

GEOPHYSICAL SURVEYING

505. Definition and Classification.—By *geophysical surveying* is meant the making and interpretation of certain physical measurements with the object of furthering the study of subsurface geological conditions of structure or material. Such surveying has been used in the mapping of ore deposits and oil-bearing structures and also in research in pure geology. The measurements are made by sensitive instruments of one kind or another, according to the particular type of geophysical results desired. The more important classes of geophysical work are based on the measurement of variations in: (1) gravity; (2) elasticity; (3) magnetic susceptibility; and (4) electrical conductivity. To these may be added (5) measurement of variations in temperature and (6) measurement of variations in radioactivity. These methods are designated, respectively, as (1) gravimetric; (2) seismic, or seismographic; (3) magnetic, or magnetometric; (4) electric; (5) geothermic; and (6) radioactive. Some of these methods—those that involve measurements in drilled holes, such as electrical logging, geothermic observations, measurements of gamma rays—have been discussed under Subsurface Geologic Surveying (Arts. 430, 432, and 433) and under Subsurface Maps (Arts. 459 and 460). The present chapter concerns the field methods in geophysics, those methods that require field surveying and the collection of data by observations at, or very near, the surface of the ground. These fall mainly under the first four methods listed above. As Barton¹ has pointed out, in all four of them three steps are recognized: (1) the mapping of the areal variation of some physical effect at the earth's sur-

¹ Bibliog., BARTON, DONALD C., 1930 (a), pp. 201–202.

face; (2) the determination of the subsurface distribution of some physical property connected with the physical effect mapped; and (3) the interpretation of these physical properties and their distribution in terms of geologic structure.

The four field methods of geophysical surveying have been ably compared and contrasted by Weaver,¹ from whom we quote, with a few slight changes:

"They (the four methods) may be divided into two classes, those which measure a potential function or some of its components, and those which determine a point.²

"Gravity, magnetic, and electric geophysical methods are measurements of a potential function, but the seismic method is not. From the standpoint of geology and geophysics, measurements of the potential function and its components have the following implications:

"1. Size (that is, mass) and distance cause most of the effect. The larger the mass, the greater the effect. The greater the distance, the less the effect.

¹ Bibliog., WEAVER, PAUL, "Relations of Geophysics to Geology," 1934, pp. 6 *et seq.*

² "Bodies in space exert force upon other bodies at a distance. The amount of the force varies in some way with the distance, usually inversely as the square of the distance. . . . To define the potential, let us take one body, which we will call *A*, at a fixed position. Let us move another body from a point 1 in space to a point 2, and let this second body be so small that every part of it can be considered the same distance from *A*, so we will call it *P*, meaning a particle. It will require work to move *P* from 1 to 2 if they are at different distances from *A*. Then the amount of work is equal to the difference in the values of the potential function for 1 and for 2. The potential function is a number, since work is a number. It has no direction, but it changes in general from every point in space to the next one, and at different rates . . . Gravity, magnetic, and electric forces each vary as the square of the distance, but differ in that the gravity force is always one of attraction, whereas the magnetic and electric forces may be either attractive or repellent." (This note quoted, with slight modification, from Weaver, *op. cit.*, footnote, p. 6, in the reference to the discussion of the potential function by W. D. McMillan in "The Theory of the Potential," McGraw-Hill Book Company, Inc.)

"2. All bodies have an effect, and this effect can become very small only if the body is very small, or very far away.

"3. The shape of the body modifies the effect only slightly.

"In reconnaissance geology, we wish to find the existence of large bodies, and so potential function methods are valuable in reconnaissance" . . . but they are limited in accuracy of interpretation due to the multiplicity of unknown variable factors which may affect observed readings. On the other hand, the seismic method " . . . attempts to map contours on an underground bed, or beds. . . . It is intended, therefore, to give a result which determines uniquely the depth to a bed, or beds, below the point of observation, and is probably the only method which gives theoretical possibilities of being equivalent to core drilling.

"There is a . . . difficulty in geophysical surveying by potential function methods. It is necessary to extend the surveys to a considerable distance because the rate of change of the values measured is important for the interpretation. In areas where there are several anomalies close together, it therefore results that the effect of each anomaly is obscured by effects from adjacent ones. . . . By the seismic method" . . . on the other hand . . . "it is possible theoretically to make accurate determinations from a few observations close together. This method, therefore, has an advantage over the potential function methods in requiring very much less areal extent to be investigated."

In the following pages no attempt is made to expound the mathematics of these various geophysical methods, and little is said by way of describing the construction of the instruments used or of explaining the technique of making observations in the field. These are matters of concern for the geophysicist himself. But every geologist should know something as to the nature and differences of these methods, what they can do and what they cannot do for geological interpretation, and the meaning of the maps on which the geophysical data are graphically represented. It is for this purpose that we are outlining some of the more significant facts. For detailed information, reference may be

had to the writings of others cited herein and to the bibliographies included in many of the citations.¹

GRAVIMETRIC METHODS

506. Gravity and Its Expression.—The principal gravimetric methods of geophysical surveying are based on (1) the use of the Eötvös torsion balance, a sensitive instrument that measures the gradient, or *rate of change*, of gravity, and (2) the use of gravimeters (or gravity meters), which are sensitive instruments capable of measuring very small *differences in the force of gravity*.

Gravity is defined as the force of attraction exerted by the earth toward itself on a body of unit mass. The *vertical*, at any point, is the direction along which the attraction of gravity acts. In most cases it is very nearly, but not quite, perpendicular to the earth's surface. A *level surface* (sometimes also called a *niveau surface*) is everywhere perpendicular to the vertical. The surface of a body of water at rest and acted on solely by gravity is a level surface, or *niveau surface*.²

507. Variations in Gravity.—"If the earth were a homogeneous sphere at rest, gravity would be the same everywhere over the surface of the earth and would vary only radially, and the level surfaces would be spherical and concentric with the earth's surface. But the earth is not at rest; it is not a sphere; and its outer crust is in no way homogeneous."³

Centrifugal force, due to the earth's rotation, tends slightly to counteract the force of gravity. Because the earth is a

¹ For these references, see Bibliog.: RYBAR, STEPHEN, 1923; AMBRONN, RICHARD, 1928; McLAUGHLIN, DONALD H. (chairman), 1929; EVE, A. S., and D. A. KEYS, 1929; HEILAND C. A., 1929; FORDHAM, W. H., 1929; BARTON, DONALD C., 1927, 1929, 1930. Also, volumes on Geophysical Prospecting, published by the A.I.M.M.E. in 1929, 1932, and 1934; *Geophysics*, published periodically by the Society of Exploration Geophysicists; HEILAND, C. A., NETTLETON, L. L., "Geophysical Exploration," Prentice-Hall, Inc., 1940; and "Geophysical Prospecting for Oil," McGraw-Hill Book Co. Inc., 1940.

² Bibliog., BARTON, DONALD C., 1929 (a), p. 417. In discussing the torsion balance, we have drawn freely on this excellent paper by Dr. Barton.

³ *Ibid.*, p. 417.

spheroid flattened at the poles and because of the rotation of the earth, the value of gravity is at a maximum at the poles and at a minimum at the equator. Certain allowance must be made in




FIG. 546.—Diagram of a small section of the earth's crust where there is supposed to be a homogeneous distribution of mass. In A, GG is the intensity of gravity, here perfectly uniform. LS represents a level surface in section. The arrows represent lines of the vertical. Strictly speaking, the lines GG and LS should be arcs of circles of large radius, and the arrows should converge slightly downward, toward the earth's center.¹

all gravity observations to correct for the *normal poleward gradient* and, in torsion balance observations, for the *normal differential curvature*, i.e., for warping of the level surfaces due to the effect of the centrifugal force of the earth's rotation and the effect of the spheroidal shape of the earth.

¹ With Dr. Barton's permission and also permission from the A.I.M.M.E., Figs. 546-552, and 557-561 (somewhat modified, as explained in the text) were copied from Barton's paper "The Eötvös Torsion Balance Method of Mapping Geologic Structure"; and Figs. 569-573 were copied from Barton's "Seismic Method of Mapping Geologic Structure." (Bibliog., BARTON, DONALD C., 1929 (a) and (b).)

The lithosphere, as all geologists know, is very irregular in the distribution and nature of the rock bodies that compose it. These rock bodies are of varying density, and consequently they produce varying amounts of deformation of the level surfaces and lines of force that constitute the normal gravitational system.




FIG. 517 — Diagram of a small section of the earth's crust with a body denser than the surrounding country rock. *GG*, intensity of gravity at a maximum above the center of the dense mass, and with steepest gradient over the edges of this mass. *LS*, level surface, arched up above the dense mass. The arrows represent lines of the vertical. (See footnote to Fig. 546.)

“As a result of the irregular distribution of mass in the earth's crust the intensity of gravity locally is at a maximum over the areas of excess of mass and at a minimum over the areas of deficiency of mass; the lines of vertical tend to crowd from the bodies deficient in mass into the bodies with excess of mass—that is, the vertical is deflected toward the excess of mass and away from the deficiency of mass; the level surfaces are warped up, convexly, over the areas of excess of mass and are warped

downward, concavely, over the areas of deficiency of mass"¹ (Figs. 546-548).

508. Quantities Measured by the Torsion Balance and Gravimeter.—The torsion balance measures directly two elements of the deformed gravity field: (1) the horizontal gradient of gravity and (2) the differential curvature. Indirectly, from (1) a third




FIG. 548.—Diagram of a small section of the earth's crust with a body lighter than the surrounding country rock. Here the gravity profile, *GG*, is curved down, with a minimum over the center of the body, and with the steepest gradient over its edges. *LS*, the level surface, is bent down over the light body. The arrows represent lines of the vertical. (See footnote to Fig. 546.)

element, the horizontal variation of gravity, can be determined. This is the quantity that is directly measured by the gravimeter (see below). It is commonly spoken of as *relative gravity* and is designated Δg .

The *horizontal gradient* of gravity is the rate of change in the intensity of gravity per horizontal centimeter. Unless specified otherwise, the term *gradient* in geophysical prospecting is under-

¹ *Ibid.*, pp. 419-420.

stood to mean the horizontal gradient of gravity and to refer to the amount and direction of the maximum gradient. On maps the gradient is represented by an arrow flying in the direction of




FIG. 549.—Original reconnaissance torsion balance map of the Nash prospect and the structure contour map as subsequently determined by drilling. The structure contours are on the top of the cap or, in the absence of the cap, on the top of the salt. (See footnote to Fig. 546.) The Nash dome is in Fort Bend County, Texas.

the increase of gravity and proportional in length to the magnitude of the gradient (see Fig. 549).

The *differential curvature*, known also as the *Eötvös curvature value*, *horizontal directing force*, or *R value*, is a function of the differential warping of the level surfaces. Its use in torsion balance work has always been subordinated to the use of the gradient,

chiefly because of the unreliability of the differential curvature in all but the flattest of terrains.¹

As previously stated, the gravimeter measures relative differences in the force of gravity from point to point (station to station), and these values are referred to an assumed datum. Neither in torsion balance surveying nor in gravimeter surveying are absolute gravity values sought. The case is in many respects similar to topographic mapping, where, in the determinations of relative *elevations* at selected stations (Cf. gravimeter) or in determinations of the *topographic slope* between selected stations (Cf. torsion balance), all the elevations are referred to an assumed datum rather than to sea level.

Referring again to the torsion balance, the variation of gravity over an area can be calculated from the gradient if the stations are close enough to one another. The gradient gives the change of gravity per centimeter. If the gradient, therefore, is known at two stations and if the stations are close enough together so that a linear variation of the gradient between the stations can be assumed, the difference in the value of gravity between the two stations can be calculated. The variation of gravity (*relative gravity* or Δg) can then be calculated over the whole of a survey with a sufficiently close net of stations. If the survey has been tied into a pendulum station, at which a determination of absolute gravity has been made, the values of gravity of the torsion balance survey can be given in terms of absolute gravity.

509. Effects of Topography on Gravity Observations.—Irregularities of topographic form of the earth's surface may affect the quantities measured in gravity exploration. If the terrain in which the torsion balance is set up is a flat horizontal plain, it produces no effect on the gradient or differential curvature. A depression adjacent to the instrument acts as a deficiency of mass and produces a gradient away from itself. A slight rise of the ground above a plain acts as an excess of mass, provided the rise is

¹ For further information on the differential curvature, see BARTON, *op. cit.*; also, JOYCE, J. WALLACE, "Theory of the Torsion Balance," U. S. Dept. of Commerce, *Tech. Paper* 546, 1933.

below the level of the instrument. If it is above the level of the instrument, its effect is reversed because its upward force tends to reduce the downward pull of gravity, as measured at that point. Any deviations of the topography from a level plain must be corrected for, and, as the topography increases in irregularity and as the materials on the surface or at shallow depths become more




FIG. 550.—Gradient arrow, *R* line, and structure map of a portion of the Luling oil field, Caldwell County, Texas. Dashed line to east is trace of fault at surface. This fault dips west so that it intersects the Edwards limestone along a line vertically below the dashed line to the west. (See Fig. 551 and footnote to Fig. 548.)

heterogeneous in density, the corrections applied are decreasingly accurate. Topographic irregularities within 2° above or below the horizontal plane of the instrument produce a negligible effect on the gradient, and topographic irregularities within 5° above or below the horizontal plane of the instrument do not seriously affect the gradient. The differential curvature is affected seriously by such irregularities of the topography, and, with increasing topographic relief, the differential curvature becomes useless

much sooner than the gradient. Distant topography, such as a high mountain range, may affect the gradient and differential curvature, but not enough to interfere with interpretation.

With regard to the gravimeter, small near-by variations in topography are less serious than in the case of the torsion balance. Topographic irregularities within 12° , plus or minus, of the hori-





FIG. 551.—Vertical section of the Luling fault, and, above it, a gradient profile, showing the effect of the fault on the gradient. (See Fig. 550 and footnote to Fig. 546.)

zontal plane through the instrument can be neglected. Beyond this angular limit, effects are increasingly serious, and corrections must be made.

510. Units of Gravity Measurement.—The unit of measurement for the gradient in work with the Eötvös torsion balance is (1×10^{-9}) dyne (per gram) per horizontal centimeter. This unit is called an *Eötvös* or an *Eötvös unit*. A gradient of 1 E. means an increase in the intensity of gravity per horizontal centimeter of about one million-millionth (1×10^{-12}) the value of gravity. The values of the gradient actually measured in the field range most commonly from 5 to 30 E.



The unit of gravimeter measurement is the *millidyne*, which is one-thousandth part of a dyne, the absolute unit of force. The word *milligal* is used by many geophysicists as synonymous with millidyne. Most gravimeters can measure gravity differences to




FIG. 553.—Gradient arrow map showing results of torsion balance observations along three intersecting traverses (AA', BB', and CC'). Compare Fig. 554.

a small fraction of a milligal. For this reason the unit often preferred in gravimeter surveying is 0.1 milligal (0.1 millidyne). Anomalous values, *i.e.*, variations from the normal gravity value, as measured by gravimeter, may range from 1 or 2 milligals to as much as 50 or 60 milligals.

511. Graphic Representation of Gravity Data.—Gravity data may be drawn on maps or in profiles. The data most commonly are reported in the form of gradient arrow maps and isogam maps.




FIG. 554.—Isogam map of torsion balance results obtained along lines AA', BB', and CC'. The structure here surveyed (the same as represented in Fig. 553) is a shallow salt dome with its cap rock approximately 1,600 ft. below the surface at the shallowest point. The cap rock sloped off moderately to near the position of the dashed line and then plunged off steeply on all sides. This was verified by drilling subsequent to gravity exploration.

R-line maps are sometimes drawn for additional information where the differential curvature values are dependable. Figures 549 and 553 are gradient arrow maps. Figure 550 shows both the gradient arrows and the *R* lines plotted at each station. *Isogam*

is the name applied to a line of equal value of relative or absolute gravity. Isogam maps, such as Figs. 552, 554, and 555, are used to picture the variation of gravity. Graphs (Fig. 556) may be used to show certain components of the gradient and the curvature in vertical profiles. The Δg curve, or profile, is a cumulative curve of gravity differences between stations along the line of the profile. It is built up by algebraically adding, for each station, the difference in gravity value between this station and the adjacent station last calculated, taken as zero, *i.e.*, as a datum (see Figs. 556, 557-561, and Art. 512).

512. Gravity Surveying for Geologic Structure.—In gravity surveying for geologic structure, those anomalies that are due to topography and to planetary effects (507) are corrected as efficiently as possible. The station sites are selected to avoid setting up where any surrounding irregularities of topographic relief are over 5° below or above the horizontal plane passing through the center of gravity of the instrument, in the case of the torsion balance, or where the irregularities are over 12° above or below this plane in the case of the gravimeter, and where any such irregularities, in the case of either instrument, are at least moderately distant from the instrument. It is best to choose station sites where the ground is level over as wide an area as possible. If necessary the ground is levelled within a radius of a few yards of the instrument, where the torsion balance is used. In rugged country, it is not practicable to use the torsion balance for gravity gradients of structure unless the gradients caused by such structures are very large. Even in regions of moderate relief, it is almost impossible to get reliable determinations of the differential curvature.

After removing from the observed reading the topographic and planetary effects, values remain that must be interpreted for their geologic significance. These values are still resultants of many unknown components that, without considerable geological skill and understanding on the part of the interpreter, would often be unintelligible, or at least subject to several different explanations. For adequate interpretation of the data, one must be well versed

in the theory of gravimetric method and also one must have had considerable geological experience.

In recording the gravity values, abnormal gradient and differential curvature values may be registered by the torsion balance




FIG. 555.—Isogram map of gravimeter results obtained in the same area as that represented in Figs. 553 and 554.

by relatively shallow and unsuspected features such as large boulders or concretions in the soil, sharp changes in the lithological characters of sedimentary deposits, irregularities in the bedrock floor on which the upper soil or unconsolidated deposits rest, etc. * Sites for stations should be examined for these possible

causes of local anomaly. Such extremely local heterogeneities produce effects on gravimeter measurements that are much less




FIG. 556.—In the upper part of this figure are shown the regional gradient curve (here taken as horizontal) and the average gradient curve, or curve-of-gravity values, measured from station to station, and averaged as between each three adjacent stations. These curves are taken along profile AA' in Fig. 554.

In the lower part of Fig. 556 are the Δg curves for the regional gradient and for the gravity values. These two curves were constructed from the curves in the upper part of the figure. Note that the cap rock at shallow depth produces a maximum or positive anomaly, whereas the salt produces a minimum or negative anomaly. Centrally the cap-rock effect is strong enough here to conceal the negative effect of the underlying salt mass. It is only where the cap rock becomes thin and is at sufficient depth that the salt effects become conspicuous in the gravity picture.

than in the case of torsion-balance measurements and that in most cases are negligible.

Gravity anomalies due to larger effects are commonly related to structure. Any particular body has a characteristic gradient

and curvature pattern that depends on the form and size of the body and its depth below the surface. The amplitude of the gradient and the differential curvature values depend on the difference between the respective densities of the body and the surrounding medium. The gradient, curvature, and Δg curves for four common simple types of geologic structure are shown in Figs. 557-561. The structures (with the exception of that in Fig. 561) are supposed to be infinitely long with the respective transverse cross sections shown in the figures. The lower part of each figure gives the structural cross section drawn with vertical and horizontal scales equal. The middle profile gives the curve of the variation of the value of R , the differential curvature, above the structure; the lower profile gives the variation of the gradient above the structure; and the upper profile is the Δg curve, or curve of relative gravity. In each case this Δg curve has been calculated from Barton's diagrams by integrating the gradient curve. On the differential curvature profile, each point on the curve above the zero line would be represented on a map by an R line at right angles to the line of the section. On the gradient profile each point on the curve above the zero line would be represented on a map by a gradient arrow flying to the right, and each point on the curve below the zero line would be represented by an arrow flying to the left. The Δg profile is the curve that would be obtained by gravimeter in exploring the geologic structure pictured below, in each figure. Observe that this curve is less distinctive of varying geologic structure than are the curvature and gradient profiles derived in torsion balance work. In other words, the torsion balance may be used for more refined (or detailed) interpretation of subsurface structure than can the gravimeter.

"A vertical fault cutting a shale section of 3,000 to 3,500 ft. thick, overlying a very thick massive limestone section, is represented in Fig. 557. The fault has a throw of 300 ft. at the surface and at 1,000 ft.; a throw of 400 ft. at 2,000 ft.; and a throw of 500 ft. at 3,000 ft. The shale section is supposed to be split into three formations with specific gravities, increasing downward, of

2.15, 2.20, and 2.30, respectively. The specific gravity of the limestone was assumed to be 2.70. Both the gradient and differential curvature are symmetrically disposed in reference to the fault plane; the differential curvature is zero and the gradient is at a maximum over the fault; on the left of the fault plane the R lines are perpendicular to the fault line, and on the right are paral-




FIG. 557.—Gradient, differential curvature, and Δg profiles for a simple vertical fault. (See footnote to Fig. 546.)

Note that where the curvature profile is above its horizontal base line the R lines on a map would be perpendicular to the fault, and where it is below the base line the R lines would parallel the fault. Where the gradient profile is above its base line, the gradient is toward the right, and *vice versa*.

lel to it; the gradient arrows all fly toward the right but increase to a maximum over the fault and then decrease symmetrically.

"A fault with a dip of 30° cutting the same stratigraphic section as in the preceding case is represented by Fig. 558. The gradient and differential curvature profiles are very similar to those of the preceding case but are not symmetrical, the gradient maximum and the numerical maxima of the curvature are slightly less than the corresponding maxima of the preceding case, and the zero of the differential curvature and the maximum of the gradient do not lie above the surface trace of the fault, but over the upper part

of the fault in the limestone basement, where the throw and the density difference are greatest. If the specific gravity had a smooth curve of increase downward, especially in the upper shale formation, both the gradient and differential curvature profiles would be very considerably modified in regard to the position of the zero points and maxima and the magnitude of the maxima.

"An anticlinal or 'buried' ridge of limestone overlain by shale and with a relief of 375 ft. is represented by Fig. 559. The top of




FIG. 558.—Gradient, differential curvature, and Δg profiles for a fault dipping 30°. (See note to Fig. 557 and footnote to Fig. 546.)

the ridge is supposed to be at a depth of 1,500 ft. and the normal level of the top of the limestone is supposed to be at 1,875 ft. The ridge is supposed to be symmetrical about its crest line. The gradient and differential curvature profiles are symmetrically disposed about the vertical axial plane of the ridge; the gradient everywhere is toward the crest of the ridge—that is, the gradient arrows to the left of the crest would fly to the right, and on the right of the crest, they would fly to the left; the gradient is zero above the crest of the ridge; and the maxima are over the flanks. The *R* lines off the structure and over the foot of its flanks are

toward the structure and reach a maximum over the lower part of each flank of the structure; over most of the structure the R lines are parallel to the crest of the structure and are at a maximum over the crest of the ridge. The relative magnitude and the absolute magnitude of the numerical value of the maxima of the curvature and the form of the central maximum vary very considerably with variation in the cross section of the ridge.




FIG. 559.—Gradient, differential curvature, and Δg profiles for a symmetrical infinitely long ridge of anticlinal nature. Here the ridge corresponds to the fault in Fig. 557. (See note to Fig. 557, and footnote to Fig. 546.)

"A ridge similar to the preceding but with the right flank much steeper is represented by Fig. 560. The gradient and differential curvature profiles are very similar to the corresponding curves of the preceding case but are asymmetrically warped by the asymmetry of the ridge. It should be noted that the zero point of the gradient and the maximum value of the differential curvature do not lie immediately above the point of the ridge that is structurally highest, but are shifted slightly to the left down the gentler slope of the ridge. The zero point where the gradient changes direction marks the point of maximum gravity and it should be noticed that in asymmetric structures the center of the anomalous

gravity high due to the structure is not exactly over the highest point of the structure; the amount of the shift of the gravity high down the gentler slope of the structure is proportional to the difference in the slope of the two flanks. In unknown structures, the shift of the gravity high due to the asymmetry of the structure can be recognized if a moderately detailed transverse profile has been run but its magnitude cannot be determined unless quantita-




FIG. 560.—Gradient, differential curvature, and Δg profiles for an asymmetrical anticlinal ridge of infinite length. The ridge corresponds to the fault in Fig. 557. (See note to Fig. 557 and footnote to Fig. 546.)

tive calculations are made. If only a scattered net of stations is available, the presence of the asymmetry may not be recognized easily, and a location made from the torsion balance data may be off just enough to miss the crest. As the gradient and differential curvature profiles of Fig. 561 show, the gradient profile is slightly modified and the differential curvature profile very considerably modified if the ridge is finite rather than infinite in length.”¹

513. Comparison of Torsion Balance and Gravimeter.—In the foregoing discussion, comparisons and contrasts have frequently

¹ Bibliog., BARTON, DONALD C., 1929 (a), pp. 436–440.

been pointed out between torsion balance surveying and gravimeter surveying. Some of the more salient points may be summarized here:

1. The probable error of an individual station observation with the best modern gravimeters is of the order of magnitude of a few hundredths of a milligal, say from 0.03 to 0.06 milligal. With




FIG. 561.—Gradient, differential curvature, and Δg profiles for a ridge similar to that in Fig. 560, but here with a length only twice the depth at each level. The dotted gradient, curvature, and Δg profiles are taken from Fig. 560. (See footnote to Fig. 546.)

this degree of instrumental accuracy, regional gravimeter surveys are probably more accurate than regional torsion balance surveys.

2. The chief advantages of gravimeters are (a) speed and economy of operation. A gravimeter party, using one instrument, can cover an area from two to four times as fast as a torsion balance party using two instruments, at a cost per unit area of one-half to one-quarter the cost of torsion balance work. (b) Gravimeters can be successfully used in rough or irregular terrain in areas where torsion balance results would be either very unreliable or entirely unusable.

3. The chief advantage of the torsion balance method is that, in favorable areas, torsion balances can be used for detailed work

on certain types of structures that can be more accurately defined by this method than by detailed gravimeter surveys. A good example of this is the mapping of the outline of cap rock on a shallow salt dome. The torsion balance gradient and differential curvature profiles are much more sensitive indicators of the edge of the cap rock and of the shape of the cap rock than the Δg profile measured by the gravimeter.

4. The quantities measured by the torsion balance and gravimeter are not the same. The torsion balance measures the horizontal gradient of gravity and the differential curvature of the level surface, both quantities being second derivatives of the gravity potential. From the horizontal gradient of gravity, the gravity difference or Δg , between any two points of the survey, can be calculated. The gravimeter measures directly these gravity differences, or Δg 's, which are first derivatives of the gravity potential. A torsion balance isogam map is therefore constructed from a knowledge of the gravity slope at a number of points in the survey. A gravimeter isogam map is contoured directly by joining points of equal gravity. How closely alike torsion balance and gravimeter maps of the same structure may be is illustrated in Figs. 554 and 555.

MAGNETOMETRIC METHOD

514. The Earth's Magnetic Field.—The earth may be described as a large irregular magnet. The intensity of its magnetism varies from place to place. The whole complex system of terrestrial magnetic forces is referred to as the *earth's* magnetic field.

If a small compass needle is suspended at its center of gravity at any point, P , in the earth's magnetic field so that it can freely swing in all directions, if undisturbed it will come to rest in a definite position. Except along one particular line (see Plate I opposite page 422), it will not lie exactly in a true north-south direction, but will point toward the earth's magnetic pole, which is several miles from the geographic pole; and instead of being level, it will be tilted from the horizontal plane. The horizontal

direction of the needle while suspended at rest at P , is called the *magnetic meridian* at P , and the horizontal angle between this magnetic meridian and the geographic meridian at P is the *declination* at this point. The vertical angle between the horizontal plane through P and the position occupied by the inclined needle is called the *magnetic dip* or *inclination* at P .

In measuring the intensity of the earth's magnetism, a unit called a *gauss* is used. A *gauss* may be defined as the intensity of a magnetic field that will act on a unit magnetic pole with a force of 1 dyne. A *unit magnetic pole* is one that will act on an equal pole with a force of 1 dyne at a distance of 1 cm. In ordinary magnetometric surveying the unit of measurement is the *gamma*, γ , which is $1/100,000$ of a gauss.

The force exerted by the earth's magnetic field on a unit pole is the total intensity, T , of the earth's magnetism at P , any given point. It acts in the direction defined by declination and inclination. In the vertical plane of the magnetic meridian through P , T can be resolved into two components perpendicular to one another, namely, the vertical intensity, Z , and the horizontal intensity, H ; and H can be still further resolved into its geographic north-south and east-west components, known as X and Y , respectively. The quantities usually measured in magnetometric surveying for geologic structure are H and Z .

515. Measurement of Magnetic Anomalies.—The instrument most commonly used in magnetometric work is called a *magnetometer* or *variometer* of the Schmidt type. The magnetometer that registers differences in vertical magnetic intensity, and is therefore called a *vertical magnetometer*, is used more commonly than the *horizontal magnetometer*, which measures differences in horizontal intensity.

For making observations, the instrument is set up at the selected station, properly levelled and oriented in such a way that the vertical plane in which the needle is free to swing will be perpendicular to the magnetic meridian, *i.e.*, to the magnetic north-south line. Usually the needle is unclamped and the scale read two or three times in this position, and then again two or

three times after the instrument has been turned 180° , and the average of all these readings is recorded.

In reconnaissance work stations are spaced from 1 to 4 miles apart, whereas for detail work they may be spaced more closely. In reconnaissance mapping observations may be made at from 20 to 30 stations a day.

516. Correction of Magnetic Readings.—Magnetometric surveying is in many respects similar to barometric surveying. Magnetic readings are subject to errors due to magnetic storms. Furthermore there is a more or less regular diurnal change in the earth's magnetic field at any locality. Experience has shown that it is best to select a "base station" which is visited several times in the course of the day, so that check readings may be made here with the instrument which is used in the field. The use of a stationary instrument at the base station, observed at intervals of from 15 to 30 min., is desirable, especially where accurate results are required. As in barometric surveying, check readings can be made by revisiting any of the field stations. At the end of the day, a diurnal correction curve is constructed and all the station records are adjusted to remove the *storm* and *diurnal* effects. Data observed during a magnetic storm are usually not dependable. Since most magnetometers now in use are compensated for temperature changes, errors due to variations in temperature are small. Correction may be made by reference to a thermometer inside the instrument. Careful calibration and tests for temperature effects are necessary from time to time.

In addition to these short-time fluctuations, there are secular, or long-period changes in the earth's magnetic field. These are sufficiently cared for, in magnetic surveying, by the proper use of isogonic charts and charts of equal magnetic vertical intensity published by the U. S. Coast and Geodetic Survey (see Art. 517).

The magnetic intensity at the base station may be assumed, being chosen somewhere near the values known to be characteristic of the general area; or the value used is that already determined in a network of base stations previously established.¹

¹ Charts and pamphlets with general information on the earth's magnetic field may be obtained from the Supt. of Documents, Washington, D. C.

517. Compilation of Field Data.—After the field data, corrected for temperature and diurnal variations, have been assembled, and the stations have been properly located on the base map correction must be made for the normal or terrestrial regional change in vertical intensity. This is done by reference to the most recently published "Equal Magnetic Vertical Intensity Chart"¹ which shows the broad regional variations in vertical intensity. The




FIG. 562.—Map of part of the Panhandle area of Texas, showing lines of equal vertical intensity anomaly (full lines) and structure contours on top of the "Big Line" (dashed lines). *ab* is the approximate axis of the main anticlinal structure in the "Big Line."

lines of regional vertical intensity (vertical isodynamics) for the area in question are laid off on the map in proper position and with proper values.² The amount of regional correction to be applied to each station value is then determined from the position of the station with respect to the lines of normal regional change. The correction for the normal variation is added to, or subtracted from, the station value, respectively, as the normal regional value is below, or above, that of the base station or other reference

¹ Obtainable from the U. S. Coast and Geodetic Survey.

² If 2 or 3 years or more have elapsed between the time of making one survey and the time of surveying an adjoining area, some readjustment of the regional vertical isodynamics may be necessary to make the corrected maps match one another. This is because of the secular changes in the earth's magnetic field.

point. The results of this operation are the local anomaly values that are placed on the map. Equal anomalies may be connected




FIG. 563.—Sketch map of Hobbs structure in Lea County, New Mexico. The full lines are isonomalies of vertical magnetic intensity; the dashed lines are structure contours on top of the anhydrite. The small squares are square miles. The upright numbers designate the sections. (See Appendix VII.) The only full township on the map is T. 18 S., R. 38 E.

by flowing lines called *isonomalies*, or *isanomulies*, which express in gammas the local variations from the average total magnetic

intensities in the area. A map so constructed is an anomaly map of vertical magnetic intensity. These anomalies may be caused by geologic structural conditions in the subsurface. They are the values sought in magnetometric surveying for geologic purposes.

518. Application to Geology.—The application of the magnetic method in geologic work depends upon the fact that rock masses and rock types differ from one another in their magnetic quality, that is, in their magnetic permeability. Some ores are highly magnetic; some igneous and metamorphic rocks contain a relatively large proportion of magnetite; and sediments, especially sands and sandstones, may be locally rich in this mineral. It is quite likely that the local anomaly values of magnetic intensity are chiefly to be attributed to the form, size, and distribution of rock bodies (igneous, sedimentary, or metamorphic) of which the constituent rocks are comparatively rich in their content of magnetite. For example, a buried hill (161) of granite or schist, or an igneous plug or dike, intrusive into sedimentary rocks and covered by alluvium, or a lens of sandstone, may cause abnormally high magnetic intensity values if these rocks carry considerable magnetite.

Interpretation of magnetic anomalies for their geologic meaning, is, however, by no means simple. In some places a distinct relationship has been demonstrated (Figs. 562, 563); but elsewhere very pronounced magnetic anomalies have not been correlated with known lithologic or structural features down to drilled depths of several thousand feet (Fig. 564). In such cases the effects mapped may be from very deep-lying causes, not reached in the drilling. In wide areas the anomalies are so slight that although unquestionably they reflect definite conditions, they cannot safely be interpreted.

In all magnetometer work, perhaps more than in any other class of geophysical surveying, one must keep firmly in mind that the net intensities measured at individual stations may, and probably do, represent the resultants of many effects, from shallow depths and from greater depths, all combined in a manner to make their correct interpretation almost impossible. An irregu-

lar distribution of magnetite in a sandstone a few feet, or a few hundred feet, below the surface of the ground may alter or mask the effects of a large deep-seated body. The safest way to apply the magnetometric method is to work from the known to the unknown. Thus, if a geologic feature such as a dike, or a contact between a high-intensity and a low-intensity rock, exposed and mappable in a certain region, passes beneath a blanket of soil or a




FIG. 564.--Magnetic vertical intensity anomaly map of an area in west Texas in which no definite relation to structure was discovered down to a depth of nearly 5,000 ft. The map represents an area of approximately 280 square miles.

younger series of consolidated strata, it may be traceable for some distance beneath its cover by careful magnetic surveying.

SEISMIC METHODS

519. Elastic Earth Waves.--The seismic methods of geophysical exploration have been widely used in searching for subsurface structures that might yield oil or gas; in localizing certain types of ore deposits; in mapping the bedrock floor beneath gravel deposits

where dams are to be constructed; in measuring the thickness of glacial ice; in studying the configuration of the basement beneath a stratified prism of rocks; and in many other ways. There is no more useful scheme devised for mapping hidden structural features of subsurface geology.

The seismic methods utilize two important characteristics of rock formations: (1) rock materials vary in respect to the speed with which they transmit elastic earth waves, and (2) the sedimentary prisms, in particular, consist of layers that are separated by sharply defined contact surfaces, and these surfaces reflect part of the energy generated as elastic earth waves.

Hard, compact rocks, such as limestone, anhydrite, salt, etc., with relatively high elasticity, transmit shock waves (seismic waves) with greater speed than softer, or less consolidated, rocks. The rate of propagation of seismic waves, on the average, varies from 3,900 ft. per second in ordinary elastic sediments to over 23,000 ft. per second in some of the plutonic igneous rocks.¹ In general, the rate increases with depth, although this fact is not easily determinable except in materials of the same nature. Observations in two localities in east Texas revealed an increase from a speed of elastic transmission of 8,800 ft. per second in a certain formation at one locality to a speed of 9,200 ft. per second in the same formation at a second locality where, 20 miles down the regional dip, it was 1,000 ft. deeper below the surface.

In all areas there is surface layer, called the *weathered layer*, of variable thickness, seldom over 100 ft. thick, but, rarely, as much as 300 or 400 ft. thick, which has a much lower velocity of transmission than the rocks below. Its velocity is usually between 800 and 3,000 ft. per second. The true nature and cause of this layer are not known. It is not strictly a layer of weathered rock materials, geologically speaking. It may be related to the ground water. In any case, there is always an abrupt change in elastic properties in passing down from this weathered zone into the underlying rocks.

¹ Bibliog., AMBRONN, RICHARD, 1928; BARTON, DONALD C., 1929 (b), p. 575; EVE, A. S., and D. A. KEYS, 1929, p. 185.

With regard to the second property mentioned above, seismic waves that travel outward from a point of explosion are reflected back toward the surface of the ground from contact surfaces between strata having distinctly different velocities of wave transmission, *i.e.*, distinctly different elastic properties. There are many such reflecting boundaries (elastic discontinuities) in a prism of strata, but most of the reflections are weak, and only those from the more pronounced contacts are recognizable on the




FIG. 565.—Paths of earth waves produced by an explosion where the underlying strata are horizontal. The beds marked 1, 3, and 5 have a lower velocity of transmission of these waves than beds 2 and 4. *s*, shot point. (See text for description.) Note that the critical angle, α , varies for different formations. It is shown here only with an approximate value, for illustration purposes.

seismographic records. Probably most of these come from the upper surfaces of high-speed beds overlain by low-speed beds, but the reverse is sometimes true; *i.e.*, distinct waves may be recorded from the basal contacts of high-speed strata.

Seismic waves, in their behavior underground, may be compared in many respects with light waves. They undergo transmission, refraction, and reflection. These properties are illustrated in simple and graphic manner in Fig. 565, where *s* is a point, called the *shot point*, at which a charge of dynamite has been exploded. A spherical elastic wave front immediately goes out in all directions from the shot. To simplify the explanation, only

lines of travel (sa , sb , sc , sj) of certain points in the wave front are shown, and only reflections from the top contacts of the high-speed beds are considered. A point in the wave front will travel directly from s along the surface, or close to the surface, of the ground (stw). This is called the *surface wave* or *ground roll*. The point of the wave front going directly down beneath the explosion will be transmitted in part, vertically downward, and reflected in part, from successive high-speed beds (2, 4, etc.), vertically upward. Other points on the wave front, *e.g.*, point b , will partly suffer refraction in passing into bed 2 and will partly be reflected upward from the top surface of 2 at the same angle at which this point in the wave front impinged on 2. Here this part of the wave front will be reflected to b' . The energy that travels along sb and passes into 2 is again refracted in passing into 3, etc., at each surface that separates two layers having different speeds of elastic transmission; and at each change in velocity, as at c , part of this energy is reflected back toward the surface (cc'). As the angle msb increases, at length a critical angle¹ is reached such that the wave front impinging on the surface mn (top of 2) will no longer enter 2 but will be refracted along this contact and upward to the surface of the ground (ee' , ff' , gg' , etc.) along innumerable paths, all of which may be regarded as parallel to ee' , ff' , gg' , etc. These paths will make an angle, tee' , equal to set , with mn . Some of the energy at this angle will be reflected (ee'), and, as the angle of incidence (set) increases, reflections will become progressively weaker (sjj' , etc.). A seismograph located, let us say, at g' will receive some vibrations directly from s (sg), some vibrations reflected from mn (sfg'), and some vibrations refracted from bed 2 ($segg'$).

From these facts one may conclude, with reference to a given reflecting horizon (*e.g.*, mn), that recording instruments (seismographs), made to detect and record the vibrations produced by

¹ This critical angle is set , which equals angle mse , where te is perpendicular to mn at e . The critical angle is defined by the equation, $\sin i = V_1/V_2$, where i is the angle of incidence (set in Fig. 565), V_1 is the velocity of transmission in medium 1, and V_2 is the velocity in medium 2.

exploding a charge at a point, such as s , (1) do not indicate refracted waves from a given rock body if they (the seismographs) are set up too near the shot point—*i.e.*, in Fig. 565, at a distance less than $2\ st$, which may be roughly stated as equal to, or less than, the depth to the reflecting horizon, mn ; (2) indicate refraction waves for the most part if the seismographs are set up at a distance on the surface of the ground as much as two or three times the depth, sm , from the shot point, s , to the reflecting horizon, mn .

Further, note that at c' , for example, although both reflected and refracted waves would be recorded from the top of 2, only reflected waves would be recorded from 4.

In seismic exploration, both the refracted waves and the reflected waves can be used to study subsurface geology. Thus we have two distinct subdivisions of this work, the refraction method that utilizes refracted waves only and the reflection method that utilizes mainly reflected waves. These will be discussed more fully in Arts. 521 and 523.

520. Instruments Used in Seismographic Work.—In seismic surveying an instrument known as a seismograph is used to record the ground vibrations caused by an artificial explosion. There are many varieties of seismograph, which we shall not take space in describing here. The instrument consists essentially of a mass suspended in such a manner that it tends to remain stationary when its support is moved under earth shocks. The relative motion of the mass and the support is utilized to move a small coil of wire in a magnetic field or to vary the magnetic flux through a coil and so generate a very small electric current that is a function of the ground motion. This minute electric current is then amplified from 5,000 to 30,000 times by a vacuum-tube amplifier. After being amplified, the current is conducted to an oscillograph, where it actuates either a string or a coil galvanometer. The motion of the galvanometer is photographed progressively on a strip of photographic paper that moves past a light beam or shadow cast by the galvanometer. One-hundredth-second time-interval lines, as regulated by a device operated by a tuning fork,

are photographed on the paper simultaneously with the galvanometer motion. The time of the shot is transmitted either by radio or by wire and is recorded on the same paper with the record of the seismic vibrations from the explosion (Fig. 574, A and B, x). The recording part of the seismograph may be at some distance from, though connected by wire with, the part that receives the vibrations of the ground, in which case the latter instrument is referred to as a seismometer, geophone, detector, or pickup.

521. The Refraction Method.—The principal object of refraction seismic work is to determine the location and depth of high-speed strata or formations. This is accomplished by plotting the time for transmission of the refracted wave against the distance between the shot point and the recording station. In all field observations this distance must be determined for each recording station, and the exact time at which the charge is exploded must be compared with the exact time at which the impulses are received on the seismographic films.

In the early stages of refraction seismic work, the distance from the shot point to the recording station was determined by the time necessary for the sound wave from the explosion to travel the intervening distance in the air. Because sound waves move more slowly in air (1,100 ft. per second) than in the lithosphere, the air waves arrive some time after the earth waves. In long shots, the earth vibrations may have nearly died out before the air wave is recorded. Since the temperature of the atmosphere, and particularly the direction and velocity of the wind, affect the time of the transmission of sound waves in air, allowance must be made for these factors to correct for distance determined in this way. However, on account of the relative inaccuracy of these corrections, it is no longer common practice to compute the distance from the shot point to recording stations by the sound-wave travel time but, instead, to survey these distances by transit or alidade.

Time is communicated by radio. As soon as each instrument man is ready, he signals by radio, at the same time stating his

identity by a chosen sign. The chief of the party waits until all the instrument men have signified that they are ready, and then he signals to the shooter to fire. When the explosion occurs, a small cap, electrically discharged at exactly the same moment as the cap that fires the main explosion, also explodes and, in so doing, breaks the continuity of the time record that is being




FIG. 566.—Fan "shot" across a prospect to locate a salt dome. *S*, firing station. *a-p*, recording stations. 1-18, stations on preliminary profile, *MN*.

transmitted to the seismographs by radio and thus records the moment of the explosion on the film.

522. Applications of Refraction Seismic Work to Geology.—In field procedure, the seismographs are set up at selected stations (recording stations), *A*, *B*, *C*, etc., and, when the proper time arrives, the charge is exploded at the *shot point*. To reduce the quantity of dynamite needed and to obtain better records, the charge is often placed in holes from 10 to several hundred ft. deep, which are drilled for that specific purpose. The object of this practice is to put the charge *below* (preferably *just below*) the base of the weathered layer.

Field work may be conducted according to one of two main plans: (1) *fan shooting* or *fanning*; (2) *profile shooting* or *profiling*.

The shot points and recording stations for both a refraction profile and a refraction fan are shown in Fig. 566. Unless the normal relation of the velocity of transmission to depth is known from previous experience in the region under investigation, a




FIG. 567.—Group of four intersecting fans, shot in looking for a salt dome in south Texas.

preliminary profile may be run to ascertain the *normal*. Such a profile is ordinarily run along, or near, a road in order to facilitate transportation. The road should be as straight as possible. *MN* in Fig. 566 is a line of preliminary profiling for the area in which the fan was later shot.

Fanning is done where the object is to discover such geologic structures as salt plugs, which have a great vertical extent but are of relatively small and approximately equidimensional horizontal cross section. By covering an area by intersecting fans (Fig.

567), if the radii are close enough, a salt plug of average size and not too deep can hardly be missed, provided the technique of the work is good.

On the other hand, in tracing geologic features of great length as compared with their width in a horizontal plane, like faults or concealed edges of hard strata and the like, or in mapping elongate folds, the refraction method of shooting may be carried out in a series of interconnected profiles laid out essentially at right angles to the direction of elongation of the geologic structure. On each profile, each group of recording stations includes at least one such station from which records were received from two shot points in the line; and, at certain stations in each profile line, records are received from shot points on adjoining lines. In this way all the observations are interrelated. Where indications of abnormal structure have been located and it is desirable to check back, such profiles may be reversed; in other words, the relative positions of the recording stations and the shot point are reversed.

In both refraction methods, final conclusions are based on a comparison of the speed of transmission of refracted waves as they should be under normal conditions with the speed of transmission of refracted waves as actually observed and recorded. If the arrival time of the refracted wave is less than the calculated normal for the area under investigation, the difference obtained by subtracting the shortened arrival time from the normal is spoken of as a "lead" and is expressed in thousandths of a second. These "leads" may indicate the approximate depth and form of high-speed strata or rock bodies in various types of geologic structure.

When the method is fanning, the shot point, on the map, may be taken as the center of a small circle from which, on a chosen scale, the leads noted at the several recording stations are plotted along the respective radii. Thus, in Fig. 568, *s* is the shot point; *a*, *b*, *c*, etc., are the recording seismographs; and *a'*, *c'*, *f'*, etc., respectively, are the leads measured along the radii from the circular base line *xy*. Note that the lead greatly increases in the central area of the fan. This is due to the presence of a salt dome

some 2,000 ft. deep, its outline being indicated by the dotted closed line. We may add that other intersecting fans were shot before this dome was exactly located.

Where profiles are shot, time is plotted vertically and distance between shot point and recording stations, horizontally. In Figs. 569 to 573, taken from Barton,¹ T_1 is the time-distance line plotted for the wave path directly from the shot point to the recording station, through the upper stratum of low velocity of




FIG. 568.—Plotting of "leads" in fan-shooting.

transmission (V_1); and T_2 is the time-distance line plotted for the wave front that reached the lower, relatively high-speed bed (with velocity V_2), was refracted along its upper contact, and then returned to the surface at the recording station. The course of this point in the wave front corresponds to such lines as $seff'$, $segg'$, etc., in Fig. 565. Quoting from Barton,¹ with reference to certain relations of seismicographic records to structure:

"If the higher speed mass is a horizontal stratum of great horizontal extent and if a profile is shot across it, the time distance

¹ Bibliog., BARTON, DONALD C., 1929 (b), pp. 591-593.

graph will consist of two intersecting straight lines, T_1 and T_2 , and the slopes of T_1 and T_2 will be the same for all azimuths (Fig. 569).¹




FIG. 569.—Figures 569-573 show time-distance curves and paths of waves for a series of types of simple geologic structure. Each formation is assumed to be homogeneous and isotropic. Figure 569 is of an infinitely extensive level flat-topped buried high-speed formation. (See footnote to Fig. 546.)

“If the stratum is dipping at a uniform rate, the time-distance graph will consist of the same two straight lines but the slope of T_2 will vary with the azimuth of the profile and will be at a




FIG. 570.—See title to Fig. 569. In Fig. 570, the infinitely extensive buried high-speed formation has a sloping plane surface.

maximum if the profile is shot down the dip and at a minimum if it is shot up the dip (Fig. 570). The angle of dip and the velocity of the lower formation can be calculated by formulas, from the profiles in which T_2 has the maximum and minimum slope respec-

¹ T_1 represents time values of transmission of the seismic waves in the formation having the low velocity of transmission, V_1 ; and T_2 , represents time values for the high-speed formation with velocity V_2 .

tively, and the direction of the dip is the azimuth of the profile in which T_2 has the minimum slope.

"If the stratum is terminated by a scarp (a) on a profile shot from a position over the relatively high-speed mass across the scarp, T_2 is straight up to a critical point beyond the scarp and




FIG. 571.—See title to Fig. 569. In Fig. 571, the level flat-topped buried high-speed formation is cut off by a vertical scarp. A, the profile buried is "shot" from over the high-speed formation across the scarp. B, the profile is "shot" from off the high-speed formation across the scarp. (See footnote to Fig. 546.)

then bends upward to become asymptotic to a line parallel to T_1 (see A, Fig. 571); (b) on a profile shot in the reverse direction, T_2 is a straight line parallel to, but above, the position which T_2 would have if the V_2 formation extended to the left under the firing point, and the graph is the same as if the V_2 bed were deeper and extended under the firing point.

"If the relatively high-speed stratum is faulted, and is present on both the upthrow and downthrow sides of the fault, T_2 is offset at a critical point in front of the fault, (a) upward if the profile is shot from the upthrown to the downthrown side and (b)




FIG. 572.—See title to Fig. 569. In Fig. 572, the level flat-topped buried high-speed formation is cut by a vertical fault. The profile is "shot" from the upthrown side in A, and from the downthrown side in B, in both cases across the fault.

downward if the profile is shot in the reverse direction. The position of the fault in the high-speed stratum . . . and the throw of the fault" can be calculated (Fig. 572).¹

Figure 573 shows the time-distance graph for the top of a buried high-speed mass similar to a salt dome.

Until 1929 or 1930 the refraction method was extensively used, especially in search of salt domes, but since that time it has very largely given place to the reflection method (Art. 523) in geologi-

¹ Bibliog., *Ibid.*, 1929 (b), pp. 592, 593.

cal exploration. Its main value lies (1) in determining the thickness of the low-velocity weathered layer in connection with reflection exploration and (2) in checking anomalies outlined in other types of geophysical work (*e.g.*, gravity exploration) where these anomalies suggest the presence of salt plugs, igneous plugs, etc., buried under a shallow cover. In certain areas, however, where reflections are difficult to get and where there are dense strata present in the underground prism, refraction methods may




FIG. 573.—See title to Fig. 569. In Fig. 573, the buried high-speed mass is the top of a salt dome or other similar buried high-speed mass.

yield more satisfactory results than reflection methods for mapping subsurface structure (*e.g.*, the West Texas Permian Basin).

523. The Reflection Method.—In the reflection method, the distance from the shot point to the recording stations is short (from very short to rarely over 3,000 ft.), as contrasted with the longer distance (commonly from 3 to 7 miles) used in the refraction seismic method. The field instruments for the reflection method, though operating according to the same principles as in the refraction method, differ in their number and arrangement. Consequently, the instruments cannot be used interchangeably in the two methods without suitable adjustments.

In reflection work, as in refraction work, the shot is detonated at the bottom of a hole drilled deep enough to extend through the weathered layer. The detectors are arranged usually in a row




FIG. 574.—Two records made in reflection seismic work. In both the mid-spread method was used (i.e., shot point in middle of detector spread). 1-6, at the left, are the traces secured from six detectors, 1 and 6 being the outside detectors of the spread. Figures from 0 to 16, along the lower margin of the record, are tenths of a second, measured from the instant of discharge (x). z, on each trace, is the first break, i.e., the beginning of reception of vibrations by that detector.

In A, horizontal beds (or reflecting surfaces) are indicated by the fact that the end traces show practically simultaneous reception of each reflection (aa' , bb' , etc.). In B, the beds (or reflecting surfaces) dip in the direction from detector 6 toward detector 1, since each reflection (aa' , bb' , etc.) is recorded on trace 1 considerably later than on trace 6.

along the same line with the shot hole and at equal distances apart. Thus, they may be 50 ft. apart, so that, if there are 12, the outermost 2 will be 550 ft. apart, which distance is known as the *detector spread*. For any setup, there is a single recording station where a single record is made, this record consisting of a number of synchronized *traces*, each one of which is the photographed path of a beam of light from a particular detector or from a compounded group of detectors. Usually there are from 6 to 12 traces on a record (see Fig. 574).

There are two objects in arranging the detectors in this way. (1) Reflected waves must be distinguished from refracted and diffracted waves as recorded instrumentally. For practical purposes, a recorded impulse that shows relatively small differences in its time of reception on the various traces is interpreted as the visible resultant of reflected energy. At least two, and preferably 6 or more, traces are necessary to define a recorded impulse as a reflection. (2) By thus obtaining slightly different recorded time arrivals of a wave reflected from a given rock medium (stratum, etc.), both the depth to and the inclination of the reflecting surface can be calculated (see below).

To compute and interpret reflection data accurately, one must know the average vertical velocity of transmission of elastic waves from the base of the weathered layer down to the various subsurface contacts that produce the reflections. Velocity data for this purpose are secured from deep wells drilled in the area to be investigated. A detector, enclosed in a special case to withstand high pressures, is lowered to known depths in the well, and for each depth a charge is fired at a shot point near the well. At the surface of the ground is recorded the time elapsed between the instant of the shot and the arrival of the first elastic wave at the detector. Two shot points are often used, with the well located midway between them, so that corrections may be made for any deviation of the hole from the vertical.

The fundamental conception of the reflection method of seismic surveying is that specific subsurface strata and contacts, down to depths amounting to many thousands of feet, can be detected by

their specific reflections on records obtained at different locations in any desired area. It is a method by which these reflections can be identified and studied, and their arrival times can be converted into depths. That is, reflection seismic surveying is a physical method of mapping subsurface structure. The records can be used in two ways: (1) the difference in arrival time of a given wave on the end traces can be noted and converted into differences in depth of the reflecting medium to give its inclination along the




FIG. 575.—Diagram to illustrate shot point (*s*) and detector spread (*x* to *y*) in the mid-spread method. *i*, image point. Reflection from *m* to *x* and *y* travel along paths *ssx* and *ssy*, respectively. Note that when the bed is inclined (*B*), the center of that part (*vw*) of the reflecting horizon from which the reflections are received at *x* and *y* is not vertically below the shot point.

line of the detectors; or (2) reflections on a group of records recognizable as coming from the same horizon, can be correlated, and the depth of this horizon below an arbitrary horizontal datum can be plotted at various points on a map, after which contours can be drawn. The first is known as the *dip method* and the second as the *correlation method*. These are more fully described below.

In Figs. 575 and 576 are shown two ways of setting up the detectors in the *dip method*. In Fig. 575 the shot point is midway between the end detectors, which may be from 1,000 to 2,000 ft. apart. In Fig. 576, the shot point is outside the group of detectors and at some distance from the nearest one. The end detectors are usually 1,000 ft. apart. In practice only the travel times

from the reflecting horizon (mn), as indicated on the two end traces (from x and y), are used to calculate the dip, the intervening traces serving merely to correlate reflections across the record. As is evident from the figures, the time of travel for an impulse from s to mn and thence to x and y , will differ according to (1) whether the reflecting surface is horizontal or inclined and (2) whether the mid-spread method (Fig. 575) or wide-spread method (Fig. 576) of dip shooting is followed. The quickest way of translating the time-interval data into distances, and so into dips,




FIG. 576.—Diagram to illustrate shot point (s) and detector spread (x to y) in the wide-spread method. A, B, and C, representing three relations, need no special explanation. The lettering in the diagrams corresponds to that in Fig. 575.

is by graphic plotting on cross-section paper. In this manner segments of the reflecting horizon, or horizons, are plotted in their proper positions with reference to all shot points, and a diagram like that in Fig. 577 is constructed.

There are several variations of the dip method. The foregoing description refers to components of true dip unless the row of detectors is at right angles to the strike. Since usually such a position cannot be selected in advance, the instruments may be set up along two lines at right angles to one another, intersecting midway between the end detectors. By this means dip components along these two rectangularly disposed lines can be obtained, and the resultant true dip can be calculated (Fig. 583).

Sometimes the shot points in the mid-spread method are chosen on a line parallel to the line of detectors. Thus, for each setup, the shot point will be at the apex of an isosceles triangle with the two end detectors at the base angles.

From Fig. 577, obviously only one-half the length of any reflecting surface is charted. For greater accuracy, the series of




FIG. 577.—Section showing dips recorded by mid-spread method with shot points at S_a , S_b , S_c , and S_d . Note that, although the detector spreads (a , b , c , d) are contiguous, end to end, only one-half coverage on reflecting horizons is obtained in this way. (Cf Fig. 578.)

detectors in each setup may be placed to overlap one-half of the adjacent setups; or, to put it in another way, for each setup the shot point may be moved only one-half the length of the spread. In this way the reflecting horizon will be *fully* covered (Fig. 578). This is called the *continuous profile method* of dip shooting.

There are advantages and disadvantages to each of these two methods of dip shooting, but we cannot go into these here. In general the dip method is applicable to any geological province

where weathering is not deep, where the surface relief is not excessive, and where regional and local dips are moderate to fairly high.

The *correlation method* of dip shooting depends, for its success, on the degree of accuracy with which the records, made at different localities within a given district, can be correlated with one




FIG. 578.—Section showing dips recorded by mid-spread method with shot points at *sa, sb*, etc. Here the detector spreads (*a, b, c*, etc.) overlap by 50 per cent, and therefore complete coverage of reflecting horizons is secured. Discontinuous reflection lines are explained by failure to receive reflections from certain horizons at certain stations.

another. The reflections from a geologic section consist of a large number of low energy reflections from the many contacts and beds that have nearly the same physical properties and of a smaller number of high energy reflections from the contacts and beds that have outstanding physical properties. From these a record is made that has definite amplitude and frequency relations between the various reflections. The arrival of the reflections, one after another, produces interference patterns and interval

relations that are governed by the intervals between the subsurface beds giving the reflections. The result is a photographic record of certain physical properties of the subsurface beds and contacts, at a specific location, which has amplitude, frequency, interference pattern, and interval characteristics that make it possible to identify certain reflections on the records and correlate them from location to location with considerable accuracy.




FIG. 579.—S, shot point; x, z, end detectors; y, middle detector. Other detectors between x and z not shown. mn, reflecting horizon (horizontal in A, inclined in B); s, image point. The impulses received at x, y, and z were reflected from point u, v, and w, respectively, on mn. Vertically above u, v, and w are depth points, 1, 2, and 3, which correspond to the positions on a map, where the depth of mn, computed from the traces of x, y, or z, as the case might be, would be plotted.

In the correlation method the detectors are usually set up in a row and in line with the shot point, which, as in the wide-spread dip method, is outside the detector spread. The distance between the end detectors may be from 300 to 900 ft., and within this distance there may be from 5 to 40 or more detectors, equally spaced. The shot point may be from 150 to 300 ft. from the nearest detector. Therefore, provided the reflecting horizon is horizontal, the path of the impulses recorded in the detector nearest to the shot point will be almost vertical, and the trace of

this detector will indicate reflections from points vertically below a point, called the *depth point*¹ (Fig. 579), midway between this detector and the shot point. If the reflecting surface is inclined (Fig. 579, B), the depth point will be shifted, depending on the amount and direction of dip of this surface. Not all the traces on a record are used for computations. For certain reasons, either the trace from the detector nearest the shot point or that from the detector farthest from the shot point or that from the detector in the middle of the spread (x , y , and z , respectively, in Fig. 579, A and B), may serve in calculating the depth to the reflecting medium, and, accordingly, this computed depth may be below 1, or 2, or 3, respectively, in these diagrams. In Fig. 580 are shown three records, taken at three different localities in a certain district where shallow correlatable beds are present. Note that certain reflections can be easily correlated across all three of these records.

524. Applications of the Reflection Method to Geology.—In planning a program for reflection seismic field exploration, several factors must be considered. If, by experimentation or through experience, the dip method would seem to promise satisfactory results, this may be selected instead of the correlation method, but for completeness of the final subsurface picture the correlation method is to be preferred, provided correlatable reflections can be obtained from the formations to be mapped. Actually, in many cases, both the dip and correlation methods are used with the same set of records. No matter where the area is that is to be investigated, a certain amount of preliminary testing is necessary to ascertain the best arrangement of detectors and shot points for securing data under the existing conditions of subsurface stratigraphy, nature of the weathered zone, and topographic relief.

Thus, in preparing to examine an area, whether by dip shooting or by correlation shooting, several methods of attack may be

¹ The *depth point* is the vertical projection, on the surface of the ground, of the point, in a reflecting surface, from which a recorded impulse is reflected. It is the point, on a map, at which the computed depth to this reflecting horizon is plotted.




FIG. 580.—Three records showing correlation of reflections. For study the records are placed as shown, with the top of each record to the left. Tenths of seconds are indicated along the bottom edge of each record, as here placed. The time of reception of the first "valley" of a correlatable reflection (as *a*), where this is found on the middle trace, or two middle traces, on each record, is translated into terms of depth below a chosen datum (here 425 ft. above sea level). Thus, on record 1, the depth of *a* is -1,542 ft.; on record 2, *a* is at -1,585 ft.; and, on record 3, this same reflecting horizon, *a*, is at -1,591 ft. Other correlatable reflections are at *b* and *c*.

In each record, *x* is the time at which the shot explodes, and *y* is the "uphole time," *i.e.*, the time at which the impulse is recorded by a detector placed on the surface of the ground close to the mouth of the hole at the bottom of which the shot is exploded.

followed. If the area is thought to be underlain by a local, more or less equidimensional, structure, two or more lines of observa-




FIG. 581.—Sketch map to show preliminary arrangement of lines of seismic exploration (*ab, cd*) laid out to check a supposed local structure.

FIG. 582.—Grid of lines along which seismic exploration was undertaken in a certain area to investigate a block of land under which sub-surface structural conditions were unknown.

tions may be run, intersecting at the center of the supposed anomaly (Fig. 581). If the geologic structures are long and




FIG. 583.—Map showing locations of isolated observations made by dip method. At each station the true dip was calculated from the dip components measured along the lines that intersect perpendicularly, and was plotted on the map by an arrow the length of which is scaled to represent the amount of the true dip.

narrow (faults, elongate folds, etc.), parallel lines of observations may be run across their trend. On the other hand, if a large

block of land is to be covered, without any previous information as to what structural features may underlie it, observations may be made along intersecting lines laid out as a grid or network (Fig. 582); or, if reasonably good correlatable reflections are obtainable, a number of isolated setups may be made, scattered over the area, and located in the most accessible places along roads, or otherwise (Fig. 583).

In the case where observations are made along intersecting lines in a network, reflecting horizons should be correlated in loops, returning to the starting point; *i.e.*, each polygon should be closed. A definite discrepancy in correlation may thus indicate either an error or the possibility of a fault across the traverse. In this event the records should be carefully reexamined to see if a fault can be located. Where broad reconnaissance is to be done, lines of observation may be far apart, or, in dip shooting, the recording setups may be widely scattered. If more detailed work is required, closer coverage must be planned in the arrangement of detectors and shot points and in the distribution of observation stations.

ELECTRIC METHODS

525. Electrical Conditions within the Lithosphere.—In speaking of the flow of an electric current through a conductor, we may refer to the relative ease with which the flow of energy occurs as the *relative conductivity* of the material, or we may speak of the degree of resistance offered by the material to the current flow as the *resistivity* of the material. An *ohm* is the resistance against which, or through which, 1 volt can force a current of 1 ampere. The *specific resistivity* of a substance is the resistance offered by a *cube* of the substance, 1 cm. on each edge. Specific resistivity is measured in ohms. Conductivity is the reciprocal of resistivity.

Let us imagine a body bounded by a horizontal plane and of infinite thickness and infinite lateral extent, and let us imagine that this body has uniform electrical conductivity (or resistivity). Consider two points, *a* and *b*, (Fig. 585) on the horizontal surface, between which there is a potential difference, the potential at *b*

being lower than that at *a*. As long as this difference of potential is maintained, an electric current will flow from *a* to *b*. This current from *a* to *b* may be conceived of as flowing along an infinite number of curved lines, or *lines of flow*, throughout the entire body. Along each one of these lines there is a potential drop from *a* to *b*. All points of the *same* potential on the different flow-lines lie in a curved surface, called an *equipotential surface*. In such an electrical field there is an infinite number of equipotential surfaces. Any equipotential surface is perpendicular to all the lines of flow (Fig. 585, A). Within this ideally uniform body, the point midway between *a* and *b* is the *potential center*.

In the lithosphere there is nowhere a condition of uniform electrical conductivity (or resistivity). Rock masses differ very greatly in respect to this property.¹ Dry rocks are poor conductors. Coal and salt, when dry, are very poor conductors, having a high resistance to the passage of electrical currents through them. However, under natural conditions, rock bodies are more or less wet, either on their outer surfaces or within their pore spaces. The result is that the electrical conductivity of a rock body is usually dependent more on its interstitial (pore space) content of water, and particularly on the nature and amount of soluble salts dissolved in this water, than on the mineral characteristics of the rock itself. Fresh water is comparatively resistant to the flow of electrical energy, whereas salt water is an excellent conductor. Clays and shales, having pore spaces too small to permit circulation, and, therefore, containing more or less original connate salt water, may be better conductors than sands or sandstones in which greater freedom of circulation has diluted and freshened the included water. Sundberg states that "for practical purposes . . . the specific resistance of a natural water is generally determined by its content of chlorine."² He gives the following table of the estimated resistivity of different rock materials when their pore spaces are filled with fresh or nearly fresh water, and when filled with salt water.

¹ See discussion of this subject on p. 573, under 430.

² Bibliog., SUNDBERG, KARL, 1930.

SPECIFIC RESISTANCE IN OHMS PER CUBIC CENTIMETER¹

Rock	Pores filled with surface water or ground water	Pores filled with salt water
Limestone and sandstone.	100,000–1,000,000	500–4,000
Sand and clay.....	40,000–400,000	200–2,000
Marl, loess.....	2,000–20,000	20–200

¹ Bibliog., SUNDBERG, KARL, 1930.

The specific resistance of crude petroleum is enormously high as contrasted with most other subsurface materials in sedimentary formations. It amounts to 10^{10} to 10^{16} ohms.

Because of the diversity of conditions within the lithosphere, the effects of the diurnal heating and cooling of the earth's surface in its rotation, the effects of magnetic storms and variations in the earth's magnetic field, and other causes, there are always local and regional differences of potential within the earth. These differences of potential result in the flow of electrical energy from places of higher potential to places of lower potential. These natural currents are called *ground currents* or *earth currents*. They are very irregular and are subject to frequent change. In some localities, as for instance in areas underlain by sulphide ore bodies, they may have considerable strength.

526. Classification of Methods of Electrical Surveying.—The many methods which have been practiced or tested in electrical prospecting may be classified in two main groups:

1. Self-potential or electro-chemical methods, which make use of earth currents;
2. Those methods which utilize electrical fields of force artificially produced. These include: (a) resistivity methods, (b) surface potential methods, (c) induction, or electromagnetic methods, (d) radiation methods,¹ and (e) the electrical transient method.

¹ We shall not discuss the radiation, or high-frequency, methods in this book.

In all these methods the underlying principle involved is the measurement of the deviation of the observed electrical properties from the values or directions which these properties would have under ideal conditions of uniform conductivity, like those postulated in Art. 525. In the case of electric currents and fields, we speak of these deviations as the distortion of flow-lines, or the distortion of equipotential lines, or the displacement of the potential center.

The reader will note that all but the self-potential methods may be compared with the seismic method in that the results sought are based on a study of artificially applied fields of force. The self-potential methods in this respect are more like the gravimetric and magnetometric methods, which deal with natural fields of force.

With reference to the second group of methods, which utilize an artificial current, it is customary to balance out any earth currents before taking readings on the artificial field.

In some methods of electrical prospecting the artificial field is established inductively. In others, it is produced by means of ground contacts through which the electric current flows. This is done by means of electrodes which are connected above ground by adequate wire leads to a source of current supply and below ground by the earth itself, thus completing the circuit. One of the difficulties attached to these electrical methods, in using uninterrupted direct current, depends on the fact that ground contacts or electrodes, if not very carefully prepared and used, tend to become polarized through local chemical action, which may cause variable potentials between the electrodes of such magnitude as seriously to modify or mask the current effects to be measured. This polarizing effect can be overcome by certain methods of reversing the energizing current applied to the electrodes.

The self-potential methods have their greatest value in mining districts where some success has been attained. We shall not dwell upon these methods here.¹

¹ Bibliog., HEILAND, C. A., 1929, p. 102; AMBRONN, RICHARD, 1928, pp. 155 *et seq.*; FIVE, A. S., and D. A. KEYS, pp. 53 *et seq.*

527. Methods Which Utilize Electrical Fields of Force Artificially Produced.— First among these methods are those which involve the measurement of earth resistivity between selected points. These are the *resistivity methods*. Here belong the Gish-Rooney method, the "Megger" method, the Jakosky method, and others. Four electrodes are staked in the ground at equal distances along a straight line. The distance from each outer electrode, C_1 and C_2 , to the nearest inner electrode, and the distance between the two inner electrodes, P_1 and P_2 , may be referred to as D . A current (either direct current or alternating current) flows through the ground from C_1 to C_2 , the difference in potential between P_1 and P_2 is measured, and the resistance between P_1 and P_2 is calculated. Experience has shown that for practical purposes and at relatively shallow depths, the resistivity of the earth or soil can be measured in this manner to a depth equal to D . Therefore, by starting observations with the distance, D (C_1 to $P_1 = P_1$ to $P_2 = P_2$ to C_2) small, and then successively increasing D by regular stages, it is possible to measure the resistance of the earth to greater and greater depths. Hence, in plotting a curve of resistivity for increasing depth, any marked break in the curve will indicate the presence of a body of either lower or higher resistivity, as the case may be. By making readings of this kind over a wide area, obviously a system of elevation points can be secured for contouring such a body. In this way, it is sometimes possible to map the subsurface configuration of buried river channels, shallow salt domes, groundwater levels, faults, etc.

Details regarding the several resistivity methods may be found in the publications already cited.

The second group of methods utilizing an artificial current, includes the *surface potential methods*. According to one plan, the *linear electrode method*, developed by Hans Lundberg, two copper wires, 2,000 or 3,000 ft. long, are laid on the ground parallel to one another, and 2,000 ft. or more apart. These wires are connected to the ground by stakes at intervals of 100 ft. One pair of adjacent ends of the wires is connected to a generator

which supplies a current (A.C. or D.C.) that flows through one wire, entering the ground at the several electrodes (stakes), passing through the ground and into the other main wire, and so back to the generator. If the subsurface were homogeneous, the current flow lines would be approximately perpendicular to the main wires and the equipotential lines would be approximately parallel to these wires. Any relatively highly conducting body within the field will crowd the current flow-lines as observed on the surface and will cause the equipotential lines to bend out around it (Fig. 584). A highly resistant body will have the opposite effect.¹

In Schlumberger's direct current (D.C.) method, the *point electrode method*, an electric field is produced by supplying an electric current to the ground through two primary point electrodes. With "secondary" or "exploring electrodes," the form and distribution of the lines of flow, or the form and distribution of the equipotential lines on the earth's surface, between the two electrodes, can be studied and mapped. Above a good conductor within the depth limits of the method the equipotential lines will spread apart, and above a bad conductor they will crowd together (Fig. 585). By Schlumberger's method some success has been achieved in mapping buried anticlinal and synclinal structures (Fig. 586), faults concealed beneath alluvium, shallow salt domes, ore bodies, etc.²

A method developed by S. H. Williston and C. R. Nichols, called the *potential center displacement method*, is designed to identify on the ground the potential center of the field artificially created, and to measure the amount and direction of the displacement of this point from the geographic center which it would occupy if the earth had uniform electrical conductivity. The displacement of the potential center is an index of the sum of the distortions which may be caused in the electric field by irregular distribution of resistance characteristics below the

¹ In using alternating current of sufficiently high frequency, capacitive and inductive effects, as well as the conductivity of the body, become of importance.

² Bibliog., LEONARDON, E. G., and SHERWIN F. KELLY, 1929.




FIG. 584.— Current flow-lines (dashed) and equipotential lines (solid) in a field established by two parallel linear electrodes, aa' and bb' . A body of high conductivity, c , would distort the field as indicated in the figure.




FIG. 585.—A, current flow-lines (dashed) and equipotential lines (full) in a field established by two point electrodes in a medium of uniform conductivity. A body of high conductivity (c) would distort the field as indicated in B.

surface of the ground and still within the effective exploration depth and radius of the field. Field observations are made along a straight line, carefully surveyed, on which station points are staked out at regular intervals, I , of 250 or 500 ft. On this




FIG. 586.—Map of the region of the Boldeschii anticline in Roumania, showing lines of equal resistivity (1, 2, 3, and 4) as determined by the Schlumberger method. These lines correspond fairly well with contours on the structure (not shown). (After E. G. Leonardon and S. F. Kelly. From "Geophysical Prospecting: 1929," published by the A. I. M. M. E. See Bibliog., McLaughlin, R. P., 1929.)

line, the primary electrodes are placed at a much greater distance, D , apart, ranging from 3,000 to 10,000 ft. The field is then energized for a short period of time, and the potential center is located and mapped. The whole system is next "stepped" forward, still maintaining I and D constant, and the procedure is repeated. In this manner, step by step, the full length of the

line is surveyed. The effective exploration depth may be regarded as roughly equivalent to $D/2$.

By successive series of observations of this kind, with a different value for D in each series, the effective exploration depth may




FIG. 587.—A, potential center displacement profile. B, map of an oil field, showing line of electrical observations, ab . In these figures only the components of displacement along the line ab are represented. In A, the amount of this displacement of the potential center is shown in feet, eastward above the zero line, or base line, and westward below the base line. The greatest displacement was found at s and t . In B, any displacements of more than 30 ft. are shown by a symbol of which the total length of the cross line represents the amount of this displacement, and the arrow head indicates the direction. Note that the maximum displacements, s and t (corresponding to s and t in Fig. 587, A) lie close to the east and west edges of the oil pool.

be decreased or increased, thus enabling the observers to study the subsurface conditions at various depths.

The data obtained are plotted in the form of a potential center displacement profile (Fig. 587, A). The displacements are at a maximum approximately over the edges of a relatively highly resistant body with lateral limits. In other words, this method is devised to outline the edges of laterally discontinuous highly resistant bodies. It can be applied in the mapping of subsurface

geologic structures, and also in the search for, and mapping of, hidden ore bodies (low resistance), and oil pools (Fig. 587).

In these or other equipotential methods, where direct current is used, the depth of penetration is assumed to be roughly one-half the horizontal distance between the primary electrodes. Within reasonable limits, therefore, the farther apart these electrodes are placed, the deeper can one explore below the earth's surface; but it is to be remembered that this statement does not take into account possible screening effects at the shallower depths, nor the relative strength of the effect being sought or measured at the greater depths. Within a given distance below the surface, other things being equal, a weak conductor or a moderately resistant body might not be detectable, whereas a good conductor or a highly resistant medium might be discovered.

A third group of electrical methods, founded on artificial electrical fields, includes the *induction* or *electromagnetic* methods. As an example of one of these, we may briefly outline the Swedish-American method. "An insulated copper cable is laid on the ground, usually in the shape of a large rectangle. An alternating electric current of moderate frequency is sent through this cable, and the resulting electromagnetic field," induced in the ground, "is measured . . . along transverse profiles which cross the cable at regular intervals. Usually the electromagnetic field is measured on each transverse line at several different distances from the cable, and both the horizontal and vertical components of the field are measured in regard to amplitude and phase."¹

The transverse profiles are commonly laid out from $\frac{1}{2}$ to 1 mile apart, and the observation points along these profiles are from 500 to 1,500 ft. apart. In its application to structure mapping in regions of sedimentary beds, this method is based on the fact that, in any sedimentary series, some beds are of relatively high conductivity, and so partially shield underlying strata from penetration of the electromagnetic effects. The depth to such a conducting body is determined at numerous points to be used in structure mapping. Experience has demonstrated that

¹ Bibliog., SUNDBERG, KARL, 1930.




FIG. 588.—Map of part of the Bruner or Salt Flat oil field in Caldwell County, Texas. *AB* is the position of a fault determined at a shallow depth by the inductive method of electrical surveying. *CD* is the trace of the same fault (which dips west) where it cuts the top of the Edwards limestone, much lower in the series than the formation cut at *AB*. The section lines (IV and V) are the lines along which electrical observations were made in this part of the field. (See Fig. 589, and also compare Figs. 550 and 561). Figure 588 copied from Hedstrom, with modifications. See Bibliog., HEDSTROM, HELMER, 1930. Reproduced with permission of the Am. Assoc. Petr. Geols.)

GEOPHYSICAL SURVEYING

laterally a conducting stratum or group of strata may maintain its characteristics of conductivity and thickness (which together give




FIG. 589.—Sections IV and V showing electrical profiles (through crosses) in relation to Salt Flat structure. (After Hedstrom.) (See Fig. 588.) (Reproduced with permission of Am. Assoc. Petr. Geol. See Bibliog., HEDSTROM, HELMER, 1930.)

the so-called induction factor, the quantity recorded) over considerable distances.

In general there is one *electrical transient method*, known by the trade name Eltran, but it may be varied in many ways. This

method utilizes "a rapidly changing direct current which may be either a simple sharp change in magnitude of current, or a short intense unidirectional pulse of current."¹ The earth is excited by these short-period electrical impulses introduced at one or more pairs of spaced current electrodes, and the voltage appearing at potential electrodes is passed into an instrument called an *oscilloscope*, where the wave form is photographed. Variations in wave form are presumed to be caused by changes in the electrical properties of the underground mediums investigated. This method is being applied more particularly in trying to localize areas that may be underlain by oil.

SUMMARY ON THE GEOPHYSICAL METHODS

528. Limitations of Methods.—In the structure of the lithosphere, rock formations of varying physical character are variously disposed. On the average, rocks are denser with depth; but in some places formations of relatively low density are buried deeply, and in other places very dense rocks are near the surface. Similarly, from one locality to another there may be wide differences in the elasticity of the underground formations. Or, again, materials of comparatively high magnetic susceptibility may be at slight depths in one district and at great depths in another district. And finally, marked differences may be observed in the electrical conductivity of certain formations contrasted with others.

Theoretically, any subterranean rock body can be distinguished, by geophysical measurements, from adjacent rock bodies from which it differs in respect to any of these properties; but in practice the results of such measurements are distinctly limited, partly because of the inadequate sensitivity of the instruments, partly because of the difficulties of making accurate observations under field conditions, and partly because of the difficulty, and often impossibility, of discriminating between the numerous unknown subsurface effects which together, at any given locality, compose the resultant actually measured.

¹ Bibliog., Rust, W. M., Jr., 1940.

It is very important that the geologist should recognize: (1) that, in geophysical surveying, methods are available which he may be able to use to advantage in seeking an explanation of subsurface structure; (2) that all these methods have limitations which must be understood and evaluated as far as possible for the most satisfactory interpretation of the results; and (3) that all these methods are not equally suitable for any given area or problem. The best method must be selected after careful consideration of all the factors involved.

Of the four groups of geophysical methods which we have briefly described the seismic and gravimetric methods have yielded the most reliable results, yet even in these analysis of the data is difficult and should be attempted only by persons who have had adequate experience.

APPENDIX

APPENDIX I

GEOLOGIC TIME SCALE

Geologic time is subdivided into eras, periods, epochs, etc. The corresponding names for the rock bodies are sequences¹ or groups, systems, and series, respectively. Note that the titles under these subdivisions are arranged in the list, with oldest at the bottom of the column and youngest at the top, in the stratigraphic sequence of the formations which they represent.

Era of Group	Period or System
CENOZOIC	Holocene (Recent) } Quaternary
	Pleistocene
	Pliocene
	Miocene } Tertiary
	Oligocene
	Eocene
MESOZOIC	Cretaceous (Upper Cretaceous) } Cretaceous
	Comanchean (Lower Cretaceous) }
	Jurassic
	Triassic
PALEOZOIC	Permian
	Pennsylvanian } Carboniferous
	Mississippian
	Devonian
	Silurian
	Ordovician
PROTEROZOIC	Cambrian
	Keweenawan
	Animikian
	Huronian
ARCHEOZOIC	Algonian ²
	Sudburian
	Laurentian ²
	Keewatin

¹ The word "group," although originally proposed for the rock body equivalent of the time division, "era," is now more commonly applied to a much smaller division. Hence some geologists prefer to use "sequence," as recommended in 1933 by R. C. Moore. See a discussion of this and other similar terms in *Geol. Soc. Am., Bull.*, vol. 51, No. 9, pp. 1397-1412, September, 1940.

² Although "Algonian" and "Laurentian," as now used, refer to periods of mountain building and batholithic intrusion, further investigation of the Pre-Cambrian terrane may reveal stratified formations which were of contemporaneous origin.

APPENDIX II

IDENTIFICATION TABLE OF COMMON ROCK MINERALS¹

Nonmetallic light- colored	Hard	Show cleavage	Flesh-colored, stubby	Orthoclase
			Gray-white, lathlike, striated	Plagioclase
			Green columnar	Actinolite
			Gray or red, greasy luster, sol.	Nepheline
	Soft	Fracture only	Isometric crystals in dark rocks	Leucite
			Green, glassy, granular	Olivine
Nonmetallic dark- colored	Hard	Cleavage	Fine-grained, yellowish green	Epidote
			Glassy, variously colored	Quartz, chert
			Cubic, salty taste	Halite
			Rhombohedral cleavage, $H = 3$	Calcite and dolomite
	Soft	Fracture	Flexible plates, etc., $H = 2$	Gypsum
			Rectangular cleavage, $H = 3.5$	Anhydrite
			Soapy feel, $H = 1$	Talc
			Elastic mica	Muscovite
			Fibrous, brittle, $H = 2-4$	Zeolites
			Fibrous, flexible, $H = 2-4$	Asbestos
	Hard	Cleavage	Yellow, burns with blue flame	Sulphur
			Earthy	Kaolinite
			Waxy look, $H = 4$	Serpentine
			Soapy feel, $H = 1$	Talc
	Soft	Fracture	Black { cleavage about 90°	Angite
			{ cleavage about 60°	Hornblende
			Green, poor cleavage	Epidote
			Dirty green	Epidote
Metallic- colored	Hard	Fracture	Brown, orthorhombic	Staurolite
			Red, isometric, glassy	Garnet
			Black, hexagonal columns fluted	Tourmaline
			Variously colored, waxy	Jasper, quartz
	Soft	Fracture	Black to red, conchoidal	Obsidian
			Brown to black, elastic mica	Biotite
			Green to dark blue-gray, $H = 1$	Chlorite
			Brown rhombohedrons	Siderite
	Black	Streak	Earthy	Clay
			Green to dark blue-gray, $H = 1$	Chlorite
			Green, waxy, $H = 4$	Serpentine
			Green, dark, sandy grains	Glaucconite
Metallic- colored	Black	Streak	Hardness = 6 { strongly magnetic	Magnetite
			{ weakly magnetic	Ilmenite
			Hardness = 1 to 3	Graphite and coal
			Streak red	Hematite
	Red	Streak	Streak yellow	Limonite
			Metallic	Copper
			Earthy	Hematite
	Yellow	Streak	Metallic, black streak, $H = 6$	Pyrite
			Earthy, yellow streak	Limonite

¹ Reproduced with permission of Prof. Frank F. Grout and D. Van Nostrand Company, Inc., from p. 20 of Grout's revised edition of "Kemp's Handbook of Rocks," published in 1940 by D. Van Nostrand Company, Inc., New York.

APPENDIX III

CLASSIFICATION OF IGNEOUS ROCKS¹

Mineral constituents	Dominant feldspars are orthoclase and microcline	Potash feldspar and plagioclase in nearly equal proportions	Dominant feldspars are plagioclase	Little or no feldspar present
Quartz is a principal constituent	(A) Granite (B) Rhyolite (C) Aplites	(A) Granodiorite (B) Dellenite	(A) Quartzdiorite (B) Dacite	
Quartz negligible or absent	(C) Felsite			
	(C) Trap			
	(A) Syenite (B) Trachyte	(A) Monzonite (B) Latite	(A) Diorite (B) Andesite	{ dark minerals, chiefly hornblende or biotite or both (A) Peridotite, etc.
			(A) Gabbro (B) Basalt	{ dark minerals, chiefly pyroxene or olivine or both (B) Limburgite, etc.
Feldspathoids present	(C) Lamprophyre			
	(A) Nepheline syenite (B) Phonolite	(A) Nepheline monzonite (B) Vicoite	(A) Theralite (essexite) (B) Tephrite and basanite	(A) Missouriite, etc. (B) Nephelinite, etc.

¹ This classification has been compiled from tables by Pirsson (see Bibliog., PIRSSON, L. V., and A. KNOFF) and tables prepared by F. M. VAN TUYL and H. T. U. SMITH.

In using the table, note that (A) refers to granitoid (even-granular, coarse-grained, or phaneritic) rocks, whereas (B) refers to felsitic (fine-grained or aphanitic) rocks. If rocks under these groups are porphyritic, add the word porphyry to the class. Thus, we may have granite porphyry, rhyolite porphyry, basalt porphyry, etc. In the same manner names preceded by (B) may be used before obsidian to indicate that the aphanitic rock is glassy; thus, rhyolite obsidian; trachyte obsidian; etc. Finally, breccias and tuffs, belonging to the pyroclastic group may be designated as rhyolite breccia or tuff; trachyte breccia or tuff; etc. (C) refers to special rocks that occur as dikes, usually either finely granular or aphanitic.

APPENDIX IV

CLASSIFICATION OF SEDIMENTARY ROCKS

A. ROCKS PARTLY OR WHOLLY MECHANICAL IN ORIGIN, CONSISTING OF PARTICLES OR FRAGMENTS OF PREEXISTING ROCKS

(a) Constituent particles or fragments distinctly visible			
		<i>Unconsolidated</i>	<i>Consolidated</i>
Psephite ¹ group	Residual	Residual gravels	Coarse arkose Arkose conglomerate Arkose breccia
	Transported	Talus Landslide debris Till Gravel, pebbles, etc. Volcanic bombs, fragments, etc.	Talus breccia Landslide breccia Tillite Conglomerate Volcanic breccia, agglomerate
Psammite ¹ group	Residual	Residual sand	Arkose from feldspathic rocks Graywacke from ferromagnesian rocks
	Transported	Sand (fluvial, marine, etc.) Volcanic ash	Sandstone Tuff

(b) Constituent particles indistinguishable; rock very fine-grained

		<i>Unconsolidated</i>	<i>Consolidated</i>
Pelite ¹ group	Residual	Residual clays, laterite, terra rossa, etc.	Residual claystones, etc.
	Transported	Clay Mud Loess, adobe Glacial clay (rock flour)	Claystone, argillite Mudstone, shale, slate

B. ROCKS OF CHEMICAL ORIGIN, SOMETIMES INDIRECTLY DUE TO THE ACTION OF ORGANISMS. MORE OR LESS FIRMLY COMPACTED

Calcareous series	Tufa, travertine, oolitic limestone, dolomite
Siliceous series	Siliceous sinter (geyserite), chert, flint
Iron ores	Ferrous carbonate (siderite), greensand, bog iron ore, hematite
Evaporation products	Gypsum, rock salt, alkali, etc.

C. ROCKS DIRECTLY OF ORGANIC ORIGIN

	<i>Unconsolidated</i>	<i>Consolidated</i>
Calcareous series	Shells and shell fragments	Shell limestone Coral limestone
	Ooze	Chalk
Carbonaceous series	Peat, etc.	Coal series
Siliceous series	Diatomaceous earth	Tripolite
Phosphates	Guano, etc.	Phosphate rock

¹ These terms are derived from the Greek. The equivalent terms, derived from the Latin and preferred by some geologists, are rudite (from *rudus*, rubble), arenite (*arena*, sand), and lutite (*lutus*, mud).

APPENDIX V

CLASSIFICATION OF METAMORPHIC ROCKS

A. ROCKS WITH A PARALLEL STRUCTURE WHICH IS OFTEN VERY CONSPICUOUS

Constituents principally silicates and quartz	Gneisses Schists (mica schists, chlorite schists, hornblende schists, talc schists, etc.) Slates Phyllites
Principal constituents carbonates	Impure marbles and dolomites
Principal constituents hematite and quartz	Itabarite
Principal constituent carbon	Graphite

B. ROCKS COMMONLY MASSIVE; SOMETIMES WITH POORLY DEVELOPED PARALLEL STRUCTURE

Constituents principally quartz or (and) silicates	Quartzite Hornfels Serpentine Soapstone Many diverse products of thermal metamorphism
Principal constituents carbonates	Marble Dolomite
Principal constituents magnetite, quartz, etc.	Magnetite rock

APPENDIX VI

TABLE FOR THE IDENTIFICATION OF CLASTIC SEDIMENTARY ROCKS¹

This table is applicable to both the unconsolidated and consolidated states. For the sake of brevity, however, a deposit, when referred to, will be given one name and not all the terms which might be applied to it in its different stages of lithification. The primary division of the table is based on texture, for this is perhaps the most striking character of clastic materials. There are three grades, psephites, psammites, and pelites (see Appendix IV). In assigning a deposit to one of these groups difficulty may be experienced because there is sometimes great variation in texture even in small exposures. In such a case, if one grade of coarseness predominates (*e.g.*, gravel), look up the material under that grade. If two or three grades are about equally represented, look up the material under the coarser grade. Remember that all the features noted for a particular kind of rock are seldom present; also, that one characteristic feature is not enough to determine the origin or classification of a rock. Study the deposit carefully and suspend judgment until every possibility has been considered.

Under "Sites of Deposition" are mentioned the principal areas where deposition of the sediment may occur. "Structure" refers to the arrangement of the constituent particles and fragments, and to the nature of the bedding in stratified materials. In the column headed, "Surface Features" (omitted under psephites), are remarks on ripple marks, sun cracks, and other phenomena which form on the original surfaces of sands, muds, and clays. The larger constituents of the psephites (pebbles, etc.) and the finer matrix in which these are embedded receive attention in separate columns which together correspond to "General Characters" in the sections on psammites and pelites. Under "Associated Materials" are mentioned only a few significant associations out of many which might be cited. The student will find it advantageous to look back in the earlier chapters of the book for the more complete descriptions of the features listed in this table.

¹ See Art. 106.

PSEPHITES (GRAVELS, CONGLOM-)

	Sites of deposition	Structure	Matrix
Marine and Littoral	Nearly all littoral, high on beach.	Pebbles usually touch one another. Well sorted. Pebbles may have a definite arrangement. Structure may be pell-mell. Larger stratification good; may not be visible. Local unconformity and cross-bedding occasional. There may be sand lenses which are elongate parallel to the shore line. Rarely over 100 feet thick.	Clear sands, fairly well sorted. Grains angular to rounded.
Lacustrine	On lake beaches, principally above the water line.	Similar to marine.	Similar to marine. Less well sorted and less clean.
Fluviatile	Alluvial cones and piedmont plains, along channels of rapid streams; small deltas.	Frequent textural variation. Sand lenses common; these often cross-bedded and showing contemporaneous erosion at their upper surfaces. They are elongate parallel to the course of the stream. Tendency for materials to accumulate in discontinuous layers. Beds vary greatly in thickness. Sorting may be very poor, like some till. Matrix may be so abundant that pebbles do not touch one another. Cross-bedding and local unconformity frequent. Series may be many hundred feet thick.	Poorly sorted. Grains angular to rounded. More apt to be rounded than lake and marine sand grains.
Aqueoglacial	Typically in kames and eskers and upper layers of sand plains; also up-stream part of valley trains and outwash aprons.	Very similar to fluvialite alluvial cone gravels as described above. Stratification may be good, poor, or absent. Structure often pell-mell owing to rapid deposition or to slumping after deposition.	Poorly sorted; angular and subangular grains predominate. Many grains may consist of feldspar and other decomposable minerals.

ERATES, BRECCIAS, ETC.)

Larger fragments (pebbles, etc.)	Associated materials	Relations to subjacent materials
Well-rounded, smooth, with a dull polish. Size pretty uniform.	Sands and sandstones; sometimes limestone which is apt to be of organic origin.	May rest unconformably upon a wave-scoured rock platform. May overlie continental deposits conformably or unconformably. Typically basal.
Similar to marine, but less well rounded and sorted.	Sands and sandstones. Associated limestones apt to be of chemical origin.	May rest unconformably upon an old rock surface or conformably above continental deposits of other kinds.
Of all sizes, up to several tons in weight. Subangular to rounded. Some angular.	Sands and sandstones, usually cross-bedded. Mudstones may be intimately associated, in thin beds.	Usually lie upon an eroded rock floor. If upon finer sediments in the same formation, local unconformity generally separates the two.
Typically subangular. Large striated boulders may be found, these having been ice-raftered or having dropped in from adjacent ice walls.	Sand or sandstone. May be till.	May rest upon till, wash, or bedrock. Local or regional unconformity may separate these deposits from the underlying materials. If bedrock underlies, it is apt to bear marks of glacial abrasion.

PSRPHITES (GRAVELS, CONGLOM-

	Sites of deposition	Structure	Matrix
Glacial	In the area originally covered by the ice, or an marginal deposits. Till belongs here.	Till and tillite have no true bedding. They may contain isolated nests and small beds of sand, which are often contorted. They consist of an unstratified mass of miscellaneous unsorted rock material.	If arenaceous, sand grains angular. Fresh feldspar and other decomposable minerals may be present. If fine, consists of rock flour which may contain scattered sand grains.
Eolian	Chiefly in deserts. Here belong lag gravels. They are usually in thin accumulations.	No definite structure is found in lag gravels because they are merely residual in the sense that they have been left behind by the wind.	Probably of typical wind-worn sand (q.v.).
Volcanic	On or near volcanic vents.	Bedding may be lacking or there may be a rude stratification due to sliding of the materials.	Volcanic sand and dust (q.v.).
Gravity	Talus at base of cliffs or on steep hill slopes. Rock glaciers in valleys in cool climates. Various places where mass movements may occur.	Bedding is absent. Talus and similar gravity accumulations are heterogeneous and unsorted, although there is a tendency for the heavier fragments to roll farthest.	Grains commonly angular, ranging in texture to the fineness of powder.
Residual	In regions of disintegration. May be the result of differential weathering of a conglomerate or similar rock or the result of spheroidal weathering.	No true bedding is developed in these materials, for there is no process of mechanical sorting to which they are subjected.	May consist of disintegration sand or eolian sand (q.v.).

ERATES, BRECCIAS, ETC.)—Continued

Larger fragments	Associated materials	Relations to subjacent materials
Angular or subangular, with snubbed ends and striated facets. Of all sizes. Proportion of pebbles to matrix varies. Pebbles may bear concave fracture scars. If not lithified when handled by the ice, fragments may be very angular and may be distorted.	May be associated with aqueoglacial materials.	If basement was not lithified, the underlying materials are apt to be disrupted and contorted. Striae are wanting. If basement was consolidated rock, it may bear striae or grooves of glacial origin. Sometimes it is fractured and the upper parts may be thrust over the lower.
Faceted einkanter, dreikanter, etc. Subangular, and with polished and often pitted faces.	Probably eolian sands.	The basement rock may show evidences of wind abrasion.
Angular, sharp-edged. Broken blocks of all sizes. Often consist of volcanic rocks, but may be fragments of country rock through which lava was ejected. Volcanic bombs may be associated.	Volcanic ash, mud flow, or lava.	No necessary relation.
Angular or subangular. Fragments may have had edges dulled by sliding or by weathering while exposed. Surfaces may be somewhat scratched.	No special association.	In case of landslides, basement rock may be scratched. No important relation for talus. Basement beneath rock glaciers may be striated and grooved by the movement of the materials.
If due to spheroidal weathering, well-rounded and with rough surfaces. If due to differential weathering, characters depend upon original source. (May be pebbles or fragments from any kind of a conglomerate, or they may be concretions.)	Associated with the parent rock.	Boulders of weathering grade down into the unaffected rock. Residual deposits due to differential weathering lie upon the roughened surface of the parent rock.

PSAMMITES (SANDS)

	Sites of deposition	Structure
Marine and Littoral	Sea sands are situated chiefly in the littoral belt. Those which are constantly submerged are usually fine and local.	Beach sands (not including dunes) have a gentle seaward dip. Their bedding may be fairly regular, but cross-bedding is not uncommon, especially in bars and reefs. Isolated boulders and "pockets" or "nests" may be found.
Lacustrine	Lake sands belong to the shore zone surrounding lakes. They may extend a few rods under water.	Similar to marine sands and sandstones.
Fluvialite	Chiefly in relatively small deltas, along river courses, and in the lower parts of alluvial cones.	Bedding is highly irregular. Numerous gravel or conglomerate lenses. Cross-bedding and local unconformity common. Cross-bedding often due to migration of bars downstream. Length of gravel or conglomerate lenses parallel to course of current.
Aqueoglacial	In valley trains, outwash plains, and some eskers and kames.	Typically cross-bedded. Great irregularity of stratification seen particularly in kames and outwash plains. Frequent local unconformities and current ripple marks. Individual beds vary in thickness. Gravel is often interbedded. Isolated boulders and gravel pockets may be found.
Eolian	Deserts and beaches.	Typically cross-bedded. Curvature of cross-lamination often flatter than in water-made cross-bedding. May contain clay galls.
Volcanic	Near volcanoes. (Includes ash and small lapilli.)	Bedding may be absent or it may be well developed. If the ash was wind-laid, eolian features may be seen. If it settled in water, lacustrine structure may be seen.
Residual	Chiefly in dry, hot or cold climates. Locally, in temperate humid climates.	Bedding is absent. The materials may contain structures inherited from the parent rock.

AND SANDSTONES)

Surface markings of the deposit	General characters
Ripple marks and wave marks typical. Rill marks, footprints, and current marks may be found.	Well-sorted. Sands are cleaner than lake and river sands.
Wave marks and rill marks rare. Ripple marks, current marks, footprints, etc., may be preserved.	Grains less rounded than in marine sands. Less clean.
Current marks common, but wave ripple marks and other beach features are lacking	Grains rounded to subangular.
No characteristic features. Current marks and ripple marks may be present.	
Rill marks may be found on the lee sides of isolated pebbles.	Grains well-rounded and with a dull polish. There may be some scattered sharp-edged particles. Mica plates may lie at various angles.

PELITES (MUDS, CLAYS, MUDSTONES,

	Sites of deposition	Structure
Marine and Littoral	Continental shelves, especially in front of river mouths (estuarine). Sometimes littoral.	Typically with uniform bedding. May be thinly banded; or if conditions of accumulation were very uniform, bedding may be absent. Cross-bedding and local unconformity rare; if present, made by submarine currents. Isolated, ice-rafted boulders possible, but not characteristic.
Lacustrine	Lake floors. May be exposed on lake shores. Playa deposits may be listed here.	Thin, uniform lamination common. Evidences of current action rare. Local deformation by slight settling may occur. Isolated, ice-rafted boulders possible, but, not characteristic.
Fluvialile	Chiefly flood plains and delta flood plains.	Considerable variation. Thin sand layers often interbedded. Local unconformity frequent. Cross-bedding typical, but better developed in sands. Beds not necessarily uniform in thickness.
Aqueoglacial	Principally continental. In glaciated areas. Sometimes many miles beyond extreme limit of ice advance.	Like lake muds and clays, since deposited in standing water. Isolated, ice-rafted pebbles and boulders, sometimes striated, are not uncommon. Local deformation by the grounding of floating blocks of ice may be observed.
Eolian	Generally far from regions where wind work predominates. Dust accumulates in distant quiet regions.	Bedding often faint or absent. Deposits of loess characteristically homogeneous. Small deposits in the lee of obstructions may show good bedding. Cross-bedding rare.
Volcanic	Usually near volcanoes, but strong winds may blow fine ash far and drop it on land or in water.	Similar to eolian deposits. Particles merely settle down. Cross-bedding rare.
Gravity	Wide distribution in moist climates, on or associated with slopes.	No bedding. Either structureless or with faint tendency toward irregular layering caused by successive mud flows.
Residual	Regions with a moist climate and with poor drainage facilities.	No bedding. Deposit merely accumulates as a residuum, the soluble constituents being gradually leached out.

ARGILLITES, SHALES, SLATES, ETC.)

Original surface features	General characters	Commonly associated beds
None of importance. Current marks and even true wave ripple marks may be made at depths up to 100 fathoms, but these are uncommon. Ripple marks may be well preserved in littoral muds. Rain prints, sun cracks, etc., seldom preserved in littoral muds and not found in marine muds.	Usually consist of kaolin and fine quartz grains together with organic matter. Common colors are grays, blues, and greenish grays. Fossils marine.	Fine sandstones or limestones. Where bays were shut off from the sea and rainfall was scant, salt, gypsum, saline muds, and other products of arid conditions may overlie the original marine muds.
Surface markings, such as sun cracks, stand a better chance of preservation than in marine muds, because exposure of the muds may be seasonal.	Usually decomposition products of land waste, as marine muds. Fossils of fresh or brackish-water organisms; occasionally terrestrial animals and plants included.	Coarser elastics overlie. If climate was arid, salt, gypsum, etc., may be interbedded. If climate was warm and moist, coal and bog iron ore may be associated.
Current marks, rain prints, sun cracks characteristic especially of flood-plain deposits in arid and semiarid climates. Sheetflood deposition may be listed here.	Colors: blue, gray, green. Red, maroon, and variegated in dry climates, but other types of mud deposit may have these colors.	Coal or peat beds may alternate with sun-cracked mud beds. In dry climates saline deposits may be associated.
Since the water body is generally temporary and sedimentation is rapid, there is little opportunity for the development and preservation of surface markings.	Largely rock flour, i.e., pulverized rock. Hence a greater proportion of soluble salts than in lake and marine muds and clays. Fossils rare on account of coolness of water.	Possibly coarser aqueo-glacial stream or lake deposits; till; or not beds.
None characteristic.	Soluble constituents abundant. Unusual amounts of lime. Fossils terrestrial.	
None characteristic.	Materials largely volcanic glass. Fossils rare. May belong to any habitat according to the site of deposition.	
Characteristically irregular, with suggestions of slow flow down slope.	Great variety under different conditions. Here belong mud-flow and soil-creep materials.	
None characteristic.	The substance of which the deposit is composed would be found thinly disseminated through the underlying parent rock. Plant remains may be found.	

APPENDIX VII

LAND SURVEY DIVISIONS, UNITED STATES

In some of the younger states, including Montana, Wyoming, Kansas, Oklahoma, and others, a system of land division has been adopted, based on measurements from a chosen principal meridian and a chosen standard parallel of latitude called a "base line." The country is laid off in quadrangles, essentially six miles square, known as *townships*. Each township is subdivided into 36 *sections*. The sides of sections are termed *section lines*. Townships are numbered beginning at the intersection of the base line and the principal meridian, and going east, west, north, and south. It is customary to designate these divisions *ranges* east and west, and *townships* north and south. Thus, in Fig. 590, the township marked *A*, consisting of




FIG. 590.—Method of designating townships and ranges.

36 sections, is described as "township 2 north, range 4 west," or "T. 2 N., R. 4 W."

Sections are numbered as shown in Fig. 591. Parts of sections are described as in Fig. 592. Since a section (square mile) consists normally of 640 acres, a quarter section contains 160 acres, $\frac{1}{2}$ of a quarter section contains 80 acres, etc.

On account of the northward convergence of meridians, townships are not always exactly six miles across, nor are sections always just one mile wide. To compensate for this convergence, there is often a slight offset

6	5	4	3	2	1
7	8	9	10	11	12
18	17	16	15	14	13
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36

FIG. 501.—Method of numbering sections within a township.

NW $\frac{1}{4}$ (160ac)	N $\frac{1}{2}$ of NE $\frac{1}{4}$ (80ac)	E $\frac{1}{2}$ of NE $\frac{1}{4}$ (80ac)
SW $\frac{1}{4}$ (160ac)	NW $\frac{1}{4}$ of SE $\frac{1}{4}$ (40ac)	NE $\frac{1}{4}$ of SE $\frac{1}{4}$ (40ac)
	N $\frac{1}{2}$ of SW $\frac{1}{4}$ of SE $\frac{1}{4}$ (20ac)	W $\frac{1}{2}$ of SE $\frac{1}{4}$ of SE $\frac{1}{4}$ (20ac)
	SW $\frac{1}{4}$ of SW $\frac{1}{4}$ of SE $\frac{1}{4}$ (10ac)	E $\frac{1}{2}$ of SE $\frac{1}{4}$ of SE $\frac{1}{4}$ (20ac)

FIG. 502.—Methods of designating parts of a section.

of section and township lines in adjoining townships where they meet along the range lines. In the surveying of sectionized land all excesses and deficiencies due to convergence of meridians are placed, as far as possible, in the northern and western quarter-sections of the township.

APPENDIX VIII

MEASUREMENT AND WEIGHT

Linear Measurement:—

- 1 inch = 2.54 centimeters (cm.).
- 1 foot = 12 inches = 30.48 centimeters.
- 1 yard = 3 feet = 91.44 centimeters = 0.9144 meters.
- 1 rod = $16\frac{1}{2}$ feet = $5\frac{1}{2}$ yards.
- 1 mile = 5,280 feet = 1.6 kilometers.
- 1 millimeter = 0.001 meter = 0.03937 inch.
- 1 centimeter = 10 millimeters = 0.394 inch.
- 1 meter = 100 centimeters = 3.2809 feet = 39.37 inches.
- 1 kilometer = 1,000 meters = 0.6214 miles
- 1 fathom = 6 feet (for depths).
- 1 link = 0.66 foot = 7.92 inches.
- 1 chain = 66 feet.
- 1 vara $\left\{ \begin{array}{l} \text{in California} = 33 \text{ inches.} \\ \text{in Texas} = 33\frac{1}{3} \text{ inches.} \\ \text{in Mexico} = 32.9931 \text{ inches.} \end{array} \right.$

Areal Measurement:—

- 1 square inch = 6.452 square centimeters.
- 1 square foot = 144 square inches = 929.0 square centimeters.
- 1 square yard = 9 square feet = 0.8360 square meters.
- 1 square rod = 30.25 square yards = $\frac{1}{160}$ acre.
- 1 acre = 43,560 square feet = 4,840 square yards = 10 square chains
(An acre is approximately equivalent to a square 209 feet on a side).
- 1 acre = 0.4046 hectares.
- 1 acre = 5,646.5 square varas (Texas value).
- 1 square centimeter = 0.155 square inch.
- 1 square meter = 1.1960 square yards.
- 1 hectare = 10,000 square meters = 2.47 acres.
- 1 square kilometer = 247.104 acres = 0.3861 square mile.
- 1 square vara (Texas value) = 7.71 square feet.
- 1 square mile = 2.5899 square kilometers.

Volumetric Measurement (solid and liquid):—

- 1 cubic inch = 16.387 cubic centimeters.
- 1 cubic yard = 27 cubic feet = 0.7645 cubic meter = 201.96 gallons.

1 cubic meter = 1,000,000 cubic centimeters = 35.316 cubic feet =
1.308 cubic yards.

1 litre (of water weighing 1 kilogram) = 1.0567 quarts.

1 quart = 0.9463 litre.

1 gallon = 8 pints = 4 quarts = 3.7852 litres = 231 cubic inches

1 barrel (of crude petroleum) = 42 gallons.

Weight:—

1 pound = 16 ounces = 0.45359 kilogram.

1 kilogram = 1,000 grams = 2.2046 pounds.

1 metric ton = 1,000 kilograms = 2204.6 pounds.

1 cubic foot of distilled water at 39°F. weighs 62.425 pounds.

1 cubic foot of distilled water at 60°F. weighs 62.36 pounds.

APPENDIX IX

SOLUTION OF TRIANGLES

Right Triangle (Fig. 593):

$$\sin A = \frac{a}{b}, \quad \cos A = \frac{c}{b}, \quad \tan A = \frac{a}{c}$$

$$\sin C = \frac{c}{b}, \quad \cos C = \frac{a}{b}, \quad \tan C = \frac{c}{a}$$

$$C = 90^\circ - A, \quad b = \sqrt{a^2 + c^2}, \quad c = \sqrt{(b+a)(b-a)}.$$




FIG. 593.




FIG. 594.

Oblique Triangle (Fig. 594):

Given	Required	Formula
A, B, a	b	$b = \frac{a \cdot \sin B}{\sin A}$
A, a, b	B	$\sin B = \frac{b \cdot \sin A}{a}$
C, a, b	B	$\tan B = \frac{b \cdot \sin C}{a - b \cdot \cos C}$
a, b, c		$\left\{ \begin{array}{l} \text{If } s = \frac{1}{2}(a + b + c), \\ \sin \frac{1}{2}A = \frac{\sqrt{(s-b)(s-c)}}{bc}; \text{ or} \\ \cos \frac{1}{2}A = \frac{\sqrt{s(s-a)}}{bc} \end{array} \right.$
a, b, c	Area	$\text{Area} = \sqrt{s(s-a)(s-b)(s-c)}$
A, B, c	Area	$\text{Area} = \frac{1}{2} bc \cdot \sin A$

APPENDIX X

NATURAL CIRCULAR FUNCTIONS¹

°	Sine	Tang.	Cosine	Cotang.	°
0	0.0000	0.0000	1.0000	Inf.	90
1	0.0175	0.0175	0.9999	57.2900	89
2	0.0349	0.0349	0.9994	28.6363	88
3	0.0523	0.0524	0.9986	19.0811	87
4	0.0698	0.0699	0.9976	14.3007	86
5	0.0872	0.0875	0.9962	11.4301	85
6	0.1045	0.1051	0.9945	9.5144	84
7	0.1219	0.1228	0.9926	8.1444	83
8	0.1392	0.1405	0.9903	7.1154	82
9	0.1564	0.1584	0.9877	6.3138	81
10	0.1737	0.1763	0.9848	5.6713	80
11	0.1908	0.1944	0.9816	5.1416	79
12	0.2079	0.2126	0.9782	4.7046	78
13	0.2250	0.2309	0.9744	4.3315	77
14	0.2419	0.2493	0.9703	4.0108	76
15	0.2588	0.2680	0.9659	3.7321	75
16	0.2756	0.2868	0.9613	3.4874	74
17	0.2924	0.3057	0.9563	3.2700	73
18	0.3090	0.3249	0.9511	3.0777	72
19	0.3256	0.3443	0.9455	2.9042	71
20	0.3420	0.3640	0.9397	2.7475	70
21	0.3584	0.3839	0.9336	2.6051	69
22	0.3746	0.4040	0.9272	2.4751	68
23	0.3907	0.4245	0.9205	2.3559	67
24	0.4067	0.4452	0.9136	2.2469	66
25	0.4226	0.4663	0.9063	2.1445	65
26	0.4384	0.4877	0.8988	2.0503	64
27	0.4540	0.5095	0.8910	1.9626	63
28	0.4695	0.5317	0.8830	1.8807	62
29	0.4848	0.5543	0.8746	1.8041	61
30	0.5000	0.5774	0.8660	1.7321	60
31	0.5150	0.6009	0.8572	1.6643	59
32	0.5300	0.6249	0.8480	1.6003	58
33	0.5446	0.6494	0.8387	1.5399	57
34	0.5592	0.6745	0.8290	1.4826	56
35	0.5736	0.7002	0.8192	1.4282	55
36	0.5878	0.7265	0.8090	1.3764	54
37	0.6018	0.7536	0.7986	1.3270	53
38	0.6157	0.7813	0.7880	1.2799	52
39	0.6293	0.8098	0.7772	1.2349	51
40	0.6428	0.8391	0.7660	1.1918	50
41	0.6560	0.8693	0.7547	1.1504	49
42	0.6691	0.9004	0.7431	1.1106	48
43	0.6820	0.9325	0.7314	1.0724	47
44	0.6947	0.9657	0.7193	1.0355	46
45	0.7071	1.0000	0.7071	1.0000	45
°	Cosine	Cotang.	Sine	Tang.	°

¹ This table has been copied from Dr. C. W. Hayes' "Handbook of Field Geology," 1909, p. 42.

APPENDIX XI

EQUIVALENT ANGLES OF SLOPE AND PER CENT GRADES¹

Angle of slope	Per cent grade	Angle of slope	Per cent grade	Angle of slope	Per cent grade	Angle of slope	Per cent grade
35'	1.0	11°	19.4	20° 3'	36.5	33° 49'	67.0
52'	1.5	11° 2'	19.5	20° 18'	37.0	34°	67.4
1° 9'	2.0	11° 19'	20.0	20° 48'	38.0	34° 13'	68.0
1° 26'	2.5	11° 35'	20.5	21°	38.4	34° 36'	69.0
1° 43'	3.0	11° 52'	21.0	21° 18'	39.0	35°	70.0
2°	3.5	12°	21.3	21° 48'	40.0	35° 23'	71.0
2° 17'	4.0	12° 8'	21.5	22°	40.4	35° 45'	72.0
2° 35'	4.5	12° 24'	22.0	22° 18'	41.0	36°	72.6
2° 52'	5.0	12° 41'	22.5	22° 47'	42.0	36° 8'	73.0
3°	5.2	13°	23.0	23°	42.5	36° 30'	74.0
3°	5.5	13° 13'	23.5	23° 10'	43.0	36° 52'	75.0
3° 26'	6.0	13° 30'	24.0	23° 45'	44.0	37°	75.4
3° 43'	6.5	13° 46'	24.5	24°	44.5	37° 14'	76.0
4°	7.0	14°	24.9	24° 14'	45.0	37° 36'	77.0
4° 17'	7.5	14° 2'	25.0	24° 42'	46.0	38°	78.0
4° 34'	8.0	14° 18'	25.5	25°	46.6	38° 19'	79.0
4° 52'	8.5	14° 34'	26.0	25° 10'	47.0	38° 40'	80.0
5°	8.8	14° 51'	26.5	25° 39'	48.0	39°	81.0
5° 9'	9.0	15°	26.8	26°	48.8	39° 21'	82.0
5° 26'	9.5	15° 7'	27.0	26° 6'	49.0	39° 42'	83.0
5° 43'	10.0	15° 23'	27.5	26° 34'	50.0	40°	84.0
6°	10.5	15° 39'	28.0	27°	50.9	40° 23'	85.0
6° 17'	11.0	15° 54'	28.5	27° 1'	51.0	40° 42'	86.0
6° 34'	11.5	16°	28.7	27° 29'	52.0	41°	87.0
6° 51'	12.0	16° 10'	29.0	27° 56'	53.0	41° 21'	88.0
7°	12.3	16° 26'	29.5	28°	53.2	41° 40'	89.0
7° 8'	12.5	16° 42'	30.0	28° 22'	54.0	42°	90.0
7° 24'	13.0	16° 58'	30.5	28° 49'	55.0	42° 18'	91.0
7° 41'	13.5	17°	30.6	29°	55.4	42° 37'	92.0
7° 58'	14.0	17° 13'	31.0	29° 15'	56.0	43°	93.0
8° 15'	14.5	17° 29'	31.5	29° 41'	57.0	43° 14'	94.0
8° 32'	15.0	17° 45'	32.0	30°	57.7	43° 32'	95.0
8° 49'	15.5	18°	32.5	30° 7'	58.0	43° 50'	96.0
9°	15.8	18° 16'	33.0	30° 33'	59.0	44°	96.5
9° 5'	16.0	18° 31'	33.5	31°	60.0	44° 8'	97.0
9° 22'	16.5	18° 47'	34.0	31° 23'	61.0	44° 25'	98.0
9° 39'	17.0	19°	34.4	31° 48'	62.0	44° 43'	99.0
9° 56'	17.5	19° 2'	34.5	32°	62.5	45°	100.0
10°	17.6	19° 17'	35.0	32° 13'	63.0		
10° 12'	18.0	19° 33'	35.5	32° 37'	64.0		
10° 29'	18.5	19° 48'	36.0	33°	65.0		
10° 44'	19.0	20°	36.4	33° 26'	66.0		

¹ See Art. 302.

APPENDIX XII

EQUIVALENT DIPS EXPRESSED IN ANGLES AND IN FEET PER MILE

Degrees	Minutes	Feet per mile	Degrees	Minutes	Feet per mile	Degrees	Minutes	Feet per mile
0	01	1.54	0	42	64.51	1	46	162.8
..	02	3.07	..	43	66.04	..	48	165.9
..	03	4.61	..	44	67.57	..	50	169.0
..	04	6.14	..	45	69.11	..	52	172.0
..	05	7.68	..	46	70.64	..	54	175.1
..	06	9.22	..	47	72.18	..	56	178.2
..	07	10.75	..	48	73.72	..	58	181.3
..	08	12.29	..	49	75.26	2	00	184.4
..	09	13.82	..	50	76.80	..	10	190.8
..	10	15.36	..	51	78.33	..	10+	200.0
..	11	16.90	..	52	79.87	..	20	215.1
..	12	18.43	..	53	81.40	..	30	230.5
..	13	19.96	..	54	82.94	..	40	245.9
..	14	21.50	..	55	84.47	..	43	250.0
..	15	23.04	..	56	86.01	..	50	261.3
..	16	24.58	..	57	87.54	3	00	276.7
..	17	26.11	..	58	89.08	..	10	292.1
..	18	27.64	..	59	90.62	..	15	300.0
..	19	29.17	1	00	92.16	..	20	307.5
..	20	30.72	..	02	95.23	..	30	322.9
..	21	32.26	..	04	98.30	..	40	338.4
..	22	33.80	..	05	100.00	..	47+	350.0
..	23	35.33	..	06	101.4	..	50	353.8
..	24	36.86	..	08	104.5	4	00	369.2
..	25	38.40	..	10	107.5	..	10	384.6
..	26	39.94	..	12	110.6	..	20	400.1
..	27	41.47	..	14	113.6	..	30	415.5
..	28	43.01	..	16	116.7	..	40	431.0
..	29	44.54	..	18	119.8	..	50	446.5
..	30	46.08	..	20	122.9	..	52	450.0
..	31	47.62	..	22	126.0	5	00	461.9
..	32	49.16	..	24	129.1	..	10	477.4
..	33	50.69	..	26	132.1	..	20	492.9
..	34	52.23	..	28	135.2	..	25	500.0
..	35	53.76	..	30	138.3	..	30	508.4
..	36	55.30	..	32	141.3	..	40	523.9
..	37	56.83	..	34	144.4	..	50	539.4
..	38	58.37	..	36	147.4	..	57	550.0
..	39	59.90	..	38	150.5	6	00	555.0
..	40	61.44	..	40	153.6
..	41	62.97	..	42	156.6
..	44	159.7

APPENDIX XIII

CORRECTION FOR DIP IN DIRECTIONS NOT PERPENDICULAR TO STRIKE¹

Angle of full dip	Angle between strike and direction of section							
	80°	75°	70°	65°	60°	55°	50°	45°
10°	9° 51'	9° 40'	9° 24'	9° 5'	8° 41'	8° 13'	7° 41'	7° 6'
15°	14° 47'	14° 31'	14° 8'	13° 30'	13° 34'	12° 28'	11° 36'	10° 4'
20°	19° 43'	19° 23'	18° 53'	18° 15'	17° 30'	16° 36'	15° 35'	14° 25'
25°	24° 48'	24° 15'	23° 39'	22° 55'	22° 0'	20° 54'	19° 39'	18° 15'
30°	29° 37'	29° 9'	28° 29'	27° 37'	26° 34'	25° 18'	23° 51'	22° 12'
35°	34° 36'	34° 4'	33° 21'	32° 24'	31° 13'	29° 50'	28° 12'	26° 20'
40°	39° 34'	39° 2'	38° 15'	37° 15'	36° 0'	34° 30'	32° 44'	30° 41'
45°	44° 34'	44° 1'	43° 13'	42° 11'	40° 54'	39° 19'	37° 27'	35° 16'
50°	49° 34'	49° 1'	48° 14'	47° 12'	45° 54'	44° 17'	42° 23'	40° 7'
55°	54° 35'	54° 4'	53° 19'	52° 18'	51° 3'	49° 29'	47° 35'	45° 17'
60°	59° 37'	59° 8'	58° 26'	57° 30'	56° 19'	54° 49'	53° 0'	50° 46'
65°	64° 40'	64° 14'	63° 36'	62° 48'	61° 42'	60° 21'	58° 40'	56° 36'
70°	69° 43'	69° 21'	68° 49'	68° 7'	67° 12'	66° 8'	64° 35'	62° 46'
75°	74° 47'	74° 30'	74° 5'	73° 32'	72° 48'	71° 53'	70° 43'	69° 14'
80°	79° 51'	79° 39'	79° 22'	78° 59'	78° 29'	77° 51'	77° 2'	76° 0'
85°	84° 56'	84° 50'	84° 41'	84° 29'	84° 14'	83° 54'	83° 29'	82° 57'
89°	88° 50'	88° 58'	88° 56'	88° 54'	88° 51'	88° 47'	88° 42'	88° 35'

Angle of full dip	Angle between strike and direction of section								
	40°	35°	30°	25°	20°	15°	10°	5°	1°
10°	6° 28'	5° 46'	5° 2'	4° 11'	3° 27'	2° 37'	1° 45'	0° 53'	0° 10'
15°	9° 46'	8° 44'	7° 38'	6° 28'	5° 14'	3° 33'	2° 40'	1° 20'	0° 16'
20°	13° 10'	11° 48'	10° 19'	8° 45'	7° 6'	5° 23'	3° 37'	1° 49'	0° 22'
25°	16° 41'	14° 58'	13° 7'	11° 9'	9° 3'	6° 53'	4° 37'	2° 20'	0° 28'
30°	20° 21'	18° 19'	16° 6'	13° 43'	11° 10'	8° 30'	5° 44'	2° 53'	0° 35'
35°	24° 14'	21° 53'	19° 18'	16° 29'	13° 28'	10° 16'	6° 56'	3° 30'	0° 42'
40°	28° 20'	25° 42'	22° 45'	19° 31'	16° 0'	12° 15'	8° 17'	4° 11'	0° 50'
45°	32° 44'	29° 50'	26° 33'	22° 55'	18° 53'	14° 30'	9° 51'	4° 59'	1° 0'
50°	37° 27'	34° 21'	30° 47'	26° 44'	22° 11'	17° 9'	11° 41'	5° 56'	1° 11'
55°	42° 33'	39° 20'	35° 32'	31° 7'	26° 2'	20° 17'	13° 55'	7° 0'	1° 26'
60°	48° 4'	44° 47'	40° 54'	36° 14'	30° 29'	24° 8'	16° 44'	8° 35'	1° 44'
65°	54° 2'	50° 53'	46° 59'	42° 11'	36° 15'	29° 2'	20° 25'	10° 35'	2° 9'
70°	60° 29'	57° 36'	53° 57'	49° 18'	43° 13'	35° 25'	25° 30'	13° 28'	2° 45'
75°	67° 22'	64° 58'	61° 49'	57° 37'	51° 55'	44° 1'	32° 57'	18° 1'	3° 44'
80°	74° 40'	73° 15'	70° 34'	67° 21'	62° 43'	55° 44'	44° 33'	26° 18'	5° 31'
85°	82° 15'	81° 20'	80° 5'	78° 19'	75° 39'	71° 20'	63° 15'	44° 54'	11° 17'
89°	88° 27'	88° 15'	88° 0'	87° 38'	87° 5'	86° 9'	84° 15'	78° 41'	44° 15'

¹ This table has been adapted from Appendix I, on p. 128, in Dr. A. R. Dwyerhouse's "Geological and Topographical Maps," published by Messrs. Edward Arnold, London.

APPENDIX XIV

PROTRACTOR FOR CORRECTION OF DIP

Professor W. S. Tangier Smith has described a protractor¹ which can be used in place of the foregoing table (Appendix XIII). In this protractor, degrees of true dip are represented by the vertical lines (Fig. 595), marked along the chord connecting the two ends of the arc; degrees of apparent dip are represented on the arc; and the angle between the strike of the inclined bed or surface and the direction in which the dip component is measured is shown by the converging lines marked on the right of the diagram.

To illustrate the use of this protractor, assume that a layer is dipping 30° from the horizontal and that we want to find its inclination measured in a direction 60° from its strike. Find the point of intersection of the inclined line marked 60° at the right of the diagram and the vertical line marked 30° for *true dip*. Through this intersection point and the vertex of the protractor (center of the arc at lower right corner) lay a straight-edge, which will then intersect the arc at approximately $26^\circ 35'$, which is the dip component or *apparent dip* required.

To find the true dip, reverse this procedure. Place the straight-edge on the center of the arc and on the angle for apparent dip as shown on the arc. Assume that this apparent dip is 15° and that the angle of inclination is in a direction at 25° to the strike. Note on which vertical line the straight-edge cuts the diagonal for 25° . Here it is approximately on the 32° vertical, thus indicating a true dip of about 32° .

Compare these figures with the values in the foregoing table.

¹ Copyrighted by Professor Smith. See Bibliog., SMITH, W. S. TANGIER, 1925.




FIG. 50. Chart copyrighted in 1925 by W. S. Tangier Smith, who kindly permitted its reproduction here. (For use of chart see text.)

APPENDIX XV

GRAPHIC DETERMINATION OF DIP COMPONENTS WHEN DIPS ARE MEASURED IN FEET PER MILE¹

The accompanying graph may be used to find the inclination of a stratum, or of any relatively flat surface or layer, in directions not perpendicular to strike, when dips are low and are recorded in *feet per mile*. Suppose that




FIG. 596.—Curves for the graphic determination of dips and dip components when dips are measured in feet per mile. (Angles recorded at base of figures are in degrees.)

¹Prepared by F. H. Lahee and printed in *Economic Geology*, Vol. XIV, pp. 262-263, 1919.

the strata dip 50 ft. per mile due north and that we want to find their inclination in the direction $N.30^{\circ}E.$ The latter inclination may be referred to as the dip component in this direction. The horizontal angle between the true dip and the dip component is here 30° . Find the point on Fig. 596 where the vertical line labeled "30" (bottom of Fig.) intersects the horizontal line marked "50" (left of Fig.). This point is between two curves which, if followed up to the left margin of the figure, will be seen to be marked "40" and "50," respectively. Since the point in question lies about one third way from the 40-ft. to the 50-ft. curve, the required dip component is found to be between 43 and 44 ft. per mile in the direction $N.30^{\circ}E.$

In like manner, the true dip may be obtained from a known dip component thus: Let the strike of the beds be $N.10^{\circ}W.$ and suppose that two well logs show that these beds are inclined 30 ft. per mile in a direction $N.40^{\circ}E.$ The true dip is in the direction $N.80^{\circ}E.$ The angle between the direction of the true dip and the direction of the dip component is 40° . On the diagram find the point where the vertical line marked "40" intersects the curve marked "30." This is approximately on the horizontal line marked "40," indicating that the required true dip is about 40 ft. per mile.

Observe that, in all cases, the horizontal lines are for true dips and the curves are for dip components.

APPENDIX XVI

DIP, DEPTH, AND THICKNESS OF INCLINED STRATA

This table may be used for determining the thickness of inclined strata or the depth of a point in an inclined stratum provided the dip and the breadth of outcrop on a horizontal surface are known. Divide the breadth of outcrop by 100 and multiply the result by the constant for thickness (or depth) for the given dip.

Dip	Thickness	Depth	Dip	Thickness	Depth	Dip	Thickness	Depth
1°	1.75	1.75	31°	51.50	60.09	61°	87.46	180.40
2°	3.49	3.49	32°	52.99	62.49	62°	88.29	188.07
3°	5.23	5.24	33°	54.46	64.94	63°	89.10	196.26
4°	6.98	6.99	34°	55.92	67.45	64°	89.88	205.03
5°	8.72	8.75	35°	57.36	70.02	65°	90.63	214.45
6°	10.45	10.51	36°	58.78	72.65	66°	91.35	224.60
7°	12.19	12.28	37°	60.18	75.36	67°	92.05	235.59
8°	13.92	14.05	38°	61.57	78.13	68°	92.72	247.51
9°	15.64	15.84	39°	62.93	80.98	69°	93.36	260.51
10°	17.36	17.63	40°	64.28	83.91	70°	93.97	274.75
11°	19.08	19.44	41°	65.61	86.93	71°	94.55	290.42
12°	20.79	21.26	42°	66.91	90.04	72°	95.11	307.77
13°	22.50	23.09	43°	68.20	93.25	73°	95.63	327.09
14°	24.19	24.93	44°	69.47	96.57	74°	96.13	348.74
15°	25.88	26.79	45°	70.71	100.00	75°	96.59	373.21
16°	27.56	28.67	46°	71.93	103.55	76°	97.03	401.08
17°	29.24	30.57	47°	73.14	107.24	77°	97.44	433.15
18°	30.90	32.49	48°	74.31	111.06	78°	97.81	470.46
19°	32.56	34.43	49°	75.47	115.04	79°	98.16	514.46
20°	34.20	36.40	50°	76.60	119.18	80°	98.48	567.13
21°	35.84	38.39	51°	77.71	123.49	81°	98.77	631.38
22°	37.46	40.40	52°	78.80	127.99	82°	99.03	711.54
23°	39.07	42.45	53°	79.86	132.70	83°	99.25	814.43
24°	40.67	44.52	54°	80.90	137.64	84°	99.45	951.44
25°	42.26	46.63	55°	81.92	142.81	85°	99.62	1143.01
26°	43.84	48.77	56°	82.90	148.26	86°	99.76	1430.07
27°	45.40	50.95	57°	83.87	153.99	87°	99.86	1908.11
28°	46.95	53.17	58°	84.80	160.03	88°	99.94	2863.63
29°	48.48	55.43	59°	85.72	166.43	89°	99.98	5739.00
30°	50.00	57.74	60°	86.60	173.21			

APPENDIX XVII

W. S. TANGIER SMITH'S CHART

"This chart¹ (Fig. 597) is intended primarily for the solution of problems which may be expressed in the form

$$\frac{a}{\sin A} = \frac{b}{\sin B} = \frac{c}{\sin C}.$$

"The solution of problems (except the first, below) is accomplished by means of a rotating arm centered at the lower right-hand corner of the figure; or by a fine line drawn on a celluloid strip, or by any convenient form of straight-edge. In solving problems, the line or straight-edge—*index line*—is always set so as to pass through the lower right-hand corner of the chart. This is assumed in most of the solutions given below.

"1. The numerical values of tangents of angles not greater than 45° or the cotangents of the complements of these angles, and conversely, the angles corresponding to the tangent-cotangent values, are given by the intersections of the curved line of the chart with its horizontal and vertical lines.

"2. If the index line is set so as to pass through the upper left and lower right corners of the chart, its intersections with the lines of the chart will give sine-cosine values of angles; also the angles corresponding to sine-cosine values.

"3. Where the true dip does not exceed 10° or where the dip is expressed in terms of grade, the apparent dip, a , the true dip, t , or the direction angle, d , may be determined by means of the chart when the other two of these three factors are known. The determination is made from the relationship

$$\frac{t}{\sin 90^\circ} = \frac{a}{\sin d}.$$

Three of these four terms are known, two of the three giving a known point on the chart. By setting the index line to pass through this point, the intersection of the line with the third known value will then give the fourth term.

"Example: If the true dip is 50 ft. per mile and the direction angle is 37°, the apparent dip is read from the chart as 30.1 ft. per mile (Fig. 598).

¹ This chart and the accompanying description were prepared by Professor W. S. Tangier Smith, who kindly permitted their publication here.

If, in this problem, $t = 5^\circ$ and $d = 37^\circ$ then, $a = 3.01^\circ = 3^\circ 0.6'$.
 (The value calculated from the dip formula is $3^\circ 0.84'$.) The error involved in using the numerical values of dip angles less than 10° instead of the tangent values is small,—not more than a few minutes at the most.





FIG. 597.—Two-variable chart prepared by W. S. Tangier Smith for solution of various problems. (See text.)

"4. All cases of right triangles; also, oblique triangles when (a) one side and any two angles, or (b) two sides and the angle opposite one of them, are given, may be solved by means of the chart. The general method of solution is indicated by Fig. 599. This shows that the three points of intersection of the lines representing the three sides and the lines representing their respective opposite angles all lie in a straight line.

"In that case of the right triangle in which the two sides, a and b , are given, a being greater than b , the smaller side is first divided by the larger in order to obtain the tangent of the smaller acute angle of the triangle ($\frac{b}{a} = \tan B$). From this tangent, the angle B is obtained from the chart (Problem 1). The rest of the solution is as in Fig. 599.



"Problems of formation depth and thickness involve triangles and, also, certain angle relationships like those between true dip, apparent dip and direction angle. Any ordinary problem concerning formation depth and thickness may, therefore, be readily worked out by means of this chart and the dip protractor."

APPENDIX XVIII

STADIA TABLES

These tables are for use in stadia surveying (412) where inclined sights are 19° or less.¹ For vertical angles of more than 3° , a correction should be applied, due to the fact that the inclined sight line is longer than its horizontal (or map) distance by a quantity which becomes larger with increase of the vertical angle (409); but for angles of 3° or less, this error may be disregarded in ordinary plane table surveying.

Example 1.—Instrument is set up at *A* and rod is at *B*. Stadia intercept at *B* is 5 ft. as seen from *A*. Therefore, distance from *A* to *B* is $5 \times 100 = 500$ ft. Vertical angle of inclined line of sight from *A* to *B* is $2^\circ 30'$. In the table we find that the elevation for a distance of 100 ft. would be 4.36 ft. At 500 ft., the difference in elevation between *A* and *B* would be 5×4.36 ft. = 21.80 ft.

Example 2.—Instrument is set up at *A* and rod is held at *B*. Observed stadia intercept is 8 ft., which is to be multiplied by 100, the *stadia constant* giving a distance value of 800 ft. Vertical angle of inclination of sight line is $12^\circ 30'$. In the table of "Horizontal Correction for Distances," the correction for 12° and 800 ft. is 34.6 and that for 13° and 800 ft. is 40.5. For, $12^\circ 30'$, it would be $\frac{1}{2}(34.6 + 40.5) = 37.5$ ft., to be subtracted from 800 ft. to give the horizontal distance from *A* to *B*. This is $800 - 37.5 = 762.5$ ft.

The vertical height for 100 ft. and $12^\circ 30'$ is 21.13. This multiplied by 8 for the distance 800, is 169.04 ft., which is the difference of elevation between *A* and *B*.

For more refined calculations, a still further correction is applied. This is a quantity, designated $c + f$, which is essentially constant for most alidades, and may be taken as 1. It is the distance, c , from the center of the instrument to the center of the objective lens plus the distance, f , from the lens to the focal point, a few inches in front of the lens. For all inclined sights, the horizontal projection of this quantity is the correction to be applied. The horizontal values of $c + f$ for different angles are given at the bottom of the accompanying tables.

Example 3.—Instrument is set up at *A* and rod is held at *B*. Rod intercept at *B* is 14, indicating distance $AB = 1,400$ ft. Vertical angle from

¹ For greater angles, consult Anderson's "Stadia Tables," or tables in handbooks on surveying. Bibliog., ANDERSON, C. G., 1917.

A to B is $6^{\circ}45'$. In table for "Horizontal Corrections for Distance," the correction for 6° and 1,000 ft. is 10.9 ft. and for 7° and 1,000 ft. is 14.9 ft. Interpolating for $45'$, the correction for 1,000 ft. and $6^{\circ}45'$ is

$$10.9 + \left(\frac{14.9 - 10.9}{4} \times 3 \right) = 10.9 + 3 = 13.9 \text{ ft.}$$

Similarly, for 400 ft. and $6^{\circ}45'$, the correction is

$$4.4 + \left(\frac{6.0 - 4.4}{4} \times 3 \right) = 4.4 + 1.2 = 5.6 \text{ ft.}$$

Therefore, for 1,400 ft. the horizontal corrected value is

$$13.9 + 5.6 = 19.5 \text{ ft.} \\ 1,400 - (13.9 + 5.6) = 1,400 - 19.5 = 1,380.5 \text{ ft.}$$

Under $(c + f)$ corrections for 6° and 7° , the value is 0.99 which for practical purposes may be called 1. Adding this quantity to 1,380.5 ft., we have, for the corrected horizontal projection of $AB + (c + f)$,

$$1,380.5 + 1 = 1,381.5 \text{ ft.}$$

In the table for Vertical Heights, we find that an angle of $6^{\circ}45'$ subtends a vertical distance of

$$11.64 \left(\frac{11.70 - 11.64}{2} \right) = 11.64 + .3 = 11.67$$

For 1,400 $+(c + f)$ ft. = 1,401 ft., the vertical difference in elevation would be

$$14.01 \times 11.67 = 163.50 \text{ ft.}$$

Under " $(c + f)$ corrections for vertical heights," the table gives 0.11 for 6° and 0.13 for 7° . For $6^{\circ}45'$, this correction factor would be

$$0.11 + \left(\frac{0.13 - 0.11}{4} \times 3 \right) = 0.11 + 0.015 = 0.125,$$

which is to be added to 163.50 ft., giving 163.625 ft., the corrected difference of elevations between A and B .

VERTICAL HEIGHTS FOR DISTANCE OF 100

Min	0°	1°	2°	3°	4°	5°	6°	7°	8°	9°
0	0 00	1.74	3.49	5.23	6.96	8.68	10.40	12 10	13.78	15.45
2	0 06	1 80	3 55	5.28	7.02	8.74	10 45	12 15	13 84	15.51
4	0 12	1 86	3.60	5.34	7.07	8.80	10.51	12 21	13 89	15.56
6	0 17	1 92	3.66	5.40	7.13	8.85	10 57	12 26	13 95	15.62
8	0 23	1.98	3 72	5.46	7.19	8.91	10.62	12 32	14.01	15.67
10	0 29	2.04	3 78	5.52	7.25	8 97	10 68	12 38	14 06	15.73
12	0 35	2.09	3.84	5.57	7.30	9.03	10 74	12 43	14 12	15.78
14	0 41	2.15	3.90	5.63	7.36	9.08	10.79	12 49	14 17	15.84
16	0 47	2 21	3 95	5.69	7 42	9.14	10.85	12.55	14.23	15.89
18	0 52	2.27	4 01	5.75	7.48	9.20	10.91	12 60	14 28	15
20	0.58	2.33	4.07	5.80	7.53	9.25	10.96	12 66	14 34	16
22	0 04	2 38	4.13	5.86	7.59	9.31	11.02	12 72	14 40	16.06
24	0 70	2.44	4.18	5.92	7.65	9.37	11.08	12 77	14 45	16 11
26	0 76	2 50	4 24	5.98	7.71	9.43	11.13	12 83	14 51	16.17
28	0 81	2 56	4 30	6.04	7.76	9.48	11.19	12.88	14 56	16.22
30	0 87	2 62	4 36	6.09	7.82	9.54	11.25	12 94	14 62	16.28
32	0.93	2.67	4.42	6.15	7.88	9.60	11.30	13 00	14 67	16.33
34	0 99	2.73	4 48	6.21	7.94	9.65	11.36	13 05	14 73	16 39
36	1 05	2.79	4.53	6.27	7.99	9 71	11.42	13 11	14.79	16.44
38	1.11	2.85	4.59	6.33	8.05	9 77	11 47	13.17	14 84	16 50
40	1.16	2.91	4.65	6.38	8.11	9.83	11 53	13 22	14.90	16.55
42	1.22	2.97	4 71	6.44	8.17	9 88	11 59	13.28	14.95	16.61
44	1 28	3.02	4 76	6.50	8.22	9.94	11 04	13 33	15 01	16.66
46	1 34	3.08	4.82	6.56	8 28	10.00	11.70	13 39	15 06	16 72
48	1 40	3.14	4 88	6.61	8.34	10.05	11 76	13 45	15 12	16.77
50	1 45	3.20	4.94	6.67	8.40	10.11	11 81	13 50	15.17	16.83
52	1 51	3 26	4 99	6.73	8.45	10.17	11.87	13 56	15.23	16
54	1.57	3 31	5 05	6.79	8.51	10.22	11.93	13.61	15 28	16 94
56	1.63	3.37	5.11	6.84	8.57	10 28	11.98	13.67	15.34	16
58	1.69	3 43	5.17	6.90	8.63	10.34	12.04	13.73	15.40	17 05
60	1.74	3 49	5 23	6.96	8.68	10 40	12.10	13.78	15 45	17.10

(c + f) corrections for vertical heights.....

0 01	0.03	0 04	0.06	0.08	0.09	0 11	0.13	0.15	0 16
------	------	------	------	------	------	------	------	------	------

HORIZONTAL CORRECTIONS FOR DISTANCE

Dis.	0°	1°	2°	3°	4°	5°	6°	7°	8°	9°
100	0 0	0.0	0.1	0.3	0.5	0.8	1.1	1.5	1 9	2.5
200	0.0	0.1	0.2	0.5	1.0	1.5	2.2	3 0	3 9	4.9
300	0 0	0.1	0.4	0.8	1.5	2.3	3.3	4.5	5.8	7.4
400	0.0	0.1	0.5	1.1	2.0	3.0	4.4	6.0	7.8	9.8
500	0.0	0.2	0.6	1.4	2.5	3.8	5.5	7.5	9.7	12.3
600	0.0	0.2	0.7	1.6	2.9	4.6	6.5	8.9	11.6	14.7
700	0.0	0.2	0.8	1.9	3 4	5 3	7.6	10.4	13.6	17.2
800	0.0	0 2	1.0	2.2	3 9	6.1	8.7	11.9	15.5	19.6
900	0.0	0.3	1.1	2.4	4.4	6.8	9.8	13.4	17.5	22.1
1,000	0.0	0.3	1.2	2.7	4.9	7.6	10.9	14.9	19.4	24 5

(c + f) corrections for horizontal distances.....

1.00	1.00	1.00	1.00	1.00	0.99	0.99	0.99	0.99	0.99
------	------	------	------	------	------	------	------	------	------

VERTICAL HEIGHTS FOR DISTANCE OF 100.—(Continued)

Min.	10°	11°	12°	13°	14°	15°	16°	17°	18°	19°
0	17.10	18.73	20.34	21.92	23.47	25.00	26.50	27.96	29.39	30.78
2	17.16	18.78	20.39	21.97	23.52	25.05	26.55	28.01	29.44	30.83
4	17.21	18.84	20.44	22.02	23.58	25.10	26.59	28.06	29.48	30.87
6	17.26	18.89	20.50	22.08	23.63	25.15	26.64	28.10	29.53	30.92
8	17.32	18.95	20.55	22.13	23.68	25.20	26.69	28.15	29.58	30.97
10	17.37	19.00	20.60	22.18	23.73	25.25	26.74	28.20	29.62	31.01
12	17.43	19.05	20.66	22.23	23.78	25.30	26.79	28.25	29.67	31.06
14	17.48	19.11	20.71	22.28	23.83	25.35	26.84	28.30	29.72	31.10
16	17.54	19.16	20.76	22.34	23.88	25.40	26.89	28.34	29.76	31.15
18	17.59	19.21	20.81	22.39	23.93	25.45	26.94	28.39	29.81	31.19
20	17.65	19.27	20.87	22.44	23.99	25.50	26.99	28.44	29.86	31.24
22	17.70	19.32	20.92	22.49	24.04	25.55	27.04	28.49	29.90	31.28
24	17.76	19.38	20.97	22.54	24.09	25.60	27.09	28.54	29.95	31.33
26	17.81	19.43	21.03	22.60	24.14	25.65	27.13	28.58	30.00	31.38
28	17.86	19.48	21.08	22.65	24.19	25.70	27.18	28.63	30.04	31.42
30	17.92	19.54	21.13	22.70	24.24	25.75	27.23	28.68	30.09	31.47
32	17.97	19.59	21.18	22.75	24.29	25.80	27.28	28.73	30.14	31.51
34	18.03	19.64	21.24	22.80	24.34	25.85	27.33	28.77	30.19	31.56
36	18.08	19.70	21.29	22.85	24.39	25.90	27.38	28.82	30.23	31.60
38	18.14	19.75	21.34	22.91	24.44	25.95	27.43	28.87	30.28	31.65
40	18.19	19.80	21.39	22.96	24.49	26.00	27.48	28.92	30.32	31.69
42	18.24	19.86	21.45	23.01	24.55	26.05	27.52	28.96	30.37	31.74
44	18.30	19.91	21.50	23.06	24.60	26.10	27.57	29.01	30.41	31.78
46	18.35	19.96	21.55	23.11	24.65	26.15	27.62	29.06	30.46	31.83
48	18.41	20.02	21.60	23.16	24.70	26.20	27.67	29.11	30.51	31.87
50	18.46	20.07	21.66	23.22	24.75	26.25	27.72	29.15	30.55	31.92
52	18.51	20.12	21.71	23.27	24.80	26.30	27.77	29.20	30.60	31.96
54	18.57	20.18	21.76	23.32	24.85	26.35	27.81	29.25	30.65	32.01
56	18.62	20.23	21.81	23.37	24.90	26.40	27.86	29.30	30.69	32.05
58	18.68	20.28	21.87	23.42	24.95	26.45	27.91	29.34	30.74	32.09
60	18.73	20.34	21.92	23.47	25.00	26.50	27.96	29.39	30.78	32.14
(c + f) corrections for vertical heights	0.18	0.20	0.22	0.23	0.25	0.27	0.28	0.30	0.32	0.33

HORIZONTAL CORRECTIONS FOR DISTANCE.—(Continued)

Dis.	10°	11°	12°	13°	14°	15°	16°	17°	18°	19°
100	3.0	3.6	4.3	5.1	5.9	6.7	7.6	8.5	9.5	10.6
200	6.0	7.3	8.6	10.1	11.7	13.4	15.2	17.1	19.1	21.2
300	9.1	10.9	13.0	15.2	17.6	20.1	22.8	25.6	28.6	31.8
400	12.1	14.6	17.3	20.2	23.4	26.8	30.4	34.2	38.2	42.4
500	15.1	18.2	21.6	25.3	29.3	33.5	38.0	42.7	47.7	53.0
600	18.1	21.8	25.9	30.4	35.1	40.2	45.6	51.3	57.3	63.6
700	21.1	25.5	30.2	35.4	41.0	46.9	53.2	59.8	66.8	74.2
800	24.2	29.1	34.6	40.5	46.8	53.6	60.8	68.4	76.4	84.8
900	27.2	32.8	38.9	45.5	52.7	60.3	68.4	76.9	85.9	95.4
1,000	30.2	36.4	43.2	50.6	58.5	67.0	76.0	85.5	95.5	106.0
(c + f) corrections for horizontal distances	0.99	0.98	0.98	0.97	0.97	0.96	0.96	0.95	0.95	0.94

BIBLIOGRAPHY

BIBLIOGRAPHY

- ADAMS, F. D.: "Experimental Contribution to the Question of the Depth of the Zone of Flow in the Earth's Crust." *Jour. Geol.*, vol. 20, pp. 97-118, 1912.
- ALDEN, W. C.: "Drumlins of Southeastern Wisconsin." U. S. Geol. Survey, *Bull.* 273, 1905.
- AMBRONN, RICHARD (translated from the German by Margaret C. Cobb): "Elements of Geophysics." N. Y., 1928.
- ANDERSON, C. G.: "Stadia Tables for Obtaining Differences of Elevation." U. S. Geol. Survey, 1917.
- APPLIN, ESTHER RICHARDS, ALVA E. ELLISOR, and HEDWIG T. KNICKER: "Subsurface Stratigraphy of the Coastal Plain of Texas and Louisiana." *Am. Assoc. Petr. Geols., Bull.*, vol. 9, pp. 79-122, 1925.
- ATHY, L. F.: "Density, Porosity, and Compaction of Sedimentary Rocks." *Am. Assoc. Petr. Geols., Bull.*, vol. 14, pp. 1-24, 1929 (a).
- Ibid.*: "Compaction and Oil Migration." *Am. Assoc. Petr. Geols., Bull.*, vol. 14, pp. 25-35, 1929 (b).
- ATWOOD, W. W.: "Glaciation of the Uinta and Wasatch Mountains." U. S. Geol. Survey, *Prof. Paper* 61, 1909.
- BALK, ROBERT: "Structural Behavior of Igneous Rocks." *Geol. Soc. of Am., Memoir* 5, N. Y., 1937.
- BARRELL, J.: "Relative Geological Importance of Continental, Littoral, and Marine Sedimentation." *Jour. Geol.*, vol. 14, pp. 316-356, 430-457, 524-568, 1906.
- Ibid.*: "Geology of the Marysville Mining District, Montana." U. S. Geol. Survey, *Prof. Paper* 57, 1907.
- Ibid.*: "Criteria for the Recognition of Ancient Delta Deposits." *Geol. Soc. Am., Bull.* 23, pp. 377-446, 1921.
- Ibid.*: "Marine and Terrestrial Conglomerates." *Geol. Soc. Am., Bull.*, vol. 36, pp. 279-342, 1925.
- BARTON, DONALD C.: "Applied Geophysical Methods in America." *Econ. Geol.*, vol. 22, pp. 649-668, 1927.
- Ibid.*: "The Hötvis Torsion Balance Method of Mapping Geologic Structure. "Geophysical Prospecting: 1929," pp. 416-479, 1929 (a). (Published by the A. I. M. M. E., N. Y.)
- Ibid.*: "The Seismic Method of Mapping Geologic Structure. "Geophysical Prospecting: 1929," pp. 572-624, 1929 (b). (Published by the A. I. M. M. E., N. Y.)

- Ibid.*: "Geophysical Prospecting for Oil." Am. Assoc. Petr. Geols., *Bull.*, vol. 14, pp. 201-226 1930 (a).
- Ibid.*: "Review of the Geophysical Methods of Prospecting." *Geog. Review*, vol. 20, pp. 288-300, 1930 (b).
- BASS, N. W.: "Origin of Bartlesville Shoestring Sands, Greenwood and Butler Counties, Kansas." Am. Assoc. Petr. Geols., *Bull.*, vol. 18, pp. 1313-1345, 1934.
- BEVAN, A.: "Rocky Mountain Front in Montana." Geol. Soc. Am., *Bull.*, vol. 40, pp. 427-456, 1929.
- BIRDSEYE, C. H.: "Topographic Instructions of the United States Geological Survey." U. S. Geol. Survey, *Bull.* 788, Washington, D. C., 1928.
- BLACKWELDER, ELIOT: "The Valuation of Unconformities," *Jour. Geol.*, vol. 17, pp. 289-299, 1909.
- Ibid.*: "Mudflow as a Geologic Agent in Semiarid Mountains." Geol. Soc. Am., *Bull.*, vol. 39, pp. 465-484, 1928.
- Ibid.*: "Cavernous Rock Surfaces of the Desert." *Am. Jour. Sci.*, 5th ser., vol. 17, pp. 393-399, 1929.
- Ibid.*: "Desert Plains," *Jour. Geol.*, vol. 39, pp. 133-140, 1931.
- BLACKWELDER, E. and H. H. BARROWS: "Elements of Geology." 1911.
- BOWEN, N. L.: "The Evolution of the Igneous Rocks." 1928.
- Ibid.*: "Crystallization-Differentiation in Igneous Magmas." *Jour. Geol.*, vol. 28, pp. 707-730, and vol. 29, pp. 1-28, 1920 and 1921.
- BRUCKS, ERNEST W.: Luling Oil Field, Caldwell and Guadalupe Counties, Texas. "Structure of Typical American Oil Fields," vol. 1, pp. 256-281, 1929. (Published by the American Association of Petroleum Geologists, Tulsa, Oklahoma.)
- BRYAN, KIRK: "The Papago Country, Arizona." U. S. Geol. Survey, *Water Supply Paper* 499, 1925.
- BUCHER, WALTER H.: "The Mechanical Interpretation of Joints." *Jour. Geol.*, vol. 28, pp. 707-730, and vol. 29, pp. 1-28, 1920 and 1921.
- Ibid.*: "On Ripples and Related Sedimentary Forms and Their Paleogeographic Interpretation." *Am. Jour. Sci.*, vol. 47, pp. 149-210, 241-269, 1919.
- CAMPBELL, M. R.: "Rapid Section Work in Horizontal Rocks." Am. Inst. Min. Eng., *Trans.*, vol. 26, 298-315, 1896.
- CHAMBERLIN, T. C.: "Rock-Scorings of the Great Ice Invasions." U. S. Geol. Survey, *An. Rept.* 7, pp. 155-248, 1888.
- CLAPP, F. G.: "Economic Geology of the Amity Quadrangle." U. S. Geol. Survey, *Bull.* 300, 1897.
- CLARK, STUART K., and JAS. I. DANIELS: "Logging Rotary Wells from Drill Cuttings." Am. Assoc. Petr. Geols., *Bull.*, vol. 12, pp. 59-76, 1928.
- COFFEY, G. N.: "Clay Dunes." *Jour. Geol.*, vol. 17, pp. 754-755, 1909.

- CORBETT, C. S.: "Method of Projecting Structure through an Angular Unconformity." *Econ. Geol.*, vol. 14, pp. 610-618, 1919.
- CORNISH, V.: "On the Formation of Sand-Dunes." *Geographical Journal* (London), vol. 9, pp. 278-309, 1897.
- CUSHMAN, JOSEPH A.: "Use of Foraminifera in Geologic Correlation." *Am. Assoc. Petr. Geols., Bull.*, vol. 8, pp. 485-491, 1924.
- Ibid.*: "Foraminifera: Their Classification and Economic Use." 401 pp., Sharon, Mass., 1928.
- DALE, T. N.: "Slate Deposits and Slate Industry of the United States." *U. S. Geol. Survey, Bull.* 275, 1906.
- Ibid.*: "Granites of Maine." *U. S. Geol. Survey, Bull.* 313, 1907.
- Ibid.*: "Slate in the United States." *U. S. Geol. Survey, Bull.* 586, 1914.
- DALY, R. A.: "Igneous Rocks and Their Origin." N. Y., 1914.
- DAVIS, RAYMOND E., FRANCIS S. FOOTE, and W. H. RAYNER: "Surveying: Theory and Practice," 2d ed., N. Y., 1934.
- DAVIS, W. M.: "Faults in the Triassic Formation near Meriden, Conn." . . . *Mus. Comp. Zool., Bull.* 16, pp. 61-87, 1889.
- Ibid.*: "Structure and Origin of Glacial Sand Plains." *Geol. Soc. Am., Bull.* 1, pp. 195-202, 1890.
- Ibid.*: "The Triassic Formation of Connecticut." *U. S. Geol. Survey, An. Rept.* 18, Pt. 2, pp. 9-192, 1898.
- Ibid.*: "Geographical Essays." 1909.
- Ibid.*: "Die Erklärende Beschreibung der Landformen." Leipzig and Berlin, 1912.
- Ibid.*: "Nomenclature of Surface Forms on Faulted Structures." *Geol. Soc. Am., Bull.* 24, pp. 187-216, 1913.
- Ibid.*: "Rock Floors in Arid and in Humid Climates." *Jour. Geol.*, vol. 38, pp. 1-27, 136-158, 1930.
- DEGOLYER, E., *et al.*: "Geology of Salt Dome Oil Fields." 1926. (Published by Am. Assoc. Petr. Geols.)
- DODGE, JOHN FRANKLIN: "Straight Hole Drilling Practice." *Am. Petr. Institute, Proceedings of the Tenth Annual Meeting*, vol. 11, No. 1, pp. 43-51, Jan. 2, 1930.
- DWERRYHOUSE, A. R.: "Geological and Topographical Maps." London, 1911. •
- ENGLISH, WALTER A.: "Some Plane Table Methods." *Am. Assoc. Petr. Geols. Bull.*, vol. 8, pp. 47-54, 1924.
- Ibid.*: "Use of Airplane Photographs in Geologic Mapping." *Am. Assoc. Petr. Geols., Bull.*, vol. 14, pp. 1049-1058, 1930.
- EVE, A. S., and D. A. KEYS: "Applied Geophysics." Cambridge, England, 1929.
- FARRELL, J. H.: "Practical Field Geology." N. Y., 1912.

- FATH, A. E.: "The Origin of the Faults, Anticlines, and 'Buried Ridge' of the Northern Part of the Mid-Continent Oil and Gas Field." U. S. Geol. Survey, *Prof. Paper* 128-C, 1920.
- FAY, A. H.: "Glossary of the Mining and Mineral Industry." U. S. Bureau of Mines, *Bull.* 95, 1920.
- FENNEMAN, N. M.: "Lakes of Southeastern Wisconsin." Wisc. Geol. and Nat. His. Survey, *Bull.* 8, 1902.
- FOLEY, LYNDON L.: "Origin of the Faults in Creek and Osage Counties, Oklahoma." Am. Assoc. Petr. Geols., *Bull.* 10, pp. 293-303, 1926.
- FORDHAM, W. H.: "Geophysical Surveying." Inst. Petr. Technologists, *Journal* (London), vol. 15, pp. 35-80, 1929.
- FULLER, M. L.: "Geology of Long Island, New York." U. S. Geol. Survey, *Prof. Paper* 82, 1914.
- Ibid.*: "Relation of Oil to Carbon Ratios of Pennsylvanian Coals in North Texas." *Econ. Geol.*, vol. 14, pp. 536-542, 1919.
- Ibid.*: "Carbon Ratios in Carboniferous Coals of Oklahoma, and Their Relation to Petroleum." *Econ. Geol.*, vol. 15, pp. 225-235, 1920.
- Ibid.*: "Quick Method of Reconnaissance Mapping." *Econ. Geol.*, vol. 14, pp. 411-423, 1919.
- GALLOWAY, J. J.: "Methods of Correlation by Means of Foraminifera." Am. Assoc. Petr. Geols., *Bull.*, vol. 10, pp. 562-567, 1926.
- GEIKIE, J.: "Structural and Field Geology." 3d edition, 1912.
- GILBERT, G. K.: "A New Method of Measuring Heights by Means of the Barometer." U. S. Geol. Survey, *An. Rept.* 2, pp. 403-566, 1882.
- Ibid.*: "Lake Bonneville." U. S. Geol. Survey, *Monog.* 1, 1890.
- Ibid.*: "Crescentic Gouges on Glaciated Surfaces." Geol. Soc. Am., *Bull.* 17, pp. 303-316, 1906.
- Ibid.*: "California Earthquake of 1906." *Am. Jour. Sci.*, 4th ser., vol. 27, pp. 48-52, 1909.
- GRABAU, A. W.: "Principles of Stratigraphy." 1913.
- GRABAU, A. W., and H. W. SHIMER: "North American Index Fossils." N. Y., 1909.
- GREGORY, H. E.: "The Rodadero—A Fault Plane of Unusual Aspect." *Am. Jour. Sci.*, 4th ser., vol. 37, 289-298, 1914.
- GRUBENMANN, U.: "Die kristallinen Schiefer." 1904 and 1907.
- GULLIVER, F. P.: "Shoreline Topography." Am. Acad. Arts and Sci., *Proc.* 34, pp. 149-258, 1899.
- HARKER, A.: "Natural History of Igneous Rocks." 1909.
- HATCH, F. H., and R. H. RASTALL: "Petrology of the Sedimentary Rocks." London, 1913.
- HAYES, C. W.: "Handbook for Field Geologists." New York, 1909.
- HEALD, K. C.: "Determination of Geothermal Gradients in Oil Fields on Anticlinal Structure." A. P. I., *Proceedings*, vol. 11, No. 1 (Drilling and Production Engineering, *Bull.* 204), pp. 102-110, 1930.

- HEDBERG, HOLLIS D.: "The Effect of Gravitational Compaction on the Structure of Sedimentary Rocks." *Am. Assoc. Petr. Geols., Bull.*, vol. 10, pp. 1035-1072, 1926.
- HEDSTROM, HELMER: "Electrical Survey of Structural Conditions in the Salt Flat Field, Caldwell County, Texas." *Am. Assoc. Petr. Geols., Bull.*, Sept., 1930.
- HEILAND, C. A.: "Geophysical Methods of Prospecting." *Colorado School of Mines, Quarterly*, vol. 24, March, 1929.
- Ibid.*: "Geophysical Exploration." N. Y., 1940.
- HEWETT, D. F.: "Measurements of Folded Beds." *Econ. Geol.*, vol. 15, pp. 367-385, 1920.
- HEWETT, D. F., and C. T. LUPTON: "Anticlines in the Southern Part of the Big Horn Basin, Wyoming." *U. S. Geol. Survey, Bull.* 656, 1917.
- HILL, RAYMOND A.: "Preliminary Survey Procedure." 1929. (Published by the American Paulin System, Inc., Los Angeles, Calif.)
- HOBBS, W. H.: "Examples of Joint-Controlled Drainage from Wisconsin and New York." *Jour. Geol.*, vol. 13, pp. 363-374, 1905.
- Houston Geological Society Study Group: "Electrical Well Logging." *Am. Assoc. Petr. Geols., Bull.*, vol. 23, pp. 1287-1313, 1939.
- HOVEY, E. O.: "Striations and U-Shaped Valleys Produced by Other than Glacial Action." *Geol. Soc. Am., Bull.* 20, pp. 409-426, 1909.
- HOWE, E.: "Landslides in the San Juan Mountains, Colorado." *U. S. Geol. Survey, Prof. Paper* 67, 1909.
- HYDE, J. E.: "Desiccation Conglomerates in the Coal-Measures Limestone of Ohio." *Am. Jour. Sci.*, 4th ser., vol. 25, pp. 400-408, 1908.
- IRVING, J. D., *et al.*: "Field and Office Methods in the Preparation of Geological Reports." *Econ. Geol.*, vol. 8, pp. 66-96, 177-181, 264-297, 373-397, 489-499, 578-597, 691-721, 795-797; vol. 9, pp. 67-72, 184-189; 1913, 1914.
- IVES, RONALD L.: "Measurement in Block Diagrams." *Econ. Geol.*, vol. 34, pp. 561-572, 1939.
- JENNY, W. P.: "Electric and Electromagnetic Prospecting for Oil." *Am. Assoc. Petr. Geols., Bull.*, Sept., 1930.
- JOHNSON, D. W.: "Beach Cusps." *Geol. Soc. Am., Bull.* 21, pp. 599-624, 1910.
- KEYES, C. R.: "Rock-Floor of Intermont Plains of the Arid Region." *Geol. Soc. Am., Bull.* 19, pp. 63-92, 1908.
- KITSON, H. W.: "Graphic Solution of Strike and Dip from Two Angular Components." *Am. Assoc. Petr. Geols., Bull.*, vol. 13, pp. 1211-1213, 1929.
- KNOFF, ELEANORA BLISS, and EARL INGERSON: "Structural Petrology." *Geol. Soc. Am., Memoir* 6, 1938.
- KRAUS, EDGAR: "Logging Wells Drilled by the Rotary Method." *Am. Assoc. Petr. Geols., Bull.*, vol. 8, pp. 641-650, 1924.

- JAHKEE, F. H.: "Graphic Determination of Dip Components Where Dips Are Measured in Feet per Mile." *Econ. Geol.*, vol. 24, pp. 262-263, 1919.
- Ibid.*: "The Barometric Method of Geologic Surveying for Petroleum Mapping." *Econ. Geol.*, vol. 25, pp. 150-169, 1920.
- Ibid.*: "Oil and Gas Fields of the Mexia and Tehuacana Fault Zones, Texas." Structure of Typical American Oil Fields, vol. 1, pp. 304-388, 1929 (a). (Published by Am. Assoc. Petr. Geols.)
- Ibid.*: "Problem of Crooked Holes." Am. Assoc. Petr. Geols., *Bull.*, vol. 13, pp. 1095-1161, 1929 (b).
- LAWSON, A. C.: "Geomorphogeny of the Upper Kern Basin." Univ. Calif., Geol. Dept. *Bull.* 3, pp. 291-376, 1902-1904.
- LAWSON, A. C., *et al.*: "Report of the State Earthquake Investigation Commission on the California Earthquake of April 18, 1906." Carnegie Inst. of Washington, 1908.
- LEE, WILLIS T.: "The Face of the Earth as Seen from the Air." Am. Geog. Soc., N. Y., *Special Bull.* 1922.
- LEITH, C. K.: "Rock Cleavage." U. S. Geol. Survey, *Bull.* 239, 1905.
- Ibid.*: "Structural Geology." New York, 1913.
- LEITH, C. K., and W. J. MEAD: "Metamorphic Geology." 1915.
- LEONARDON, E. G., and SHERWIN F. KELLY: "Some Applications of Potential Methods to Structural Studies." "Geophysical Prospecting: 1929," pp. 180-198, 1929. Published by A. I. M. M. E.
- LEVORSEN, A. I.: "Convergence Studies in the Mid-Continent Region." Am. Assoc. Petr. Geols., *Bull.* 11, pp. 657-682, 1927.
- LEWIS, J. V.: "Origin of Pillow Lavas." Geol. Soc. Am., *Bull.* 25, pp. 591-654, 1914.
- LINDGREN, W.: "Mineral Deposits." 4th ed., New York, 1933.
- LINK, THEODORE A.: "En Echelon Tension Fissures and Faults." Am. Assoc. Petr. Geols., *Bull.* 13, pp. 627-644, 1929.
- LOVERING, T. S.: "Field Evidence to Distinguish Overthrusting from Underthrusting." *Jour. Geol.*, vol. 40, pp. 651-663, 1932.
- LYNTON, E. D.: "Laboratory Orientation of Well Cores by Their Magnetic Polarity." Am. Assoc. Petr. Geols., *Bull.*, vol. 21, pp. 580-615, 1937.
- Ibid.*: "Recent Developments in Laboratory Orientation of Cores by Their Magnetic Polarity." *Geophys.*, vol. 3, No. 2, 1938.
- MANLY, J. M., and J. A. POWELL: "Manual for Writers." 1913.
- MATHER, KIRTLEY F.: "The Manipulation of the Telescopic Alidade in Geologic Mapping." *Bull. of the Scientific Laboratories of Denison University, Granville, Ohio*, vol. 19, pp. 97-142, 1919.
- MATTHEW, G. F.: "Post Glacial Faults at St. John, N. B." *Am. Jour. Sci.*, 3rd. ser., vol. 48, pp. 501-503, 1894.
- MCCUTCHIN, JOHN A.: "Determination of Geothermal Gradients in Oklahoma." Am. Assoc. Petr. Geols., *Bull.* 14, pp. 535-558, 1930.

- McLAUGHLIN, R. P. (Chairman): "Geophysical Prospecting: 1929." N. Y., 1929. Published by the A. I. M. M. E.
- McQUEEN, H. S.: "Insoluble Residues as a Guide in Stratigraphic Studies." Missouri Bureau of Geol. & Mines, 56th Biennial Rept., Appendix 1, 1931.
- MEAD, W. J.: "Notes on the Mechanics of Geologic Structures." *Jour. Geol.*, vol. 28, pp. 505-523, 1920.
- Ibid.*: "Determination of Attitude of Concealed Bedded Formations by Diamond Drilling." *Econ. Geol.*, vol. 16, pp. 37-47, 1921.
- MERRILL, G. P.: "Rocks, Rock-Weathering, and Soils." 1907. (Later edition in 1913.)
- MILNER, HENRY B.: "Sedimentary Petrography." 2d ed., London and N. Y., 1924.
- MOON, F. W.: "Field and Office Methods in the Preparation of Geologic Reports." *Econ. Geol.*, vol. 8, pp. 795-797, 1913.
- MOULTON, GAIL F.: "Some Features of Redbed Bleaching." *Am. Assoc. Petr. Geols., Bull.*, vol. 10, pp. 304-311, 1926. Also discussion of same in same vol., pp. 636-637.
- NETTLETON, L. L.: "Geophysical Prospecting for Oil." N. Y., 1940.
- NEVIN, C. M.: "Principles of Structural Geology." 2d ed., N. Y., 1936.
- NEVIN, C. M., and R. E. SHERRILL: "Studies in Differential Compaction." *Am. Assoc. Petr. Geols., Bull.*, vol. 13, pp. 1-22, 1929.
- NEWSOM, J. F.: "Clastic Dikes." *Geol. Soc. Am., Bull.* 14, pp. 227-268, 1903.
- OFFICER, H. G., GLENN C. CLARK, and F. L. AURIN: "Core Drilling for Structure in the North Mid-Continent Area." *Am. Assoc. Petr. Geols., Bull.*, vol. 10, pp. 513-530, 1926.
- PIRSSON, L. V., and A. KNOPF: "Rocks and Minerals." 2d Ed., 1926.
- POWERS, SIDNEY: "Reflected Buried Hills and Their Importance in Petroleum Geology." *Econ. Geol.*, vol. 17, pp. 233-259, 1922.
- Ibid.*: "Reflected Buried Hills in the Oil Fields of Persia, Egypt, and Mexico." *Am. Assoc. Petr. Geols., Bull.*, vol. 10, pp. 422-442, 1926.
- PRICE, W. ARMSTRONG: "Reynosa Problem of South Texas, and Origin of Caliche." *Am. Assoc. Petr. Geols., Bull.*, vol. 17, pp. 488-522, 1933.
- Ibid.*: The Role of Diastrophism in Topography of Corpus Christi Area, South Texas, in "Gulf Coast Oil Fields." *Am. Assoc. Petr. Geols.*, 1936.
- PUTNAM, W. C.: "Marine Cycle of Erosion for a Steeply Sloping Shore Lane of Emergence." *Jour. Geol.*, vol. 45, pp. 844-850, 1937.
- REED, R. D.: "Some Methods of Heavy Mineral Investigations." *Econ. Geol.*, vol. 19, pp. 320-337, 1924.
- REED, R. D., and J. P. BAILEY: "Subsurface Correlation by Means of Heavy Minerals." *Am. Assoc. Petr. Geols., Bull.*, vol. 11, pp. 359-368, 1927.

- REID, H. F.: "Geometry of Faults." *Geol. Soc. Am., Bull.* 20, pp. 171-196, 1909.
- REID, H. F., *et al.*: "Report of the Committee on the Nomenclature of Faults." *Geol. Soc. Am., Bull.* 24, pp. 163-186, 1913.
- RETTGER, R. E.: "On Specifying the Type of Subsurface Structural Contouring." *Am. Assoc. Petr. Geols., Bull.* 13, pp. 1559-1561, Dec., 1929.
- RICH, J. L.: "Simple Graphical Method for Determining True Dip from Two Components." *Am. Assoc. Petr. Geols., Bull.*, vol. 16, pp. 92-94, 1932.
- ROGERS, G. SHERBURNE: "Intrusive Origin of the Gulf Coast Salt Domes." *Econ. Geol.*, vol. 13, pp. 447-485, 1918.
- ROSS, CLARENCE S.: "Methods of Preparation of Sedimentary Materials for Study," *Econ. Geol.*, vol. 21, pp. 454-468, 1926.
- ROSS, J. S., and E. A. SWEDENBORG: Analyses of Waters of the Salt Creek Field Applied to Underground Problems. "Petroleum Development and Technology for 1928-29." A. I. M. M. E., 1929.
- RUSSELL, I. C.: "Hanging Valleys." *Geol. Soc. Am., Bull.* 16, pp. 75-90, 1905.
- RYBAR, STEPHEN: "The Eötvös Torsion Balance, and Its Application to the Finding of Mineral Deposits." *Econ. Geol.*, vol. 18, pp. 639-662, 1923.
- SALISBURY, R. D.: "Distinct Glacial Epochs . . ." *Jour. Geol.*, vol. 1, pp. 61-84, 1893.
- Ibid.*: "Glacial Geology of New Jersey." *Geol. Survey of N. J., Final Rept.*, vol. 5, 1902.
- SALISBURY, R. D., and W. W. ATWOOD: "Interpretation of Topographic Maps." U. S. Geol. Survey, *Prof. Paper* 60, 1908.
- SCHLUMBERGER, C. and M., and E. G. LEONARDON: "Electrical Coring; A Method of Determining Bottom-hole Data by Electrical Measurements." A. I. M. M. E., *Trans.*, vol. 110, pp. 237-272, 1934.
- SCHUCHERT, CHARLES: "The Value of Micro-Fossils in Petroleum Exploration." *Am. Assoc. Petr. Geols., Bull.*, vol. 8, pp. 539-553, 1924.
- SECRET, MARK H.: "Perspective Block Diagrams." *Econ. Geol.*, vol. 31, pp. 867-880, 1936.
- SHALER, N. S.: "Geology of Cape Ann, Mass." U. S. Geol. Survey, *An. Rept.* 9, pp. 537-610, 1889.
- Ibid.*: "Beaches and Tidal Marshes of the Atlantic Coast." *Nat. Geog. Monographs*, No 5, 1895.
- SHARPE, C. F. STEWART: "Landslides and Related Phenomena." Columbia University Press, N. Y., 1938.
- SHELDON, P.: "Some Observations and Experiments on Joint Planes." *Jour. Geol.*, vol. 20, pp. 53-79, 164-183, 1912.
- SHERBILL, R. E.: "Origin of the En Echelon Faults in North-Central Oklahoma." *Am. Assoc. Petr. Geols., Bull.* 13, pp. 31-37, 1929.

- SHERZER, W. H.: "Criteria for the Recognition of the Various Types of Sand Grains." *Geol. Soc. Am., Bull.* 21, pp. 625-656, 1910.
- SKEELS, D. C.: "Structural Geology of the Trail Creek-Canyon Mountain Area, Montana." *Jour. Geol.*, vol. 47, pp. 816-840, 1939.
- SMITH, A. L.: "Delta Experiments." *Geog. Soc. Am., Bull.* 41, pp. 729-742, 1909.
- SMITH, W. S. TANGIER: "An Apparent-Dip Protractor." *Econ. Geol.*, vol. 20, pp. 181-184, 1925.
- STEIDTMANN, E.: "The Secondary Structures of the Eastern Part of the Baraboo Quartzite Range, Wisconsin." *Jour. Geol.*, vol. 18, pp. 259-270, 1910.
- SUNDBERG, KARL: "Electrical Prospecting for Oil Structure." *Am. Assoc. Petr. Geols., Bull.*, Sept., 1930.
- TARR, R. S., and L. MARTIN: "College Physiography." New York, 1914.
- TEAS, L. P.: "Differential Compacting the Cause of Certain Claiborne Dips." *Am. Assoc. Petr. Geols., Bull.*, vol. 7, pp. 370-378, 1923.
- THOM, W. T., JR.: "Relation of Earth Temperatures to Buried Hills and Anticlinal Folds." *Econ. Geol.*, vol. 20, pp. 524-530, 1925.
- TICKELL, F. G.: "The Correlative Value of the Heavy Minerals." *Am. Assoc. Petr. Geols., Bull.*, vol. 8, pp. 158-168, 1924.
- TRACY, JOHN CLAYTON: "Plane Surveying." John Wiley & Sons, N. Y., 1914.
- TRUEMAN, J. D.: "The Value of Certain Criteria for the Determination of the Origin of Foliated Crystalline Rocks." *Jour. Geol.*, vol. 20, pp. 228-258, 300-315, 1912.
- TWENHOFEL, W. H.: "Treatise on Sedimentation." Baltimore, 1926.
- VAN HISE, C. R.: "Principles of North American Pre-Cambrian Geology." U. S. Geol. Survey, *An. Rept.* 15, Pt. 1, pp. 581-843, 1896.
- Ibid.*: "A Treatise on Metamorphism." U. S. Geol. Survey, *Monog.* 47, 1904.
- VAN ORSTRAND, C. E.: "Apparatus for Measurement of Temperatures in Deep Wells." *Econ. Geol.* 19, pp. 229-248, 1924.
- Ibid.*: "Variation of Temperature with Geologic Structure in California and Wyoming Oil Districts." *Econ. Geol.*, vol. 21, pp. 145-165, 1926.
- Ibid.*: Temperature Gradients, in "Problems of Petroleum Geology." *Am. Assoc. Petr. Geols.*, pp. 989-1021, 1934.
- WALCOTT, C. D.: "Paleozoic Intra-Formational Conglomerates." *Geol. Soc. Am., Bull.* 5, pp. 191-198, 1894.
- WENTWORTH, CHESTER K.: "Striated Cobbles in Southern States." *Geol. Soc. Am., Bull.*, vol. 39, pp. 941-954, 1928.
- Ibid.*: "Plotting and Measurement of Exaggerated Sections." *Econ. Geol.*, vol. 25, pp. 827-831, 1930.
- WHITE, DAVID: "Some Relations in Origin between Coal and Petroleum." *Washington Acad. of Sci., Jour.*, vol. 6, pp. 189-212, 1915.

- WILLCOX, H. CASE: Value of Aerial Photographic Surveying and Mapping to Petroleum Companies and Their Geologists. A. I. M. E., "Production of Petroleum in 1924." N. Y., 1925.
- WILLIS, BAILEY: "Mechanics of Appalachian Structure." U. S. Geol. Survey, *An. Rept.* 13. Pt. 2, pp. 213-281, 1892.
- Ibid.*: "Geologic Structures." N. Y., 1923.
- Ibid.*: "The Dead Sea Problem, Rift Valley or Ramp Valley." Geol. Soc. Am., *Bull.*, vol. 39, pp. 490-542, 1928.
- WOOD, G. M.: "Suggestions to Authors of Papers Submitted for Publication by the United States Geological Survey." 2d edition, 1913. (Published by the U. S. Geol. Survey.)
- WOODWORTH, J. B.: "Original Micaceous Cross-Banding of Strata by Current Action." *Am. Geol.*, vol. 27, pp. 281-283, 1901.
- Ibid.*: "Boulder Beds of the Caney Shales at Talihina, Oklahoma." Geol. Soc. Am., *Bull.* 23, pp. 457-462, 1912 (a).
- Ibid.*: "Geological Expedition to Brazil and Chile." Mus. Comp. Zool., *Bull.* 56, 1912 (b).
- ZERNITZ, EMILIE R.: "Drainage Patterns and Their Significance." *Jour. Geol.*, vol. 40, pp. 498-521, 1932.
- ZIEGLER, V.: "Factors Influencing the Rounding of Sand Grains." *Jour. Geol.*, vol. 19, pp. 645-654, 1911.

INDEX

A

- Abandoned shore lines, 376, 378
- Abbreviations, 448, 454, 633
- Ablation, 355
- Accumulation, rate of, 56
- Accuracy, in barometer method 489
 - in field work, 419, 462, 463
 - in taking dip and strike, 406
- Adams, F. D., 163
- Aerial base map, 462, 536
 - mapping, 536-558
 - photographs, 404, 462, 537-542
- Aero Exploration Company, 551, 555
- Age, geologic, 110, 156, 188
 - of faults, 234, 236
 - of igneous rocks, 154
 - of joints, 256
 - of metamorphic rocks, 282
 - of mineral deposits, 287
 - relative, 110, 154, 188
 - of sedimentary materials, 110, 111
- Agglomerate, volcanic, 13, 121, 261, 262
- Aggradation by streams, 112, 314, 336
- Airplane (*see* Aerial base map)
- Airplane mapping, 536-558
 - uses of, 536, 542-550
- Airplane photographs, 537-542, 545
 - distortion in, 540, 554
 - errors in, 540
- Airplane reconnaissance, 537
- Albite, 129
- Alden, W. C., 352, 353
- Alidade, adjustment of the, 437
 - care of the, 436
 - open sight, 420, 433, 434, 462, 463, 525, 529
 - telescopic, 433, 434, 435, 490, 529
- Alluvial cone deposits, 58, 65, 101
- Alluvial cones, 57, 77, 95
- Alluviation by rivers, 314
- Altimeter, 427
 - Paulin, 431, 461, 482
- Ambronn, Richard, 716, 743, 769
- American Association of Petroleum Geologists, 564, 655, 776, 777
- American Geographical Society, 537, 538
- American Institute of Mining and Metallurgical Engineers, 717, 773
- Amygdales, 9, 13, 117, 118, 285, 286
- Amygdaloidal structure, 117, 118, 133, 134
- Anamorphism, zone of, 204
- Andalusite, 141, 570
- Anderson, C. G., 813
- Aneroid barometer, 429-431, 461-490
- Angle, of inclination of bedding, 17
 - of repose in sediments, 66, 84, 140, 192, 291, 292, 295, 335, 355
- Anhydrite, 181, 182, 577
- Animal tracks, 54
- Anticlinal nose on a structure contour map, 630
- Anticlines, asymmetrical, 164
 - composite, 168
 - narrowing of, with depth, 166
 - regional, 168
 - symmetrical, 164
- Anticlinorium, 168
- Apatite, 570
- Apophysis (-es), 124, 144, 152, 153, 155, 281, 289, 399
- Applin, Esther Richards, 570
- Aprons, frontal, 320
- Arbuckle Mountain uplift, 168
- Arenite, 785
- Arid regions, 53, 318, 342
 - (*See also* Deserts)
- Aridity, evidences for, 100, 101
- Arkose, 12, 70, 101, 108
- Arrangement of minerals, 265-270, 278
- Arroyos, 342
- Ash, volcanic, 118
- Assimilation, marginal, 137, 144, 151
- Asphalt, 75
- Astronomy, use of, in determining declination, 494, 495
- Athy, L. F., 64
- Atmospheric pressure, 430, 467, 469

Attitude, of contorted strata, 411
 defined, 6
 of eruptive contacts, 411, 413
 of faults, 205
 of fossils, 96, 97, 98
 Atwood, W. W., 333, 357, 358, 375, 383
 Augite, 18, 36
 Aurin, F. L., 565
 Autoclastic rocks, 106
 Autoclastic structures, 259-262
 Automobile, 442, 462, 463
 Automobile traverses, 529
 Avalanche, débris, 2
 Avalanches, folding and erosion by, 192
 Axes, crystallographic, 268
 Axial regions in sections, 623
 plane of a fold, 165
 surface of a fold, 164, 165, 166
 Axis of a fold, 165, 166

B

Backsight, 496, 512, 513, 514
 Bailey, J. P., 571
 Bajada, 318, 325
 Baking, 92, 138, 139, 145, 403
 of clay, 59, 92
 Balance, Eotvos torsion, 716
 Balk, Robert, 119, 136, 151, 247, 248, 249,
 250, 595
 Balabock, 300, 363
 Barbers Hill salt dome, 550
 Barchans, 351
 Barite, 286
 Barograph, 431, 432
 Barometer, aneroid, 429-431
 Barometer method, 404, 449, 461-490, 545
 Barometric readings, correction of, 467,
 469-489
 Barrell, J., 53, 81, 104, 138
 Barrows, H. H., 266
 Bars, bay mouth, 309, 336
 offshore, 306, 370
 sand, 83, 87
 Barton, Donald C., 713, 716, 717, 721, 730,
 734, 743, 751
 Basalt flow, 58
 Base level, 365, 366
 Base maps, 441, 454, 462, 538, 545
 Base section, 610
 Base station, 738
 Basin on a structure contour map, 630

Basins, barrier, 335, 336, 344, 378
 constructional, 334
 deposits of interior, 104
 destructional, 337
 down warp, 334
 fault, 218, 239, 330
 glaciated, 108
 identification of, 328
 lake, 335
 structural, 169
 volcanic, 334
 wind scoured, 337
 Bass, N. W., 89
 Batholith on a map, 678
 Batholiths, 122, 125, 126, 127, 136, 138,
 142, 144, 147, 148, 150, 151, 152, 154
 156, 159, 160, 161, 403
 Bausch & Lomb, 520
 Beach cusps, 49
 structure, 84, 87
 Beaches, 49, 50, 51, 52, 54, 65, 69, 70, 72,
 84, 94, 191, 309
 barrier, 306
 bay head, 306
 classification of, 305
 Beaman intervals, 520
 Beaman stadia arc, 435, 517
 Bedding, 56
 absence of, 56
 in chemical deposits, 56
 in mechanical deposits, 55
 obscure, 403
 in organic deposits, 56
 Bedrock, 2, 4, 5, 7, 69
 Beds, competent, in folding, 172, 173, 174,
 273, 275, 286
 top and bottom of, 187
 (See also Strata)
 Behre, Charles, H., Jr., 291
 Bench, 309
 topographic, 298
 Benches, abandoned, 312
 canyon, 312, 313
 fault, 310
 marine, 312
 wave cut, 297, 312, 313, 362, 371
 Bergschrund, 22, 300
 Bevan, A., 212
 Revealing of outcrops, 406
 Bibliographies for reference, 41
 Bibliography, 817
 Big Lake field, 587
 Biotite, 18, 35, 36, 95, 265, 266, 268, 570
 Birdseye, C. H., 496

- Bit, conventional, 561
 fish-tail, 560
 percussion, 560
 Black Hills, 380
 Blackwelder, E., 33, 110, 266, 318, 322, 325
 Blake, J. H., 46
 Block diagram, requisite data for a, 665
 Block diagrams, 659-666
 construction of, 660
 nonperspective, 661
 perspective, 660
 Block map, 660
 Block relief, 660
 Blow-outs, 337
 Bog iron ore, 56
 Bolinas Bay, 307
 Bolinas-Tomasales valley, 331, 332
 Bolson, 325, 326
 Bombs, volcanic, 13, 47, 121
 Bore-holes, correlation of samples from, 568
 crooked, 654-659
 electrical logging of, 573
 omission and repetition of beds observed in, 233
 (See also Wells)
 Borings, 404
 Borium, 562
 Bornhardt, W., 360
 Bosses, igneous, 122
 Bottomsets, 81, 85
 Bowen, N. L., 137
 Bowing, anticlinal, 170
 synclinal, 170
 Boulder belts, 358
 Boulders, 35
 isolated, 92, 190, 192
 and outcrops distinguished, 307
 Breccias, 12, 259-262
 fault, 11, 106
 flow, 262
 intraformational, 93
 intrusive, 143, 144
 structure, 200
 vein, 11
 Bridges, natural, 347, 348
 Brucks, Ernest W., 224
 Bubble impressions, 54
 Bucher, W. H., 49, 253, 254
 Buried hills, 176
 Buried ridge, gravity effects of a, 732, 733, 734
 Buttes, 298, 360, 361
- C
- Calcite, 19, 60, 62, 268, 269, 570
 Calderas, 334
 Caliche, 19
 California, 307, 311, 331, 332, 344, 350, 369, 544, 546, 583, 587, 589
 California State Earthquake Investigation Commission, 331, 332
 Cameras, 417, 441, 539
 Campbell, M. R., 461, 464
 Canyon Mountain area, Montana, 214
 Cap rock, 181
 effect of, on gravity measurements, 729
 Capillary action, 18, 38
 Carbon ratio, fixed, 279, 280
 Carbonaceous matter, 141
 Carbonation, 46
 Carlsbad Cavern, 347
 Casing in wells, 500
 Cataclastic structure, 268
 Caverns and caves, 2, 22, 337, 338, 347, 348
 Cementation, 60, 63, 139, 140
 belt of, 263
 Central Mineral Region of Texas, 168
 Chalcopyrite, 286
 Chamberlin, T. C., 30
 Chatter marks, 25, 30, 42
 Checking barometer readings, 469-471
 Chemical analysis, 417
 Chilling of lava or magma, 132, 133
 Chimneys, 362
 Chlorine content, maps recording, 639
 Choice of field method, 630
 Chonoliths, 124, 127, 147, 152, 412
 Chute, 630
 Circulation of mud or water in drilling, 500, 562
 Cirques, glacial, 209, 344, 345, 346, 368
 Clapp, C. H., 456
 Clapp, F. G., 627, 630
 Clark, Glenn C., 565
 Clark, Stuart K., 565
 Classification, of igneous rocks, 784
 of metamorphic rocks, 786
 of sedimentary rocks, 785
 Clay galls, 13, 100
 Clays, prodelta, 81, 319, 320
 Clay-shavings, 93
 Cleavage, 188
 in country rock, 145, 148
 discrimination between, and bedding, 272
 flow, 266, 267, 268, 271, 273
 fracture, 200, 258, 259, 266, 271

- Cleavage, peripheral, 138, 141, 143
 in relation to intrusive contacts, 141, 142
 relations of, and bedding in folds, 273
 relations of flow, to fracture cleavage, 271, 272
 rock, 258
 in slates, 139
 slaty, 267
 symbols for, on maps, 597
 uses of, in geologic interpretation, 274
- Cliffs, 22, 293
 abandoned shore line, 295, 296
 destructural, 297
 fault, 294, 295
 ice quarried, 299
 ice capped, 299
 identification of, 294
 river, 297
 sea, 297
 shore line, 295
 volcanic, 295
 wave cut, 313, 362, 371
- Climate, 18, 19, 21, 28, 35, 56, 93, 99, 100, 104, 108, 400, 671
- Clinometer, 403, 404, 412, 420, 425, 426, 428 and compass method, 449-459
- Cloos, Ernst, 254
- Closures, anticlinal, 170
 synclinal, 170
- Clots, 116
- Coal, 59, 60, 75, 96, 101, 103, 279, 767
- Coast and Geodetic Survey, 440
- Coffey, G. N., 352
- Collecting specimens, 416
- Colloidal matter, 60
- Colloids, removal of, 570
- Colorado, 122
- Colors of rocks, 8, 10, 11, 12, 18-20, 60
- Column, geologic, 668, 669, 782
- Compaction of sediments, 60, 63, 64
- Compass, 412, 420
 Brunton, 420, 422, 423, 425, 426, 460
 and clinometer method, 449-459
 Gurley, 420, 422, 423, 433, 463, 525
 setting the, 423
 traverse, 451, 452, 453, 457-459, 531
- Competent beds, 172, 173, 186, 273, 275, 286
- Composition in sedimentary rocks, 56, 66
- Compressibility of sediments, 64, 176
- Compression, in folding, 179
 of sediments, 63, 64, 177, 178
 or shearing stress, 271
 tangential, 178
- Computations, geologic, 683-701
- Concordant igneous bodies, 122
- Concretions, 8, 13, 14, 47, 60, 61
- Conductivity, electrical, 578, 713, 766, 767
- Cones, alluvial, 57, 65, 77, 295, 296, 318, 344
 cinder, 292
 lava, 291
 volcanic, 126, 149, 155, 350
 on a map, 678
- Conformable strata on a map, 673
- Conformity, 66
 line of, 15
- Conglomerate, 8, 59, 403
 basal, 70, 106, 108, 109, 187, 400
 intraformational, 77, 79, 93
- Conglomerates, crush, 106
- Conjugate sets of joints, 252
- Conodonts, 569
- Consequent stream, 382
- Consolidation, by cementation, 60
 of chemical sediments, 61
 by drying, 159
 of mechanical sediments, 59
 of molten rock, 128, 154
 of organic sediments, 61
 by pressure, 60
- Contact line, 7
- Contact lines, 14, 15
- Contact metamorphism, 15, 121, 161, 162
- Contact phenomena, interpretation of, 151
- Contact zones, 121, 133-143, 403
 relations of, to topography, 162
- Contacts, on airplane maps, 545
 altitude of, 413
 chilled, 133
 eruptive, 401, 411
 igneous, 15, 20, 115, 130-133, 398, 399
 importance of, 398
 on maps, 598, 600, 601, 602, 615
 relations of, to erosion, 157
 to topography, 162
 shape of, 150, 412
 study of, 153, 155
- Contour, index, 385
- Contour interval, 385
- Contour maps, 384
 interpretation of, 390
 requisite data on, 386
- Contour sketching, 530
- Contouring, equispaced, 648
 mechanical, 647
 parallel, 647
- Contours, 384
 spacing of, 391
 use of, for recording data on maps, 659

- Contraction in formation of dolomite, 62
 Control, ground, 539
 horizontal, 462
 stations, 463
 Controls for mapping, 446, 554
 Convergence, 171, 649, 650, 651, 652
 effect of, on structure, 653
 Coordinate system of note-taking, 454, 455
 Coquina, 59
 Corbett, C. S., 653
 Core barrel, 562
 conventional, 561
 wire line, 561
 Cores, 563, 564, 573
 orientation of, 590
 oriented, 565
 relation of, to bedding, 564, 590-593
 study of, 564, 572
 Corrosion, 1
 Correction curve of barometric readings,
 467, 469-480
 in barometric surveying, 474-480
 for curvature, 504
 for refraction, 504
 Correlation, 4
 field, 408-411
 local, 199
 method in seismic work, 758, 761
 of outcrops, 199
 of rocks in sections, 615
 of samples from wells, 568
 by use of radioactivity, 645
 Corrosion, 1, 33, 338
 Country rock, 67, 115, 140, 149, 400, 401
 conditions of, at time of intrusion, 151
 Cracks, 15, 16
 Creases, 321, 335, 342
 Creep, rock, 2, 293
 soil, 2, 293, 366, 374, 400
 Crenulations, 172, 271
 Criteria, for igneous rocks, 281
 for sediments, 280, 281
 Crooked holes, 561, 588-593, 654
 Cross-bedding, 16, 80-88, 98, 102, 103, 106,
 183, 184, 187, 275, 276, 280, 406, 407
 eolian, 85, 86, 87
 significance of, 98
 torrential, 83
 wave built, 84
 Crystallisation, 116, 117, 118, 128, 129, 130,
 132, 139, 154
 Crystallographic axes, 268
 Cuenta face, 298
 Cuesta scarp, 298
 Cuestas, 360, 661
 Cupolas, 125, 159, 160, 161
 Current action, 98
 direction of, 50, 52, 86, 98, 99
 marks, 49
 strength of, 99
 Currents, effects of, 97
 longshore, 84
 work by, 89
 Curvature, correction for, 504
 differential, 717, 720, 722, 730, 736
 Curve, first, 579
 fourth, 579, 580
 natural, 574
 permeability, 574, 576, 578, 580
 porosity, 574
 potential, 574
 resistivity, 574, 579
 second, 579, 580
 self-potential, 574, 576, 580, 643
 third, 579, 580
 Cushman, Joseph A., 570
 Cusps beach, 49
 Cuttings, rock, 560, 563
 Cyanite, 570
 Cycle, of arid erosion, 367, 368, 373-375
 of lake shores, 373
 of marine erosion, 366-373
 of mountain glacier erosion, 368, 369
 of river erosion, 323, 324, 365-368
 Cycles, of erosion, 364, 365
 geomorphic, 365
 physiographic, 365
 in sedimentation, 91, 92
- D
- Dale, T. N., 251, 259
 Daly, R. A., 122, 125, 126, 138, 148, 144
 Daniels, J. L., 565
 Darton, N. H., 380
 Davis, Foote and Rayner, 540
 Davis, W. M., 83, 242, 293, 303, 304, 320,
 322, 325, 341, 360, 370, 373, 375
 Day, Arthur L., 128
 Decke(n), 212
 Decarbonation, 140
 Declination, correction for, 422, 423, 449,
 462
 determination of, 493-495
 magnetic, 737
 Decomposition, 1, 22, 27, 31, 100, 101, 192,
 237

- Deepest bore-hole in the world, 589
 Deflation, 325, 374
 Deformation, contemporaneous, 80, 189,
 191, 192
 by fracture and flowage, 163
 manner of, 171
 DeGolyer, E., 182
 Degradation by rivers, 314
 Dehydration, 140
 Δg in gravity measurements, 721, 730
 Δg curve, 727, 729, 730
 Delta plains, glacial, 320
 structure, 80, 81, 82, 86
 Deltas, 66, 77, 87, 103, 318, 319
 Dendritic drainage pattern, 381
 Denison University, 502
 Density in the lithosphere, 718
 Deposits, aqueoglacial, 59, 77, 95, 100, 112,
 190, 335, 356, 788, 789, 792, 793, 794,
 795
 aqueous, 87
 arrangement of, 70, 71, 177
 chemical, 2, 56, 58, 403
 classification of, 788-793
 clastic, 2
 consolidated, 60
 continental, 53, 101, 102
 deep water, 90
 eolian, 77, 87, 790-795
 fluvial, 788, 789, 792-795
 fragmental, 2
 glacial, 57, 59, 112, 332, 333, 334, 335,
 790, 791
 gravity, 790, 791, 794, 795
 inorganic, 2
 lacustrine, 788, 789, 792-795
 lake, 72
 littoral, 101, 102, 788, 789, 792-795
 marine, 71, 72, 101, 102, 788, 789, 792-
 795
 mechanical, 2, 55-56
 mineral, 283-289
 organic, 2, 56, 58
 piedmont slope, 104
 quiet water, 58
 residual, 2, 6, 69, 790-795
 shallow water, 90
 sheetflood, 100
 transported, 2, 6
 unconsolidated, 60
 vein, size of, 287
 volcanic, 790-795
 *Deposition in quiet water, or not, 98
 Depth, dip, and thickness of inclined strata,
 809
 of a point, determination of, 690
 point, 763
 De-roofing, 125
 Desert varnish, 18, 19
 Deserts, sediments in, 104
 topographic forms in, 321, 324, 350
 Desjardins, Louis, 551
 Desiccation fissures, 52
 Detail mapping, 447
 Detector spread, 757
 Deviation of holes, 561, 589-593
 Diagrams, block, 650-666
 serial, 668
 skeleton, 666, 667
 Diamond drill, 550
 Diamond drilling, 562
 Diatoms, 569
 Differential movement in folding, 171, 173
 174
 Differentiates, 137
 Differentiation, magmatic, 137, 147
 Dikes, 9, 11, 123, 127, 135, 149, 155, 412
 branching, 154
 clastic, 74, 75, 111
 discrimination between, and veins, 288
 erosion of, 158
 intersecting, 154
 on a map, 678
 in relation to topography, 162
 Diller, J. S., 292
 Dip, 6, 174, 175
 in cores, 565-568, 590-593
 corrections for, 804, 805, 806, 807, 810
 depth, and thickness of inclined strata,
 809
 determination of, 403-406, 412, 460, 691-
 696
 discrimination between primary and
 secondary, 183
 of faults, 205
 variations in, 219, 220
 homoclinal, 91
 initial, 66, 175
 as a measure of tilting, 185
 method of shooting in seismic work, 758,
 760
 normal, 169
 original, 65, 66, 183, 184
 primary, 65, 66
 recording of, 448, 454
 regional, 169, 217

- Dip, slope, 360, 361
 and strike on a map, 673
 symbols for, 595, 596, 597
 true, 461
- Dips, drag, 179
 expressed as angles and as feet per mile, 803
 mapping where, are low, 459
 relations of, to contours, 672
 to topography, 672, 675, 676, 677
 as seen in sections, 620-623
- Direction, of ascent and descent on a map, 390
 of currents, 50, 52, 86, 87, 98, 99
 determination of, 420, 444, 460, 462, 490, 529
 of forces in folding, 185
 of a geologic section, 626
 of ice movement, 362
 of ice thrust, 190
 indicated on a map, 386
 of transportation, 108, 109
 of wind, 50, 54, 85, 101, 350, 351
- Directional drilling, 593
- Directions, magnetic, 421
 recording of, 420
 true, 421
- Discoloration, 140, 145
- Disconformity, 67, 68, 77, 105, 106
- Discordant igneous bodies, 122
- Disintegration, 1, 5, 21, 22, 23, 27, 41, 339
 howlders of, 13, 46
 sands, 37
- Displacement, as evidence of faulting, 222
 of a fault, 206-210
 relative to sea level, 241
 variations in, 219
- Distance, horizontal, measurement of, 497
 inclined, measurement of, 501
 map, 444
 measurement of, 428, 444, 460, 462, 490, 529
 slope, 444
 between two points on a map, 392
- Distortion of objects in shearing, 275, 278
- Diurnal variations, in pressure, 468
 in temperature, 485
- Dodge, John Franklin, 589, 593
- Dolomite, 62
- Dome, 189
 on a structure contour map, 630
- Domes, exfoliation, 360, 361
 piercement, 182
 salt, 180-183, 194, 217, 550, 657, 659, 720, 736, 749, 754, 755
- Drag, 205, 220, 222, 223
 dips, 179, 205
 strikes, 205
- Drainage pattern, 378, 379, 380-382
- Dreikanter, 44, 45
- Drift hollows, 345
 of a bore hole (*see* Deviation)
- Drill stem, 560
 leaning of, in drilling, 589
- Driller's terms, 564
- Drilling, cable tool, 559, 564, 589
 diamond, 562
 directional, 593
 exploratory, 563
 inclined, 593
 methods of, 559-563
 percussion, 559
 rate of, 581
 rotary, 560, 564
 standard, 559
- Drilling-rate charts, 581
- Drumlins, 57, 59, 352, 353
- Drusy cavities, 289
- Dune hollows, 332
- Dune topography, 332, 350
- Dunes, 85, 87, 96
 clay, 352
 migration of, 85
 sand, 332, 350-352, 370
- Dust, volcanic, 121
- Dutton, C. E., 291
- E
- Earth flow, 366
- Earthquakes, 76, 201
- Economic Geology*, 456, 807
- Economic Geology, Annotated Bibliography
 of, 415, 456, 807
- Einkanter, 44, 45
- Elastic discontinuities, 744
- Elastic earth waves, 742
 rate of propagation of, 744
- Elasticity, 713
- Electric methods, 713, 714, 766-778
 classification of, 768
 high frequency, 768, 771
 induction, 768, 775
 radiation, 768
 resistivity, 768, 770
 self-potential, 768, 769
- Electrical conductivity, 713
 logging, 573-581
 surveying, 573
 transient method, 768, 777

- Electrodes, 578, 579
 Electro-filtration, 575, 577, 578
 Electromagnetic methods, 768, 775
 Elevation, of a given point on a map, 391
 of land, 327
 negative, 646
 positive, 646
 subsea, 646
 Elevations, determination of, 453, 461, 470,
 476, 490, 514
 Eltran, 777
 Emplacement of igneous bodies, 122, 151
 Endomorphism, 121
 English, Walter A., 542
 Eötvös torsion balance, 716
 Eötvös unit, 723
 Epidote, 570
 Era, 782
 Erosion, 1, 5, 264
 agents of, 1, 34, 68
 contemporaneous, 76, 77, 78, 79, 100
 cycles of, 364
 differential, 28, 339
 of eruptive bodies, 156, 157
 by ice, 298, 299, 344, 345
 processes of, 1, 21, 22, 24
 products of, 1
 relations of contacts to, 157
 by rivers, 347
 by waves, 312, 347, 368, 370
 by wind, 325, 350
 Error, limits of, 419, 528, 629
 sources of, 406, 408, 410, 527
 triangle of, 510
 Errors, in aerial photographs, 540-542, 554
 correction of, in barometric surveying,
 468, 469-480
 Eruption, manner of, 151
 Eruptions, central, 125
 fissure, 125
 Eruptive bodies, classification of, 121-127,
 149
 depth of, 156-157
 field recognition of, 152
 field interpretation of, 149
 in relation to land surface, 156
 in relation to time of origin, 154
 shape of, 149
 size of, 127
 topographic expression of, 157
 Eruptive rock defined, 114
 Eskers, 45, 57, 190, 385, 384, 355
 Evaporation, 18
 Eve, A. S., 716, 743, 769
 Everglades, 326
 Exaggeration of scale in sections, 617
 Exfoliation, 21, 40, 41, 148, 402
 boulders of, 41
 contact, 144
 cracks, 200
 domes, 360, 361
 scale, 12
 Exomorphism, 121, 138
 Expansion, 508
 Exposure, 2
 Exposures, study of, 5, 6
 Extrusive rock defined, 111
- F
- Facets, triangular, 303, 304
 Fairchild Aerial Surveys, 547, 548
 Fanning, 749, 750, 751
 Fans, alluvial, 318, 342
 joint, 248
 Fan-shooting, 749, 750, 751
 Fath, A. E., 203
 Fault, bedding, 216
 blocks, 205
 breccias, 205, 260
 cliffs, 294
 complex, 215
 diagonal, 216
 dip, 216
 gouge, 205
 inlier, 680
 line, 15
 longitudinal, 216
 outlier, 679
 passing into a flexure, 210, 213
 scarp, original inclination of a, 242
 scarps, 295, 296, 302, 303, 330
 strike, 216, 220
 surfaces, 28, 29, 204
 tilt of strata toward a, 221
 trace, 205
 transverse, 216
 trough, 217
 wedge, 216
 zones, 203
 Faulting, 24
 causes of, 201
 effects of, on streams, 241
 evidences for, 221
 flexing caused by, 179, 198
 hillside ridge made by, 311
 intermittent, 201, 221
 Fault-line gaps, 340, 341, 342

- Fault-line scarps, 301, 302
 Fault-line valleys, 340
 Faults, 200-243, 414
 on airplane maps, 545, 548
 branch, 215
 classification of, 200, 210, 224-234
 compression, 211, 265
 contrasted with other contacts, 398, 399
 determination of slip and shift of, 696-701
 displacement of, 201, 206, 210
 distribution of, 202
 distributive, 215
 dying out, upward or downward, 210
 en echelon, 203
 extent of, 201, 212
 folded, 235
 gravity, 237, 238
 gravity effects of, 731, 732
 hinge, 215
 interpretation of, 224-234
 on a map, 679, 680
 multiple, 215
 normal, 204, 211
 overlapping, 203
 pivotal, 215
 in relation to intrusion, 155
 in relation to the land surface, 239, 310, 347
 in relation to their time of origin, 234
 relations of, to folds, 210, 213, 220
 relative age of, 234
 reverse, 204, 211
 rotational, 215
 scissors, 215
 in sections, 625, 626
 symbols for, on maps, 599
 tear, 213
 tension, 211
 terms pertaining to, 204-206
 topographic forms related to, 238
 in unconsolidated deposits, 236, 237
 warped, 235
 Fay, A. H., 111
 Feldspar, 19, 36, 267, 268
 Feldspars, sliced, 267
 Feldspathic sandstone, 101
 Felsite, 11
 Fenneman, N. M., 84
 Fenster, 241
 Field geology, 3
 Field mapping, choice of method of, 530
 comparison of methods of, 528
 Field observations, schedule for, 413
 suggestions for, 418
 Field work, procedure in, 17
 scope of, 396
 Filtration, 574, 580
 electro-, 575, 577, 578
 Firing station, 748
 Fissility, 142, 258
 Fissures, desiccation, 52
 marginal, 247, 248, 249, 250
 Fixed carbon ratio, 279, 280
 Flats, estuarine, 321
 mud, 321
 tidal, 352
 Fleming, R. C., 283
 Flexures, classification of, 164, 210, 213
 Flood plains, 53, 51, 77
 Florida, 59
 Flow, 11, 126
 breccias, 262
 cleavage, 266
 lava, 22, 58, 149
 layers, 119, 120, 136
 lines, 119, 120, 136
 rate of, 151
 Flow structure, 9, 10, 118, 133, 135, 153, 403, 413
 and fracture systems associated with
 batholiths, 247
 linear, 119, 153
 platy, 119, 153
 primary, 119
 Flowage, 163, 171
 rock, 265, 275, 276, 278, 282, 284
 zone of, 163, 172, 173, 174, 263, 282, 285
 Flows, 155, 412
 Fluid content of rocks, 573, 578, 583
 Fluid movement in rocks, 63
 Fluidity of lava, 128
 Fold, axial surface of a, 164, 165, 166
 axis of a, 165, 166
 basin, 169
 crest line of a, 167
 crestral surface of a, 167
 dome, 169
 flank of a, 166
 limb of a, 166
 ridge, 170
 trough line of a, 167
 trough surface of a, 167
 Fold axes, deformation of, 188
 Folding, causes and conditions of, 175
 cross, 188
 isoclinal, 624
 minor, 411
 parallel, 170, 274, 623

- Folding, similar, 17, 411, 623
 two or more periods of, 188
- Folds, 414
 on airplane maps, 537, 546, 547
 asymmetrical, 166, 167
 axial regions of, least metamorphosed, 280
 canoe, 169, 170
 carinate, 623
 chevron, 164
 classification of, 104
 complex, 168, 170
 relations of jointing to, 252
 composite, 168, 173, 186
 concentric, 171
 diastrophic, 185
 discrimination between, originating before
 and after consolidation, 193
 drag, 173, 174, 185, 186, 188, 273, 274
 isoclinal, 624
 minor, in relation to major, 186, 188
 overturned, 212
 parallel, 171, 172, 173, 623
 recumbent, 164
 relation of cleavage and bedding in, 273
 in relation to the land surface, 194
 in relation to time of origin, 188
 relations of, to faults, 210, 213, 220
 in schists and gneisses, 186
 similar, 171, 172, 274, 623
 size of, 172
 subordinate, 411
 symmetrical, 166, 167, 185
 in unconsolidated sediments, 189-193
 upward and downward dying out of, 171, 624
 varieties of, 167-172
- Foley, Lyndon, 203
- Foliation, 266
- Foliated, 266
- Foliation, 59, 266
- Footnotes in a geologic report, 708, 709
- Footprints, 54, 100
- Foraminifera, 569, 570
- Fordham, W. H., 716
- Foreland, cusped, 308, 309
- Foresets, 80, 81, 82, 83, 84, 85
- Foret, 513, 514
- Formation lines, 71, 73
- Fossil imprints, 29, 102, 103, 188
- Fossils, 31, 47, 54, 60, 61, 99, 102, 103, 110, 280, 321, 411, 569
 diagnostic, 644
 distortion of, 275, 277, 278
 environment of, 411
 index, 73, 74, 410
- Fossils, original environment of, 74
 position of, 96, 97, 98, 187
 replaced, 285
 transgression of, 74, 411
- Fourbles, 560
- Fraction, representative, 385
- Fracture, and flowage, 163, 200
 zone of, 163, 172, 173, 174, 200, 263, 282, 285
- Fracture cleavage, 258, 266
- Fracture structure, 133, 153, 200
- Fracture systems, 135, 153, 403, 413
 in igneous rocks, 245
- Fractures, 15, 200
 crescentic, 25, 200
 parallel, 8
- Fragments, intraformational, 92, 94
- Freezing, action of, 1, 46, 54, 93, 346
 of molten rock, 154
- Frost action, 21, 22, 40
 marks, 54
 in soil, 293
- Fuller, M. L., 279, 311, 335, 457
- Furrows (*see* Grooves; Scratches; Slickensides; Striae)
- G
- Galloway, J. J., 570
- Galls, clay, 13
- Gamma, 737
- Gamma rays, 588
- Gap, in faulting, 208, 209, 227
- Gaps, destructional, 341
 fault, 331, 332, 341
 fault line, 331, 340, 341, 342
 water, 341
 wind, 341
- Garnet, 18, 35, 95, 141, 265, 570
- Gas, 63, 64, 75, 91, 559, 578, 582, 583, 588, 651, 656
- Gases, 140, 289
 causes of metamorphism, 15.
 volcanic, 129
- Gauss, 737
- Geanticline, 168
- Geodes, 285
- Geography, description of, in a geologic report, 705
- Geologic column, 668, 669
- Geologic history from a geologic map, 680
- Geologic history, description of, in a geologic report, 707

- Geologic structure, description of, in a
geologic report, 707
- Geologic surveying, procedures in, 443
schedule for, 413
suggestions for, 414-416, 418
uses of, 395
- Geologic time scale, 782
- Geological Society of America, 119, 247
- Geology, field, 3
- Geomorphic cycles of erosion, 365
- Geomorphology, 708
- Geophysical surveying, 713
classes of, 713
methods of, 713, 714, 778
- Geosynclines, 168, 180, 182
- Geothermal data, 582-587
- Geothermal gradient, 587
- Geothermic method, 713
- Germany, 180, 183
- Gilbert, G. K., 30, 331, 377, 461
- Gish-Rooney method, 770
- Glacial advances, two or more, 356, 357
- Glacial epochs, 67, 111, 112, 113
- Glacial front, retreating, 190
- Glacial striae, 25, 42
- Glaciated rock surfaces, 26
- Glaciated valleys, 31
- Glaciation, continental, 352
- Glaciers, mountain, 298
- Gliding, crystal, 64
- Glyptoliths, 44
- Gneiss, 8, 10, 64, 268
- Gneissic structure, 10
- Gossan, 287
- Gouges, crescentic, 25, 30
- Graham, A., 38, 49, 51, 73, 80, 126, 411
- Grahen, 217, 218, 239
- Grade, 365, 366
per cent, 394
- Grades, per cent, and angles of slope, 802
- Gradient, 717, 719, 721, 730
arrow map, 725
constructional, 66
depositional, 66
geothermal, 582, 587
horizontal, 719, 720, 736
normal poleward, 717
of a slope, 394
- Granite Ridge of Kansas, 176
- Granularity, 21
- Granulation, 64, 183
- Gravimeter, 721, 723, 725
compared with torsion balance, 734
surveys, advantages of, 735
- Gravimetric methods, 713, 714, 716-736
quantities measured in, 736
- Gravity, 713
data, graphic representation of, 726
measurement, units of, 723
observations, effects of topography on
721, 722, 723
relative, 721
surveying, 727
variations in, 716
- Great South Bay, 306
- Greensands, 39
- Gregory, H. E., 20
- Grooves, 21, 23, 24-29, 100, 109, 339, 344
parallel, 8
solution, 27
- Ground control, 539
- Ground roll, 745
- Groundmass, 115
- Groundwater, 19
level, 263
- Group, 782
- Grout, Frank F., 783
- Gulf Coast, 181, 183
- Gulf Coastal Plain, 199, 220
- Gunther, C. G., 283
- Gypsum, 56, 58, 181, 182, 321

H

- Hade of a fault, 206
- Half-cell electro-chemical potential, 575
- Hand level, 473
- Hand-level method, 459, 461
- Harris, G. D., 695
- Hatch, F. H., and Rastall, R. H., 34
- Hayes, C. W., 413, 424, 801
- Haytellite, 562
- Heald, K. C., 524, 585, 587
- Heat, conduction of, in rocks, 139
a factor in metamorphism, 269
- Heating, 1
- Heave, 209
- Heavy minerals, 570, 571
- Hedberg, Hollis D., 64
- Hedstrom, Helmer, 776, 777
- Height of instrument (H.I.), 491
- Heiland, C. A., 716, 769
- Hematite, 18, 60, 140, 286
- Hewett, D. F., 167, 426
- Hiatus, 107, 109, 110
- Hill, Raymond A., 431
- Hill, Robert T., 363

Hills, 348
 buried, 176
 constructional, 350
 destructional, 359
 Hobbs, W. H., 258
 Hobbs structure, 740
 Hogbacks, 360, 361
 Hole, deepest in the world, 589
 Holes, cased, logging of, 588
 crooked, 561, 588-593
 uncased, logging of, 588
 Holland, 180, 183
 Homoclinial dip, 91
 Homoclinial dips in sections, 619
 Homocline, 164, 165
 Hoodoos, 362
 Horizon, key, 404, 408, 628, 631, 645
 Horizon line in perspective, 601
 Horizontal control, 462
 Hornblende, 18, 36, 265
 Hornstone, 139, 140
 Horse, 205
 Horses, 288
 Horst, 210, 217, 218, 239
 Houston Geological Society, 574
 Hovey, E. O., 26
 Howe, E., 359
 Hower, S. Grace, 551
 Huerfano, 363
 Huntley, L. G., 630
 Hyde, J. E., 93
 Hydration, 46
 Hydrogen sulphide, 20
 Hypotheses, multiple working, 4

I

Ice, expansion of, 191
 interstitial, 2, 191
 Ice abrasion, 344
 Ice action, 57, 190, 300, 301
 Ice advances, two or more, 356, 357
 Ice bergs, 192
 Ice blocks, effects of floating, 189
 Ice crowding in swamps, 191
 Ice dams, 335
 Ice erosion, 26
 Ice front, retreat of, 78
 Ice lobe, 26
 Igneous rock, defined, 114
 Igneous rocks, classification of, 784
 on a map, 678
 metamorphosed, distinguished from
 metamorphosed sedimentary rocks,
 280

Igneous rocks, in sections, 624, 625
 symbols for, on maps, 595
 Illinois, 336
 Illustrations for a geologic report, 709
 Ilmenite, 278, 570
 Imbricate structure, 215
 Imperial Valley, 546
 Inclination of a slope on a map, 394
 Inclined drilling, 593
 Inclusions, 54, 115, 133, 148, 149, 403
 character of, 144
 cognate, 142, 143, 146, 147
 distinguished from segregations, 147
 foreign, 142, 143, 144, 155
 in igneous rocks, 8, 13, 47
 source of, 146
 Incompetent beds, 273, 275
 Index map, 711
 Indiana, 336
 Inference in field geology, 3
 Infiltration, 574, 580
 of molten rock, 132, 138, 139
 of volatile constituents, 138, 140, 142
 Ingerson, Earl, 95, 120, 270
 Injected igneous bodies, 122
 Inliers, 241
 Inselberg(s), 360, 363, 375
 Insequent drainage pattern, 378, 381
 Instrument man, 490
 Informational sheet, 123
 International Critical Tables, 65
 Interpretation, of bore-hole data, 656, 657,
 658, 659
 of contour maps, 390
 Interruption, 375
 Intersection, 507, 525
 Interstitial moisture freezing of, 93
 Interstratification, 58
 Interval, half, 435, 515
 stratigraphic, 90, 404, 552
 in surveying, 435, 515
 Intraformational fragments, 92
 Intrusion, 265
 contemporaneous with deformation, 156
 of igneous material, 67, 151
 Intrusive rock defined, 114
 Irving, J. D., 456
 Isanomalies, 740
 Island mountains, 325, 360, 363, 375
 Islands, 348
 Isochore, 653
 Isogam, 726
 Isogam map, 726, 728
 Isonomalies, 740

Isopach, 653

Isopach map, 653

Isostatic settling, 175, 178

Ives, Ronald; L., 661

J

Jaggar, Thomas A., 128

Jakosky method, 770

Johnson, D. W., 49

Johnson, R. H., 630

Joint, 244

Joint blocks, 244

detachment of, 22, 23

riven off by ice action, 300

Joint fans, 248

Joint, intersecting, systems, 251

Joint surfaces, 244

Joint walls, 244

Jointing, columnar, 246, 247, 251

sheet, 59, 250, 251

tension, 158, 246, 247, 248

transverse, 246, 247, 251

Joints, 16, 20, 22, 188, 414

age of, 256

classification of, 244

compression, 252, 253, 272

conjugate sets of, 252, 256

cross, 247

diagonal, 249

dip, 253

of a drill stem, 560

field study of, 255, 256

flat lying, 249, 250

gash, 254, 286

in relation to cleavage, 257

in relation to the land surface, 258

in relation to their time of origin, 256

interpretation of, 255

longitudinal, 249

major, 244

on maps, 608

master, 244, 254

shear, 270

in stratified rocks, 251, 254

strike, 249, 252, 253

symbols for, on maps, 598

tension, 155, 248, 253, 254, 270

Journal of the American Chemical Society,

65

Journal of Geology, 214, 291, 318, 363, 372

Joyce, J. Wallace, 721

Jumping of beds, 409

K

Kames, 45, 57, 190, 335, 355

Kansas, 173, 332, 585, 587

Kaolin, 99

Karst topography, 339

Katamorphism, zone of, 264

Kelly, Sherwin F., 771, 773

Kentucky, 347

Kernbut, 310, 311

Kerneol, 310, 311

Kettle holes, 321, 335

Key beds, 563, 558

Key horizon, 404, 408, 478, 628, 631, 645

Keyes, C. R., 324

Keys, D. A., 716, 743, 769

Kitson, H. W., 694, 695

Klippe (n), 241

Knopf Eleanor H., 95, 120, 270

Knots, 141

Kraus, Edgar, 565

L

Laccoliths, 122, 123, 127, 147, 152, 156, 157,

161

on a map, 678

Lagoon, 306, 308, 309, 327, 336, 370, 371

Lahee, F. H., 203, 234, 431, 464, 564, 589,

593, 655, 658, 807

Lake basins, glacial, 335

Lake deposits, 72

Lake succession, 73

Lakes, abandoned shorelines of, 376, 377

glacial, 343

oxbow, 336, 367

playa, 337

saline, 343

temporary, 843, 378

walled, 191

Lamina, 56

Laminæ, 89, 92, 95, 403

textural variations in, 90, 187

Lamination, 9

uniform, 89, 98

Land forms, 290

changing, 365

constructional, 290

destructional, 290

identification of positive, 348

negative, 290

positive, 290, 348

Land survey divisions, 796

Landslide action, 41

- Monadnocks, 325, 360, 361
 Monoclinial dip, 165
 flexure on a structure contour map, 630
 Monocline, 164, 167, 185
 Montana, 214
 Moon, F. W., 693
 Moore, R. C., 782
 Moraines, 355
 ground, 344, 356
 lateral, 344, 356, 355, 358
 marginal, 356, 357
 medial, 356
 recessional, 344, 357, 358
 terminal, 333, 334, 356, 357
 Moulton, Gail F., 20
 Movements, mass, 2
 Moulins, 31
 Mountain building, 265
 Mountains, block, 350
 fault, 350
 island, 300, 363, 375
 table, 360
 Movement, differential, in folding, 171, 173,
 174, 185, 186
 Mud, 35
 Mud cracks, 52, 53, 79, 92, 100, 188
 Mud flats, 53
 used in drilling, 560, 562, 574, 575, 576
 Mudflow, 2, 24, 27, 192, 318, 374
 débris, 335
 Muds, lake floor, 72
 Mudstone, 59, 403
 Muenster-Bulcher ridge, 724
 Multiple hypotheses, 4
 Muscovite, 8, 35, 95, 570
 Muskegs, 327
- N**
- Nadir point, 541
 Nappe (s), 212
 Nash salt dome, 720
 Natural circular functions, 801
 Neck, 124
 volcanic, 126
 Necks on a map, 678
 Nests, 94
 in till, 14
 Nettleton, L. L., 716
 Nêvé, 346
 Nevin, C. M., 64, 213
 New England, 320
 New Jersey, 333, 334, 354
 New Mexico, 347, 740
 New York, 306, 308, 320, 334, 343, 354, 379
 Newson, J. F., 75
 Nichols, C. R., 771
 Nip, 371, 378
 Nivation, 346
 Niveau surface, 716
 Nonconformity, 67, 68
 North, magnetic, 386, 421, 423, 424
 true, 421, 423, 424
 North America, 354
 North Carolina, 378
 Nose, anticlinal, 170
 Notch, 297
 Notebook, 448, 450, 451, 462-467, 476, 490,
 491, 492
 Note-taking, 448, 453, 461, 463-467
 Nunataks, 360, 362
- O**
- Observation in field geology, 3
 Occurrence, mode of, 121
 Odometer, 440, 449, 460, 462, 463, 520
 Officer, H. G., 565
 Offset, 208, 209, 224, 225, 227, 412
 Oil, 63, 64, 91, 559, 577, 578, 583, 588, 651,
 656, 658
 Oil fields, mapping of, 646, 774, 775, 776
Oil and Gas Journal, 551
Oil Weekly, 589
 Oklahoma, 168, 202, 203, 585, 586, 587, 588
 Old age (see Cycles of erosion)
 Omission of beds, 219, 222, 232, 233
 Oolites, 38, 39
 Orientation, crystallographic, 120
 dimensional, 120
 preferred, 95, 120, 270
 Original of a projected line, 392
 Orthoclase, 129
 Ostracods, 560
 Ottrelite, 265
 Outcrop, 2
 breadth of, 195
 effects of topography on breadth of, 195
 Outcrops, beveling of, 406
 correlation of, 199
 distribution of, as affected by topography,
 196
 settling of, 408
 study of, 5, 396, 419
 Outliers, 241
 Overdeepening by ice, 3
 Overhang, 297

Overlap, 70, 71, 208, 209, 226

lake, 71, 72

marine, 71, 72, 73

nonmarine, 73

regressive, 70, 71, 72

transgressive, 70, 71, 72

Oversteepening by ice, 298, 344

Overthrusting, 274

contrasted with underthrusting, 213

Overthrusts, 212, 214

Owens Valley, Calif., 46, 58

Oxidation, 46, 140

P

Pace counter, 140

Pace length, 445, 446

Pacing, 460, 463

Pahoehoe, 23, 131

Panhandle of Texas, 739

Paper for the plane table, 433

Parallel banded or streaked character in rocks, 8

Parallel linear structure, 267, 268

Parallel structure, 27

Pattern, valley, 378, 379, 380-382

Pay, 657

Peat, 58, 59, 101, 370

Pebbles, 35, 40, 61

arrangement of, 94, 95

in conglomerates, 8, 13, 34, 54

distortion of, 275, 276

faceted, 40, 41, 42

glaciated, 42, 43

grooved, 40

intraformational, 77

isolated, 64, 92, 102, 190

pitted, 40, 43

rounded, 45, 46

scratched, 40, 41, 42

sheared, 14, 47

subangular, 40, 45

wind worn, 44

Pecos River, 548

Peg models, 666, 667

Pegmatite dikes, 150, 281, 289

Pegmatitic texture, 116, 129

Pelite, 36, 785

Pell-mell structure, 58

Penepplain, 105, 322, 323, 324, 374

dissected, 324

Penepplane, 322

Pennsylvania, 627

Period, 782

Periods of folding, 188

Permeability of sediments, 61, 63, 91, 576, 579

Permian Basin of Western Texas, 168, 755

Perspective, angular, 660, 661, 662

horizon line in, 661

parallel, 660, 661, 662

viewpoint in, 663

Petrofabrics, 270

Petrography, description of, in a geologic report, 706

Petroleum, 279, 280

(*See also* Gas; Oil)

Phenocrysts, 8, 9, 12, 115, 116, 119, 120, 131, 135

Photographic mapping, aerial, 538, 539

Photographs, 417, 448, 670

auplane, 538, 558

balance in, 418

oblique, 537

recording, 456

selection of subjects for, 417

Physiographic conditions at time of deposition, 101

Physiographic cycles of erosion, 365

Pillars, rain, 362

Pillow lava, 12

Pillow structure, 118

Pillows, 12, 47, 117

Pinching out of beds, 90, 91

Pinnacles, 348, 359

Pipe, in wells, 560

Pipes, clastic, 76, 111

Pirsson, L. V., 784

Pisoliths, 39

Pitch of a fold, 174, 175, 180

Pits, 29, 30

Plagioclase, 129

Plain, of arid denudation, 324

graded river flood, 322

of marine denudation, 324

Plains, 315

alluvial, 66, 314, 315, 320

coastal, 66, 317, 321

constructional, 317

delta, 320, 321

destructional, 322

flood, 318, 366

identification of, 316

lake floor, 321

outwash, 320, 333, 355

sand, 321, 335

till, 321

volcanic, 317

- Plane table, 432, 462, 463, 525, 526
 centering the, 491
 leveling the, 491
 mapping, 545
 method, 404, 490-526
 oriented, 433, 529, 532
 orienting the, 495
 paper for the, 433
 unoriented, 432
- Playa lakes, 100, 103, 352
- Playas, 53, 54, 321, 322, 337, 352
- Pleistocene glaciation, 111, 312
 extent of, 354
- Plotting scale, 490
- Plucking by ice, 22, 40, 41
- Plunge of a fold, 174
- Pneumatolysis, 142, 400
- Polarity in cores, 567, 508
- Polarization, 575
- Pole Star, 494
- Polish, on fault surfaces, 222
 on rocks, 20, 21
- Ponding of streams, 336
- Pores in rock material, 61, 64
- Porosity, determination of, 572, 573
 maximum, 62
 minimum, 62
 of sediments, 61, 62, 91
- Porphyritic structure (texture), 116, 134
- Porphyry, 116
- Potential, boundary electro-chemical, 570, 577
 defined, 714
 electrical, 574
 half-cell electro-chemical, 575, 577
- Potential center, 767
- Potential function, 714
 methode, 715
- Potholes, 31
- Powers, Sidney, 176
- Precision, degree of, in barometric method, 489
- Preferred orientation, 95, 120, 270
- Prehnite, 286
- Pressure, correction for, in barometric surveying, 474-480, 485
 differential, 263, 265
 effects of decrease of, on molten rock, 128
 hydrostatic, 75, 561
 increase of, with depth, 65
 normal atmospheric, 430
 in relation to rock deformation, 163
 static, 263
- Price, W. Armstrong, 19, 352
- Primary features on rocks, 6
- Prints, rectified, 542
 scale corrected, 542
 tilt corrected, 542
- Problem, three point, 511
- Profile method, continuous, 760
 sections in map construction, 604, 605
 shooting (seismic), 749
- Projection, cabinet, 660
 isometric, 660
- Protractor, 440
 for correction of dip, 805, 806
- Psammite, 785
- Psephite, 785
- Pseudophenocrysts, 269
- Pseudoporphyrity, 269
- Pseudostratification, 59
- Putnam, W. C., 371, 372
- Pyrite, 18, 286, 570
- Pyroclastic debris, 59
- Pyroclastic rocks, 121, 156
- Q
- Quantities measured, 444
- Quarrying, natural, 22
- Quartz, 35, 36, 95, 99, 129, 141, 266, 268, 276, 281, 289, 570
- Quartzite, 12, 60, 139, 269
- Quotations in a geologic report, 708
- R
- R value, in gravity measurements, 720
- Radial drainage pattern, 380, 381
- Radiation, 506
- Radioactive method, 713
- Radioactivity, in bore holes, 587-588
 for correlation, 645
 measurement of, 713
- Rain prints, 53, 54, 102, 103
- Ramp, 212
 trough, 217
 valley, 240
- Ranges, 796
- Reconnaissance, 397, 416, 715
 mapping, 447
 preliminary, 416
 sketching, 537
- Recrystallization, 64, 183, 266, 268, 269
- Rectangular drainage pattern, 379, 381
- Reduction tables, stadia, 439, 813
- Reed, R. D., 571
- Reef, sand, 306

- Reflection method, 755-766
 applications of, to geology, 763
 subsurface fault indicated by, 219, 220
 Refraction, correction for, 504, 505
 fan, 748, 749
 Refraction method, 747-755
 applications of, to geology, 748
 Regression, 70, 73
 Reid, H. F., 200, 206, 207, 211, 684
 Rejuvenation of streams, 305, 314, 315
 Repetition of beds, 219, 222, 230, 231, 233
 Reports, geologic, preparation of, 702, 712
 Repose, angle of, 66, 84, 149, 192, 335, 355
 Representative fraction, 385
 Resection, 452, 509, 525
 Residues, insoluble, 569
 Resistivity, of different rock materials,
 578, 768
 specific, 766
 Rettger, R. E., 648
 Reversals in dip, 160
 Rhode Island, 320
 Rhythms in stratification, 91, 92
 Rich, John L., 537, 538, 695
 Ridges, 348
 constructional, 350
 destructional, 359
 winter talus, 359
 Rift, 211, 217
 trough, 217
 valley, 240
 Rifts, 330, 331
 Rill marks, 51, 52, 98, 102
 Ripple mark, 16, 86, 98, 275, 270, 280
 Ripple marks, 49-51, 86, 95, 96, 98, 102, 103,
 187
 River beds, pebbles in, 95
 River erosion, 297, 314, 347, 365-368
 downward, 313, 314, 366
 lateral, 313, 314, 366
 Rivers, consequent, 382
 superposed, 382
 undermining by, 22
 work of, 76, 77
 Roches moutonnées, 23, 344, 360, 362
 Rock creep, 2, 293
 Rock destruction, 1
 Rock fabric, 270
 Rock fragments, 40, 41
 Rock glaciers, 24, 25
 Rock types, symbols for, on maps, 596,
 597, 600
 Rocks, study of, 413
 surface features of, 5
 Rodman, 433, 490
 Rods, leveling, 433
 stadia, 433
 Rogers, G. Sherburne, 182
 Roof pendants, 125, 147, 148
 Root growth, 22
 Ross, Clarence S., 571
 Roumania, 180, 183, 773
 Rudite, 785
 Run-off, 326
 Russell, I. C., 346
 Rust, W. M., 778
 Rust, 18, 60
 Rutile, 35, 570
 Rybar, Stephen, 716
- S
- Sabine uplift, 168
 Saddle, 170
 Salinity of subsurface waters, 576
 increase of, with depth, 65
 Salisbury, R. D., 111, 113, 333, 383
 Salt, 56, 58, 65, 194, 321, 576, 707
 effects of, in gravity measurements, 729
 Salt Creek dome, 584
 Salt crystals, 100
 Salt domes, 180-183, 217, 657, 659, 720,
 726, 749, 754, 755
 on airplane maps, 550
 Salt flat field, 776
 Salt lakes, 58
 Samples from bore-holes, study of, 568, 569
 Sand, sheet, 572
 Sand conditions, 91
 Sand grains, arrangement of, 95
 shape of, 36-39
 size of, 34, 35, 38
 Sand plains, pitted, 321
 Sands, angular, 36, 37
 aqueoglacial, 37
 corroded, 39
 eolian, 36, 38, 39
 oolitic, 38
 residual, 35
 shoestring, 89
 volcanic, 37
 wind blown, 36, 38, 39, 84, 96
 Sandstones, 59, 403
 basal, 70
 river laid, 98
 wind laid, 98
 Santa Barbara, 544
 Sapping, 40, 41, 300

- Sayles, R. W., 57
- Scale, 626
 exaggeration of, in sections, 617
 on maps, 385
 exaggerated, 387, 388
 natural, 387, 388
 natural, 617, 673
 for plotting, 440
- Scale-corrected prints, 542
- Scarps, fault, 295, 296, 302, 303
 fault line, 301, 302
 (See also Cliffs)
- Schist, 8, 17, 27, 64
 contorted laminae in, 172
 in relation to intrusive rock, 145, 150
 symbols for, on maps, 597
- Schistosity, 10, 267, 272
 linear, 268, 276
 plane, 268, 276
- Schliers, 10, 117, 118, 133, 138
- Schlumberger, C. and M., 574
- Schlumberger's direct-current method, 771, 773
- Schuchert, Charles, 570
- Scleraceous structure, 131
- Scratches, glacial, 25, 190, 344
 distinguished from slickensides, 222
 on rocks, 8, 23-29
- Sea, regressing, 71, 72
 transgressing, 71, 72
- Secondary features on rocks, 6
- Secrist, Mark H., 663
- Section, axial, 611
 base, 610
 completed, requisite data on, 626
 line of, 387, 610
- Sections, columnar, 668
 construction of, 389
 direction for, 626
 enlargement of, 389, 390
 across faults, 625, 626
 across folded strata, 619-624
 geologic, 609, 610, 611
 construction of, 613-618, 710, 711
 across igneous rocks, 624, 625
 interpretation of geologic, 618
 as land survey divisions, 797, 798
 profile, 386
 in map construction, 604, 605
- Sediment, defined, 2
- Sedimentary, defined, 2
- Sedimentary deposits, surface features of, 48-54
- Sedimentary rocks, classification of, 785
 identification of, 787
 metamorphosed, distinguished from metamorphosed igneous rocks, 280
- Sedimentation, 264
- Sediments, identification of, 788-795
 source of, 97
- Segregations, 13, 47, 54, 116, 117, 118, 133, 138
 distinguished from inclusions, 147
- Seismic methods, 713, 714, 715
 instruments used in, 746
- Seismic records, 756, 764
- Seismic waves, 742, 743, 744, 745
- Seismograph, 746
- Seismographic (see Seismic)
- Self-potential curve, 574
- Semi-arid regions, 53, 93
- Separation, 206, 207, 208, 209
- Sequence, 782
 of strata in traversing, 198
- Settling, differential, 178
 gravitative, 211
 isostatic, 175, 178
 of sediments, 95, 192, 408
- Shaler, N. S., 84, 608
- Sharpe, C. F. Stewart, 2, 293
- Shaw, E. W., 363
- Shearing, 179
 of till, 59
- Sheet, interformational, 123
- Sheet jointing, 59
- Sheet sand, 572
- Sheetflood, 2, 100, 324
- Sheets, 123
 intrusive, 412
 joint, 251
- Sheldon, P., 608, 609
- Shells on beaches, 52
- Sherrill, R. E., 64, 203
- Sherzer, W. H., 36
- Shift, 206, 209
 of a fault, determination of, 696-701
- Shoestring sands, 89
- Shore lines, abandoned, 376, 378
- Shortening, 179
- Shot point, 744, 748
- Shrinkage of sediments under overburden, 177-178
- Sights, inclined, 501-504
- Silica, 60
- Sills, 9, 11, 122, 123, 127, 149, 161, 412
 distinguished from flows, 152, 153
 on a map, 678

- Sills, in relation to topography, 162
 topographic expression of, 157
- Silt, 35
- Sinks, 76
 destructional, 337
 in limestone countries, 337, 338
 volcanic, 331, 334
- Skels, D. C., 214
- Sketches, 670
- Sky line, even, 324
- Slickensides, 21, 28, 43, 205, 221, 222, 241
 distinguished from glacial scratches,
- Slide rule, stadia, 439
- Slip, 206, 209
 of a fault, determination of, 696-701
- Slope, dip, 360, 361
 distance, 444, 529, 530
 of dunes, 352
 equivalent angles of, and per cent gr., 802
 inclination of, on a map, 394
 measurement of, 425, 426, 427, 428,
 methods of expressing, 394
- Slopes, dip, 291
 significance of, 291-293
 sliding on, 400, 401, 408
 of volcanic cones, 350
- Slumping, 56, 57, 84, 183
- Slush pit, 560
- Smith, A. L., 82, 319
- Smith, H. T. U., 784
- Smith, W. S. Tangier, 692, 805, 806, 810, 811
- Sodium carbonate, 56
- Soil creep, 2, 293, 366, 374, 400
- Soil mantle, 400
- Soils, residual, 19
- Sole, 212
- Solifluction, 2
- Solution, 1, 30, 31, 43, 44, 59, 75, 76, 183, 192
 caves, 347
 of country rock, 132
 grooves, 27
 magmatic, 145
 (See also Differentiation; Magmatic)
- pits, 32, 43
 of problems, 684, 701
 valleys, 341
- Sorting, 55, 56, 77
- South Dakota, 380
- Spalls, 41, 148, 149, 200
- Specimens, collection and trimming of, 416
 hand, 416
 recording, 456
- Spherulites, 13
- Spine, 149
- Spits, 84, 306, 307
- Spray imprints, 54
- Spurr, J. E., 283
- Spurs, faceted, 293, 302, 303
- Stacks, 312, 313, 362
- Stadia, reduction tables, 439, 813-810
- Stadia, rods, 433
- Stadia, slide rule, 439
- Stadia, traversing, 512, 525, 533
- Stalactites, 286
- Stalagmites, 286
- Staurolite, 141, 265, 570
- Stebinger drum, 435, 436, 499, 500, 501, 519, 521, 523
- Step, half, 435, 515
 in surveying, 435, 460, 515
- Stepping, 426, 460, 515
 in electrical field work, 773
- Steps, plateau, 312, 313, 314
- Steptoes, 360, 363
- Stereoscope in geologic mapping, 550-558
- Stocks, igneous, 122, 136, 159
- Stopping, overhead, 143, 150, 151
- Strata, 56
 on maps, 601, 602, 603
 in relation to topography, 196-198
 symbols for, on maps, 595, 596, 597
- Stratigraphic interval, 90, 404, 552
- Stratigraphic section, variations in thickness of, 644
- Stratigraphic sequence, 110, 409, 410
- Stratification, 10, 55, 56, 59
 absence of, 56-58
- Stratigraphy, description of, in a geologic report, 706
- Striae, glacial, 2542
- Strike, 6, 174, 175
 determination of, 403-406, 412, 420, 460, 691-696
 of faults, 205
 recording of, 448, 454
 symbols for, 595, 596, 597
 traverses along or across, 197, 198
- String, of pipe, 560
 of tools, 559, 562
- Structure, cataclastic, 268
- Structure contour maps, 626-631
 (See also Maps, structure contour)

Structure, geologic, relations of subsurface temperature to, 585-587
 imbricate, 215
 Structures, geologic, on airplane photographs, 545
 Stufe, 313, 314
 Subjacent igneous bodies, 122
 Subsidence, 2, 104, 327
 effects of, 81, 203
 Subsurface geology, 559-593
 Subsurface structure, interpretations of, 648
 Sun baking, 92
 Sun cracks, 11, 52, 53, 79, 92, 100, 102, 103, 104, 188
 Sundberg, Karl, 767, 768, 775
 Superposed stream, 382
 Surface, equipotential, 767
 Surfaces, smooth, 20, 21
 of weakness, 20
 Surveying, electrical, 573-581
 Susceptibility, magnetic, 713
 Swamps, 317, 326
 coastal plain, 326
 hillside, 326
 Swedenborg, E. A., 571
 Symbols, on maps, 595-599
 on sections, 600, 610, 612
 on topographic maps, 383
 Synclinal bowing on a structure contour map, 630
 Synclines, 164
 asymmetrical, 164, 166, 167
 composite, 168
 isoclinal, 164
 regional, 168, 182
 symmetrical, 164, 166, 167
 Synclinorium, 168
 Syntectics, 137
 System, 782

T

Tally register, 440
 Talus, 41, 56, 260, 295, 298, 301, 361
 Talus blocks, 45
 Tape, steel, 440
 Taping, 529
 Tehuantepec, Isthmus of, 180
 Temperature, in barometric surveying, 468, 474, 480-489
 in contact metamorphism, 141
 Temperature changes, 21
 Temperature effects of decrease of, on molten rock, 128
 Temperature gradient, 582, 587

Temperature increase with depth, 60, 65
 Temperature measurement of, 713
 Temperature in relation to igneous intrusion, 149, 150
 Temperature in relation to rock deformation, 163
 Temperature underground, 582-587
 Terra rossa, 69
 Terrace, 309
 structural, 164, 165, 167
 on a structure contour map, 630
 Terraces, 309
 constructional, 311
 ice pushed, 312
 off shore, 311
 river, 312, 314, 315
 wave built, 311, 312
 Texas, 168, 180, 183, 203, 233, 548, 550, 585, 720, 722, 724, 739, 743, 749, 755, 776
 Texture, amorphous, 116
 dense, 116
 glassy, 116
 granular, 116
 in igneous rocks, 115, 116, 130
 marginal, 133, 135, 137
 pegmatitic, 116, 129
 porphyritic, 116
 in sedimentary rocks, 56, 66
 Thickness, of beds, 425
 dip, and depth, of inclined strata, 809
 of formations, 654
 of a layer, measurement of, 680
 of stratigraphic section, variations in, 644
 Thinning, of formations (*see* Convergence)
 of sedimentary layers, 90
 Thom, W. T., Jr., 583, 584
 Thompson, G., 377
 Three-point problem, 511
 Thribbles, 560
 Throw, 209
 Thrusts, 211, 212, 237
 Thunderstorms, 468
 Tickell, F. G., 57
 Tiebar, 308, 309
 Tightness, 63
 Till, glacial, 37, 57, 59, 69, 77, 78, 93, 94, 190, 321, 352, 356
 Tillite, 59
 Tilt-coffected prints, 542
 Tilting, amount of, 185
 Time as a factor in metamorphism, 263
 Time lines, 71, 73
 Time scale, 110, 782
 Time value, 107, 109

- Tobin Aerial Surveys, 547, 549, 550
 Trench, 368
 Top and bottom of beds, 187
 Topaz, 570
 Topographic development, 365
 Topographic expression, 364, 409, 410
 of folds, 194
 of igneous bodies, 157
 Topographic forms, 290
 constructional, 290
 destructional, 290
 negative, 290
 positive, 290
 related to faulting, 235-243
 Topographic instructions, 519
 Topographic maps, 383
 Topographic unconformity, 375
 Topography, 413
 desert, 321, 324, 325, 337, 342, 350, 373-375
 dune, 332, 337, 350, 351, 352
 effects of, on breadth of outcrop, 195
 on distribution of outcrops, 196
 on gravity observations, 721, 722, 723
 fault, 294, 296, 302-304, 310, 330, 331, 350
 fault line, 301, 340, 341, 342
 glacial, 321, 333, 334, 352, 353, 355, 356, 357
 glacial outwash, 320, 327, 335, 343, 354, 355, 358
 glaciated, 298-301, 304, 305, 337, 343, 344, 345, 346, 361, 362, 368
 karst, 338, 339
 landslide, 302, 335, 340, 358, 359
 moraine, 332, 334
 mountain, 296, 359
 plateau, 298, 313, 314, 360
 relations of, to geologic mapping, 599
 relations of joints to, 258
 river made, 297, 313, 314, 315, 318, 322, 323, 324, 326, 336, 339, 340, 341, 343, 359, 360, 361, 365, 368
 shore line, 297, 305-309, 311, 312, 313, 318, 319, 321, 322, 326, 327, 336, 347, 368-373
 volcanic, 295, 317, 331, 334, 347, 350, 360
 Topsets, 80, 81, 85
 Tornados, 468
 Torsion, 180
 in faulting, 203
 in relation to faults, 203
 to joints, 253
 Torsion balance, 716, 721
 Torsion balance, compared with gravimeter, 734
 quantities measured by, 719
 surveys, advantages of, 735
 Tourmaline, 141
 Townships, 796
 Tracy, I. C., 510
 Trains, valley, 320, 358
 Transgression, 70, 73, 177
 of fossils, 74
 Transmission of seismic waves, 712, 743, 744, 750
 Transportation, of mechanical sediments, 55, 56
 of sand, 35
 Traverse defined, 443
 Traverses, barometer, 470, 471, 473, 476
 compass, 451, 452, 453, 457, 459, 531
 hand level, 461
 plane table, 532
 stadia, 533
 across strike, 197
 along strike, 197
 Triangle of error, 510
 Triangles, solution of, 800, 810, 811, 812
 Triangulation, 462, 525, 529, 534
 net, 508, 509
 Trimming specimens, 416, 417
 Trueman, J. D., 281
 Tuff, 262
 Turning points, 513, 514
 Tuscarora quartzite, 339, 537
 Twenhofel, W. H., 49
 Twisters, 468
- U
- Unconformities, 176, 188, 190, 400, 409, 414
 contrasted with other contacts, 398, 399
 interpretation of, 104-110
 on a map, 679
 Unconformity, angular, 68, 188
 in bed rock, 69
 blended, 15, 67, 69
 conditions of, 104-110
 local, 15, 76, 77, 78, 88, 98, 187
 parallel, 68
 regional, 15, 67, 68, 70, 106, 187
 in relation to subsurface maps, 649, 650
 surface of, 67, 69
 topographic, 375
 Undercut, 297
 Underthrusting, 213
 Uniform texture in sediments, 98

- United States, southwestern, 363
 U. S. Coast and Geodetic Survey, 738, 739
 U. S. Geological Survey, 75, 383, 519, 591, 595, 606, 682
 Utah, 377
- V
- Valley pattern, 378, 379, 380, 382
 Valleys, 327
 constructional, 331
 along contacts, 157, 158
 contact erosion, 340
 destructive, 339
 fault, 330
 fault line, 340
 glaciated, 299, 305, 332, 343
 hanging, 346, 347
 identification of, 329
 solution, 341
 U shaped, 341, 343, 344, 345
 V shaped, 340, 366, 367
 Van Hise, C. R., 104, 106, 168
 Van Nostrand Co., 783
 Van Orstrand, C. E., 582, 585, 587
 Van Tuyl, F. M., 784
 Vapors, 289
 Variometer, 737
 Varves, 80, 92, 100
 Vectorial properties of a crystal, 269
 Vegetation, 409
 on airplane maps, 543, 546, 549, 550, 552
 Vein structure, 9
 Veins, 11, 284, 285, 286, 411
 composition of, 286
 discrimination between, and dikes, 288
 fracture, 286
 gash, 285
 general field relations of, 287
 Ventifacts, 44
 Vertical, the, in reference to gravity, 716
 Verticality of holes, 589, 593
 (*See also* Crooked holes, Deviation of holes)
 Vesicles, 117
 Vesicular structure, 117, 133, 134
 Vesuvianite, 141
 Viewpoint in perspective, 663
 Virginia, 307, 338, 339, 379
 Viscosity of molten rock, 129, 130, 149, 150, 151
 Visibility between points on a map, 392, 393
 Voids in rocks, 61
 Volatile constituents of rocks, 279, 280
 Volcanic agglomerate, 13
 Volcanic ash, 118
 Volcanic bombs, 13
 Volcanic cone, 126
 Volcanic dust, 121
 Volcanic eruption, 128, 129
 Volcanic gas, 129
- W
- Walcott, C. D., 93
 Walking beds, 199, 398, 404, 545
 Wall, foot, 287
 hanging, 287
 Warping of sediments, 176
 Wash, glacial, 93, 94
 Watch, 432, 462
 Water, adsorbed, 578
 clear, evidence for, 98
 compressibility of, 65
 connate, 572, 767
 cool, 583
 depth of, 98
 expansibility of, 65
 formation, 576
 fresh, 578, 767
 hot, 583
 increase of salinity of, with depth, 65
 interstitial, 2, 60, 63, 767
 quiet, deposition, 58
 in rocks, 589, 650
 running, action of, 50, 52, 55
 work of, 45
 salinity of, 576
 salt, 578, 767
 samples of, 572
 table, 263
 vapor, 140
 Waters, descending, action of, 59, 60
 Wave action, 22, 23, 49, 51
 Wave erosion, 297, 304, 305, 312, 347, 368, 370
 Wave marks, 51, 98, 102
 Waves, elastic earth, 742
 rate of propagation of, 743, 7-
 Weathered layer, 743, 748
 Weathering, 1, 11, 29, 32, 337, 366, 402
 belt of, 263
 concentric, 22, 45, 46
 differential, 54, 61, 342
 fretwork, 33
 honeycomb, 30, 32
 of igneous rocks, 148
 spheroidal, 46

- Weaver, Paul, 714
 Wedge, fault, 216
 Wedging by ice, 301
 Weight of drill stem, 561, 589
 Weight measures, table of, 799
 Well, deepest, in the world, 589
 Well logs, 631-645, 667
 Well Surveys, Inc., 588
 Wells, wildcat, 564
 (See also Bore-holes)
 Wentworth, Chester K., 43, 618
 West Virginia, 339, 379, 537, 538
 White, David, 279
 Wide-spread method in seismic work, 759,
 762
 Wildcat wells, 564
 Wiley and Sons, Inc., 510
 Willcox, R. Case, 542
 Willis, Bailey, 66, 173, 176, 211, 212
 Wallistou, S. H., 771
 Willoughby, Spit, 307
 Wind action, 55, 84, 89
 direction of, 85
 Wind erosion, 21, 26, 44, 100,
 Winter talus ridges, 359
 Wisconsin, 353
 Wood, G. M., 703, 705, 709
 Woodworth, J. B., 42, 43, 95, 320
 Wyoming, 157, 339, 369, 380, 583,
 X
 Xenoliths, 115, 118, 144, 147, 148, 150, 154
 Y
 Yellowstone Park, 126
 Youth *(see Cycles of erosion)*
 Z
 Zernitz, E. R., 380
 Ziegler, V., 38
 Zircon, 35, 570

